NYC PLANNING

Final
Environmental
Impact
Statement

May 26, 2017

Greater East Midtown Rezoning



CEQR No. 17DCP001M
ULURP Nos.: N 170186 ZRM
C 170187 ZMM, N 170186(A) ZRM

LEAD AGENCY
City Planning Commission
City of New York
Marisa Lago, Chair

vhb

GREATER EAST MIDTOWN REZONING

Final Environmental Impact Statement (FEIS)

May 26, 2017

CEQR No.:	17DCP001M
ULURP Nos.:	N 170186 ZRM, C 170187 ZMM, N 170186(A) ZRM
Lead Agency:	City Planning Commission, City of New York
Lead Agency Contact:	Robert Dobruskin, AICP, Director Environmental Assessment and Review Division New York City Department of City Planning 120 Broadway, 31st Floor New York, New York, 10271-3100 (212) 720-3423
Prepared By:	 VHB Engineering, Surveying and Landscape Architecture, P.C. One Penn Plaza Suite 715 New York, New York 10119 With: STV, Inc. Historical Perspectives, Inc. Urbanomics, Inc. SIMCO Engineering, P.C.
Prepared For:	The New York City Department of City Planning Edith Hsu-Chen, Director Manhattan Office

Table of Contents

Foreword

FOREWORD....F-1

Executive Summary

S.1 INTRODUCTION....S-1
S.2 BACKGROUND AND EXISTING CONDITIONS....S-2
Current Status and Recent Trends....S-2
S.3 PURPOSE AND NEED FOR PROPOSED ACTION....S-3
Challenges Affecting East Midtown....S-3
Aging Building Stock....*S-3*
Limited Recent Office Development and Few Available Office Development Sites....*S-4*
Public Realm Challenges – Pedestrian Realm and Transit Network....*S-5*
Challenges of Current Zoning....*S-6*
Consequences of Long Term Challenges....*S-8*
Prior Studies in the East Midtown Area....S-8
2013 Proposed Action....*S-8*
The Vanderbilt Corridor....*S-9*
East Midtown Steering Committee....*S-10*
S.4 THE PROPOSED ACTION....S-11
Goals of the Proposed Action....S-11
Description of the Proposed Action....S-14
Proposed Zoning Text Amendment....*S-14*
Proposed Zoning Map Amendment....*S-22*
S.5 FRAMEWORK FOR ENVIRONMENTAL ANALYSIS....S-23
Reasonable Worst-Case Development Scenario (RWCDS)....S-23
Development Site Criteria....*S-23*
New Construction Development Assumptions....*S-24*
Projected and Potential Development Sites....*S-25*
Summary....*S-25*
The Future without the Proposed Action (No-Action Condition)....S-26
The Future with the Proposed Action (With-Action Condition)....S-26
Conceptual Analysis of the Discretionary Actions....*S-27*
Conceptual Construction Schedule....*S-28*
Alternatives....*S-28*
S.6 PUBLIC REVIEW PROCESS FOR THE PROPOSED ACTION....S-29
Environmental Review....S-29
Uniform Land Use Review Procedure....S-30
S.7 PROBABLE IMPACTS OF THE PROPOSED ACTION....S-31
Land Use, Zoning and Public Policy....S-31
Socioeconomic Conditions....S-31
Direct and Indirect Residential Displacement....*S-32*
Direct Business and Institutional Displacement....*S-32*
Indirect Business and Institutional Displacement....*S-33*
Adverse Effects on Specific Industries....*S-34*

Open Space S-34
Direct Effects *S-34*
Indirect Effects *S-35*
Shadows S-35
Historic and Cultural Resources S-36
Urban Design and Visual Resources S-37
Hazardous Materials S-38
Water and Sewer Infrastructure S-38
Water Supply *S-38*
Sanitary Sewage *S-39*
Stormwater Drainage and Management *S-39*
Solid Waste and Sanitation Services S-40
Energy S-40
Transportation S-40
Traffic *S-40*
Transit *S-41*
Pedestrians *S-42*
Vehicular and Pedestrian Safety *S-42*
Parking *S-43*
Air Quality S-43
Greenhouse Gas Emissions S-44
Noise S-45
Public Health S-45
Neighborhood Character S-46
Mitigation S-48
Open Space *S-48*
Shadows *S-49*
Historic and Cultural Resources *S-50*
Transportation *S-51*
Air Quality (Mobile Source) *S-61*
Construction *S-61*
Alternatives S-63
No-Action Alternative *S-63*
No Unmitigated Significant Adverse Impact Alternative *S-63*
Lesser Density Alternative *S-65*
Modified Rezoning Boundary Alternative *S-67*
Mandatory POPS Alternative *S-68*
Conceptual Analysis S-69
Unavoidable Adverse Impacts S-70
Open Space *S-70*
Shadows S-71
Historic and Cultural Resources S-72
Transportation S-72
Traffic *S-72*
Transit *S-73*
Pedestrians *S-74*
Construction S-75
Historic and Cultural Resources *S-75*
Transportation (Traffic) *S-75*
Noise *S-76*
Growth-Inducing Impacts of the Proposed Action S-76

Irreversible and Irretrievable Commitment of Resources S-77
Amended Application Analysis S-78
Historic Resources: Direct Impacts *S-78*
Open Space *S-79*
Transportation *S-79*
Construction *S-80*
Mitigation and Unavoidable Adverse Impacts *S-80*

Chapter 1: Project Description

1.1 INTRODUCTION 1-1
1.2 BACKGROUND AND EXISTING CONDITIONS 1-2
Current Status and Recent Trends 1-2
1.3 PURPOSE AND NEED FOR PROPOSED ACTION 1-3
Challenges Affecting East Midtown 1-3
Aging Building Stock *1-3*
Limited Recent Office Development and Few Available Office Development Sites *1-4*
Public Realm Challenges – Pedestrian Realm and Transit Network *1-5*
Challenges of Current Zoning *1-6*
Consequences of Long Term Challenges *1-8*
Prior Studies in the East Midtown Area 1-8
2013 Proposed Action *1-8*
The Vanderbilt Corridor *1-9*
East Midtown Steering Committee *1-9*
1.4 THE PROPOSED ACTION 1-11
Goals of the Proposed Action 1-11
Description of the Proposed Action 1-13
Proposed Zoning Text Amendment *1-13*
Proposed Zoning Map Amendment *1-21*
1.5 FRAMEWORK FOR ENVIRONMENTAL ANALYSIS 1-22
Reasonable Worst-Case Development Scenario (RWCDS) 1-22
Development Site Criteria *1-22*
New Construction Development Assumptions *1-23*
Projected and Potential Development Sites *1-23*
Summary *1-24*
The Future without the Proposed Action (No-Action Condition) 1-25
The Future with the Proposed Action (With-Action Condition) 1-25
Conceptual Analysis of the Discretionary Actions *1-26*
Conceptual Construction Schedule *1-27*
Alternatives *1-27*
1.6 PUBLIC REVIEW PROCESS FOR THE PROPOSED ACTION 1-28
Environmental Review 1-28
Uniform Land Use Review Procedure 1-29

Chapter 2: Land Use, Zoning and Public Policy

CHAPTER 2: LAND USE, ZONING AND PUBLIC POLICY 2-1
2.1 INTRODUCTION 2-1
Principal Conclusions 2-1

2.2 METHODOLOGY 2-2
Study Area Definition 2-3
2.3 DETAILED ASSESSMENT 2-3
Existing Conditions 2-3
Land Use *2-3*
Zoning *2-10*
Public Policy *2-16*
The Future without the Proposed Action (No-Action Condition) 2-20
Land Use *2-20*
Zoning *2-23*
Public Policy *2-23*
The Future with the Proposed Action (With-Action Condition) 2-23
Land Use *2-23*
Zoning *2-24*
Public Policy *2-31*
Assessment 2-32
Land Use and Zoning *2-32*
Public Policy *2-33*

Chapter 3: Socioeconomic Conditions

CHAPTER 3: SOCIOECONOMIC CONDITIONS 3-1
3.1 INTRODUCTION 3-1
Principal Conclusions 3-2
Direct and Indirect Residential Displacement *3-2*
Direct Business and Institutional Displacement *3-2*
Indirect Business and Institutional Displacement *3-3*
Adverse Effects on Specific Industries *3-4*
3.2 METHODOLOGY 3-5
Analysis Approach 3-6
Study Area Definition 3-6
Data Sources 3-7
3.3 PRELIMINARY ASSESSMENT 3-8
Direct Business and Institutional Displacement 3-8
Indirect Business/Institutional Displacement 3-10
Adverse Effects on Specific Industries 3-14
3.4 DETAILED ASSESSMENT 3-15
Direct Business and Institutional Displacement 3-16
Existing Conditions *3-16*
The Future without the Proposed Action (No-Action Condition) *3-31*
The Future with the Proposed Action (With-Action Condition) *3-32*
Indirect Business and Institutional Displacement 3-34
Existing Conditions *3-34*
The Future without the Proposed Action (No-Action Condition) *3-40*
The Future with the Proposed Action (With-Action Condition) *3-40*

Chapter 4: Open Space

4.1 INTRODUCTION 4-1
Principal Conclusions 4-1
Direct Effects *4-2*
Indirect Effects *4-2*
4.2 METHODOLOGY 4-3
Open Space Study Area 4-4
Preliminary Assessment 4-5
Framework for Detailed Analysis 4-5
Direct Effects Analysis *4-5*
Indirect Effects Analysis *4-6*
Impact Assessment *4-6*
4.3 DETAILED ASSESSMENT 4-7
Existing Conditions 4-7
Study Area Population *4-7*
Inventory of Publicly Accessible Open Space *4-10*
Assessment of Open Space Adequacy *4-22*
The Future without the Proposed Action (No-Action Condition) 4-23
Study Area Population *4-23*
Open Space Resources *4-25*
Assessment of Open Space Adequacy *4-27*
The Future with the Proposed Action (With-Action Condition) 4-28
Direct Effects Analysis *4-28*
Indirect Effect Effects Analysis *4-28*
Determining Impact Significance *4-29*

Chapter 5: Shadows

5.1 INTRODUCTION 5-1
Principal Conclusions 5-1
5.2 METHODOLOGY 5-2
Preliminary Screening Assessment 5-5
Tier 1 and Tier 2 Screening Assessments *5-5*
Tier 3 Screening Assessment *5-5*
Resources of Concern 5-6
Open Space Resources *5-6*
Historic Resources *5-6*
5.3 DETAILED SHADOW ANALYSIS 5-16
The Future without the Proposed Action (No-Action Condition) 5-16
The Future with the Proposed Action (With-Action Condition) 5-17
5.4 ASSESSMENT 5-18
Open Spaces 5-18
Section I. Longer Shadow Durations *5-18*
Section II. Shorter / Reduced Shadows *5-44*

Chapter 6: Historic and Cultural Resources

6.1 INTRODUCTION 6-1
Principal Conclusions 6-1
6.2 METHODOLOGY 6-3
Development Background 6-3
6.3 ASSESSMENT 6-5
Archaeological Resources 6-5
Architectural Resources 6-6
Criteria and Regulations 6-6
Existing Conditions 6-7
Designated Individual Landmarks Historic Resources 6-10
The Future without the Proposed Action (No-Action Condition) 6-62
The Future with the Proposed Action (With-Action Condition) 6-64

Chapter 7: Urban Design and Visual Resources

7.1 INTRODUCTION 7-1
Principal Conclusions 7-2
7.2 METHODOLOGY 7-3
Determining Whether an Urban Design and Visual Resources Assessment is Appropriate 7-4
Study Areas 7-5
Primary Study Area "Analysis Areas" 7-6
Secondary Study Area "Analysis Areas" 7-7
7.3 PRELIMINARY ASSESSMENT 7-7
7.4 DETAILED ANALYSIS, PART I – URBAN DESIGN: STREETS, BUILDINGS, AND OPEN SPACE 7-8
Existing Conditions 7-8
Primary Study Area 7-8
Primary Study Area – Analysis Areas 7-11
Secondary Study Area 7-22
Open Space 7-31
The Future without the Proposed Action (No-Action Condition) 7-33
Primary Study Area - Analysis Areas 7-37
Secondary Study Area – Analysis Areas 7-38
Open Space 7-40
The Future with the Proposed Action (With-Action Condition) 7-41
Primary Study Area 7-44
Primary Study Area – Analysis Areas 7-45
Secondary Study Area 7-49
Public Realm Improvements 7-49
Open Space 7-51
7.5 DETAILED ANALYSIS, PART II – VISUAL RESOURCES 7-55
Introduction 7-55

Chapter 8: Hazardous Materials

8.1 INTRODUCTION 8-1
8.2 PRINCIPAL CONCLUSIONS 8-1

8.3 METHODOLOGY 8-2
Regulatory Databases 8-2
Historic Sanborn Fire Insurance Maps 8-3
City Directories 8-3
Limitations 8-4
8.4 ASSESSMENT 8-4
Existing Conditions 8-4
The Future without the Proposed Action (No-Action Condition) 8-4
The Future with the Proposed Action (With-Action Condition) 8-5

Chapter 9: Water and Sewer Infrastructure

9.1 INTRODUCTION 9-1
Principal Conclusions 9-1
Water Supply *9-2*
Sanitary Sewage *9-2*
Stormwater Drainage and Management *9-2*
9.2 METHODOLOGY 9-3
9.3 ASSESSMENT 9-3
Existing Conditions 9-3
Water Supply *9-3*
Wastewater Treatment *9-5*
Stormwater and Drainage Management *9-7*
Water Conservation and WWTP Load Reduction *9-9*
The Future without the Proposed Action (No-Action Condition) 9-9
Water Supply *9-9*
Wastewater Treatment *9-10*
Stormwater and Drainage Management *9-10*
The Future with the Proposed Action (With-Action Condition) 9-11
Water Supply *9-11*
Wastewater Treatment *9-11*
Stormwater and Drainage Management *9-13*
Stormwater Best Management Practices *9-15*

Chapter 10: Solid Waste and Sanitation Services

10.1 INTRODUCTION 10-1
Principal Conclusions 10-1
10.2 METHODOLOGY 10-1
10.3 ASSESSMENT 10-2
Existing Conditions 10-2
Description of Current Solid Waste Sanitation Services *10-2*
Solid Waste Generation on Projected Development Sites *10-3*
The Future without the Proposed Action (No-Action Condition) 10-4
The Future with the Proposed Action (With-Action Condition) 10-5

Chapter 11: Energy

11.1 INTRODUCTION 11-1
Principal Conclusions 11-1
11.2 METHODOLOGY 11-2
11.3 ASSESSMENT 11-2
Existing Conditions 11-2
Energy Providers 11-2
Recent Energy Conservation Directives 11-3
Existing Demands 11-3
The Future without the Proposed Action (No-Action Condition) 11-4
The Future with the Proposed Action (With-Action Condition) 11-5

Chapter 12: Transportation

12.1 INTRODUCTION 12-1
Principal Conclusions 12-2
Traffic 12-2
Transit 12-6
Pedestrians 12-7
Vehicular and Pedestrian Safety 12-10
Parking 12-11
12.2 METHODOLOGY 12-11
Preliminary Analysis Methodology 12-11
Level 1 Screening Assessment 12-12
Level 2 Screening Assessment 12-16
Transportation Analysis Methodologies 12-23
Traffic 12-23
Transit 12-24
Pedestrians 12-27
Pedestrian and Vehicular Safety Evaluation 12-30
Parking 12-31
12.3 TRAFFIC 12-31
Existing Conditions 12-31
Study Area Street Network 12-31
Future Traffic Conditions without the Proposed Action (No-Action Condition) 12-60
Future No-Action Traffic Growth 12-60
Changes to the Study Area Street Network 12-62
Intersection Capacity Analysis 12-63
Future Traffic Conditions with the Proposed Action (With-Action Condition) 12-81
Future With-Action Traffic Growth 12-81
Above-Grade Public Realm Improvements 12-82
Intersection Capacity Analysis 12-82
12.4 TRANSIT 12-106
Existing Conditions 12-106
Subway Stations 12-106
Subway Line Haul 12-127
Commuter Railroad 12-129
Bus 12-130

Future Transit Conditions without the Proposed Action (No-Action Condition) 12-133
Subway Stations *12-133*
Subway Line Haul *12-150*
Commuter Railroad *12-153*
Bus *12-155*
Future Transit Conditions with the Proposed Action (With-Action Condition) 12-155
Subway Stations *12-155*
Subway Line Haul *12-182*
Commuter Railroad *12-184*
Bus *12-188*
12.5 PEDESTRIANS 12-188
Existing Conditions 12-188
Sidewalks *12-188*
Crosswalks *12-195*
Corner Areas *12-199*
Future Pedestrian Conditions without the Proposed Action (No-Action Condition) 12-202
Sidewalks *12-202*
Crosswalks *12-208*
Corner Areas *12-212*
Future Pedestrian Conditions with the Proposed Action (With-Action Condition) 12-216
Above-Grade Public Realm Improvements *12-217*
Street-Level Pedestrian Operations Analysis *12-218*
12.6 VEHICULAR AND PEDESTRIAN SAFETY EVALUATION 12-234
Second Avenue and East 39th Street 12-237
Second Avenue and East 42nd Street 12-238
Second Avenue and East 53rd Street 12-238
Second Avenue and East 57th Street 12-238
Third Avenue and East 42nd Street 12-239
Third Avenue and East 47th Street 12-239
Third Avenue and East 49th Street 12-239
Third Avenue and East 53rd Street 12-239
Third Avenue and East 54th Street 12-240
Third Avenue and East 57th Street 12-240
Lexington Avenue and East 42nd Street 12-241
Lexington Avenue and East 50th Street 12-241
Park Avenue and East 52nd Street 12-241
Park Avenue and East 57th Street 12-242
Madison Avenue and East 42nd Street 12-242
Fifth Avenue and 42nd Street 12-242
12.7 PARKING 12-243
Existing Conditions 12-243
Off-Street Parking *12-243*
On-Street Parking *12-247*
Future Parking Conditions without the Proposed Action (No-Action Condition) 12-253
Off-Street Parking *12-253*
On-Street Parking *12-253*
Future Parking Conditions with the Proposed Action (With-Action Condition) 12-254
Off-Street Parking *12-254*
On-Street Parking *12-254*

Chapter 13: Air Quality

13.1 INTRODUCTION 13-1
Principal Conclusions 13-1
13.2 POLLUTANTS OF CONCERN 13-2
Carbon Monoxide 13-3
Nitrogen Oxides, VOCs, and Ozone 13-3
Lead 13-3
Respirable Particulate Matter - PM_{10} and $PM_{2.5}$ 13-3
Sulfur Dioxide 13-4
Non-Criteria Pollutants 13-4
13.3 AIR QUALITY STANDARDS, REGULATIONS AND BENCHMARKS 13-5
National and State Air Quality Standards 13-5
NAAQS Attainment Status and State Implementation Plans 13-7
Determining the Significance of Air Quality Impacts 13-8
CO De Minimis Criteria 13-9
$PM_{2.5}$ De Minimis Criteria 13-9
Non-Criteria Pollutant Thresholds 13-9
13.4 METHODOLOGY 13-10
Mobile Sources 13-10
Intersection Analysis 13-11
Stationary Sources 13-15
Individual HVAC Systems 13-16
Cumulative Impacts from HVAC Systems 13-16
Industrial Sources Analysis 13-17
"Large" or "Major" Source Analysis 13-20
13.5 ASSESSMENT 13-23
Existing Conditions 13-23
The Future without the Proposed Action (No-Action Condition) 13-24
Mobile Sources 13-24
Stationary Sources 13-25
The Future with the Proposed Action (With-Action Condition) 13-25
Mobile Sources 13-26
Stationary Sources 13-28
Industrial Sources Analysis 13-32
Results of the Cancer Risk and Hazard Index Evaluation 13-36
Summary of Air Toxics Results 13-37
"Large" or "Major" Source Analysis 13-39

Chapter 14: Greenhouse Gas Emissions

14.1 INTRODUCTION 14-1
Principal Conclusions 14-1
14.2 POLLUTANTS OF CONCERN 14-2
Carbon Dioxide (CO_2) 14-2
Methane (CH_4) 14-2
Nitrous Oxide (N_2O) 14-2
Fluorinated Gases 14-2
14.3 METHODOLOGY 14-3

14.4 ASSESSMENT 14-4
GHG Emissions 14-4
Operational Emissions *14-4*
Mobile Source Emissions *14-4*
Construction Phase Emissions *14-5*
Emissions from Solid Waste Management *14-5*
Projected GHG Emissions from the Proposed Action 14-6
Consistency with the GHG Reduction Goal 14-6

Chapter 15: Noise

15.1 INTRODUCTION 15-1
Principal Conclusions 15-1
15.2 METHODOLOGY 15-2
Acoustic Fundamentals 15-2
"A"- Weighted Sound Level (dBA) *15-2*
Sound Level Descriptors *15-2*
Noise Standards and Impact Criteria 15-3
New York CEQR Noise Standards *15-3*
CEQR Noise Exposure Standards *15-4*
New York City Noise Control Code *15-5*
Noise Prediction Methodology 15-6
General Methodology *15-6*
15.3 ASSESSMENT 15-7
Existing Noise Levels 15-7
Noise Monitoring Locations *15-7*
Noise Monitoring Equipment *15-8*
Existing Noise Levels at Receptor Locations *15-8*
Mechanical Equipment *15-14*

Chapter 16: Public Health

16.1 INTRODUCTION 16-1
Principal Conclusions 16-1
16.2 PUBLIC HEALTH ASSESSMENT – CONSTRUCTION NOISE 16-1

Chapter 17: Neighborhood Character

17.1 *INTRODUCTION* 17-1
Principa*l* Conclusions 17-1
17.2 METHODOLOGY 17-3
Study Area 17-3
17.3 PRELIMINARY *ASSESSMENT* 17-4
Defining Features 17-4
Grand Central Analysis Area *17-4*
Park Avenue Analysis Area *17-6*
Madison Avenue Analysis Area *17-7*
Lexington/Third Avenue Analysis Area *17-7*

East Grand Central Analysis Area *17-8*
Midtown Analysis Area *17-8*
Upper East Side Analysis Area *17-9*
East 50s/Turtle Bay Analysis Area *17-9*
Murray Hill/Tudor City Analysis Area *17-10*
Midtown South Analysis Area *17-11*
Assessment of the Potential to Affect the Defining Features of the Neighborhood 17-11
Land Use, Zoning, and Public Policy *17-11*
Socioeconomic Conditions *17-12*
Open Space *17-13*
Historic and Cultural Resources *17-14*
Urban Design and Visual Resources *17-15*
Shadows *17-15*
Transportation *17-16*
Noise *17-17*

Chapter 18: Construction

18.1 INTRODUCTION 18-1
Principal Conclusions 18-1
Transportation *18-1*
Air Quality *18-2*
Noise and Vibration *18-3*
Other Technical Areas *18-4*
18.2 METHODOLOGY 18-5
Conceptual Construction Schedule and Activities 18-5
Construction Sequencing *18-6*
Typical Construction Activities *18-6*
Estimate of Construction Period Trucks and Construction Workers *18-7*
Determining Peak Year for Cumulative Construction and Operational Effects *18-7*
Construction Working Hours *18-7*
Construction Staging Areas, Sidewalk and Lane Closures *18-8*
18.3 PRELIMINARY ASSESSMENT 18-9
Transportation 18-9
Traffic *18-9*
Transit *18-13*
Pedestrians *18-16*
Parking *18-18*
Air Quality 18-18
Noise and Vibration 18-19
Other Technical Areas 18-19
Land Use and Neighborhood Character *18-19*
Socioeconomic Conditions *18-20*
Open Space *18-20*
Historic and Cultural Resources *18-20*
Hazardous Materials *18-21*
18.4 PROBABLE IMPACTS OF THE PROPOSED ACTION 18-21
Transportation 18-21
Traffic *18-21*
Air Quality 18-23
Air Quality Analysis Methodologies *18-24*

Emission Estimation Process *18-24*
Impacts Assessment *18-27*
Probable Impacts from Proposed Project *18-30*
Noise 18-31
Construction Noise Impact Criteria *18-31*
Noise Analysis Methodology *18-32*
Determining Existing Noise Levels *18-38*
Construction Noise Analysis Results *18-39*
Vibration 18-46
Introduction *18-46*
Construction Vibration Criteria *18-46*
Analysis Methodology *18-47*
Construction Vibration Analysis Results *18-48*

Chapter 19: Mitigation

19.1 INTRODUCTION 19-1
Principal Conclusions 19-1
Open Space *19-1*
Shadows *19-2*
Historic and Cultural Resources *19-3*
Transportation *19-4*
Air Quality (Mobile Source) *19-12*
Construction *19-13*
19.2 OPEN SPACE 19-14
19.3 SHADOWS 19-16
19.4 HISTORIC AND CULTURAL RESOURCES 19-18
19.5 TRANSPORTATION 19-20
Traffic 19-20
Action-Without-Improvements *19-20*
Action-With-Improvements *19-59*
Proposed Mitigation Schedule for Traffic Mitigation Measures 19-63
Transit 19-63
Subway Stations 19-64
Grand Central 42nd Street Subway Station *19-64*
42nd St-Bryant Park Subway Station *19-64*
Lexington Avenue-53rd Street Subway Station *19-64*
Pedestrians 19-67
Action-Without-Improvements *19-67*
Sidewalks *19-67*
Crosswalks *19-69*
Corner Areas *19-74*
Action-With-Improvements *19-77*
19.6 AIR QUALITY 19-78
19.7 CONSTRUCTION 19-79
Historic and Cultural Resources 19-79
Traffic 19-80
Noise 19-84

Chapter 20: Alternatives

CHAPTER 20: ALTERNATIVES 20-1
20.1 INTRODUCTION 20-1
Principal Conclusions 20-2
No-Action Alternative *20-2*
No Unmitigated Significant Adverse Impact Alternative *20-2*
Lesser Density Alternative *20-4*
Modified Rezoning Boundary Alternative *20-6*
Mandatory POPS Alternative *20-7*
20.2 NO-ACTION ALTERNATIVE 20-8
Land Use, Zoning, and Public Policy 20-8
Socioeconomic Conditions 20-9
Direct Business and Institutional Displacement *20-9*
Indirect Business and Institutional Displacement *20-9*
Adverse Effects on Specific Industries *20-10*
Open Space 20-10
Shadows 20-11
Historic and Cultural Resources 20-11
Urban Design and Visual Resources 20-11
Hazardous Materials 20-12
Water and Sewer Infrastructure 20-12
Solid Waste and Sanitation Services 20-12
Energy 20-13
Transportation 20-13
Traffic *20-13*
Transit *20-15*
Pedestrians *20-17*
Parking *20-18*
Air Quality 20-18
Greenhouse Gas (GHG) Emissions 20-18
Noise 20-18
Public Health 20-19
Neighborhood Character 20-19
Construction 20-20
20.3 NO UNMITIGATED SIGNIFICANT ADVERSE IMPACT ALTERNATIVE 20-20
Open Space 20-21
Shadows 20-21
Historic and Cultural Resources 20-22
Transportation 20-23
Traffic *20-23*
Transit *20-23*
Pedestrians *20-24*
Construction 20-24
Historic and Cultural Resources *20-24*
Transportation (Traffic) *20-25*
Noise *20-25*
20.4 LESSER DENSITY ALTERNATIVE 20-25
Land Use, Zoning, and Public Policy 20-28

Socioeconomic Conditions 20-29
Open Space 20-30
Shadows 20-31
Historic and Cultural Resources 20-31
Urban Design and Visual Resources 20-32
Hazardous Materials 20-33
Water and Sewer Infrastructure 20-33
Water Supply *20-33*
Wastewater Treatment *20-33*
Stormwater *20-33*
Solid Waste and Sanitation Services 20-34
Energy 20-34
Transportation 20-35
Traffic *20-36*
Transit *20-38*
Pedestrians *20-39*
Parking *20-40*
Air Quality 20-41
Mobile Source Analysis *20-41*
Stationary Source Analysis *20-41*
Greenhouse Gas Emissions (GHG) 20-41
Noise 20-42
Public Health 20-42
Neighborhood Character 20-42
Construction 20-43
20.5 MODIFIED REZONING BOUNDARY ALTERNATIVE 20-43
20.6 MANDATORY POPS ALTERNATIVE 20-44
Land Use, Zoning, and Public Policy 20-47
Socioeconomic Conditions 20-47
Open Space 20-48
Shadows 20-49
Historic and Cultural Resources 20-49
Urban Design and Visual Resources 20-50
Hazardous Materials 20-51
Water and Sewer Infrastructure 20-51
Water Supply *20-51*
Wastewater Treatment *20-51*
Stormwater *20-51*
Solid Waste and Sanitation Services 20-52
Energy 20-52
Transportation 20-52
Air Quality 20-53
Mobile Source Analysis *20-53*
Stationary Source Analysis *20-53*
Greenhouse Gas Emissions (GHG) 20-53
Noise 20-53
Public Health 20-53
Neighborhood Character 20-54
Construction 20-55

Chapter 21: Conceptual Analysis

21.1 INTRODUCTION 21-1
Principal Conclusions 21-2
21.2 METHODOLOGY AND ANALYSIS FRAMEWORK 21-2
21.3 INCREMENT FOR CONCEPTUAL ANALYSIS 21-8
Analysis Framework for Conceptual Analysis 21-10
21.4 ENVIRONMENTAL ASSESSMENT 21-11
Land Use, Zoning, and Public Policy 21-11
Socioeconomic Conditions 21-11
Open Space 21-12
Shadows 21-12
Historic and Cultural Resources 21-13
Urban Design and Visual Resources 21-14
Hazardous Materials 21-15
Water and Sewer Infrastructure 21-15
Water Supply *21-15*
Wastewater Treatment *21-15*
Stormwater and Drainage Management *21-16*
Solid Waste and Sanitation Services 21-16
Energy 21-17
Transportation 21-17
Traffic *21-19*
Transit *21-21*
Pedestrians *21-21*
Parking *21-22*
Air Quality 21-23
Greenhouse Gas Emissions 21-23
Noise 21-24
Public Health 21-24
Neighborhood Character 21-24
Construction 21-25

Chapter 22: Unavoidable Adverse Impacts

22.1 INTRODUCTION 22-1
22.2 ANALYSIS 22-1
Open Space 22-1
Shadows 22-2
Historic and Cultural Resources 22-3
Transportation 22-3
Traffic *22-3*
Transit *22-4*
Pedestrians *22-5*
Construction 22-6
Historic and Cultural Resources *22-6*
Traffic *22-6*
Noise *22-7*

Chapter 23: Growth Inducing Aspects

23.1 INTRODUCTION 23-1

Chapter 24: Irreversible Commitment

24.1 INTRODUCTION 24-1

Chapter 25: Amended Application Analysis

CHAPTER 25: AMENDED APPLICATION ANALYSIS 25-1
25.1 INTRODUCTION 25-1
25.2 PRINCIPAL CONCLUSIONS 25-1
Historic Resources: Direct Impacts *25-2*
Open Space *25-2*
Transportation *25-2*
Construction *25-3*
Mitigation and Unavoidable Adverse Impacts *25-4*
25.3 DESCRIPTION OF THE AMENDED APPLICATION 25-6
25.4 AMENDED WITH-ACTION CONDITION REASONABLE WORST CASE DEVELOPMENT SCENARIO 25-8
Proposed Amendment to Select Special Transit Land Use Districts *25-10*
Qualifying Site Modification *25-10*
Other Modifications in the Proposed A-Text *25-10*
25.5 REVISED ENVIRONMENTAL ANALYSES FOR THE AMENDED APPLICATION 25-11
1. Land Use, Zoning, and Public Policy 25-11
Qualifying Site Modification *25-11*
TA Subdistrict Ancillary Building Easement *25-12*
2. Socioeconomic Conditions 25-12
Qualifying Site Modification *25-12*
3. Open Space 25-13
Qualifying Site Modification *25-13*
4. Shadows 25-14
Methodology *25-15*
Resources of Concern *25-15*
Assessment *25-16*
Open Space Resources *25-16*
Historic Resources *25-17*
5. Historic and Cultural Resources 25-19
Qualifying Site Modification *25-19*
6. Urban Design and Visual Resources 25-21
Qualifying Site Modification *25-21*
Transit Easement Volume Ancillary Facility Text Amendment *25-22*
7. Hazardous Materials 25-23
8. Water and Sewer Infrastructure 25-24
9. Solid Waste and Sanitation Services 25-25
10. Energy 25-25
11. Transportation 25-26
Qualifying Site Modification *25-26*

Traffic *25-28*
Transit *25-34*
Pedestrians *25-40*
Vehicular and Pedestrian Safety *25-42*
Parking *25-42*
12. Air Quality 25-43
Mobile Sources *25-43*
Stationary Sources *25-45*
TA Subdistrict Ancillary Building Easement *25-47*
13. Greenhouse Gas Emissions 25-47
Qualifying Site Modification *25-47*
14. Noise 25-47
Qualifying Site Modification *25-48*
TA Subdistrict Ancillary Building Easement *25-51*
15. Public Health 25-52
16. Neighborhood Character 25-52
Qualifying Site Modification *25-53*
17. Construction 25-53
Qualifying Site Modification *25-54*
25.6 MITIGATION 25-57
Open Space 25-57
Shadows 25-58
Transportation 25-59
Traffic *25-59*
Transit *25-65*
Pedestrians *25-65*
18. Air Quality 25-67
25.7 CONCEPTUAL ANALYSIS 25-68

Chapter 26: Response to Comments on the DEIS

1.1 INTRODUCTION 26-1
1.2 LIST OF ELECTED OFFICIALS, ORGANIZATIONS, AND INDIVIDUALS WHO COMMENTED ON THE DEIS 26-1
Elected Officials 26-1
Public Agencies 26-1
Community Board 26-2
Organizations and Interested Public 26-2
1.3 COMMENTS AND RESPONSES ON THE DEIS 26-3

List of Appendices

APPENDIX A: REASONABLE WORST-CASE DEVELOPMENT SCENARIO, TABLES 1A AND 1B
APPENDIX B: PROPOSED ZONING TEXT
- APPENDIX B.1: Proposed Zoning Text
- APPENDIX B.2: Proposed Amended Action Zoning Text

APPENDIX C: SOCIOECONOMIC CONDITIONS
APPENDIX D: AGENCY CORRESPONDENCE
APPENDIX E: HAZARDOUS MATERIALS
- APPENDIX E.1: Regulatory Agency Database Report
- APPENDIX E.2: Historical Sanborn Fire Insurance Maps
- APPENDIX E.3: City Directory Reviews

APPENDIX F: TRANSPORTATION
- APPENDIX F.1: Transportation Planning Factors
- APPENDIX F.2: Modification of Synchro Adjustment Factors
- APPENDIX F.3: A Listing of Changes in Intersection Configuration Between Existing and No-Action Conditions
- APPENDIX F.4: Assignment of Auto Trips to Off-Street Parking Facilities
- APPENDIX F.5: Traffic LOS Tables for Existing, No-Action, and With-Action Conditions
- APPENDIX F.6: Traffic Volume Figures for Proposed Action with PRI Condition
- APPENDIX F.7: A Listing of Changes in Intersection Configuration in the Proposed Action with PRI Condition
- APPENDIX F.8: Traffic LOS Tables for Proposed Action with PRI Condition
- APPENDIX F.9: Proposed Traffic Mitigation Measures for Proposed Action with PRI Condition
- APPENDIX F.10: Traffic LOS Tables for Proposed Action with PRI Condition With and Without Proposed Mitigation
- APPENDIX F.11: Subway Station Assignments
- APPENDIX F.12: Subway Station Volumes
- APPENDIX F.13: Results of Proposed Action Without Subway Station Improvements (With-Action Without-Improvement)
- APPENDIX F.14: Pedestrian Volumes (Sidewalks, Crosswalks and Corners)
- APPENDIX F.15: A Listing of Changes to Pedestrian Elements in the Proposed Action with PRI Condition
- APPENDIX F.16: Pedestrian LOS Tables for Proposed Action with PRI Condition
- APPENDIX F.17: Pedestrian LOS Tables for Proposed Action with PRI Condition and Mitigation

APPENDIX G: NOISE
APPENDIX H: CONSTRUCTION
- APPENDIX H.1: Traffic Volume Figures
- APPENDIX H.2: Traffic LOS Tables
- APPENDIX H.3: Parking Demand

APPENDIX I: ALTERNATIVES
- APPENDIX I.1: Lesser Density Alternative RWCDS
- APPENDIX I.2: Lesser Density Alternative Traffic Volume Figures
- APPENDIX I.3: Lesser Density Alternative Traffic LOS Tables
- APPENDIX I.4: Lesser Density Alternative Subway LOS Tables
- APPENDIX I.5: Lesser Density Alternative Pedestrian LOS Tables (Sidewalks, Corners and Crosswalks)
- APPENDIX I.6: Lesser Density Alternative Parking Accumulation

APPENDIX J: CONCEPTUAL ANALYSIS
- APPENDIX J.1: Conceptual Analysis RWCDS Table

APPENDIX J.2: Traffic Volume Figures
APPENDIX J.3: Traffic LOS Tables
APPENDIX J.4: Pedestrian LOS Tables (Sidewalks, Corners and Crosswalks)
APPENDIX J.5: Parking Accumulation
APPENDIX K: E DESIGNATIONS
APPENDIX K.1: Hazardous Materials
APPENDIX K.2: Air Quality
APPENDIX K.3: Noise
APPENDIX L: AMENDED APPLICATION
APPENDIX L.1: Amended Application RWCDS
APPENDIX L.2: Hazardous Materials
APPENDIX L.3: Shadows Tables
APPENDIX L.4: Shadows Figures
APPENDIX L.5: Parking Assignment for Amended Action
APPENDIX L.6: Traffic Volume Figures for Amended Action Without PRI Condition
APPENDIX L.7: Traffic LOS Tables for Amended Action Without PRI Condition
APPENDIX L.8: Traffic Volume Figures for Amended Action with PRI Condition
APPENDIX L.9: Traffic LOS Tables for Amended Action with PRI Condition
APPENDIX L.10: Subway Station Assignments for Amended Action
APPENDIX L.11: Subway Station Analysis for Amended Action
APPENDIX L.12: Subway Station Analysis for Amended Action without Subway Station Improvements
APPENDIX L.13: Pedestrian LOS Tables (Sidewalks, Corners, Crosswalks) for Amended Action Without PRI Condition
APPENDIX L.14: Pedestrian LOS Tables (Sidewalks, Corners, Crosswalks) for Amended Action With PRI Condition
APPENDIX L.15: Parking Accumulation for Amended Action
APPENDIX L.16: Proposed Traffic Mitigation Measures for Amended Action Without PRI Condition
APPENDIX L.17: Traffic LOS Tables for Amended Action Without PRI Condition with and without Proposed Mitigation
APPENDIX L.18: Proposed Traffic Mitigation Measures for Amended Action With PRI Condition
APPENDIX L.19: Traffic LOS Tables for Amended Action With PRI Condition with and without Proposed Mitigation
APPENDIX L.20: Amended Action Subway Station Analysis with Mitigation
APPENDIX L.21: Pedestrian LOS Tables for Amended Action without PRI Condition and Mitigation
APPENDIX L.22: Pedestrian LOS Tables for Amended Action with PRI Condition and Mitigation
APPENDIX M: AMENDED ACTION E-DESIGNATIONS
APPENDIX M.1: Hazardous Materials
APPENDIX M.2: Air Quality
APPENDIX M.3: Noise
APPENDIX N: DEIS COMMENTS
APPENDIX O: ADDITIONAL SHADOWS MITIGATION ANALYSIS OF ST. BARTHOLOMEW'S EPISCOPAL CHURCH

List of Tables

Executive Summary

Table S.1: Blocks and Lots within the Rezoning Area S-13
Table S.2: RWCDS and Population Summary for Projected Development Sites S-27
Table S.3: Summary of Movements/Intersections with Significant Adverse Traffic Impacts S-52
Table S.4: Summary of Locations with Significant Adverse Traffic Impacts S-53
Table S.5 Summary of Elements with Significant Adverse Pedestrian Impacts S-57
Table S.6: Unmitigated Pedestrian Impacts S-59
Table S.7: Comparison of Proposed Action and Lesser Density Alternative FARs by Subarea S-66

Chapter 1: Project Description

Table 1.1: Blocks and Lots within the Rezoning Area 1-12
Table 1.2: RWCDS and Population Summary for Projected Development Sites 1-26

Chapter 2: Land Use, Zoning and Public Policy

Table 2.1: Existing Land Uses within the Primary Study Area 2-4
Table 2.2: Primary Study Area Existing Zoning Designations 2-11
Table 2.3: Secondary Study Area Existing Zoning Designation 2-14
Table 2.4: Development Projects in the 2036 Future without the Proposed Action 2-21
Table 2.5: No-Action to With-Action Comparison of Development for Projected Development Sites 2-24

Chapter 3: Socioeconomic Conditions

Table 3.1: Midtown Manhattan Office Submarkets located within the Primary Study Area 3-17
Table 3.2: Age of the Office Building Stock in the Primary Study Area 3-18
Table 3.3: Size of the Office Building Stock in Primary Study Area 3-19
Table 3.4: Total Employment by Sector in the Primary Study Area 3-21
Table 3.5: RWCDS for the 16 Projected Development Sites 3-22
Table 3.6: Potentially Directly Displaced Business/Institutions and Employment on Projected Development Sites 3-24
Table 3.7: Directly Displaced Employment as a Percentage of the Primary and Secondary Study Areas' Employment 3-25
Table 3.8: Potential Directly Displaced Accommodation and Food Service Businesses 3-26
Table 3.9: Potential Directly Displaced Professional, Scientific, and Technical Service Businesses 3-29
Table 3.10: Midtown Manhattan Office Submarkets included in the Secondary Study Area and Overall Totals for Midtown and Manhattan Office Markets 3-35
Table 3.11: Total Employment by Sector in the Secondary Study Area 3-39

Chapter 4: Open Space

Table 4.1: RWCDS and Population/Employment Summaries for Projected Development Sites, Compared to the No-Action Condition 4-4

Table 4.2: Existing Non-Residential Population in the Open Space Study Area 4-8
Table 4.3: Existing College/Post-Secondary Student Population in the Open Space Study Area 4-9
Table 4.4: Existing Residential Population in the Open Space Study Area 4-10
Table 4.5: Summary of Open Space User Groups within the Study Area 4-10
Table 4.6: Inventory of Existing Open Space Resources Included in the Quantitative Analysis 4-13
Table 4.7: Existing Conditions: Adequacy of Open Space Resources 4-23
Table 4.8: Development Projects in the Future without the Proposed Action 4-24
Table 4.9: New Open Space Resources in the Future without the Proposed Action 4-26
Table 4.10: No-Action Condition - Adequacy of Open Space Resources 4-28
Table 4.11: With-Action Condition: Adequacy of Open Space Resources 4-29
Table 4.12: 2036 Future with the Proposed Action: Passive Open Space Ratios Summary 4-30
Table 4.13: Open Space Utilization Within a Quarter-Mile of Projected Development Sites 4-32

Chapter 5: Shadows

Table 5.1: Resources of Concern within Defined Shadow Radius – Open Spaces Affected by Incremental Shadows 5-7
Table 5.2: Resources of Concern within Defined Shadow Radius – Open Spaces Not Affected by Incremental Shadows 5-12
Table 5.3: Resources of Concern within Defined Shadow Radius – Sunlight-Sensitive Historic Resources Affected by Incremental Shadows 5-15
Table 5.4: Resources of Concern within Defined Shadow Radius – Sunlight-Sensitive Historic Resources Not Affected by Incremental Shadows 5-16
Table 5.5: Incremental Shadow Duration on Resources of Concern – Open Space and Sunlight Sensitive Historic 5-48
Table 5.6: Historic Resources with no Incremental Shadows on Sunlight Sensitive Features 5-59

Chapter 6: Historic and Cultural Resources

Table 6.1: Designated Individual Historic Resources in the Rezoning area and Study Area 6-72
Table 6.2: Eligible Historic Resources in the Rezoning area and Study Area 6-76
Table 6.3: RWCDS Projected and Potential Development Sites Within or Located in Proximity to NYCL- or S/NR-designated, and NYCL- or S/NR-eligible Historic Resources 6-79
Table 6.4: Assessment of Proposed Action's Potential Impacts on Designated or Eligible Historic Resources in the Rezoning area and Study Area 6-83

Chapter 7: Urban Design and Visual Resources

Table 7.1: Development Projects in the 2036 Future without the Proposed Action 7-34
Table 7.2: Visual Resources (Refer to Figure 7-10, and Figures 7-11A-W) 7-56

Chapter 8: Hazardous Materials

Table 8.1: Federal and State Regulatory Agency Databases Reviewed 8-3
Table 8.2: Summary of Environmental Issues for Projected and Potential Development Sites 8-7

Chapter 9: Water and Sewer Infrastructure

Table 9.1: Water Consumption and Wastewater Generation Rates 9-4
Table 9.2: Existing Water Consumption and Wastewater Generation on Projected Development Sites 9-5
Table 9.3: Monthly Average Dry Weather Flows from the Newtown Creek WWTP 9-6
Table 9.4: Existing Wastewater Generation on Projected Development Sites by Subcatchment Area 9-7
Table 9.5: Existing Stormwater Runoff to the Newtown Creek WWTP 9-8
Table 9.6: Existing Combined Stormwater Runoff and Wastewater Generation to the Newtown Creek WWTP 9-8
Table 9.7: No-Action Water Consumption and Wastewater Generation 9-10
Table 9.8: Water Consumption and Wastewater Generation in the No-Action and With-Action Conditions 9-12
Table 9.9: Combined Stormwater Runoff and Wastewater Generation Flow Volume to the Combined Sewer System in the Proposed Rezoning Area—With-Action Condition 9-13
Table 9.10: Incremental Increase in Combined Stormwater Runoff and Wastewater Generation Flow Volumes to the Combined Sewer System in the Proposed Rezoning Area 9-14

Chapter 10: Solid Waste and Sanitation Services

Table 10.1: Existing Solid Waste Generation on Projected Development Sites 10-4
Table 10.2: No-Action Solid Waste Generation on Projected Development Sites 10-5
Table 10.3: With-Action Solid Waste Generation on Projected Development Sites 10-6
Table 10.4: Comparison of Weekly Solid-Waste Generation on Projected Development Sites (Existing, No-Action, and With-Action Conditions) 10-6

Chapter 11: Energy

Table 11.1: Existing Estimated Annual Energy Consumption on Projected Development Sites 11-4
Table 11.2: No-Action Condition: Estimated Annual Energy Consumption on Projected Development Sites 11-4
Table 11.3: With-Action Condition: Estimated Annual Energy Consumption on Projected Development Sites 11-5

Chapter 12: Transportation

Table 12.1: RWCDS Summary for Projected Development Sites 12-1
Table 12.2: Summary of Significant Adverse Traffic Impacts 12-3
Table 12.2: Summary of Significant Adverse Traffic Impacts (Continued) 12-4
Table 12.2: Summary of Significant Adverse Traffic Impacts (Continued) 12-5
Table 12.3: Summary of Significant Adverse Pedestrian Impacts 12-8
Table 12.3: Summary of Significant Adverse Pedestrian Impacts (Continued) 12-9
Table 12.4: Transportation Planning Factors 12-13
Table 12.5: Travel Demand Forecast with the Proposed Action (2036) 12-15
Table 12.6: Summary of Incremental Trips Generated by the Proposed Action 12-16
Table 12.7: Net Incremental Peak Hour Subway Trips by Station or Station Complex 12-17
Table 12.8: Net Incremental Peak Hour Local Bus Trips by Route 12-20
Table 12.9: Number of Rezoning Area Express Bus Routes and Estimated Distribution of Net Incremental Peak Hour Express Bus Trips by Borough/County 12-21
Table 12.10: Intersection Level of Service Criteria 12-24
Table 12.11: Level of Service Criteria for Subway Station Elements 12-25

Table 12.12: Significant Impact Thresholds for Stairways and Passageways 12-26
Table 12.13: Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions 12-28
Table 12.14: Significant Impact Criteria for Sidewalks with Platooned Flow in a CBD Location 12-29
Table 12.15: Significant Impact Criteria for Corners and Crosswalks in a CBD Location 12-30
Table 12.16: Summary of Existing Levels of Service by Movement 12-36
Table 12.17: Intersections with Existing Congested Approach Movements 12-37
Table 12.17: Intersections with Existing Congested Approach Movements (Continued) 12-38
Table 12.17: Intersections with Existing Congested Approach Movements (Continued) 12-39
Table 12.17: Intersections with Existing Congested Approach Movements (Continued) 12-40
Table 12.17: Intersections with Existing Congested Approach Movements (Continued) 12-41
Table 12.17: Intersections with Existing Congested Approach Movements (Continued) 12-42
Table 12.18: East Midtown Development Projects Included in the No-Action Condition Traffic Analysis 12-61
Table 12.19: Summary of Existing and No-Action Levels of Service by Movement 12-63
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour 12-64
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-65
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-66
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-67
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-68
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-69
Table 12.20: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-69
Table 12.21: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour 12-70
Table 12.21: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour (Continued) 12-71
Table 12.21: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour (Continued) 12-72
Table 12.21: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour (Continued) 12-73
Table 12.21: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour (Continued) 12-74
Table 12.21: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour (Continued) 12-75
Table 12.22: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour 12-76
Table 12.22: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-77
Table 12.22: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-78
Table 12.22: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-79
Table 12.22: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-80
Table 12.22: Existing and No-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-81
Note: This Table has been updated for the FEIS 12-81
Table 12.23: Summary of No-Action and With-Action Level of Service by Movement 12-83
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour 12-84
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-85
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-86
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-87
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-88
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-89
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-90
Table 12.24: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the AM Peak Hour (Continued) 12-90
Table 12.25: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the Midday Peak Hour 12-90
Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour 12-96
Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-97
Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-98
Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued) 12-99

Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued).... 12-100
Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued).... 12-101
Table 12.26: No-Action and With-Action Intersections with LOS E/F or V/C ≥ 0.90 in the PM Peak Hour (Continued).... 12-102
Table 12.27: Summary of Approach Movements and Intersections with Significant Impacts with the Proposed Action.. 12-102
Table 12.28: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Action-With-Improvements Condition and Action-Without-Improvements Condition 12-103
Table 12.29: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Action-With-Improvements Condition and Action-Without-Improvements Condition..... 12-104
Table 12.29: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Action-With-Improvements Condition and Action-Without-Improvements Condition (Continued)..... 12-105
Table 12.30: Existing Conditions Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex..... 12-109
Table 12.30: Existing Conditions Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex (Continued) 12-110
Table 12.31: Existing Conditions Escalator Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-111
Table 12.32: Existing Conditions Passageway Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex..... 12-111
Table 12.33: Existing Conditions Fare Control Area Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex..... 12-112
Table 12.34: Existing Conditions Stair Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station..... 12-114
Table 12.35: Existing Conditions Fare Control Area Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station..... 12-115
Table 12.36: Existing Conditions Stair Analysis at the Fifth Avenue (7) Subway Station 12-116
Table 12.37: Existing Conditions Fare Control Area Analysis at the Fifth Avenue (7) Subway Station..... 12-116
Table 12.38: Existing Conditions Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station..... 12-118
Table 12.39: Existing Conditions Fare Control Area Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-119
Table 12.40: Existing Conditions Stair Analysis at the 51st Street (6) Subway Station..... 12-121
Table 12.41: Existing Conditions Escalator Analysis at the 51st Street (6) Subway Station 12-121
Table 12.42: Existing Conditions Passageway Analysis at the 51st Street (6) Subway Station..... 12-121
Table 12.43: Existing Conditions Fare Control Area Analysis at the 51st Street (6) Subway Station..... 12-122
Table 12.44: Existing Conditions Stair Analysis at the Lexington Avenue/53rd Street Subway Station 12-123
Table 12.45: Existing Conditions Escalator Analysis at the Lexington Avenue/53rd Street Subway Station..... 12-123
Table 12.46: Existing Conditions Fare Control Area Analysis at the Lexington Avenue/53rd Street Subway Station. 12-124
Table 12.47: Existing Conditions Stair Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-125
Table 12.48: Existing Conditions Fare Control Area Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station..... 12-125
Table 12.49: Existing Conditions Escalator Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-126
Table 12.50: Existing Conditions Stair Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station..... 12-126
Table 12.51: Existing Conditions Escalator Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-127
Table 12.52: Existing Conditions Subway Line Haul Analysis 12-128
Table 12.53: Existing Conditions Stair Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-129

Table 12.54: Existing Conditions Escalator Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-130
Table 12.55: Existing Conditions Passageway Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-130
Table 12.56: No-Action Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-137
Table 12.56: No-Action Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex (Continued) 12-138
Table 12.57: No-Action Escalator Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex... 12-139
Table 12.58: No-Action Passageway Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-139
Table 12.59: No-Action Fare Control Area Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-140
Table 12.60: No-Action Stair Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-141
Table 12.61: No-Action Fare Control Area Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-142
Table 12.62: No-Action Stair Analysis at the Fifth Avenue (7) Subway Station 12-142
Table 12.63: No-Action Fare Control Area Analysis at the Fifth Avenue (7) Subway Station 12-143
Table 12.64: No-Action Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-144
Table 12.65: No-Action Fare Control Area Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-145
Table 12.66: No-Action Stair Analysis at the 51st Street (6) Subway Station 12-146
Table 12.67: No-Action Escalator Analysis at the 51st Street (6) Subway Station 12-146
Table 12.68: No-Action Passageway Analysis at the 51st Street (6) Subway Station 12-146
Table 12.69: No-Action Fare Control Area Analysis at the 51st Street (6) Subway Station 12-147
Table 12.70: No-Action Stair Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-147
Table 12.71: No-Action Escalator Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-148
Table 12.72: No-Action Fare Control Area Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-148
Table 12.73: No-Action Stair Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-149
Table 12.74: No-Action Fare Control Area Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-149
Table 12.75: No-Action Escalator Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station . 12-149
Table 12.76: No-Action Stair Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-150
Table 12.77: No-Action Escalator Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-150
Table 12.78: No-Action Subway Line Haul Analysis 12-152
Table 12.78: No-Action Subway Line Haul Analysis (Continued) 12-153
Table 12.79: No-Action Stair Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-154
Table 12.80: No-Action Escalator Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-154
Table 12.81: No-Action Passageway Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-154
Table 12.82: With-Action Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-157
Table 12.82: With-Action Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station (Continued) 12-158
Table 12.83: With-Action Escalator Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-159
Table 12.84: With-Action Passageway Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-159
Table 12.85: With-Action Fare Control Area Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station... 12-160
Table 12.86: With-Action Stair Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-162
Table 12.87: With-Action Fare Control Area Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station... 12-163
Table 12.88: With-Action Stair Analysis at the Fifth Avenue (7) Subway Station 12-165
Table 12.89: With-Action Fare Control Area Analysis at the Fifth Avenue (7) Subway Station 12-165
Table 12.90: With-Action Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-167

Table 12.90: With-Action Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station (Continued) 12-168
Table 12.91: With-Action Fare Control Area Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-169
Table 12.92: With-Action Stair Analysis at the 51st Street (6) Subway Station 12-171
Table 12.93: With-Action Escalator Analysis at the 51st Street (6) Subway Station 12-171
Table 12.94: With-Action Passageway Analysis at the 51st Street (6) Subway Station 12-172
Table 12.95: With-Action Fare Control Area Analysis at the 51st Street (6) Subway Station 12-172
Table 12.96: With-Action Stair Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-175
Table 12.97: With-Action Escalator Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-176
Table 12.98: With-Action Fare Control Area Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-176
Table 12.99: With-Action Stair Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-178
Table 12.100: With-Action Fare Control Area Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-178
Table 12.101: With-Action Escalator Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-179
Table 12.102: With-Action Stair Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-181
Table 12.103: With-Action Escalator Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-181
Table 12.104: With-Action Subway Line Haul Analysis 12-183
Table 12.104: With-Action Subway Line Haul Analysis (Continued) 12-184
Table 12.105: With-Action Stair Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-186
Table 12.106: With-Action Escalator Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-186
Table 12.107: With-Action Passageway Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-187
Table 12.108: Existing Sidewalk Conditions in the AM Peak Hour 12-189
Table 12.108: Existing Sidewalk Conditions in the AM Peak Hour (Continued) 12-190
Table 12.109: Existing Sidewalk Conditions in the Midday Peak Hour 12-191
Table 12.109: Existing Sidewalk Conditions in the Midday Peak Hour (Continued) 12-192
Table 12.110: Existing Sidewalk Conditions in the PM Peak Hour 12-193
Table 12.110: Existing Sidewalk Conditions in the PM Peak Hour (Continued) 12-194
Table 12.111: Existing Crosswalk Conditions in the AM Peak Hour 12-196
Table 12.112: Existing Crosswalk Conditions in the Midday Peak Hour 12-197
Table 12.113: Existing Crosswalk Conditions in the PM Peak Hour 12-198
Table 12.114: Existing Corner Conditions 12-199
Table 12.114: Existing Corner Conditions (Continued) 12-200
Table 12.114: Existing Corner Conditions (Continued) 12-201
Table 12.115: No-Action Sidewalk Conditions in the AM Peak Hour 12-203
Table 12.115: No-Action Sidewalk Conditions in the AM Peak Hour (Continued) 12-204
Table 12.116: No-Action Sidewalk Conditions in the Midday Peak Hour 12-205
Table 12.116: No-Action Sidewalk Conditions in the Midday Peak Hour (Continued) 12-206
Table 12.117: No-Action Sidewalk Conditions in the PM Peak Hour 12-207
Table 12.117: No-Action Sidewalk Conditions in the PM Peak Hour (Continued) 12-208
Table 12.118: No-Action Crosswalk Conditions in the AM Peak Hour 12-209
Table 12.119: No-Action Crosswalk Conditions in the Midday Peak Hour 12-210
Table 12.120: No-Action Crosswalk Conditions in the PM Peak Hour 12-211
Table 12.121: No-Action Corner Conditions 12-213
Table 12.121: No-Action Corner Conditions (Continued) 12-214
Table 12.121: No-Action Corner Conditions (Continued) 12-215
Table 12.122: With-Action Sidewalk Conditions in the AM Peak Hour 12-219

Table 12.122: With-Action Sidewalk Conditions in the AM Peak Hour (Continued) 12-220
Table 12.123: With-Action Sidewalk Conditions in the Midday Peak Hour 12-221
Table 12.123: With-Action Sidewalk Conditions in the Midday Peak Hour (Continued) 12-222
Table 12.124: With-Action Sidewalk Conditions in the PM Peak Hour 12-223
Table 12.124: With-Action Sidewalk Conditions in the PM Peak Hour (Continued) 12-224
Table 12.125: With-Action Crosswalk Conditions in the AM Peak Hour 12-226
Table 12.126: With-Action Crosswalk Conditions in the Midday Peak Hour 12-227
Table 12.127: With-Action Crosswalk Conditions in the PM Peak Hour 12-228
Table 12.128: With-Action Corner Conditions 12-230
Table 12.128: With-Action Corner Conditions (Continued) 12-231
Table 12.128: With-Action Corner Conditions (Continued) 12-232
Table 12.129: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Action-With-Improvements Condition and Action-Without-Improvements Condition 12-233
Table 12.130: Summary of Motor Vehicle Crash Data, 2012-2014 12-234
Table 12.130: Summary of Motor Vehicle Crash Data, 2012-2014 (Continued) 12-235
Table 12.131: Existing Off-Street Parking Facilities in Study Area 12-243
Table 12.131: Existing Off-Street Parking Facilities in Study Area (Continued) 12-244
Table 12.131: Existing Off-Street Parking Facilities in Study Area (Continued) 12-245
Table 12.131: Existing Off-Street Parking Facilities in Study Area (Continued) 12-246
Table 12.132: Parking Regulation Code Definitions 12-248
Table 12.132: Parking Regulation Code Definitions (Continued) 12-249
Table 12.132: Parking Regulation Code Definitions (Continued) 12-250
Table 12.132: Parking Regulation Code Definitions (Continued) 12-251
Table 12.132: Parking Regulation Code Definitions (Continued) 12-252
Table 12.133: No-Action Condition Off-Street Parking Capacity, Demand, and Utilization 12-254
Table 12.134: With-Action Condition Net Incremental Weekday Hourly Parking Accumulation by Land Use 12-255
Table 12.135: With-Action Condition Off-Street Parking Capacity, Demand, and Utilization 12-256

Chapter 13: Air Quality

Table 13.1: National Ambient Air Quality Standards 13-7
Table 13.2: NYSDEC Air Guideline Concentrations for Non-Criteria Pollutants 13-10
Table 13.3: Background Concentrations for Intersection Analysis 13-14
Table 13.4: Intersection Analysis Sites 13-15
Table 13.5: Cluster Sites for Cumulative HVAC Analysis 13-17
Table 13.6: Background Concentrations for Stationary Sources Analysis 13-23
Table 13.7: Ambient Background Concentrations 13-24
Table 13.8: No-Action Maximum Predicted CO Concentrations (ppm) 13-25
Table 13.9: No-Action Maximum Predicted 24-Hour PM_{10} Concentrations ($\mu g/m^3$) 13-25
Table 13.10: With-Action Maximum Predicted CO Concentrations (ppm) 13-26
Table 13.11: With-Action Maximum Predicted 24-Hour PM_{10} Concentrations ($\mu g/m^3$) 13-26
Table 13.12: Maximum Predicted 24-Hour $PM_{2.5}$ Incremental Concentrations ($\mu g/m^3$) 13-27
Table 13.13: Maximum Predicted Annual $PM_{2.5}$ Incremental Concentrations ($\mu g/m^3$) 13-27
Table 13.14: HVAC Screening Analysis Results 13-30
Table 13.15: Existing Active Industrial Sources Permit Information 13-34
Table 13.16: Maximum Predicted Impacts on Projected and Potential Sites from Industrial Sources 13-35

Table 13.17: Cancer Risk (CR) and Chronic Non-Cancer Hazard Quotients (HQ) and Total Hazard Index (HI) of the Toxic Pollutants 13-38
Table 13.18: Acute Quotients (AHQ) and Total Hazard Index (AHI) of the Toxic Pollutants 13-39
Table 13.19: Emission Rates & Stack Parameters for Existing Power Plant Building 13-39
Table 13.20: Maximum Predicted Concentration (µg/m^3) from Existing Power Plant Building 13-40

Chapter 14: Greenhouse Gas Emissions

Table 14.1: Global Warming Potential for Primary Greenhouse Gases 14-3
Table 14.2: Operational Emissions 14-4
Table 14.3: Proposed Action (RWCDS) Annual Vehicle Miles Traveled (miles per year) 14-5
Table 14.4: Mobile Source Emissions 14-5
Table 14.5: Total GHG Emissions 14-6

Chapter 15: Noise

Table 15.1: Common Noise Levels 15-2
Table 15.2: Noise Exposure Guidelines for Use in City Environmental Quality Review[1] 15-5
Table 15.3: New York City Noise Code 15-6
Table 15.4: Noise Monitoring Site Locations 15-8
Table 15.5: Existing Short-Term Noise Levels (dBA) 15-9
Table 15.6: 2036 No-Action Weekday Noise Levels (dBA) 15-10
Table 15.7: 2036 With-Action Weekday Noise Levels (dBA) 15-12
Table 15.8: Required Attenuation Values to Achieve Acceptable Interior Noise Levels 15-13
Table 15.9: 2036 With-Action Weekday Noise Levels (dBA) 15-14

Chapter 18: Construction

Table 18.1: Quarterly Peak Numbers of Daily Construction Workers and Delivery Trucks (16 Projected Development Sites with New Construction) 18-8
Table 18.2: Total Daily Vehicle Trips During Construction by Quarter 18-11
Table 18.3: 2032 First Quarter Construction-Vehicle Trip Projections (in PCEs) 18-12
Table 18.4: 2032 First Quarter Construction Weekday AM Transit Trips 18-14
Table 18.5: 2032 First Quarter Construction Weekday PM Transit Trips 18-14
Table 18.6: 2032 First Quarter Construction Weekday AM Pedestrian Trips 18-17
Table 18.7: 2032 First Quarter Construction Weekday PM Pedestrian Trips 18-17
Table 18.8: Summary of Significant Adverse Traffic Impacts 18-22
Table 18.9: Ambient Background Concentrations 18-29
Table 18.10 Maximum Predicted Total Concentrations for Construction Activities 18-30
Table 18.11 Construction Equipment Noise Emission Levels (dBA) 18-34
Table 18.11 Construction Equipment Noise Emission Levels (dBA) (Continued) 18-35
Table 18.12: Construction Noise Receptor Locations 18-38
Table 18.13: Existing Short-Term Noise Levels (dBA) 18-39
Table 18.14: Construction Noise Analysis Results (dBA) 18-40
Table 18.15: Vibration Source Levels for Construction Equipment 18-48

Chapter 19: Mitigation

Table 19.1: Summary of Movements/Intersections with Significant Adverse Traffic Impacts 19-4
Table 19.2: Summary of Locations with Significant Adverse Traffic Impacts 19-5
Table 19.2: Summary of Locations with Significant Adverse Traffic Impacts (Continued) 19-6
Table 19.2: Summary of Locations with Significant Adverse Traffic Impacts (Continued) 19-7
Table 19.3 Summary of Elements with Significant Adverse Pedestrian Impacts 19-9
Table 19.4: Unmitigated Pedestrian Impacts 19-11
Table 19.5: 2036 Future with the Proposed Action: Passive Open Space Ratios Summary 19-16
Table 19.6: AM Proposed Traffic Mitigation Measures 19-21
Table 19.7: Midday Proposed Traffic Mitigation Measures 19-25
Table 19.8: PM Proposed Traffic Mitigation Measures 19-28
Table 19.9: AM Level of Service Analysis with and without Proposed Mitigation 19-34
Table 19.10: Midday Level of Service Analysis with and without Proposed Mitigation 19-43
Table 19.11: PM Level of Service Analysis with and without Proposed Mitigation 19-51
Table 19.12: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Action-With-Improvements Condition and Action-Without-Improvements Condition 19-61
Table 19.13: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Action-With-Improvements Condition and Action-Without-Improvements Condition 19-62
Table 19.14: Mitigated With-Action With-Improvements Subway Escalator Analysis at the Grand Central-42nd Street (4, 5, 6, 7, S) Subway Station 19-66
Table 19.15: Mitigated With-Action With-Improvements Subway Escalator Analysis at the Lexington Avenue-53rd Street (E, M) Subway Station 19-66
Table 19.16 Action-With-Mitigation, Sidewalk Conditions 19-68
Table 19.17: Action-With-Mitigation, AM Peak Hour Crosswalk Conditions 19-71
Table 19.18: Action-With-Mitigation: Midday Peak Hour Crosswalk Conditions 19-72
Table 19.19: Action-With-Mitigation: PM Peak Hour Crosswalk Conditions 19-73
Table 19.20: Action-With-Mitigation: AM Peak Hour Corner Conditions 19-75
Table 19.21: Action-With-Mitigation: Midday and PM Peak Hour Corner Conditions 19-76
Table 19.22: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Action-With-Improvements Condition to Action-Without-Improvements Condition 19-77
Table 19.23: Maximum Predicted $PM_{2.5}$ Concentrations ($\mu g/m^3$) with Traffic Mitigation 19-78
Table 19.24: AM Proposed Traffic Mitigation Measures - Construction 19-80
Table 19.25: PM Proposed Traffic Mitigation Measures - Construction 19-81
Table 19.26: AM Level of Service Analysis with and without Proposed Mitigation - Construction 19-82
Table 19.27: PM Level of Service Analysis with and without Proposed Mitigation - Construction 19-83

Chapter 20: Alternatives

Table 20.1: Comparison of Proposed Action and Lesser Density Alternative FARs by Subarea 20-5
Table 20.2: Summary of Level of Service by Movement – No-Action Alternative vs. Proposed Action 20-14
Table 20.2: Summary of Level of Service by Movement – No-Action Alternative vs. Proposed Action (Continued) 20-14
Table 20.3: Summary of Lesser Density Alternative Development Scenario 20-27
Table 20.4: Summary of Lesser Density Alternative Population and Employment 20-27
Table 20.5: Summary of No-Action to With-Action Incremental Development – Proposed Action vs. Lesser Density Alternative 20-27
Table 20.6: Net Difference in Person Trips between the Lesser Density Alternative and the Proposed Action 20-35

Table 20.7: Net Difference in Vehicle Trips between the Lesser Density Alternative and the Proposed Action 20-36
Table 20.8: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Lesser Density Alternative and Proposed Action 20-37
Table 20.9: Number of Subway Station Elements with Significant Adverse Transit Impacts – Comparison of Lesser Density Alternative and Proposed Action 20-38
Table 20.10: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Lesser Density Alternative and Proposed Action 20-40
Table 20.11 – Locations of POPS under Mandatory POPS Alternative 20-46

Chapter 21: Conceptual Analysis

Table 21.1: Comparison of Special Permit Scenario to With-Action RWCDS 21-6
Table 21.2: Conceptual Analysis - Special Permit Scenario 21-9
Table 21.3: Conceptual Analysis - Special Permit Scenario Increment 21-10
Table 21.4: Net Difference in Person Trips between the Special Permit Scenario and the Proposed Action 21-18
Table 21.5: Net Difference in Vehicle Trips between the Special Permit Scenario and the Proposed Action 21-18
Table 21.6: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Special Permit Scenario and Proposed Action 21-20
Table 21.7: Off-Street Parking Capacity, Demand, and Utilization – Comparison of Special Permit Scenario and Proposed Action 21-23

Chapter 25: Amended Application Analysis

Table 25.1: Added Projected and Potential Development Sites with the Amended With-Action Condition 25-8
Table 25.2: Proposed Action Development Scenario 25-9
Table 25.3: Amended With-Action Condition 25-9
Table 25.4: Difference in Proposed Action vs Amended With-Action Condition Increment 25-10
Table 25.5: Summary of Environmental Issues for Projected and Potential Development Sites 25-23
Table 25.6: Net Difference in Person Trips between the Amended With-Action Condition and the Proposed Action .. 25-27
Table 25.7: Net Difference in Vehicle Trips between the Amended With-Action Condition and the Proposed Action .. 25-27
Table 25.8: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Amended Action Without PRI Condition and Proposed Action Without PRI Condition 25-29
Table 25.9: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Amended Action Without PRI Condition and Proposed Action Without PRI Condition 25-30
Table 25.10: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition 25-32
Table 25.11: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition 25-32
Table 25.11: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition (Continued) 25-33
Table 25.12: Net Incremental Peak Hour Subway Trips by Station or Station Complex 25-35
Table 25.13: Net Incremental Peak Hour Local Bus Trips by Route 25-36
Table 25.14: Number of Rezoning Area Express Bus Routes and Estimated Distribution of Net Incremental Peak Hour Express Bus Trips by Borough/County 25-37
Table 25.15: Existing Local Bus Analysis 25-38
Table 25.16: No-Action Local Bus Analysis 25-39
Table 25.17: Amended With-Action Condition Local Bus Analysis 25-39

Table 25.18: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Amended Action Without PRI Condition and Proposed Action Without PRI Condition 25-41
Table 25.19: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition 25-42
Table 25.20: Off-Street Parking Capacity, Demand, and Utilization – Comparison of Amended With-Action Condition and Proposed Action 25-42
Table 25.21: Maximum Predicted 24-Hour PM_{10} Concentrations (µg/m^3) 25-44
Table 25.22: Maximum Predicted 24-Hour $PM_{2.5}$ Incremental Concentrations (µg/m^3) 25-45
Table 25.23: Maximum Predicted Annual $PM_{2.5}$ Incremental Concentrations (µg/m^3) 25-45
Table 25.24: Amended Noise Monitoring Site Locations 25-48
Table 25.25: Amended Existing Short-Term Noise Levels (dBA) 25-49
Table 25.26: Amended 2036 No-Action Weekday Noise Levels (dBA) 25-49
Table 25.27: Amended 2036 With-Action Weekday Noise Levels (dBA) 25-49
Table 25.28: Amended 2036 With-Action Weekday Noise Levels (dBA) 25-50
Table 25.30: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Amended Action Without PRI Condition and Proposed Action Without PRI Condition 25-60
Table 25.31: Summary of Locations with Different Significant Adverse Traffic Impacts – Amended Action Without PRI Condition and Proposed Action Without PRI Condition 25-61
Table 25.32: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition 25-63
Table 25.33: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition 25-64
Table 25.33: Summary of Locations with Different Significant Adverse Traffic Impacts – Comparison of Amended Action With PRI Condition and Amended Action Without PRI Condition (Continued) 25-65
Table 25.34: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Amended Action Without PRI Condition to Proposed Action Without PRI Condition 25-66
Table 25.35: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Amended Action With PRI Condition to Amended Action Without PRI Condition 25-67
Table 25.36: Maximum Predicted 24-Hour $PM_{2.5}$ Incremental Concentrations (µg/m^3) 25-68
Table 25.37: Maximum Predicted Annual $PM_{2.5}$ Incremental Concentrations (µg/m^3) 25-68

List of Figures

Executive Summary

Following Page:

Figure S-1: Proposed Rezoning Area S-1
Figure S-2: Proposed Subdistricts S-10
Figure S-3: Public Realm Improvements S-12
Figure S-4: Pedestrian Plaza Illustration S-14
Figure S-5: Park Avenue Improvements S-14
Figure S-6: Existing Zoning S-16
Figure S-6: Proposed Zoning Amendment S-17
Figure S-8: Proposed Rezoning Area RWDCS Sites S-17

Chapter 1: Project Description

Figure 1-1: Proposed Rezoning Area 1-1
Figure 1-2: Proposed Subdistricts 1-14
Figure 1-3: Public Realm Improvements 1-16
Figure 1-4: Pedestrian Plaza Illustration 1-17
Figure 1-5: Park Avenue Improvements 1-17
Figure 1-6: Existing Zoning 1-21
Figure 1-7: Proposed Zoning Amendments 1-21
Figure 1-8: Proposed Rezoning Area RWCDS Sites 1-23

Chapter 2: Land Use

Figure 2-1: Land Use and Zoning Study and Analysis Areas (Primary and Secondary) 2-2
Figure 2-2: Coastal Zone Boundary 2-2
Figure 2-3: Primary Study Area Existing Land Use 2-4
Figure 2-4: Secondary Study Area Existing Land Use 2-6
Figure 2-5: Existing Zoning 2-10
Figure 2-6: Special Midtown District and Subdistricts 2-12
Figure 2-7: Historic Resources 2-18
Figure 2-8: Business Improvement Districts 2-18
Figure 2-9: No Build Development Projects 2-20
Figure 2-10: Proposed Zoning Amendments 2-24
Figure 2-11: Proposed FAR Subareas 2-24

Chapter 3: Socioeconomic Conditions

Figure 3-1: Socioeconomics Study Area 3-6
Figure 3-2: Office Submarket Boundaries 3-16
Figure 3.3: Office Buildings by Year Built 3-18
Figure 3.4: Office Buildings by Floorspace 3-19

Figure 3.5: Hotel Locations 3-31

Chapter 4: Open Space

Figure 4-1: Open Space Study Area 4-5
Figure 4-2: Existing Open Space Inventory 4-11
Figure 4-3: Open Space Resources in the No-Action Condition 4-25
Figure 4-4: Open Space Resources Observed Utilization Levels 4-31

Chapter 5: Shadows

Figure 5-1: Open Spaces and Historic Resources within the Maximum Shadow Radius (Tiers 1 and 2) 5-3
Figure 5-2a: P3 December Detailed Shadows Analysis 5-59
Figure 5-2b: P3 March Detailed Shadows Analysis 5-59
Figure 5-2c: P3 May Detailed Shadows Analysis 5-59
Figure 5-2d: P3 June Detailed Shadows Analysis 5-59
Figure 5-3a: P5 March Detailed Shadows Analysis 5-59
Figure 5-3b: P5 May Detailed Shadows Analysis 5-59
Figure 5-3c: P5 June Detailed Shadows Analysis 5-59
Figure 5-4a: P15 December Detailed Shadows Analysis 5-59
Figure 5-4b: P15 March Detailed Shadows Analysis 5-59
Figure 5-4c: P15 May Detailed Shadows Analysis 5-59
Figure 5-4d: P15 May Detailed Shadows Analysis Base 5-59
Figure 5-5: P25N May Detailed Shadows Analysis 5-59
Figure 5-6a: P27 March Detailed Shadows Analysis 5-59
Figure 5-6b: P27 May Detailed Shadows Analysis 5-59
Figure 5-6c: P27 June Detailed Shadows Analysis 5-59
Figure 5-7a: P28 March Detailed Shadows Analysis 5-59
Figure 5-7b: P28 May Detailed Shadows Analysis 5-59
Figure 5-7c: P28 June Detailed Shadows Analysis Base 5-59
Figure 5-8: P30 May Detailed Shadows Analysis 5-59
Figure 5-9a: P31 December Detailed Shadows Analysis 5-59
Figure 5-9b: P 31 March Detailed Shadows Analysis 5-59
Figure 5-9c: P31 May Detailed Shadows Analysis 5-59
Figure 5-10: POPS No. 2 Detailed Shadow Analysis 5-59
Figure 5-11: POPS No. 3 Detailed Shadow Analysis 5-59
Figure 5-12: POPS No. 4 Detailed Shadow Analysis 5-59
Figure 5-13: POPS No. 5 Detailed Shadows Analysis 5-59
Figure 5-14: POPS No. 6 Detailed Shadows Analysis 5-59
Figure 5-15: POPS No. 8 Detailed Shadows Analysis 5-59
Figure 5-16: POPS No. 9 Detailed Shadows Analysis 5-59
Figure 5-17: POPS No. 10 Detailed Shadows Analysis 5-59
Figure 5-18: POPS No. 11 Detailed Shadows Analysis 5-59
Figure 5-19: POPS No. 12 Detailed Shadows Analysis 5-59
Figure 5-20: POPS No. 13 Detailed Shadows Analysis 5-59
Figure 5-21: POPS No. 15 Detailed Shadows Analysis 5-59

Figure 5-22: POPS No. 16 Detailed Shadows Analysis 5-59
Figure 5-23: POPS No. 17 Detailed Shadows Analysis 5-59
Figure 5-24: POPS No. 18 Detailed Shadows Analysis 5-59
Figure 5-25: POPS No. 19 Detailed Shadows Analysis 5-59
Figure 5-26: POPS No. 20 Detailed Shadows Analysis 5-59
Figure 5-27: POPS No. 21 Detailed Shadows Analysis 5-59
Figure 5-28: POPS No. 22 Detailed Shadows Analysis 5-59
Figure 5-29: POPS No. 23 Detailed Shadows Analysis 5-59
Figure 5-30: POPS No. 24 Detailed Shadows Analysis 5-59
Figure 5-31: POPS No. 25 Detailed Shadows Analysis 5-59
Figure 5-32: POPS No. 26 Detailed Shadows Analysis 5-59
Figure 5-33: POPS No. 27 Detailed Shadows Analysis 5-59
Figure 5-34: POPS No. 28 Detailed Shadows Analysis 5-59
Figure 5-35: POPS No. 30 Detailed Shadows Analysis 5-59
Figure 5-36: POPS No. 31 Detailed Shadows Analysis 5-59
Figure 5-37: POPS No. 32 Detailed Shadows Analysis 5-59
Figure 5-38: POPS No. 33 Detailed Shadows Analysis 5-59
Figure 5-39: POPS No. 48 Detailed Shadows Analysis 5-59
Figure 5-40: POPS No. 62 Detailed Shadows Analysis 5-59
Figure 5-41: POPS No. 63 Detailed Shadows Analysis 5-59
Figure 5-42: POPS No. 66 Detailed Shadows Analysis 5-59
Figure 5-43: POPS No. 68 Detailed Shadows Analysis 5-59
Figure 5-44: POPS No. 70 Detailed Shadows Analysis 5-59
Figure 5-45: POPS No. 72 Detailed Shadows Analysis 5-59
Figure 5-46: POPS No. 82 Detailed Shadows Analysis 5-59
Figure 5-47: POPS No. 83 Detailed Shadows Analysis 5-59
Figure 5-48a: POPS No. 84 Detailed Shadows Analysis 5-59
Figure 5-48b: Greenacre Park Site Plan Map 5-59
Figure 5-48c: Greenacre Park May 6 Duration 1 Site Plan 5-59
Figure 5-48d: Greenacre Park May 6 Duration 2 Site Plan 5-59
Figure 5-48e: Greenacre Park June 21 Site Plan 5-59
Figure 5-48f: Greenacre Park Site Photographs 5-59
Figure 5-49: POPS No. 85 Detailed Shadows Analysis 5-59
Figure 5-50: POPS No. 103 Detailed Shadows Analysis 5-59
Figure 5-51: POPS No. 143 Detailed Shadows Analysis 5-59
Figure 5-52: H1 December Detailed Shadows Analysis 5-59
Figure 5-53a: H2 March Detailed Shadows Analysis 5-59
Figure 5-53b: H2 May Detailed Shadows Analysis 5-59
Figure 5-53c: H2 June Detailed Shadows Analysis Base 5-59
Figure 5-54a: H3 May Detailed Shadows Analysis 5-59
Figure 5-54b: H3 June Detailed Shadows Analysis 5-59
Figure 5-55a: H5 May Detailed Shadows Analysis 5-59
Figure 5-55b: H5 June Detailed Shadows Analysis 5-59
Figure 5-56a: H6 December Detailed Shadows Analysis 5-59
Figure 5-56b: H6 March Detailed Shadows Analysis 5-59
Figure 5-56c: H6 May Detailed Shadows Analysis 5-59
Figure 5-56d: H6 June Detailed Shadows Analysis 5-59
Figure 5-57: H12 May Detailed Shadows Analysis 5-59

Figure 5-58a: H14 December Detailed Shadows Analysis 5-59
Figure 5-58b: H14 March Detailed Shadows Analysis 5-59
Figure 5-58c: H14 June Detailed Shadows Analysis 5-59
Figure 5-59a: H15 May Detailed Shadows Analysis 5-59
Figure 5-59b: H15 June Detailed Shadows Analysis 5-59
Figure 5-60: H17 December Detailed Shadows Analysis 5-59
Figure 5-61a: H18 March Detailed Shadows Analysis Base 5-59
Figure 5-61b: H18 May Detailed Shadows Analysis Base 5-59
Figure 5-62a: H19 March Detailed Shadows Analysis Base 5-59
Figure 5-62b: H19 May Detailed Shadows Analysis Base 5-59
Figure 5-62c: H19 June Detailed Shadows Analysis Base 5-59
Figure 5-63a: H20 December Detailed Shadows Analysis 5-59
Figure 5-63b: H20 March Detailed Shadows Analysis 5-59
Figure 5-63c: H20 May Detailed Shadows Analysis 5-59
Figure 5-63d: H20 June Detailed Shadows Analysis 5-59
Figure 5-64: H21 Dec Detailed Shadows Analysis Base 5-59
Figure 5-65a: H22 Dec Detailed Shadows Analysis Base 5-59
Figure 5-65b: H22 May Detailed Shadows Analysis Base 5-59
Figure 5-65c: H22 June Detailed Shadows Analysis Base 5-59
Figure 5-66: P4 December 21 Analysis Period 5-59
Figure 5-67: ODR Esplanade June 21 Analysis Period Base 5-59
Figure 5-68: POPS No. 147 Detailed Shadows Analysis Base 5-59
Figure 5-69: H17 December Detailed Shadows Analaysis Base 5-59

Chapter 6: Historic and Cultural Resources

Figure 6-1: Historic Resources Study Area and RWCDS Sites 6-1
Figure 6-2: Designated Historic Districts 6-7
Figure 6-3: Representative Photographs of Designated Historic Districts and Resources 6-7
Figure 6-4: Designated Historic Landmarks 6-7
Figure 6-5: Eligible Historic Districts and Landmarks 6-7
Figure 6-6: Representative Photographs of Eligible Historic Resources in the Project Area 6-7
Figure 6-7: Designated Historic Districts and Landmarks, and RWCDS Sites 6-7
Figure 6-8: Eligible Historic Districts and Landmarks, and RWCDS Sites 6-7

Chapter 7: Urban Design and Visual References

Figure 7-1: Urban Design and Visual Resources Primary Study Area - Aerial View 7-5
Figure 7-2: Urban Design Primary and Secondary Study Areas 7-6
Figure 7-3: Existing Density in Primary and Secondary Study Areas 7-8
Figure 7-4: Existing Building Height (Number of Floors) in Primary and Secondary Study Areas 7-8
Figure 7-5a: Views of the Built Context within the Primary Study Area Key Map 7-8
Figure 7-5b: Views of the Built Context within the Primary Study Area 7-8
Figure 7-6a: Views of the Built Context within the Secondary Study Area Key Map 7-22
Figure 7-6b: Views of the Built Context within the Secondary Study Area 7-22
Figure 7-7: Development and Transportation Projects in the Future without the Proposed Action 7-33

Figure 7-8: Urban Design Primary and Secondary Study Areas 7-44
Figure 7-9a: Public Realm Improvements 7-50
Figure 7-9b: Pedestrian Plaza Illustration 7-50
Figure 7-9c: Park Avenue Improvements 7-50
Figure 7-10: Visual Resources and Photo Key for Visual Resources Figures 7-55
Figure 7-11: Visual Resources Photographs 7-55

Chapter 9: Water and Sewer Infrastructure

Figure 9-1: Subcatchment Areas Map 9-6

Chapter 12: Transportation

Figure 12-1: Proposed Rezoning Area RWCDS Sites 12-1
Figure 12-2: Traffic Analysis Locations 12-16
Figure 12-3: Study Area Subway Stations 12-16
Figure 12-4: Study Area Local Bus Routes 12-18
Figure 12-5: Study Area Express Bus Routes 12-18
Figure 12-6: Pedestrian Study Areas 12-22
Figure 12-7a: 2016 Existing Traffic Volumes Weekday AM Peak Hour 12-35
Figure 12-7b: 2016 Existing Traffic Volumes Weekday AM Peak Hour 12-35
Figure 12-8a: 2016 Existing Traffic Volumes Weekday Midday Peak Hour 12-35
Figure 12-8b: 2016 Existing Traffic Volumes Weekday Midday Peak Hour 12-35
Figure 12-9a: 2016 Existing Traffic Volumes Weekday PM Peak Hour 12-35
Figure 12-9b: 2016 Existing Traffic Volumes Weekday PM Peak Hour 12-35
Figure 12-10a: 2036 No-Action Traffic Volumes Weekday AM Peak Hour 12-62
Figure 12-10b: 2036 No-Action Traffic Volumes Weekday AM Peak Hour 12-62
Figure 12-11a: 2036 No-Action Traffic Volumes Weekday Midday Peak Hour 12-62
Figure 12-11b: 2036 No-Action Traffic Volumes Weekday Midday Peak Hour 12-62
Figure 12-12a: 2036 No-Action Traffic Volumes Weekday PM Peak Hour 12-62
Figure 12-12b: 2036 No-Action Traffic Volumes Weekday PM Peak Hour 12-62
Figure 12-13a: Project Generated Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-13b: Project Generated Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-14a: Project Generated Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-14b: Project Generated Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-15a: Project Generated Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-15b: Project Generated Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-16a: 2036 With-Action Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-16b: 2036 With-Action Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-17a: 2036 With-Action Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-17b: 2036 With-Action Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-18a: 2036 With-Action Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-18b: 2036 With-Action Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-19: Impacted Intersections Weekday AM Peak Hour 12-98
Figure 12-20: Impacted Intersections Weekday Midday Peak Hour 12-98
Figure 12-21: Impacted Intersections Weekday PM Peak Hour 12-98

Figure 12-22: Grand Central 42nd Street Subway Station Complex—Lexington Avenue Line and Shuttle Mezzanine 12-100
Figure 12-23: Grand Central 42nd Street Subway Station Complex—Flushing Line 12-101
Figure 12-24: 42nd Street-Bryant Park/Fifth Avenue Subway Station Complex 12-106
Figure 12-25: 47th-50th Streets-Rockefeller Center Subway Station 12-110
Figure 12-26: 51st Street/Lexington Avenue-53rd Street Subway Station Complex 12-114
Figure 12-27: Lexington Avenue-59th Street Subway Station 12-118
Figure 12-28: Fifth Avenue-53rd Street Subway Station 12-120
Figure 12-29: Grand Central Terminal 47th Street Crosspassage 12-123
Figure 12-30: Grand Central Terminal 47th Street Crosspassage in No-Action Condition 12-147
Figure 12-31: Off-Street Parking Facilities 12-239
Figure 12-32a: Off-Street Parking Regulations 12-243
Figure 12-32b: Off-Street Parking Regulations 12-243

Chapter 13: Air Quality

Figure 13-1: Air Quality Mobile Sources Analysis Sites 13-14

Chapter 15: Noise

Figure 15-1: Noise Receptor Locations 15-6

Chapter 17: Neighborhood Character

Figure 17-1: Study and Analysis Areas (Primary and Secondary) ..... Figure 17-3

Chapter 18: Construction

Figure 18-1a: Construction Schedule: 2019-2028 18-6
Figure 18-1b: Construction Schedule: 2026-2036 18-6
Figure 18-2: Traffic Analysis Locations 18-21
Figure 18-3: Construction Air Quality Analysis Clusters 18-26
Figure 18-4: Projected Peak Daily PM2.5 Construction Emissions Profile by Quarter 18-26
Figure 18-5: Projected Annual PM2.5 Construction Emissions Profile 18-26
Figure 18-6a: Noise Monitoring and Receptor Sites 18-35
Figure 18-6b: Noise Monitoring and Receptor Sites 18-35
Figure 18-7a: Site 4-5 Construction Noise Contour 18-40
Figure 18-7b: Site 15 Construction Noise Contour 18-40

Chapter 19: Mitigation

Figure 19-1: With-Action Intersection Mitigation Weekday AM Peak Hour 19-33
Figure 19-2: With-Action Intersection Mitigation Weekday Midday Peak Hour 19-33
Figure 19-3: With-Action Intersection Mitigation Weekday PM Peak Hour 19-33

Chapter 20: Alternatives

Figure 20-1: Lesser Density Alternatives Subdistricts and Sites..... 20-4

Chapter 21: Conceptual Analysis

Figure 21-1: RWCDS Sites for Conceptual Analysis 21-4

Chapter 25: Amended Application

Figure 25-1: RWCDS Map 25-4
Figure 25-2: UD Figure 1 25-4
Figure 25-3: UD Figure 2 25-4
Figure 25-4: Air Quality Mobile Source Analysis Sites Map..... 25-4
Figure 25-5: Noise Receptor Location 25-4
Figure 25-6a: Construction Schedule 2019-2029 25-4
Figure 25-6b: Construction Schedule 2026-2036 25-4