SAINT VINCENTS CAMPUS REDEVELOPMENT

Draft Environmental Impact Statement	CEQR No.: 10DCP003M

Lead Agency:
City Planning Commision, City of New York
Amanda M. Burden, FAICP, *Chair*

Prepared by:
AKRF, Inc.

August 2011

DRAFT ENVIRONMENTAL IMPACT STATEMENT
For
SAINT VINCENTS CAMPUS REDEVELOPMENT
August 19, 2011

CEQR No.: 10DCP003M
ULURP Nos.: 120029ZSM
120030ZSM
120031ZSM
N120032ZRM
120033ZMM

ACTION LOCATION:
Manhattan, New York

LEAD AGENCY:

City Planning Commission
City of New York
Amanda M. Burden, FAICP, Chair

LEAD AGENCY CONTACT:

Robert Dobruskin, AICP, Director
Environmental Assessment and Review Division
New York City Department of City Planning
22 Reade Street, Room 4E
New York, NY 10007
(212) 720-3423

PREPARED BY:

AKRF, Inc.

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

Table of Contents

Executive Summary **S-1**

1: Project Description **1-1**
A. Introduction 1-1
B. History and Site Conditions 1-2
North Shore Long Island Jewish Health System 1-4
C. Purpose and Need for the Proposed East Site Project 1-4
East Site 1-4
Triangle Site 1-4
D. Purpose and Need for the Center for Comprehensive Care 1-5
E. Proposed Project Approvals 1-5
Approvals for the Proposed East Site Project 1-5
Approvals for the Center for Comprehensive Care 1-9
F. Project Description 1-9
Proposed East Site Project 1-9
Center for Comprehensive Care 1-10
G. Environmental Review 1-11
H. Uniform Land Use Review Procedure 1-12
I. Framework for Analysis 1-13
Scope of Environmental Analysis 1-13
Baseline Conditions 1-14
Probable Impacts of the Proposed Projects 1-15

2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
Principal Conclusions 2-1
B. Methodology 2-3
C. Background and Development History 2-4
D. Existing Conditions 2-5
Land Use 2-5
Zoning 2-6
E. The Future Without the Proposed Projects 2-11
Land Use 2-11
Zoning 2-13
Public Policy 2-13
F. Probable Impacts of the Proposed Projects 2-13
Land Use 2-13
Zoning 2-14
Public Policy 2-17

3: Socioeconomic Conditions 3-1
A. Introduction 3-1
Principal Conclusions 3-1
B. Methodology 3-2
Determining Whether A Socioeconomic Assessment Is Appropriate 3-3
Analysis Format 3-4
Study Area Delineation 3-4
Data Sources 3-4
C. Preliminary Assessment 3-5
Direct Residential Displacement 3-5
Direct Business and Institutional Displacement 3-5
Indirect Residential Displacement 3-5
Indirect Business and Institutional Displacement 3-10
Adverse Effects On Specific Industries 3-13

4: Community Facilities and Services 4-1
A. Introduction 4-1
Principal Conclusions 4-1
B. Preliminary Screening 4-2
Direct Effects 4-2
Indirect Effects 4-2
C. Direct Effects On Health Care Services 4-4
D. Indirect Effects On Public Schools 4-4
Methodology 4-4
Existing Conditions 4-6
The Future Without the Proposed Projects 4-7
Probable Impacts of the Proposed Projects 4-9

5: Open Space 5-1
A. Introduction 5-1
Principal Conclusions 5-1
B. Methodology 5-2
Direct Effects Analysis 5-2
Indirect Effects Analysis 5-3
C. Preliminary Assessment 5-5
Existing Conditions 5-6
The Future Without the Proposed Projects 5-11
Probable Impacts of the Proposed Projects 5-12

6: Shadows 6-1
A. Introduction 6-1
Principal Conclusions 6-1
B. Definitions and Methodology 6-1
Definitions 6-1
Methodology 6-2
C. Preliminary Screening Assessment 6-3
Tier 1 Screening Assessment 6-3
Tier 2 Screening Assessment 6-4

Open Space Resources of Concern 6-4
Historic Resources of Concern 6-4
D. Detailed Analysis 6-5
Analysis Framework 6-5
Analysis Results 6-6

7: Historic and Cultural Resources 7-1
A. Introduction 7-1
Principal Conclusions 7-2
B. Methodology 7-3
Archaeological Resources 7-3
Architectural Resources 7-3
C. Existing Conditions 7-5
Project Area 7-5
Study Area 7-8
D. The Future Without the Proposed Projects 7-11
No Build Projects 7-12
E. Probable Impacts of the Proposed Projects 7-12
Project Area 7-12
Study Area 7-17

8: Urban Design and Visual Resources 8-1
A. Introduction 8-1
Principal Conclusions 8-1
B. Methodology 8-5
B. Existing Conditions 8-6
Project Area 8-6
Study Area 8-12
C. The Future Without the Proposed Projects 8-17
Project Area 8-17
Other Future Projects 8-18
D. Probable Impacts of the Proposed Projects 8-18
Project Area 8-18
Study Area 8-24

9: Natural Resources 9-1

10: Hazardous Materials 10-1
A. Introduction 10-1
Principal Conclusions 10-1
B. Potential Contaminants of Concern 10-2
C. Existing Conditions 10-4
Topography, Geology, and Groundwater 10-4
Environmental Investigations 10-4
D. The Future Without the Proposed Projects 10-8
E. Probable Impacts of the Proposed Projects 10-9
Remedial Action Plan 10-10
Construction Health and Safety Plan 10-11

11: Water and Sewer Infrastructure 11-1
A. Introduction 11-1
Principal Conclusions 11-1
B. Water Supply 11-1
C. Wastewater and Stormwater Conveyance and Treatment 11-2
D. Industrial Pretreatment Program (IPP) 11-2

12: Solid Waste and Sanitation Services 12-1
A. Introduction 12-1
Principal Conclusions 12-1
B. Existing Conditions 12-1
Description of Current Solid Waste Sanitation Services 12-1
Solid Waste Generation 12-2
C. The Future Without the Proposed Projects 12-3
D. Probable Impacts of the Proposed Projects 12-3

13: Energy 13-1
A. Introduction 13-1
Principal Conclusions 13-1
B. Energy Supply 13-2
C. Operational Energy Consumption 13-2

14: Transportation 14-1
A. Introduction 14-1
Principal Conclusions 14-1
B. Preliminary Analysis Methodology 14-2
C. Evaluation Parameters 14-3
The Future Without the Proposed Projects (No Build Condition) 14-3
The Future With the Proposed Projects (Build Condition) 14-3
D. Level 1 Screening Assessment 14-4
Travel Demand Assumptions 14-4
Trip Generation Estimates 14-7
Level 1 Screening 14-8
E. Level 2 Screening Assessment 14-9
Traffic 14-9
Pedestrians 14-10
Access and Circulation 14-11
F. Pedestrian Analysis Methodology 14-12
Significant Impact Criteria 14-13
G. Pedestrian Analysis 14-15
Pedestrian Study Area 14-15
Baseline Conditions 14-16
The Future Without the Proposed Projects (No Build Condition) 14-17
The Future With the Proposed Projects (Build Condition) 14-18
H. Vehicular and Pedestrian Safety 14-19
I. Parking Supply and Demand 14-25
Existing Conditions 14-25
The Future Without the Proposed Projects (No Build Condition) 14-26

The Future With the Proposed Projects (Build Condition) 14-26

15: Air Quality 15-1
A. Introduction 15-1
Principal Conclusions 15-1
B. Pollutants for Analysis 15-1
Carbon Monoxide 15-2
Nitrogen Oxides, VOCs, and Ozone 15-2
Lead 15-3
Respirable Particulate Matter—PM_{10} and $PM_{2.5}$ 15-3
Sulfur Dioxide 15-4
C. Air Quality Regulations, Standards, and Benchmarks 15-4
National and State Air Quality Standards 15-4
NAAQS Attainment Status and State Implementation Plans 15-5
Determining the Significance of Air Quality Impacts 15-7
D. Methodology for Predicting Pollutant Concentrations 15-9
Mobile Sources 15-9
Parking Garage 15-9
Stationary Sources 15-10
E. Existing Conditions 15-14
F. The Future Without the Proposed Projects 15-14
G. Probable Impacts of the Proposed Projects 15-15
Parking Garage 15-15
Stationary Sources 15-15

16: Greenhouse Gas Emissions 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Pollutants of Concern 16-2
C. Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 16-3
D. Methodology 16-5
Building Operational Emissions 16-6
Mobile Source Emissions 16-6
Construction Emissions 16-7
Emissions from Solid Waste Management 16-7
E. Projected GHG Emissions from the Proposed Projects 16-7
Building Operational Emissions 16-7
Mobile Source Emissions 16-8
Construction Emissions 16-8
Emissions from Solid Waste Management 16-8
Summary 16-9
F. Elements of the Proposed Projects That Would Reduce GHG Emissions 16-9
Build Efficient Buildings 16-10
Use Clean Power 16-10
Transit-Oriented Development and Sustainable Transportation 16-11
Reduce Construction Operation Emissions 16-11
Use Building Materials With Low Carbon Intensity 16-11
Conclusion 16-11

17: Noise 17-1
A. Introduction 17-1
Principal Conclusions 17-1
B. Acoustical Fundamentals 17-1
A-Weighted Sound Level (dBA) 17-1
Effects of Distance On Sound 17-2
Sound Level Descriptors 17-3
C. Noise Standards and Criteria 17-3
New York CEQR Noise Standards 17-3
D. Existing Noise Levels 17-5
E. The Future Without the Proposed Projects 17-7
F. Probable Impacts of the Proposed Projects 17-7
Noise Levels At Triangle Site Open Space 17-8
Noise Attenuation Measures 17-8

18: Public Health 18-1
A. Introduction 18-1
Principal Conclusions 18-1
B. Public Health Assessment—Construction Noise 18-1

19: Neighborhood Character 19-1
A. Introduction 19-1
Principal Conclusions 19-1
B. Methodology 19-2
Neighborhood Character Components 19-2
Study Area 19-3
C. Existing Conditions 19-3
Project Area 19-3
Study Area 19-5
D. The Future Without the Proposed Projects 19-6
Project Area 19-6
Study Area 19-6
E. Probable Impacts of the Proposed Projects 19-7
Project Area 19-7
Study Area 19-8

20: Construction Impacts 20-1
A. Introduction 20-1
Principal Conclusions 20-2
B. Methodology 20-8
C. Construction Phasing and Activities 20-8
Introduction 20-8
Construction Overview 20-9
Center for Comprehensive Care Construction Activities 20-10
East Site Construction Activities 20-13
Triangle Site 20-17
General Construction Practices 20-18
Number of Construction Workers and Material Deliveries 20-21

C. The Future Without the Proposed Projects 20-22
D. Probable Impacts of the Proposed Projects 20-22
Transportation 20-23
Air Quality 20-29
Noise and Vibration 20-43
Determining Existing and No Build Noise Levels 20-63

21: Alternatives 21-1
A. Introduction 21-1
B. Principal Conclusions 21-1
C. Alternatives Considered But Not Analyzed 21-2
D. No Action Alternative 21-7
Description of the No Action Alternative 21-7
Land Use, Zoning, and Public Policy 21-7
Socioeconomic Conditions 21-8
Community Facilities 21-9
Open Space 21-9
Shadows 21-10
Historic and Cultural Resources 21-10
Urban Design and Visual Resources 21-10
Natural Resources 21-11
Hazardous Materials 21-11
Water and Sewer Infrastructure 21-12
Solid Waste and Sanitation Services 21-12
Energy 21-12
Transportation 21-12
Air Quality 21-13
Greenhouse Gas Emissions 21-13
Noise 21-13
Public Health 21-13
Neighborhood Character 21-14
Construction Impacts 21-14
E. No Unmitigated Impact Alternative 21-15
F. No Action Alternative With East Site Reuse 21-16
Description of the No Action Alternative With East Site Reuse 21-16
Land Use, Zoning, and Public Policy 21-17
Socioeconomic Conditions 21-18
Community Facilities 21-19
Open Space 21-19
Shadows 21-19
Historic and Cultural Resources 21-19
Urban Design and Visual Resources 21-20
Natural Resources 21-21
Hazardous Materials 21-21
Water and Sewer Infrastructure 21-21
Solid Waste and Sanitation Services 21-21
Energy 21-22
Transportation 21-22

Air Quality 21-24
Greenhouse Gas Emissions 21-24
Noise 21-24
Public Health 21-25
Neighborhood Character 21-25
Construction Impacts 21-25
G. Community Facility Use in Materials Handling Facility Alternative 21-27
Description 21-27
Land Use, Zoning and Public Policy 21-28
Socioeconomic Conditions 21-28
Community Facilities and Services 21-28
Open Space 21-29
Shadows 21-29
Historic Resources 21-29
Urban Design and Visual Resources 21-29
Natural Resources 21-30
Hazardous Materials 21-30
Water and Sewer Infrastructure 21-30
Solid Waste and Sanitation 21-30
Energy 21-30
Transportation 21-30
Air Quality 21-31
Greenhouse Gas 21-31
Noise 21-31
Public Health 21-32
Neighborhood Character 21-32
Construction Impacts 21-32

22: Mitigation Measures 22-1
A. Introduction 22-1
B. Noise Impacts During Construction 22-1

23: Unavoidable Adverse Impacts 23-1

24: Growth-Inducing Aspects of the Proposed Projects 24-1

25: Irreversible and Irretrievable Commitments of Resources 25-1

APPENDICES (CD Only)

Appendix A Proposed Zoning Text Amendment

Appendix B Agency Correspondence

Appendix C Air Quality

Appendix D Construction Impacts

List of Tables

1-1 Former Saint Vincent's Hospital Buildings 1-3

1-2 Comparison of Existing, No Build and Build Conditions 1-13

2-1 Existing Zoning Districts in ¼-Mile Study Area 2-8

2-2 Developments Planned, In Construction or Recently Completed in the Vicinity of the Project Area 2-12

3-1 Population and Income Characteristics Study Area, Borough of Manhattan, and New York City 3-6

3-2 Housing Unit Characteristics Study Area, Manhattan, and New York City 3-7

3-3 Households and Housing Value Characteristics Study Area, Manhattan, and New York City 3-7

3-4 Recent Condominium Sales Prices in the Study Area 3-8

3-5 Estimated Study Area Businesses in 2010 Study Area, Manhattan, and New York City ... 3-11

3-6 Employees in 2010 Study Area, Borough of Manhattan, and New York City 3-13

4-1 Preliminary Screening Analysis Criteria 4-3

4-2 Public Elementary and Intermediate Schools Serving the Study Area Enrollment and Capacity Data, 2009-2010 School Year 4-6

4-3 Projected New Housing Units and Estimated Number of Students Introduced in the Study Area: 2015 Future Without the Proposed Projects 4-8

4-4 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization: 2015 Future Without the Proposed Projects 4-9

4-5 Estimated Number of Students Introduced in the Study Areas: 2015 Future With the Proposed Projects 4-10

4-6 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization: 2015 Future With the Proposed Projects 4-10

5-1 2015 Future With the Proposed Projects: Open Space Ratios Summary 5-2

5-2 Existing Residential Population 5-6

5-3 Study Area Open Space Inventory 5-7

5-4 Existing Conditions: Adequacy of Open Space Resources 5-10

5-5 Future Without the Proposed Projects: Adequacy of Open Space Resources 5-11

5-6 Future With the Proposed Projects: Adequacy of Open Space Resources 5-12

5-7 2015 Future With the Proposed Projects: Open Space Ratios Summary 5-13
6-1 Incremental Shadow Durations 6-6
7-1 Former Saint Vincent's Hospital Buildings 7-5
12-1 Solid Waste Generation: Existing Conditions 12-2
12-2 Solid Waste Generation: the Future Without the Proposed Projects 12-3
12-3 Solid Waste Generation: the Future With the Proposed Projects 12-4
13-1 Estimated Operational Energy Demand (Million BTU Per Year) 13-3
14-1 NSLIJ Center for Comprehensive Care Population Breakdown 14-4
14-2 No Build Travel Demand Assumptions 14-5
14-3 Build Travel Demand Assumptions 14-6
14-4 Trip Generation Summary: No Build Condition 14-7
14-5 Trip Generation Summary: Build Condition 14-8
14-6 Trip Generation Summary: Net East Site Project and Center for Comprehensive Care Increments 14-8
14-7 Analysis Locations Exceeding 200 Pedestrian Trips 14-10
14-8 Level of Service Criteria for Pedestrian Elements 14-13
14-9 Significant Impact Guidance for Sidewalks 14-14
14-10 Significant Impact Guidance for Corners and Crosswalks 14-15
14-11 Baseline (2007) Conditions Sidewalk Analysis 14-16
14-12 Baseline (2007) Conditions Corner Analysis 14-17
14-13 2015 No Build Condition Sidewalk Analysis 14-17
14-14 2015 No Build Condition Corner Analysis 14-18
14-15 2015 Build Condition Sidewalk Analysis 14-18
14-16 2015 Build Condition Corner Analysis 14-19
14-17 Accident Summary 14-20
14-18 Vehicle and Pedestrian Accident Details 14-22
14-19 2011 Existing Off-Street Parking - 1/4 Mile Weekday Utilization 14-26
14-20 2011 Existing and 2015 No Build Parking Supply and Utilization 14-26
14-21 Projected Incremental Parking Demand 14-27
14-22 2015 No Build and Build Parking Supply and Utilization 14-28
15-1 National Ambient Air Quality Standards (NAAQS) 15-5
15-2 Emission Rates and Stack Parameters 15-12
15-3 Representative Monitored Ambient Air Quality Data 15-14

15-4 Maximum Modeled CO Concentrations from Proposed Parking Garage (in ppm)... 15-15

15-5 Maximum Modeled Pollutant Concentration (in $\mu g/m^3$) 15-16

16-1 Global Warming Potential (GWP) for Major GHGs 16-3

16-2 Annual Vehicle Miles Traveled (Miles Per Year) 16-7

16-3 Building Operational Emissions 16-8

16-4 Mobile Source Emissions (Metric Tons CO_2e)..... 16-8

16-5 Summary of Annual GHG Emissions 2015 (Metric Tons CO_2e) 16-9

17-1 Common Noise Levels..... 17-2

17-2 CEQR Noise Exposure Guidelines 17-4

17-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels..... 17-4

17-4 Existing Noise Levels At Sites 1 Through 6 (in dBA) 17-7

17-5 Building Attenuation Requirements 17-8

20-1 Conceptual Construction Schedule..... 20-10

20-2 Construction Oversight in New York City 20-18

20-3 Number of Construction Workers and Delivery Truck 20-21

20-4 Peak Construction Vehicle Trip Projections..... 20-24

20-5 2011 Existing and 2014 No Build and Construction Build LOS Summary 20-27

20-6 Background Pollutant Concentrations 20-35

20-7 Mobile Source Analysis Intersection Location..... 20-37

20-8 No Build Maximum Predicted 8-Hour Carbon Monoxide Concentrations (parts per million) 20-38

20-9 East Site Maximum Predicted Total Concentrations for Construction Activities 20-39

20-10 East Site Maximum $PM_{2.5}$ Increments 20-39

20-11 Center for Comprehensive Care Maximum Predicted Total Concentrations for Construction Activities 20-40

20-12 Center for Comprehensive Care Maximum $PM_{2.5}$ Increments 20-40

20-13 No Build Maximum Predicted 8-Hour Carbon Monoxide Concentrations (Parts Per Million) 20-42

20-14 Construction Equipment Noise Emission Levels (dBA) 20-48

20-15 Construction Noise Receptor Locations 20-50

20-15a Additional Construction Noise Receptor Locations 20-51

20-16 Construction Noise Analysis Results for Weekday in dBA 20-52

20-16a Construction Noise Analysis Results for Weekday in dBA 20-55

20-17 Construction Noise Analysis Results for Saturday in dBA 20-57

20-18 Vibration Source Levels for Construction Equipment 20-62

21-1 Comparison of 2015 Open Space Ratios 21-10

21-2 No Action Alternative with East Site Reuse — Potential Program 21-17

21-3 No Action Alternative with East Site Reuse and Proposed East Site Project Trip Generation Summary 21-23

List of Figures

		following page
1-1	Project Location	1-2
1-2	Existing St. Vincent's Hospital Buildings	1-2
1-3	Existing Zoning	1-4
1-4	Existing Large-Scale Community Facility Development (LSCFD)	1-4
1-5	Proposed Zoning	1-6
1-6	Proposed Large-Scale General Development (LSGD)	1-8
1-7	Proposed East Site Development Height and Setback on Seventh Avenue	1-8
1-8	Proposed East Site Development Height and Setback on West 11th and West 12th Streets	1-8
1-9	Proposed East Site Development Height and Setback on West 11th and West 12th Streets	1-8
1-10	Proposed East Site Development Height and Setback on West 11th and West 12th Streets	1-8
1-11	Proposed Site Plan for East Site Development	1-10
1-12	Proposed East Site Development – New Buildings and Adaptive Reuse	1-10
1-13	Illustrative Ground Floor Plan for East Site Development	1-10
1-14	Proposed Seventh Avenue Elevation for East Site Development	1-10
1-15	Proposed West 11th Street Elevation for East Site Development	1-10
1-16	Proposed West 12th Street Elevation for East Site Development	1-10
1-17	Triangle Site Open Space - Illustrative Plan	1-10
1-18	Proposed Center for Comprehensive Care Ground Floor Plan	1-10
1-19	Proposed Center for Comprehensive Care South Elevation	1-10
1-20	Proposed Center for Comprehensive Care Seventh Avenue Elevation	1-10
1-21	Proposed Center for Comprehensive Care View including Roof	1-12
2-1	Land Use	2-6
2-2	Existing Zoning	2-6
2-3	Background Development: Land Use Study Area	2-12
2-4	Proposed Zoning	2-14

3-1 Socioeconomic Study Area 3-4
4-1 Public Elementary and Intermediate Schools Serving the Project Area 4-6
5-1 Census Tracts and Study Area 5-4
5-2 Study Area Open Space Resources 5-6
6-1 Tier 1 & Tier 2 Screening Assessments 6-4
6-2 The Church of the Village 6-4
6-3 Three-Dimensional Computer Model 6-6
6-4 O'Toole Building - View North 6-6
7-1 Architectural Resources 7-4
7-2 East Site – Smith and Raskob Buildings 7-6
7-3 East Site – Reiss Pavilion and Cronin Building 7-6
7-4 East Site – Coleman and Link Pavilions 7-6
7-5 East Site – Nurses' Residence 7-6
7-6 East Site – Spellman Pavilion 7-6
7-7 Triangle Site 7-6
7-8 O'Toole Building 7-8
7-9 Study Area – Greenwich Village Historic District 7-10
7-10 Study Area – Greenwich Village Historic District 7-10
7-11 Study Area – Known Architectural Resources 7-10
7-12 Known Architectural Resources 7-10
7-13 Existing and Proposed Views of the East Site: Southeast on Seventh Avenue 7-12
7-14 Existing and Proposed Views of the East Site: Northeast on Seventh Avenue 7-12
7-15 Existing and Proposed Views of the East Site: West on West 11th Street 7-12
7-16 Existing and Proposed Views of the East Site: East on West 12th Street 7-12
7-17 Existing and Proposed Views of the East Site: West on West 11th Street 7-12
8-1a Project Location 8-6
8-1b Photograph View Locations 8-6
8-1c Aerial 8-6
8-2 Existing Large Scale Community Facility Development (LSCFD) 8-6
8-3 Project Area Views 8-8
8-4 Project Area Views 8-8
8-5 Project Area Views 8-8
8-6 Project Area Views 8-8

8-7 Project Area Views 8-10
8-8 Project Area View....8-10
8-9 Project Area Views 8-10
8-10 Primary Study Area Views 8-12
8-11 Primary Study Area Views 8-12
8-12 Primary Study Area Views 8-12
8-13 Primary Study Area Views 8-12
8-14 Primary Study Area Views 8-12
8-15 Primary Study Area Views 8-12
8-16 Primary Study Area Views 8-14
8-17 Primary Study Area Views 8-16
8-18 Primary Study Area Views 8-16
8-19 Primary Study Area Views 8-16
8-20 Primary Study Area Views 8-16
8-21 Proposed Project Area Plan 8-18
8-22a East Site: North Elevation at West 12th Street 8-18
8-22b East Site: West Elevation at Seventh Avenue....8-18
8-22c East Site: West Elevations at West 11th Street....8-18
8-23 Views of the East Site: East on West 12th Street 8-18
8-24 Views of the East Site: Southeast on Seventh Avenue 8-18
8-25 Views of the East Site: Northeast on Seventh Avenue 8-18
8-26 Views of the East Site: West on West 11th Street 8-18
8-27 Views of the East Site: West on West 11th Street 8-18
8-28a View North on Seventh Avenue to the Triangle Site and the O'Toole Building 8-18
8-28b View Southwest from West 13th Street to the O'Toole Building 8-18
14-1 Incremental Vehicle Trips Weekday AM Peak Hour 14-10
14-2 Incremental Vehicle Trips Weekday Midday Peak Hour 14-10
14-3 Incremental Vehicle Trips Weekday PM Peak Hour....14-10
14-4 Incremental Pedestrian Trips Weekday AM Peak Hour....14-10
14-5 Incremental Pedestrian Trips Weekday Midday Peak Hour....14-10
14-6 Incremental Pedestrian Trips Weekday PM Peak Hour....14-10
14-7 Pedestrian Analysis Locations 14-16
14-8 Baseline (2007) Pedestrian Volumes Weekday Peak 15 Minutes 14-16

14-9 No Build (2015) Pedestrian Volumes Weekday Peak 15 Minutes 14-18
14-10 Incremental Pedestrian Volumes Weekday Peak 15 Minutes 14-18
14-11 Build (2015) Pedestrian Volumes Weekday Peak 15 Minutes 14-18
14-12 Off Street Parking Facilities 14-28
17-1 Noise Receptor Locations 17-6
20-1 Conceptual Construction Schedule 20-10
20-2 Peak Construction-Generated Traffic Volumes Weekday (6 AM to 7 AM) 20-28
20-3 Peak Construction-Generated Traffic Volumes Weekday (7 AM to 8 AM) 20-28
20-4 Peak Construction-Generated Traffic Volumes Weekday (3 PM to 4 PM) 20-28
20-5 2011 Existing Traffic Volumes Weekday (6 AM to 7 AM) 20-28
20-6 2014 No Build Traffic Volumes Weekday (6 AM to 7 AM) 20-28
20-7 2014 Construction Traffic Volumes Weekday (6 AM to 7 AM) 20-30
20-8 Construction Noise Receptor Locations 20-52
20-9 Noise Impact Locations 20-58

✷