RHEINGOLD REZONING

Draft Environmental Impact Statement (EIS)

CEQR No. 09DCP002K

ULURP Nos.: 110179 ZRK, 080322 MK, 070250 MMK

Lead Agency:
City Planning Commission, City of New York
Amanda M. Burden, FAICP, Chair

May 2013

Rheingold Rezoning

Draft Environmental Impact Statement

CEQR No.: 09DCP002K
ULURP Nos.: 110179 ZRK, 080322 MK, 070250 MMK
Project Location: Brooklyn, New York

LEAD AGENCY:
City Planning Commission, City of New York
Amanda M. Burden, FAICP, Chair

LEAD AGENCY CONTACT:
Robert Dobruskin, AICP, Director
Environmental Assessment and Review Division
New York City Department of City Planning
22 Reade Street, Room 4E
New York, New York, 10007
(212) 720-3423

Prepared by: Philip Habib & Associates
With: Sandstone Environmental Associates, Inc.
.

PREPARED FOR:
Forrest Lots, LLC

Acceptance Date: May 31, 2013

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

TABLE OF CONTENTS

Executive Summary……...…ES-1

Chapter 1: Project Description…….1-1
A. Introduction…….....1-1
B. Existing Conditions……..……..1-2
C. Purpose and Need for the Proposed Action……...1-3
D. Description of the Proposed Action……...1-4
E. Reasonable Worst Case Development Scenarios (RWCDS)…….....1-6
Development Site Criteria……..1-6
Definition of Projected and Potential Development……..1-7
The Future Without the Proposed Actions (No-Action)……...…….....1-7
The Future With the Proposed Action (With-Action)……...……...……..1-7
F. Approvals Required……1-10
Uniform Land Use Review Procedure (ULURP)……1-10
Environmental Review (CEQR)……..1-11

Chapter 2: Land Use, Zoning, and Public Policy……2-1
A. Introduction……2-1
B. Principal Conclusions……2-2
C. Methodology……..2-3
Study Area Definition……2-3
D. Preliminary Assessment…….2-4
Land Use and Zoning…….2-4
Public Policy……..2-5
E. Detailed Assessment……2-10
Existing Conditions……..2-10
The Future Without the Proposed Action (No-Action)……...2-18
The Future With the Proposed Action (With-Action)…….2-19

Chapter 3: Socioeconomic Conditions…….3-1
A. Introduction……3-1
B. Principal Conclusions……3-1
Direct Residential Displacement…….....3-1
Direct Business and Institutional Displacement……3-1
Indirect Residential Displacement…….3-2
Indirect Business and Industrial Displacement……..3-2
Adverse Effects on Specific Industries……..3-2
C. Methodology……..3-2
Analysis Format…….3-3
Study Area Definition……3-3
Data Sources……..3-4
D. Preliminary Assessment…….3-4

Direct Residential Displacement……3-4
Direct Business and Institutional Displacement……3-4
Indirect Residential Displacement…….....3-6
Indirect Business Displacement…….....3-9
Adverse Effect on a Specific Industry…….3-13

Chapter 4: Community Facilities…….. ……4-1
A. Introduction……4-1
B. Principal Conclusions……4-1
C. Preliminary Screening……..…..4-2
D. Indirect Effects on Public Schools…….4-5
Existing Conditions……4-6
The Future Without the Proposed Action (No-Action)…….4-8
The Future With the Proposed Action (With-Action)…….……..…..4-11
E. Indirect Effects on Publicly Funded Day Care……4-13
Methodology……4-13
Existing Conditions……..4-14
The Future Without the Proposed Action (No-Action)……...4-15
The Future With the Proposed Action (With-Action)…….……..…..4-16
F. Indirect Effects on Libraries……4-17
Methodology……4-17
Existing Conditions…….4-17
The Future Without the Proposed Action (No-Action)……...4-19
The Future With the Proposed Action (With-Action)…….4-19

Chapter 5: Open Space……..5-1
A. Introduction……5-1
B. Principal Conclusions……5-2
C. Open Space Study Area and Methodology……5-3
Open Space Study Area…….5-3
Analysis Framework……..5-4
D. Preliminary Assessment…….5-5
E. Detailed Analysis……...5-6
Existing Conditions……5-6
The Future Without the Proposed Action (No-Action)…….……..5-14
The Future With the Proposed Action (With-Action)…….……5-16

Chapter 6: Shadows……...6-1
A. Introduction……6-1
B. Principal Conclusions……6-2
C. Resources of Concern..……..6-2
Open Space Resources……...6-2
Historic Resources……6-2
D. Methodology……..…6-3

E. Preliminary Screening……6-3
F. Detailed Shadows Analysis……...……..……...6-4
Assessment……..……..……..6-6

Chapter 7: Urban Design and Visual Resources……7-1
A. Introduction……7-1
B. Principal Conclusions……7-2
C. Methodology……..7-3
Determining Whether an Urban Design Analysis is Necessary……7-3
Study Area……..7-4
D. Preliminary Assessment…….7-5
Existing Conditions……7-5
E. The Future Without the Proposed Action (No-Action)…...……7-14
F. The Future With the Proposed Action (With-Action)…….7-16

Chapter 8: Hazardous Materials……..……8-1
A. Introduction……8-1
B. Principal Conclusions……8-2
C. Methodology……..8-2
D. Existing Conditions...…….8-3
E. The Future Without the Proposed Action (No-Action)……...…8-12
F. The Future With the Proposed Action (With-Action)……..……...8-12

Chapter 9: Water and Sewer Infrastructure……...….9-1
A. Introduction……..……..9-1
B. Principal Conclusions……..…..9-1
Water Supply……..……9-1
Sanitary Sewage……..…...9-1
Stormwater Drainage and Management……..…...9-1
C. Existing Conditions……..……..9-2
Water Supply…….……9-2
Sanitary Sewage…….9-3
Stormwater and Drainage Management…….....9-4
D. The Future Without the Proposed Action (No-Action)…….9-6
E. The Future With the Proposed Action (With-Action)……...9-6
Water Supply……..……9-6
Sanitary Sewage…….....9-6
Stormwater Drainage and Management…….9-7
Stormwater Best Management Practices……9-9
Street Mapping…….9-10

Chapter 10: Transportation……..10-1
A. Introduction……..10-1
B. Principal Conclusions……..10-1

C. Levels 1 and 2 Screening Analysis……..10-2
Parking…….10-3
Subway……...…..10-4
Pedestrians…….……..10-4
D. Vehicular Traffic……..10-5
Street Network……...……..10-5
Analysis Methodology……..…...10-6
Future Without the Proposed Action…….……..10-7
Future With the Proposed Action…….....10-8
E. Subway Transit……..10-12
Existing Conditions……...…….10-13
Future Without the Proposed Action…….……10-13
Future With the Proposed Action……..…….10-13
F. Pedestrians……..…...10-15
Existing Conditions……...…….10-16
Future Without the Proposed Action…….……10-16
Future With the Proposed Action…….…….10-16
G. Vehicular and Pedestrian Safety Evaluation…….…10-19

Chapter 11: Air Quality…….11-1
A. Introduction……..11-1
B. Principal Conclusions……..11-1
C. Standards and Criteria……..11-2
D. Existing Conditions……..11-5
E. Future Without the Proposed Action……...11-7
F. Future With the Proposed Action……11-7
Mobile Source Analysis……..11-9
Stationary Source HVAC……..11-14
Air Toxics…….11-24
G. Conclusions and Recommendations……11-30
Mobile Sources…….11-30
Parking Facilities……..11-30
Air Toxics…….11-30
Stationary Source HVAC…….11-30
Air Quality (E) Designations……11-30

Chapter 12: Greenhouse Gas Emissions……...12-1
A. Introduction……..12-1
B. Principal Conclusions……..12-1
C. Pollutants of Concern……...12-2
Carbon Dioxide (CO_2)…….12-2
Methane (CH_4)…….……12-2
Nitrous Oxide (N_20)…….……12-2
Fluorinated Gases…….12-2

D. Methodology……12-3
E. GHG Emissions……12-4
Operational Emissions……12-4
Mobile Source Emissions……12-4
Construction Phase Emissions……12-5
Emissions from Solid Waste Management……..12-5
F. Projects GHG Emissions From the Proposed Action……..12-5
G. Consistency With the GHG Reduction Goal……...12-6

Chapter 13: Noise……...13-1
A. Introduction……..13-1
B. Principal Conclusions……..13-1
C. Noise Fundamentals……13-2
D. Noise Standards and Criteria……13-4
E. Existing Conditions……..…13-6
Affected Properties……...…13-6
Noise Monitoring……13-7
F. Future Without the Proposed Action……13-10
G. The Future With the Proposed Action (With-Action)…….……..13-10
Traffic Noise ……...……..13-10
Window/Wall Attenuation……13-12
H. Noise Attenuation Measures……..13-14

Chapter 14: Neighborhood Character…….14-1
A. Introduction……..14-1
B. Principal Conclusions……..14-2
C. Methodology……14-2
Study Area……14-2
D. Preliminary Assessment……...14-3
Existing Neighborhood Character and Defining Features……...14-3
Assessment of Proposed Action's Potential Effects on Neighborhood Character...14-5

Chapter 15: Construction……..15-1
A. Introduction……..15-1
B. Principal Conclusions……..15-1
C. Regulatory Framework……15-2
Governmental Coordination and Oversight…….15-2
Hours of Work…….15-3
D. Conceptual Construction Schedule and Activities……...15-4
Construction Sequencing……15-4
Typical Construction Activities……...15-4
Estimate of Construction workers……15-6
Estimate of Construction Period Trucks……..15-6
Determining Peak Year for Cumulative Construction and Operational Effects…..15-6

E. Preliminary Assessment……...15-7
Transportation……..15-7
Construction Traffic…….15-7
Street Lane and Sidewalk Closures……15-10
Transit and Pedestrian Screening……...15-10
Air Quality……..……..15-11
Noise……..15-16
Other Technical Areas……...15-23

Chapter 16: Mitigation……..16-1
A. Introduction……..16-1
B. Principal Conclusions……..16-1
C. Community Facilities…….…..16-2
D. Open Space…….....16-3
E. Transportation……..16-4

Chapter 17: Alternatives……...17-1
A. Introduction……..17-1
B. Principal Conclusions……..17-1
No-Action Alternative……..17-1
Lower Density Alternative……..…….17-2
No Unmitigated Significant Adverse Impacts…….17-2
C. No-Action Alternative……..17-2
Conclusions……..……17-7
D. Lower Density Alternative……...17-7
E. No Unmitigated Significant Adverse Impacts Alternative……..17-9
F. Conclusions……17-10

Chapter 18: Unavoidable Adverse Impacts..……...18-1
A. Introduction……..18-1
B. Open Space…….....18-1

Chapter 19: Growth-Inducing Aspects of the Proposed Action..…….....19-1

Chapter 20: Irreversible and Irretrievable Commitment of Resources……...20-1

Chapter 21: Public Health……..……21-1

Chapter 22: Response to Comments on the Draft Scope of Work……22-1

Appendices

Appendix 1 Proposed Zoning Text Amendment

Appendix 2 Written Comments Received on the Draft Scope of Work

List of Tables

ES-1 Summary of Proposed Zoning Changes……ES-3
ES-2 Summary of RWCDS (Increment)……ES-7
ES-3 2016 Future With the Proposed Action: Open Space Ratios……ES-12
ES-4 Proposed Traffic Mitigation Measures……ES-20
1-1 List of Block and Lots Included Within the Proposed Rezoning Area……..……...1-2
1-2 Projected and Potential Development Sites Existing Land Use and Zoning……..1-2*
1-3 Summary of Proposed Zoning Districts and Regulations…….……1-5
1-4 RWCDS for Projected and Potential Development Sites…….....1 -12*
1-5 Summary of RWCDS (Increment)……1-8
2-1 Existing Zoning Districts in the Primary and Secondary Study Areas……....2-17
2-2 No-Action Development Sites within the Secondary Study Area……...……2-19
2-3 Summary of Proposed Zoning Districts and Regulations……...2-22
3-1 Businesses Subject to Directly Displacement under the Proposed Action by Projected Development Site……...…3-5
3-2 Population Income Characteristics in the ¼-Mile Study Area, Borough of Brooklyn, and New York City…….……..3-7
3-3 Housing Cost Characteristics for the ¼-Mile Study Area, Brooklyn, and New York City……...….3-7
3-4 Residential Population in the ½-Mile Study Area, Brooklyn, and New York City……..……3-8
3-5 Average Rent Summary for Apartment in 2012……....3-9
3-6 Estimated Study Area Employment and Business in 2000 and 2012.....3-12
4-1 Preliminary Screening Analysis Criteria……...4-3
4-2 Existing Study Area Public Elementary School, Capacity, and Utilization Figures for 2011-2012 Academic Year……...…4-7
4-3 Estimated Study Area Public Intermediate School Enrollment, Capacity, and Utilization Figures for 2011-2012 Academic Year ……..…4-8
4-4 2011-2012 High School Enrollment, Capacity, and Utilization Data in the Borough of Brooklyn……..…..4-8
4-5 High Schools within a Mile Radius from the Rezoning Area……...……4-9
4-6 Estimated Number of Students Introduced in the Study Area: 2016 Figure without the Proposed Action…….……...4-9
4-7 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization in the Study Area: 2016 Future without the Proposed Action…….4-10
4-8 Estimated Public High School Enrollment, Capacity, and Utilization in Brooklyn: 2016 Future without the Proposed Action……...4-11
4-9 Estimated Number of Elementary and Intermediate Students Introduced in the Study Area: 2016 Future with the Proposed Action……4-11
4-10 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization in the Study Area: 2016 Future with the Proposed Action……..4-12
4-11 2016 Future With-Action High School Enrollment, Capacity, and Utilization Data in Brooklyn.....4-13

4-12 Public Day Care Centers and Head Start Facilities within a 1.5-Mile Study Area……..…4-15
4-13 Projected Number of Public Day Care Pupils Generated by new Development in the 2016 Future Without the Proposed Action……..4-15
4-14 Projected Number of Public Day Care Pupils Generated by New Developments on Projected Development Sites in the Future With the Proposed Action……..…4-16
4-15 Comparison of Budget Capacity, Enrollment, Available slots and Percent Utilized for the 2016 Future Without and Future With the Proposed Action……4-16
4-16 Public Libraries in the ¾-Mile Study Area……..4-18
5-1 Existing Worker Population in Open Space Study Areas……..…..5-8
5-2 2010 Residential Population and Age Distribution in the Nonresidential and Residential Open Space Study Areas…….5-9
5-3 Summary of 2010 Open Space User Groups Within the Two Study Areas……..5-9
5-4 Inventory of Existing Open Space and Recreational Facilities…….……5-10*
5-5 Existing Conditions: Adequacy of Open Space Resources…….5-12
5-6 Development Projects Anticipated to be Completed in the No-Action Within the Defined Open Space Study Areas……...5-15
5-7 No-Action Conditions: Adequacy of Open Space Resources…….5-16
5-8 With-Action Conditions: Adequacy of Open Space Resources……..5-18
5-9 With-Action OSR: Private Open Space…….……..5-19
5-10 2016 Future With the Proposed Action: Open Space Ratios Summary……..5-21
5-11 Partial With-Action Open Space Ratio……5-22
6-1 Results of Shadows Analysis…….……6-5
9-1 Water Consumption and Wastewater Generation Rates-Existing Conditions…….....9-3
9-2 Monthly Average Dry Weather Flows for the Newtown Creek WPCP ……...9-3
9-3 Surface Types on the Projected Development Sites – Existing Conditions …… 9-5
9-4 Combined Stormwater Runoff and Wastewater Generation on Projected Development Sites – Existing Conditions……..9-5
9-5 Water Consumption and Sewage Generation on the Projected Development Sites – No- and With-Action Conditions…….....9-7
9-6 Surface Types on the Projected Development Sites—With-Action Conditions……..9-7
9-7 Combined Stormwater Runoff and Wastewater Generation Flow Volumes on the Projected Development Sites —With-Action Condition……..9-8
9-8 Incremental Increased in Combined Stormwater Runoff and Wastewater Generation Flow Volumes to Combined Sewer System on the Projected Development Sites…….....9-8
10-1 Transportation Planning Assumptions……...10-3*
10-2 Trip Generation…… 10-3*
10-3 Parking Accumulation……..... 10-4*
10-4 Parking Accumulation……..... 10-4*
10-5 Project Generated Subway Trips (by Station)……..... 10-4*
10-6 Project Generated Transit and Pedestrian Trips……10-5*
10-7 Roadway Level of Service (LOS) Criteria……10-7
10-8 2012 Existing Conditions Level of Service Analysis…….. 10-7*
10-9 2016 No-Build Conditions Level of Service Analysis…… 10-8*

10-10 Intersection Level of Service Summary Comparison: No-Action vs. With-Action Conditions…….…10-11
10-11 2016 Build Condition Level of Service Analysis…….....10-11*
10-12 2012 Existing Subway Control Analysis at the Flushing Avenue (J,M) and Myrtle Avenue (J,M,Z) Station……10-13*
10-13 2012 Existing Subway Stair Analysis at the Flushing Avenue (J, M) and Myrtle Avenue (J, M, Z) Station…….....10-13*
10-14 2016 No-Build Subway Control Area Analysis at the Flushing Avenue (J, M) and Myrtle Avenue (J, M, Z) Station …….....10-13*
10-15 2016 No-Build Subway Stair Analysis at the Flushing Avenue (J, M) and Myrtle Avenue (J, M, Z) Station …….....10-13*
10-16 2016 Build Subway Control Area Analysis at the Flushing Avenue (J, M) and Myrtle Avenue (J, M, Z) Station ……..... ..10-13*
10-17 2016 Build Subway Stair Analysis at the Flushing Avenue (J, M) and Myrtle Avenue (J, M, Z) Station ……..... 10-13*
10-18 Level of Service Criteria for Subway Station Elements……..10-14
10-19 Significant Impact Thresholds for Stairways and Passageways …….10-14
10-20 Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions…….10-15
10-21 2012 Existing Sidewalk Locations…… .10-16*
10-22 2012 Existing Corner Conditions……..... 10-16*
10-23 2012 Existing Crosswalk Conditions……. 10-16*
10-24 2016 No-Build Sidewalk Conditions……. 10-16*
10-25 2016 No-Build Corner Conditions……. 10-16*
10-26 2016 No-Build Crosswalk Conditions……..... 10-16*
10-27 2016 Build Sidewalk Conditions……... 10-16*
10-28 2016 Build Corner Conditions……10-16*
10-29 2016 Build Crosswalk Conditions……. 10-16*
10-30 Significant Impact Criteria for Sidewalks with Platooned Flow in a Non-CBD Location…..10-17
10-31 Significant Impact Criteria for Corners and Crosswalks in a Non-CBD Location …….10-18
10-32 Summary Motor Vehicle Accident Data 2008-2010 ……. 10-19*
11-1 National and New York State Ambient Air Quality Standards……..11-3
11-2 Monitored CO Concentrations (ppm)…….11-5
11-3 Affected Properties…….11-6
11-4 Projected and Potential Development Sites……11-8
11-5 $PM_{2.5}$ Screen for Signalized Intersections……....11-10
11-6 Mobile Source Air Quality for PM_{10} and $PM_{2.5}$ Action Conditions…….....11-11
11-7 Hourly Garage Parking Demand (Projected Site #2)……....11-12
11-8 Potential Garage Vent Locations, Projected Development Site 2…….11-12
11-9 CO Air Quality for Garage (ppm)…….11-14
11-10 CEQR Manual HVAC Screening Nomograph Analyses……..11-18
11-11 Nitrogen Dioxide AERMOD Concentration ……11-21
11-12 $PM_{2.5}$ AERMOD Concentrations……...11-23
11-13 PM_{10} AERMOD Concentrations……...11-23
11-14 Sulfur Dioxide AERMOD Concentrations……....11-24

11-15 Commercial and Industrial Sites within 400 feet of Rezoning Boundaries…….....11-25
11-16 Summary of Industrial Source Screen Results……..11-28
11-17 Wolski Woodworks AERMOD Results……11-29
11-18 Cumulative Hazard Index……..11-29
12-1 Global Warming Potential for Primary Greenhouse Gases…..……..12-3
12-2 Operational Emissions……12-4
12-3 Mobile Source Emissions…….…..12-5
12-4 Total Emissions……..12-6
13-1 Sound Pressure Level and Loudness of Typical Noises in Indoor and Outdoor Environments.13-3
13-2 CEQR Noise Exposure Guidelines for Use in City Environmental Impact Review……..13-5
13-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels……..13-4
13-4 Affected Properties……..…13-6
13-5 Monitored Noise Levels (dBA) ……..13-9
13-6 1-Hour Equivalent Observed Traffic Volumes and PCEs…… 13-10
13-7 2016 No-Build Traffic and PCEs…….....…….13-11
13-8 2016 No-Build Noise Levels…….13-11
13-9 2016 Traffic and PCEs with the Proposed Action……..……...13-12
13-10 2016 Noise Levels (dBA) Future with the Proposed Action…….……13-12
13-11 Minimum CEQR Attenuation Requirements for the Proposed Development……..13-13
15-1 Construction Oversight in New York City……..15-3
15-2 Estimated Total Number of Construction Workers and Construction Trucks On-Site Per Day.15-6
15-3 1Q 2016 Peak Construction Vehicle Trip Projections…….15-9
15-4 1Q 2016 Peak Hour Construction and Operational Traffic Volumes……..15-9
15-5 1Q 2016 Peak Hour Construction and Operational Transit and Walk Trips…….15-11
15-6 Typical Construction Equipment Noise Emissions……...15-20
16-1 Elementary School Mitigation Timing for Applicant Sites…….16-3
16-2 Proposed Traffic Mitigation Measures……. 16-4*
16-3 2016 Build with Mitigation Level of Service Analysis…… 16-5*
17-1 Intersection Level of Service Comparison: No-Action Alternative vs. Proposed Action with Mitigation……...17-6
17-2 Estimated Open Space Ratio (Residential Study Area) under No Unmitigated Significant Adverse Impacts Alternative……17-10

*Denotes that the table follows the specified page

List of Figures

		Following Page
ES-1	Proposed Rezoning Area	ES-1
ES-2	Existing Zoning	ES-1
ES-3	Proposed Zoning	ES-1
ES-4	RWCDS Projected and Potential Development Sites	ES-1
ES-5	Proposed Mapped Streets	ES-5
1-1	Project Location	1-1
1-2	Existing Zoning	1-3
1-3	Existing Zoning	1-2
1-4	Proposed Zoning	1-4
1-5	Illustrative Site Plan	1-8
2-1	Land Use and Zoning Study Area (Primary and Secondary)	2-4
2-2	West Bushwick Urban Renewal Area	2-5
2-3	North Brooklyn IBZ	2-9
2-4	Existing Land Use	2-10
2-5	Existing Zoning	2-14
2-6	No-Action Sites	2-18
2-7	Proposed Zoning	2-20
3-1	Socioeconomic Conditions Study Area	3-4
4-1	Elementary and Intermediate Schools in Study Area	4-5
4-2	High Schools within One-Mile of Proposed Rezoning Area	4-8
4-3	Group Child Day Care & Head Start Facilities within Study Area	4-14
4-4	Public Libraries	4-17
5-1	Open Space Study Area	5-3
5-2	Open Space Resources	5-10
6-1	Open Space and Historic Resources within Maximum Shadow Radius (Tiers 1 and 2)	6-2
6-2	Shadows on Open Spaces—Bushwick Pool and Playground/Garden Playground	6-4
6-3	Shadows on Open Spaces—Green Central Knoll	6-6
7-1	Urban Design Study Area	7-1
7-2	Urban Design Study Area Aerial View	7-5
7-3a	Existing Zoning	7-5
7-3b	Proposed Zoning	7-5
7-4a	Existing Conditions	7-6
7-4b	Existing Conditions	7-7
7-4c	Existing Conditions	7-8
7-4d	Existing Conditions	7-9
7-4e	Existing Conditions	7-10
7-4f	Existing Conditions	7-10
7-4g	Primary Study Area Photo Key Map	7-10
7-5	Existing Density	7-8

7-6 Existing Building Heights……...……...7-10
7-7 Existing and Proposed Perspective – Site 1……7-18
7-8 Projected Development Sites 1 & 2 - Elevations…….....7-18
7-9 Existing and Proposed Perspective – Sites 1 & 2 …….....7-18
7-10 Existing and Proposed Perspective – Site 2…….7-18
7-11 Projected Development Site 2 – Elevations……7-18
7-12 Existing and Proposed Perspective – Site 3……7-19
7-13 Existing and Proposed Perspective – Site 5……7-19
7-14 Existing and Proposed Perspective – Site 4……7-19
7-15 Projected Development Sites 3 & 4 – Elevations……7-19
7-16 Existing and Proposed Perspective – Site 4……7-19
7-17 RWCDS Projected & Potential Development Sites……....7-19
7-18 Existing and Proposed Perspective – Site 6……7-19
7-19 Existing and Proposed Perspective – Site 7……7-19
7-20 Existing and Proposed Perspective – Site 8……7-20
9-1 Affected Subcatchment Areas……...9-3
9-2 Stormwater BMP Concept Plan……..9-10
10-1 Project Net Increment Traffic Volumes……..10-3
10-2 Peak Hour Project Increment Pedestrian Volumes for Proposed Project……10-5
10-3 Proposed Pedestrian Analysis Locations…….10-5
10-4 Study Area……..……....10-5
10-5 2012 Existing Traffic Volumes……...10-5
10-6 2016 No-Build Traffic Volumes……..……10-8
10-7 Study Area Build Conditions……..……..10-9
10-8 Projected Sites Incremental Traffic Volumes……...……...10-9
10-9 Diversions Traffic Volumes…….……...10-9
10-10 2016 Build Traffic Volumes……...……...……..10-9
10-11 Rezoning Area Subway and Bus Service……..10-12
10-12 Analyzed Subway Stations in Proximity to Proposed Development…….10-12
11-1 Projected and Potential Development Sites…….……11-6**
11-2 Vent and Receptor Locations for Garage Analysis……...……..…..11-13**
11-3 400-ft and 1,000-ft Radii from the Rezoning Boundaries……..…11-15**
11-4 Projected Boiler Stack Locations and Heights……...……...11-17**
11-5 Permit Locations……11-27**
11-6 Proposed Site Plan for Applicant's Sites……..11-20
13-1 Affected Properties……13-7**
13-2 Noise Monitoring Locations……..13-8**
14-1 Neighborhood Character Study Area…….14-2
15-1 Assumed Construction Schedule for Assessment of Construction Impacts……..15-4
15-2 RWCDS Projected & Potential Development Sites…….15-10
16-1 Proposed On-Site Open Space Mitigation – Preliminary Illustrative Plan……....16-4

**Denotes that the figure is on the specified page