GREATER EAST MIDTOWN REZONING

Draft Environmental Impact Statement



CEQR No.: 17DCP001M
ULURP Nos.: N 170186 ZRM
170187 ZMM

LEAD AGENCY:
City Planning Commission, City of New York
Carl Weisbrod, Chair

December 30, 2016

vhb

GREATER EAST MIDTOWN REZONING

Draft Environmental Impact Statement (DEIS)

December 30, 2016

CEQR No.: 17DCP001M

ULURP Nos.: N 170186 ZRM, 170187 ZMM

Lead Agency: City Planning Commission, City of New York

Lead Agency Contact:
Robert Dobruskin, AICP, Director
Environmental Assessment and Review Division
New York City Department of City Planning
120 Broadway, 31st Floor
New York, New York, 10271-3100
(212) 720-3423

Prepared By:
VHB Engineering, Surveying and Landscape Architecture, P.C.
Two Penn Plaza
Suite 2602
New York, New York 10121

With: STV, Inc.
Historical Perspectives, Inc.
Urbanomics, Inc.
SIMCO Engineering, P.C.

Prepared For:
The New York City Department of City Planning
Edith Hsu-Chen, Director
Manhattan Office

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

Table of Contents

Executive Summary

S.1 INTRODUCTION S-1
S.2 PURPOSE AND NEED S-2
Challenges Affecting East Midtown S-2
Aging Building Stock S-2
Limited Recent Office Development and Few Available Office Development Sites S-3
Public Realm Challenges – Pedestrian Realm and Transit Network S-4
Challenges of Current Zoning S-5
Consequences of Long Term Challenges S-7
S.3 THE PROPOSED ACTION S-7
Goals of the Proposed Action S-7
Description of the Proposed Action S-9
Proposed Zoning Text Amendment S-9
Proposed Zoning Map Amendment S-16
S.4 REASONABLE WORST-CASE DEVELOPMENT SCENARIO (RWCDS) S-17
The Future without the Proposed Action (No-Action Condition) S-18
The Future with the Proposed Action (With-Action Condition) S-19
Conceptual Analysis of the Special Permits S-20
S.5 PUBLIC REVIEW PROCESS FOR THE PROPOSED ACTION S-20
Environmental Review S-20
Uniform Land Use Review Procedure S-22
S.6 PROBABLE IMPACTS OF THE PROPOSED ACTION S-22
Land Use, Zoning and Public Policy S-22
Socioeconomic Conditions S-23
Direct and Indirect Residential Displacement S-23
Direct Business and Institutional Displacement S-23
Indirect Business and Institutional Displacement S-24
Adverse Effects on Specific Industries S-25
Open Space S-25
Direct Effects S-25
Indirect Effects S-26
Shadows S-26
Historic and Cultural Resources S-27
Urban Design and Visual Resources S-28
Hazardous Materials S-29
Water and Sewer Infrastructure S-29
Water Supply S-29
Sanitary Sewage S-30
Stormwater Drainage and Management S-30
Solid Waste and Sanitation Services S-30
Energy S-31
Transportation S-31

Traffic *S-31*
Transit *S-32*
Pedestrians *S-33*
Vehicular and Pedestrian Safety *S-33*
Parking *S-34*
Air Quality S-34
Greenhouse Gas Emissions S-35
Noise S-35
Public Health S-36
Neighborhood Character S-36
Construction S-37
Historic and Cultural Resources *S-37*
Transportation *S-37*
Construction Noise *S-37*
Mitigation S-38
Open Space *S-38*
Shadows *S-39*
Historic and Cultural Resources *S-39*
Transportation *S-40*
Construction Impacts *S-41*
Alternatives S-42
No-Action Alternative *S-42*
No Unmitigated Significant Adverse Impact Alternative *S-42*
Construction Impacts *S-44*
Lesser Density Alternative *S-44*
Conceptual Analysis S-45
Unavoidable Adverse Impacts S-46
Open Space *S-46*
Shadows *S-47*
Historic and Cultural Resources *S-47*
Transportation *S-48*
Construction Impacts *S-48*
Growth-Inducing Impacts of the Proposed Action S-49
Irreversible and Irretrievable Commitment of Resources S-50

Chapter 1: Project Description

1.1 INTRODUCTION 1-1
1.2 BACKGROUND AND EXISTING CONDITIONS 1-2
Current Status and Recent Trends 1-2
1.3 PURPOSE AND NEED FOR PROPOSED ACTION 1-3
Challenges Affecting East Midtown 1-3
Aging Building Stock *1-3*
Limited Recent Office Development and Few Available Office Development Sites *1-4*
Public Realm Challenges – Pedestrian Realm and Transit Network *1-5*
Challenges of Current Zoning *1-6*
Consequences of Long Term Challenges *1-8*

Prior Studies in the East Midtown Area 1-8
2013 Proposed Action *1-8*
The Vanderbilt Corridor *1-9*
East Midtown Steering Committee *1-9*
1.4 THE PROPOSED ACTION 1-11
Goals of the Proposed Action 1-11
Description of the Proposed Action 1-13
Proposed Zoning Text Amendment *1-13*
Proposed Zoning Map Amendment *1-20*
1.5 FRAMEWORK FOR ENVIRONMENTAL ANALYSIS 1-21
Reasonable Worst-Case Development Scenario (RWCDS) 1-21
Development Site Criteria *1-21*
New Construction Development Assumptions *1-22*
Projected and Potential Development Sites *1-22*
Summary *1-23*
The Future without the Proposed Action (No-Action Condition) 1-24
The Future with the Proposed Action (With-Action Condition) 1-24
Conceptual Analysis of the Discretionary Actions *1-25*
Conceptual Construction Schedule *1-26*
Alternatives *1-26*
1.6 PUBLIC REVIEW PROCESS FOR THE PROPOSED ACTION 1-27
Environmental Review 1-27
Uniform Land Use Review Procedure 1-28

Chapter 2: Land Use, Zoning and Public Policy

2.1 INTRODUCTION 2-1
Principal Conclusions 2-1
2.2 METHODOLOGY 2-2
Study Area Definition 2-3
2.3 DETAILED ASSESSMENT 2-3
Existing Conditions 2-3
Land Use *2-3*
Zoning *2-10*
Public Policy *2-16*
The Future without the Proposed Action (No-Action Condition) 2-20
Land Use *2-20*
Zoning *2-23*
Public Policy *2-23*
The Future with the Proposed Action (With-Action Condition) 2-23
Land Use *2-23*
Zoning *2-24*
Public Policy *2-30*
Assessment 2-30
Land Use and Zoning *2-30*
Public Policy *2-32*

Chapter 3: Socioeconomic Conditions

3.1 INTRODUCTION 3-1
Principal Conclusions 3-2
Direct and Indirect Residential Displacement 3-2
Direct Business and Institutional Displacement 3-2
Indirect Business and Institutional Displacement 3-3
Adverse Effects on Specific Industries 3-4
3.2 METHODOLOGY 3-5
Analysis Approach 3-6
Study Area Definition 3-6
Data Sources 3-7
3.3 PRELIMINARY ASSESSMENT 3-8
Direct Business and Institutional Displacement 3-8
Indirect Business/Institutional Displacement 3-10
Adverse Effects on Specific Industries 3-14
3.4 DETAILED ASSESSMENT 3-15
Direct Business and Institutional Displacement 3-16
Existing Conditions 3-16
The Future without the Proposed Action (No-Action Condition) 3-31
The Future with the Proposed Action (With-Action Condition) 3-32
Indirect Business and Institutional Displacement 3-34
Existing Conditions 3-34
The Future without the Proposed Action (No-Action Condition) 3-40
The Future with the Proposed Action (With-Action Condition) 3-40

Chapter 4: Open Space

4.1 INTRODUCTION 4-1
Principal Conclusions 4-1
Direct Effects 4-2
Indirect Effects 4-2
4.2 METHODOLOGY 4-3
Open Space Study Area 4-4
Preliminary Assessment 4-5
Framework for Detailed Analysis 4-5
Direct Effects Analysis 4-5
Indirect Effects Analysis 4-6
Impact Assessment 4-6
4.3 DETAILED ASSESSMENT 4-7
Existing Conditions 4-7
Study Area Population 4-7
Inventory of Publicly Accessible Open Space 4-10
Assessment of Open Space Adequacy 4-22
The Future without the Proposed Action (No-Action Condition) 4-23
Study Area Population 4-23
Open Space Resources 4-25

Assessment of Open Space Adequacy *4-27*
The Future with the Proposed Action (With-Action Condition) 4-28
Direct Effects Analysis *4-28*
Indirect Effect Effects Analysis *4-28*
Determining Impact Significance *4-29*
Qualitative Analysis *4-30*

Chapter 5: Shadows

5.1 INTRODUCTION **5-1**
Principal Conclusions 5-1
5.2 METHODOLOGY **5-2**
Preliminary Screening Assessment 5-4
Tier 1 and Tier 2 Screening Assessment *5-4*
Tier 3 Screening Assessment *5-5*
Resources of Concern 5-5
Open Space Resources *5-5*
Historic Resources *5-6*
5.3 DETAILED SHADOW ANALYSIS **5-6**
The Future without the Proposed Action (No-Action Condition) 5-6
The Future with the Proposed Action (With-Action Condition) 5-7
5.4 ASSESSMENT **5-7**
Open Spaces 5-7
Section I. Longer Shadow Durations *5-8*
Section II. Shorter / Reduced Shadows *5-30*

Chapter 6: Historic and Cultural Resources

6.1 INTRODUCTION **6-1**
Principal Conclusions 6-1
6.2 METHODOLOGY **6-3**
Development Background 6-3
6.3 ASSESSMENT **6-5**
Archaeological Resources 6-5
Architectural Resources 6-6
Criteria and Regulations 6-6
Existing Conditions *6-7*
Designated Individual Landmarks Historic Resources *6-10*
The Future without the Proposed Action (No-Action Condition) *6-62*
The Future with the Proposed Action (With-Action Condition) *6-64*

Chapter 7: Urban Design and Visual Resources

7.1 INTRODUCTION **7-1**
Principal Conclusions 7-2
7.2 METHODOLOGY **7-3**

Determining Whether an Urban Design and Visual Resources Assessment is Appropriate 7-4
Study Areas 7-5
Primary Study Area "Analysis Areas" *7-6*
Secondary Study Area "Analysis Areas" *7-7*
7.3 PRELIMINARY ASSESSMENT 7-7
7.4 DETAILED ANALYSIS, PART I – URBAN DESIGN: STREETS, BUILDINGS, AND OPEN SPACE 7-8
Existing Conditions 7-8
Primary Study Area *7-8*
Primary Study Area – Analysis Areas *7-11*
Secondary Study Area *7-22*
Open Space *7-31*
The Future without the Proposed Action (No-Action Condition) 7-33
Primary Study Area - Analysis Areas *7-37*
Secondary Study Area – Analysis Areas *7-38*
Open Space *7-40*
The Future with the Proposed Action (With-Action Condition) 7-41
Primary Study Area *7-44*
Primary Study Area – Analysis Areas *7-45*
Secondary Study Area *7-49*
Public Realm Improvements *7-49*
Open Space *7-51*
7.5 DETAILED ANALYSIS, PART II – VISUAL RESOURCES 7-55
Introduction 7-55

Chapter 8: Hazardous Materials

8.1 INTRODUCTION 8-1
8.2 PRINCIPAL CONCLUSIONS 8-1
8.3 METHODOLOGY 8-2
Regulatory Databases 8-2
Historic Sanborn Fire Insurance Maps 8-3
City Directories 8-3
Limitations 8-4
8.4 ASSESSMENT 8-4
Existing Conditions 8-4
The Future without the Proposed Action (No-Action Condition) 8-4
The Future with the Proposed Action (With-Action Condition) 8-5

Chapter 9: Water and Sewer Infrastructure

9.1 INTRODUCTION 9-1
Principal Conclusions 9-1
Water Supply *9-2*
Sanitary Sewage *9-2*
Stormwater Drainage and Management *9-2*
9.2 METHODOLOGY 9-3

9.3 ASSESSMENT 9-3
Existing Conditions 9-3
Water Supply 9-3
Wastewater Treatment 9-5
Stormwater and Drainage Management 9-7
Water Conservation and WWTP Load Reduction 9-9
The Future without the Proposed Action (No-Action Condition) 9-9
Water Supply 9-9
Wastewater Treatment 9-10
Stormwater and Drainage Management 9-10
The Future with the Proposed Action (With-Action Condition) 9-11
Water Supply 9-11
Wastewater Treatment 9-11
Stormwater and Drainage Management 9-13
Stormwater Best Management Practices 9-15

Chapter 10: Solid Waste and Sanitation Services

10.1 INTRODUCTION 10-1
Principal Conclusions 10-1
10.2 METHODOLOGY 10-1
10.3 ASSESSMENT 10-2
Existing Conditions 10-2
Description of Current Solid Waste Sanitation Services 10-2
Solid Waste Generation on Projected Development Sites 10-3
The Future without the Proposed Action (No-Action Condition) 10-4
The Future with the Proposed Action (With-Action Condition) 10-5

Chapter 11: Energy

11.1 INTRODUCTION 11-1
Principal Conclusions 11-1
11.2 METHODOLOGY 11-1
11.3 ASSESSMENT 11-2
Existing Conditions 11-2
Energy Providers 11-2
Recent Energy Conservation Directives 11-3
Existing Demands 11-3
The Future without the Proposed Action (No-Action Condition) 11-4
The Future with the Proposed Action (With-Action Condition) 11-5

Chapter 12: Transportation

12.1 INTRODUCTION 12-1
Principal Conclusions 12-2
Traffic 12-2

Transit *12-6*
Pedestrians *12-7*
Vehicular and Pedestrian Safety *12-10*
Parking *12-11*
12.2 METHODOLOGY 12-11
Preliminary Analysis Methodology 12-11
Level 1 Screening Assessment *12-11*
Level 2 Screening Assessment *12-16*
Transportation Analysis Methodologies 12-23
Traffic *12-23*
Transit *12-24*
Pedestrians *12-27*
Pedestrian and Vehicular Safety Evaluation *12-30*
Parking *12-31*
12.3 TRAFFIC 12-31
Existing Conditions 12-31
Study Area Street Network *12-31*
Future Traffic Conditions without the Proposed Action (No-Action Condition) 12-60
Future No-Action Traffic Growth *12-60*
Changes to the Study Area Street Network *12-62*
Intersection Capacity Analysis *12-63*
Future Traffic Conditions with the Proposed Action (With-Action Condition) 12-78
Future With-Action Traffic Growth *12-78*
Above-Grade Public Realm Improvements *12-79*
Intersection Capacity Analysis *12-79*
12.4 TRANSIT 12-100
Existing Conditions 12-100
Subway Stations *12-100*
Subway Line Haul *12-121*
Commuter Railroad *12-123*
Bus *12-124*
Future Transit Conditions without the Proposed Action (No-Action Condition) 12-127
Subway Stations *12-127*
Subway Line Haul *12-144*
Commuter Railroad *12-147*
Bus *12-149*
Future Transit Conditions with the Proposed Action (With-Action Condition) 12-149
Subway Stations *12-149*
Subway Line Haul *12-176*
Commuter Railroad *12-178*
Bus *12-182*
12.5 PEDESTRIANS 12-182
Existing Conditions 12-182
Sidewalks *12-182*
Crosswalks *12-189*
Corner Areas *12-193*
Future Pedestrian Conditions without the Proposed Action (No-Action Condition) 12-196
Sidewalks *12-196*

Crosswalks *12-202*
Corner Areas *12-206*
Future Pedestrian Conditions with the Proposed Action (With-Action Condition) 12-210
Above-Grade Public Realm Improvements *12-211*
Street-Level Pedestrian Operations Analysis *12-212*
12.6 VEHICULAR AND PEDESTRIAN SAFETY EVALUATION 12-229
Second Avenue and East 39th Street 12-233
Second Avenue and East 42nd Street 12-233
Second Avenue and East 53rd Street 12-234
Second Avenue and East 57th Street 12-234
Third Avenue and East 42nd Street 12-234
Third Avenue and East 47th Street 12-235
Third Avenue and East 49th Street 12-235
Third Avenue and East 53rd Street 12-235
Third Avenue and East 54th Street 12-236
Third Avenue and East 57th Street 12-236
Lexington Avenue and East 42nd Street 12-236
Lexington Avenue and East 50th Street 12-237
Park Avenue and East 52nd Street 12-237
Park Avenue and East 57th Street 12-237
Madison Avenue and East 42nd Street 12-238
Fifth Avenue and 42nd Street 12-238
12.7 PARKING 12-239
Existing Conditions 12-239
Off-Street Parking *12-239*
On-Street Parking *12-243*
Future Parking Conditions without the Proposed Action (No-Action Condition) 12-248
Off-Street Parking *12-248*
On-Street Parking *12-248*
Future Parking Conditions with the Proposed Action (With-Action Condition) 12-249
Off-Street Parking *12-249*
On-Street Parking *12-249*

Chapter 13: Air Quality

13.1 INTRODUCTION 13-1
Principal Conclusions 13-1
13.2 POLLUTANTS OF CONCERN 13-2
Carbon Monoxide 13-2
Nitrogen Oxides, VOCs, and Ozone 13-3
Lead 13-3
Respirable Particulate Matter - PM_{10} and $PM_{2.5}$ 13-3
Sulfur Dioxide 13-4
Non-Criteria Pollutants 13-4
13.3 AIR QUALITY STANDARDS, REGULATIONS AND BENCHMARKS 13-5
National and State Air Quality Standards 13-5
NAAQS Attainment Status and State Implementation Plans 13-7

Determining the Significance of Air Quality Impacts 13-8
CO De Minimis Criteria 13-8
$PM_{2.5}$ De Minimis Criteria 13-8
Non-Criteria Pollutant Thresholds 13-9
13.4 METHODOLOGY 13-10
Mobile Sources 13-10
Intersection Analysis 13-10
Stationary Sources 13-14
Individual HVAC Systems 13-15
Cumulative Impacts from HVAC Systems 13-16
Industrial Sources Analysis 13-16
"Large" or "Major" Source Analysis 13-20
13.5 ASSESSMENT 13-23
Existing Conditions 13-23
The Future without the Proposed Action (No-Action Condition) 13-24
Mobile Sources 13-24
Stationary Sources 13-25
The Future with the Proposed Action (With-Action Condition) 13-25
Mobile Sources 13-25
Stationary Sources 13-27
Industrial Sources Analysis 13-30
Results of the Cancer Risk and Hazard Index Evaluation 13-34
Summary of Air Toxics Results 13-35
"Large" or "Major" Source Analysis 13-37

Chapter 14: Greenhouse Gas Emissions

14.1 INTRODUCTION 14-1
Principal Conclusions 14-1
14.2 POLLUTANTS OF CONCERN 14-2
Carbon Dioxide (CO_2) 14-2
Methane (CH_4) 14-2
Nitrous Oxide (N_2O) 14-2
Fluorinated Gases 14-2
14.3 METHODOLOGY 14-3
14.4 ASSESSMENT 14-4
GHG Emissions 14-4
Operational Emissions 14-4
Mobile Source Emissions 14-4
Construction Phase Emissions 14-5
Emissions from Solid Waste Management 14-5
Projected GHG Emissions from the Proposed Action 14-6
Consistency with the GHG Reduction Goal 14-6

Chapter 15: Noise

15.1 INTRODUCTION 15-1
Principal Conclusions 15-1
15.2 METHODOLOGY 15-1
Acoustic Fundamentals 15-1
"A"- Weighted Sound Level (dBA) 15-2
Sound Level Descriptors 15-2
Noise Standards and Impact Criteria 15-3
New York CEQR Noise Standards 15-3
CEQR Noise Exposure Standards 15-4
New York City Noise Control Code 15-5
Noise Prediction Methodology 15-5
General Methodology 15-5
15.3 ASSESSMENT 15-6
Existing Noise Levels 15-6
Noise Monitoring Locations 15-6
Noise Monitoring Equipment 15-7
Existing Noise Levels at Receptor Locations 15-7
Mechanical Equipment 15-15

Chapter 16: Public Health

16.1 INTRODUCTION 16-1
Principal Conclusions 16-1
16.2 PUBLIC HEALTH ASSESSMENT – CONSTRUCTION NOISE 16-1

Chapter 17: Neighborhood Character

17.1 INTRODUCTION 17-1
Principal Conclusions 17-1
17.2 METHODOLOGY 17-3
Study Area 17-3
17.3 PRELIMINARY ASSESSMENT 17-3
Defining Features 17-3
Grand Central Analysis Area 17-4
Park Avenue Analysis Area 17-6
Madison Avenue Analysis Area 17-6
Lexington/Third Avenue Analysis Area 17-7
East Grand Central Analysis Area 17-7
Midtown Analysis Area 17-8
Upper East Side Analysis Area 17-8
East 50s/Turtle Bay Analysis Area 17-9
Murray Hill/Tudor City Analysis Area 17-10
Midtown South Analysis Area 17-11
Assessment of the Potential to Affect the Defining Features of the Neighborhood 17-11

Land Use, Zoning, and Public Policy *17-11*
Socioeconomic Conditions *17-12*
Open Space *17-13*
Historic and Cultural Resources *17-14*
Urban Design and Visual Resources *17-14*
Shadows *17-15*
Transportation *17-15*
Noise *17-16*

Chapter 18: Construction

18.1 INTRODUCTION 18-1
Principal Conclusions 18-1
Transportation *18-1*
Air Quality *18-2*
Noise and Vibration *18-3*
Other Technical Areas *18-4*
18.2 METHODOLOGY 18-5
Conceptual Construction Schedule and Activities 18-5
Construction Sequencing *18-6*
Typical Construction Activities *18-6*
Estimate of Construction Period Trucks and Construction Workers *18-7*
Determining Peak Year for Cumulative Construction and Operational Effects *18-7*
Construction Working Hours *18-7*
Construction Staging Areas, Sidewalk and Lane Closures *18-8*
18.3 PRELIMINARY ASSESSMENT 18-9
Transportation 18-9
Traffic *18-9*
Transit *18-13*
Pedestrians *18-15*
Parking *18-17*
Air Quality 18-17
Noise and Vibration 18-18
Other Technical Areas 18-18
Land Use and Neighborhood Character *18-18*
Socioeconomic Conditions *18-19*
Open Space *18-19*
Historic and Cultural Resources *18-19*
Hazardous Materials *18-20*
18.4 PROBABLE IMPACTS OF THE PROPOSED ACTION 18-20
Transportation 18-20
Traffic *18-20*
Air Quality 18-22
Air Quality Analysis Methodologies *18-23*
Emission Estimation Process *18-23*
Impacts Assessment *18-26*
Probable Impacts from Proposed Project *18-29*

Noise 18-30
Construction Noise Impact Criteria 18-30
Noise Analysis Methodology 18-31
Determining Existing Noise Levels 18-36
Construction Noise Analysis Results 18-36
Vibration 18-40
Introduction 18-40
Construction Vibration Criteria 18-41
Analysis Methodology 18-41
Construction Vibration Analysis Results 18-42

Chapter 19: Mitigation

19.1 INTRODUCTION 19-1
Principal Conclusions 19-1
Open Space 19-1
Shadows 19-2
Historic and Cultural Resources 19-2
Transportation 19-3
Air Quality (Mobile Source) 19-10
Construction 19-11
19.2 OPEN SPACE 19-12
19.3 SHADOWS 19-13
19.4 HISTORIC AND CULTURAL RESOURCES 19-14
19.5 TRANSPORTATION 19-16
Traffic 19-16
Proposed Mitigation Schedule for Traffic Mitigation Measures 19-59
Transit 19-59
Subway Stations 19-60
Grand Central 42nd Street Subway Station 19-60
42nd St-Bryant Park Subway Station 19-60
Lexington Avenue-53rd Street Subway Station 19-60
Pedestrians 19-60
Sidewalks 19-61
Crosswalks 19-63
Corner Areas 19-68
19.6 AIR QUALITY 19-71
19.7 CONSTRUCTION 19-71
Historic and Cultural Resources 19-71
Traffic 19-72
Noise 19-76

Chapter 20: Alternatives

20.1 INTRODUCTION 20-1
Principal Conclusions 20-1

No-Action Alternative *20-1*
No Unmitigated Significant Adverse Impact Alternative *20-2*
Lesser Density Alternative *20-4*
Modified Rezoning Boundary Alternative *20-4*
20.2 NO-ACTION ALTERNATIVE 20-6
Land Use, Zoning, and Public Policy 20-6
Socioeconomic Conditions 20-7
Direct Business and Institutional Displacement *20-7*
Indirect Business and Institutional Displacement *20-8*
Adverse Effects on Specific Industries *20-8*
Open Space 20-8
Shadows 20-9
Historic and Cultural Resources 20-9
Urban Design and Visual Resources 20-10
Hazardous Materials 20-10
Water and Sewer Infrastructure 20-11
Solid Waste and Sanitation Services 20-11
Energy 20-11
Transportation 20-11
Traffic *20-12*
Transit *20-13*
Pedestrians *20-15*
Parking *20-16*
Air Quality 20-16
Greenhouse Gas (GHG) Emissions 20-16
Noise 20-16
Public Health 20-17
Neighborhood Character 20-17
Construction 20-18
20.3 NO UNMITIGATED SIGNIFICANT ADVERSE IMPACT ALTERNATIVE 20-18
Open Space 20-19
Shadows 20-20
Historic and Cultural Resources 20-20
Transportation 20-21
Traffic *20-21*
Transit *20-21*
Pedestrians *20-21*
Construction 20-22
Historic and Cultural Resources *20-22*
Traffic *20-23*
Noise *20-23*
20.4 LESSER DENSITY ALTERNATIVE 20-23
Land Use, Zoning, and Public Policy 20-26
Socioeconomic Conditions 20-27
Open Space 20-28
Shadows 20-28
Historic and Cultural Resources 20-29
Urban Design and Visual Resources 20-30

Hazardous Materials 20-30
Water and Sewer Infrastructure 20-31
Water Supply *20-31*
Wastewater Treatment *20-31*
Stormwater *20-31*
Solid Waste and Sanitation Services 20-31
Energy 20-32
Transportation 20-32
Traffic *20-34*
Transit *20-35*
Pedestrians *20-37*
Parking *20-38*
Air Quality 20-38
Mobile Source Analysis *20-38*
Stationary Source Analysis *20-38*
Greenhouse Gas Emissions (GHG) 20-39
Noise 20-39
Public Health 20-39
Neighborhood Character 20-39
Construction 20-40
20.5 MODIFIED REZONING BOUNDARY ALTERNATIVE 20-41

Chapter 21: Conceptual Analysis

21.1 INTRODUCTION 21-1
Principal Conclusions 21-2
21.2 METHODOLOGY AND ANALYSIS FRAMEWORK 21-2
21.3 INCREMENT FOR CONCEPTUAL ANALYSIS 21-7
Analysis Framework for Conceptual Analysis 21-9
21.4 ENVIRONMENTAL ASSESSMENT 21-10
Land Use, Zoning, and Public Policy 21-10
Socioeconomic Conditions 21-10
Open Space 21-11
Shadows 21-12
Historic and Cultural Resources 21-13
Urban Design and Visual Resources 21-13
Hazardous Materials 21-14
Water and Sewer Infrastructure 21-14
Water Supply *21-14*
Wastewater Treatment *21-15*
Stormwater and Drainage Management *21-15*
Solid Waste and Sanitation Services 21-15
Energy 21-16
Transportation 21-16
Traffic *21-18*
Transit *21-19*
Pedestrians *21-20*

Parking *21-20*
Air Quality 21-21
Greenhouse Gas Emissions 21-21
Noise 21-21
Public Health 21-22
Neighborhood Character 21-22
Construction 21-23

Chapter 22: Unavoidable Adverse Impacts

22.1 INTRODUCTION 22-1
22.2 ANALYSIS 22-1
Open Space 22-1
Shadows 22-2
Historic and Cultural Resources 22-2
Architectural Resources *22-2*
Transportation 22-2
Traffic *22-3*
Pedestrians *22-3*
Construction 22-3
Historic and Cultural Resources *22-3*
Construction Traffic *22-4*
Construction Noise *22-4*

Chapter 23: Growth Inducing Aspects

23.1 INTRODUCTION 23-1

Chapter 24: Irreversible Commitment

24.1 INTRODUCTION 24-1

List of Appendices

APPENDIX A: REASONABLE WORST-CASE DEVELOPMENT SCENARIO, TABLES 1A AND 1B
APPENDIX B: PROPOSED ZONING TEXT
APPENDIX C: SOCIOECONOMIC CONDITIONS
APPENDIX D: AGENCY CORRESPONDENCE
APPENDIX E: HAZARDOUS MATERIALS
- APPENDIX E.1: Regulatory Agency Database Report
- APPENDIX E.2: Historical Sanborn Fire Insurance Maps
- APPENDIX E.3: City Directory Reviews

APPENDIX F: TRANSPORTATION
- APPENDIX F.1: Transportation Planning Factors
- APPENDIX F.2: Modification of Synchro Adjustment Factors
- APPENDIX F.3: A listing of changes in intersection configuration between Existing and No-Action Conditions
- APPENDIX F.4: Assignment of Auto Trips to Off-Street Parking Facilities
- APPENDIX F.5: Traffic LOS Tables for Existing, No-Action, and With-Action Conditions
- APPENDIX F.6: Subway Station Assignments
- APPENDIX F.7: Subway Station Volumes
- APPENDIX F.8: The results of the Proposed Action without Subway Station Improvements (With-Action Without-Improvement)
- APPENDIX F.9: Pedestrian Volumes (Sidewalks, Crosswalks and Corners)

APPENDIX G: NOISE
APPENDIX H: CONSTRUCTION
- APPENDIX H.1: Traffic Volume Figures
- APPENDIX H.2: Traffic LOS Tables
- APPENDIX H.3: Parking Demand

APPENDIX I: ALTERNATIVES
- APPENDIX I.1: Lesser Density Alternative Traffic Volume Figures
- APPENDIX I.2: Lesser Density Alternative Traffic LOS Tables
- APPENDIX I.3: Lesser Density Alternative Subway LOS Tables
- APPENDIX I.4: Lesser Density Alternative Pedestrian LOS Tables (Sidewalks, Corners and Crosswalks)
- APPENDIX I.5: Lesser Density Alternative Parking Accumulation

APPENDIX J: CONCEPTUAL ANALYSIS
- APPENDIX J.1: Traffic Volume Figures
- APPENDIX J.2: Traffic LOS Tables
- APPENDIX J.3: Pedestrian LOS Tables (Sidewalks, Corners and Crosswalks)
- APPENDIX J.4: Parking Accumulation

APPENDIX K: E DESIGNATIONS
- APPENDIX K.1: Hazardous Materials
- APPENDIX K.2: Air Quality
- APPENDIX K.3: Noise

List of Tables

Executive Summary

Table S.1: Blocks and Lots within the Rezoning Area S-8
Table S.2: RWCDS and Population Summary for Projected Development Sites S-18
Table S.3: RWCDS and Population/Employment Summaries for Projected Development Sites, Compared to the No-Action Condition S-19

Chapter 1: Project Description

Table 1.1: Blocks and Lots within the Rezoning Area 1-12
Table 1.2: RWCDS and Population Summary for Projected Development Sites 1-25

Chapter 2: Land Use, Zoning and Public Policy

Table 2.1: Existing Land Uses within the Primary Study Area 2-4
Table 2.2: Primary Study Area Existing Zoning Designations 2-11
Table 2.3: Secondary Study Area Existing Zoning Designation 2-14
Table 2.4: Development Projects in the 2036 Future without the Proposed Action 2-21
Table 2.5: No-Action to With-Action Comparison of Development for Projected Development Sites 2-24

Chapter 3: Socioeconomic Conditions

Table 3.1: Midtown Manhattan Office Submarkets located within the Primary Study Area 3-17
Table 3.2: Age of the Office Building Stock in the Primary Study Area 3-18
Table 3.3: Size of the Office Building Stock in Primary Study Area 3-19
Table 3.4: Total Employment by Sector in the Primary Study Area 3-21
Table 3.5: RWCDS for the 16 Projected Development Sites 3-22
Table 3.6: Potentially Directly Displaced Business/Institutions and Employment on Projected Development Sites 3-24
Table 3.7: Directly Displaced Employment as a Percentage of the Primary and Secondary Study Areas' Employment 3-25
Table 3.8: Potential Directly Displaced Accommodation and Food Service Businesses 3-26
Table 3.9: Potential Directly Displaced Professional, Scientific, and Technical Service Businesses 3-29
Table 3.10: Midtown Manhattan Office Submarkets included in the Secondary Study Area and Overall Totals for Midtown and Manhattan Office Markets 3-35
Table 3.11: Total Employment by Sector in the Secondary Study Area 3-39

Chapter 4: Open Space

Table 4.1: RWCDS and Population/Employment Summaries for Projected Development Sites, Compared to the No-Action Condition 4-4
Table 4.2: Existing Non-Residential Population in the Open Space Study Area 4-8

Table 4.3: Existing College/Post-Secondary Student Population in the Open Space Study Area 4-9
Table 4.4: Existing Residential Population in the Open Space Study Area 4-10
Table 4.5: Summary of Open Space User Groups within the Study Area 4-10
Table 4.6: Inventory of Existing Open Space Resources Included in the Quantitative Analysis 4-13
Table 4.7: Existing Conditions: Adequacy of Open Space Resources 4-23
Table 4.8: Development Projects in the Future without the Proposed Action 4-24
Table 4.9: New Open Space Resources in the Future without the Proposed Action 4-26
Table 4.10: No-Action Condition - Adequacy of Open Space Resources 4-28
Table 4.11: With-Action Condition: Adequacy of Open Space Resources 4-29
Table 4.12: 2036 Future with the Proposed Action: Passive Open Space Ratios Summary 4-30
Table 4.13: Open Space Utilization Within a Quarter-Mile of Projected Development Sites 4-31

Chapter 5: Shadows

Table 5.1: Resources of Concern within Defined Shadow Radius – Open Spaces Affected by Incremental Shadows 5-34
Table 5.2: Resources of Concern within Defined Shadow Radius – Open Spaces Not Affected by Incremental Shadows 5-38
Table 5.3: Resources of Concern within Defined Shadow Radius – Sunlight-Sensitive Historic Resources Affected by Incremental Shadows 5-41
Table 5.4: Resources of Concern within Defined Shadow Radius – Sunlight-Sensitive Historic Resources Not Affected by Incremental Shadows 5-42
Table 5.5: Incremental Shadow Duration on Resources of Concern – Open Space and Sunlight Sensitive Historic 5-43
Table 5.6: Historic Resources with no Incremental Shadows on Sunlight Sensitive Features 5-54

Chapter 6: Historic and Cultural Resources

Table 6.1: Designated Individual Historic Resources in the Rezoning area and Study Area 6-72
Table 6.2: Eligible Historic Resources in the Rezoning area and Study Area 6-76
Table 6.3: RWCDS Projected and Potential Development Sites Within or Located in Proximity to NYCL- or S/NR-designated, and NYCL- or S/NR-eligible Historic Resources 6-79
Table 6.4: Assessment of Proposed Action's Potential Impacts on Designated or Eligible Historic Resources in the Rezoning area and Study Area 6-83

Chapter 7: Urban Design and Visual Resources

Table 7.1: Development Projects in the 2036 Future without the Proposed Action 7-34
Table 7.2: Visual Resources (Refer to Figure 7-10, and Figures 7-11A-W) 7-56

Chapter 8: Hazardous Materials

Table 8.1: Federal and State Regulatory Agency Databases Reviewed 8-3
Table 8.2: Summary of Environmental Issues for Projected and Potential Development Sites 8-7

Chapter 9: Water and Sewer Infrastructure

Table 9.1: Water Consumption and Wastewater Generation Rates 9-4

Table 9.2: Existing Water Consumption and Wastewater Generation on Projected Development Sites....9-5
Table 9.3: Monthly Average Dry Weather Flows from the Newtown Creek WWTP....9-6
Table 9.4: Existing Wastewater Generation on Projected Development Sites by Subcatchment Area....9-7
Table 9.5: Existing Stormwater Runoff to the Newtown Creek WWTP....9-8
Table 9.6: Existing Combined Stormwater Runoff and Wastewater Generation to the Newtown Creek WWTP....9-8
Table 9.7: No-Action Water Consumption and Wastewater Generation....9-10
Table 9.8: Water Consumption and Wastewater Generation in the No-Action and With-Action Conditions....9-12
Table 9.9: Combined Stormwater Runoff and Wastewater Generation Flow Volume to the Combined Sewer System in the Proposed Rezoning Area—With-Action Condition....9-13
Table 9.10: Incremental Increase in Combined Stormwater Runoff and Wastewater Generation Flow Volumes to the Combined Sewer System in the Proposed Rezoning Area....9-14

Chapter 10: Solid Waste and Sanitation Services

Table 10.1: Existing Solid Waste Generation on Projected Development Sites....10-4
Table 10.2: No-Action Solid Waste Generation on Projected Development Sites....10-5
Table 10.3: With-Action Solid Waste Generation on Projected Development Sites....10-6
Table 10.4: Comparison of Weekly Solid-Waste Generation on Projected Development Sites (Existing, No-Action, and With-Action Conditions)....10-7

Chapter 11: Energy

Table 11.1: Existing Estimated Annual Energy Consumption on Projected Development Sites....11-4
Table 11.2: No-Action Condition: Estimated Annual Energy Consumption on Projected Development Sites....11-4
Table 11.3: With-Action Condition: Estimated Annual Energy Consumption on Projected Development Sites....11-5

Chapter 12: Transportation

Table 12.1: RWCDS Summary for Projected Development Sites....12-1
Table 12.2: Summary of Significant Adverse Traffic Impacts....12-3
Table 12.3: Summary of Significant Adverse Pedestrian Impacts....12-8
Table 12.4: Transportation Planning Factors....12-13
Table 12.5: Travel Demand Forecast with the Proposed Action (2036)....12-15
Table 12.6: Summary of Incremental Trips Generated by the Proposed Action....12-16
Table 12.7: Net Incremental Peak Hour Subway Trips by Station or Station Complex....12-17
Table 12.8: Net Incremental Peak Hour Local Bus Trips by Route....12-20
Table 12.9: Number of Rezoning Area Express Bus Routes and Estimated Distribution of Net Incremental Peak Hour Express Bus Trips by Borough/County....12-21
Table 12.10: Intersection Level of Service Criteria....12-24
Table 12.11: Level of Service Criteria for Subway Station Elements....12-25
Table 12.12: Significant Impact Thresholds for Stairways And Passageways....12-26
Table 12.13: Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions....12-28
Table 12.14: Significant Impact Criteria for Sidewalks With Platooned Flow in a Cbd Location....12-29
Table 12.15: Significant Impact Criteria for Corners And Crosswalks in a Cbd Location....12-30
Table 12.16: Summary of Existing Levels of Service by Movement....12-36
Table 12.17: Intersections with Existing Congested Approach Movements....12-37

Table 12.18: East Midtown Development Projects Included in the No-Action Condition Traffic Analysis 12-61
Table 12.19: Summary of Existing and No-Action Levels of Service By Movement 12-63
Table 12.20: Existing and No-Action Intersections with Los E/F Or V/C ≥ 0.90 in the AM Peak Hour 12-64
Table 12.21: Existing and No-Action Intersections with Los E/F Or V/C ≥ 0.90 in the Midday Peak Hour 12-69
Table 12.22: Existing and No-Action Intersections with Los E/F Or V/C ≥ 0.90 in the PM Peak Hour 12-74
Table 12.23: Summary of No-Action and With-Action Level of Service by Movement 12-80
Table 12.24: No-Action and With-Action Intersections with Los E/F or V/C ≥ 0.90 in the AM Peak Hour 12-81
Table 12.25: No-Action and With-Action Intersections with Los E/F or V/C ≥ 0.90 in the Midday Peak Hour 12-87
Table 12.26: No-Action and With-Action Intersections with Los E/F or V/C ≥ 0.90 in the PM Peak Hour 12-92
Table 12.27: Summary of Approach Movements and Intersections with Significant Impacts with the Proposed Action 12-99
Table 12.28: Existing Conditions Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-104
Table 12.29: Existing Conditions Escalator Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-105
Table 12.30: Existing Conditions Passageway Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-105
Table 12.31: Existing Conditions Fare Control Area Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-106
Table 12.32: Existing Conditions Stair Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-108
Table 12.33: Existing Conditions Fare Control Area Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-109
Table 12.34: Existing Conditions Stair Analysis at the Fifth Avenue (7) Subway Station 12-110
Table 12.35: Existing Conditions Fare Control Area Analysis at the Fifth Avenue (7) Subway Station 12-110
Table 12.36: Existing Conditions Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-112
Table 12.37: Existing Conditions Fare Control Area Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-113
Table 12.38: Existing Conditions Stair Analysis at the 51st Street (6) Subway Station 12-115
Table 12.39: Existing Conditions Escalator Analysis at the 51st Street (6) Subway Station 12-115
Table 12.40: Existing Conditions Passageway Analysis at the 51st Street (6) Subway Station 12-115
Table 12.41: Existing Conditions Fare Control Area Analysis at the 51st Street (6) Subway Station 12-116
Table 12.42: Existing Conditions Stair Analysis at the Lexington Avenue/53rd Street Subway Station 12-117
Table 12.43: Existing Conditions Escalator Analysis at the Lexington Avenue/53rd Street Subway Station 12-117
Table 12.44: Existing Conditions Fare Control Area Analysis at the Lexington Avenue/53rd Street Subway Station 12-118
Table 12.45: Existing Conditions Stair Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-119
Table 12.46: Existing Conditions Fare Control Area Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-119
Table 12.47: Existing Conditions Escalator Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-120
Table 12.48: Existing Conditions Stair Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-120
Table 12.49: Existing Conditions Escalator Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-121
Table 12.50: Existing Conditions Subway Line Haul Analysis 12-122
Table 12.51: Existing Conditions Stair Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-123
Table 12.52: Existing Conditions Escalator Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-124
Table 12.53: Existing Conditions Passageway Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-124
Table 12.54: No-Action Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-131

Table 12.55: No-Action Escalator Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-133
Table 12.56: No-Action Passageway Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-133
Table 12.57: No-Action Fare Control Area Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station Complex 12-134
Table 12.58: No-Action Stair Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-135
Table 12.59: No-Action Fare Control Area Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-136
Table 12.60: No-Action Stair Analysis at the Fifth Avenue (7) Subway Station 12-136
Table 12.61: No-Action Fare Control Area Analysis at the Fifth Avenue (7) Subway Station 12-137
Table 12.62: No-Action Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-138
Table 12.63: No-Action Fare Control Area Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-139
Table 12.64: No-Action Stair Analysis at the 51st Street (6) Subway Station 12-140
Table 12.65: No-Action Escalator Analysis at the 51st Street (6) Subway Station 12-140
Table 12.66: No-Action Passageway Analysis at the 51st Street (6) Subway Station 12-140
Table 12.67: No-Action Fare Control Area Analysis at the 51st Street (6) Subway Station 12-141
Table 12.68: No-Action Stair Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-141
Table 12.69: No-Action Escalator Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-142
Table 12.70: No-Action Fare Control Area Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-142
Table 12.71: No-Action Stair Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-143
Table 12.72: No-Action Fare Control Area Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-143
Table 12.73: No-Action Escalator Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-143
Table 12.74: No-Action Stair Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-144
Table 12.75: No-Action Escalator Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-144
Table 12.76: No-Action Subway Line Haul Analysis 12-146
Table 12.77: No-Action Stair Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-148
Table 12.78: No-Action Escalator Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-148
Table 12.79: No-Action Passageway Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-148
Table 12.80: With-Action Stair Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-151
Table 12.81: With-Action Escalator Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-153
Table 12.82: With-Action Passageway Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-153
Table 12.83: With-Action Fare Control Area Analysis at the Grand Central 42nd Street (4, 5, 6, 7, S) Subway Station 12-154
Table 12.84: With-Action Stair Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-156
Table 12.85: With-Action Fare Control Area Analysis at the 42nd Street-Bryant Park (B, D, F, M) Subway Station 12-157
Table 12.86: With-Action Stair Analysis at the Fifth Avenue (7) Subway Station 12-159
Table 12.87: With-Action Fare Control Area Analysis at the Fifth Avenue (7) Subway Station 12-159
Table 12.88: With-Action Stair Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-161
Table 12.89: With-Action Fare Control Area Analysis at the 47th-50th Streets-Rockefeller Center (B, D, F, M) Subway Station 12-163
Table 12.90: With-Action Stair Analysis at the 51st Street (6) Subway Station 12-165
Table 12.91: With-Action Escalator Analysis at the 51st Street (6) Subway Station 12-165
Table 12.92: With-Action Passageway Analysis at the 51st Street (6) Subway Station 12-166
Table 12.93: With-Action Fare Control Area Analysis at the 51st Street (6) Subway Station 12-166
Table 12.94: With-Action Stair Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-169
Table 12.95: With-Action Escalator Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-170
Table 12.96: With-Action Fare Control Area Analysis at the Lexington Avenue/53rd Street (E, M) Subway Station 12-170

Table 12.97: With-Action Stair Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-172
Table 12.98: With-Action Fare Control Area Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-172
Table 12.99: With-Action Escalator Analysis at the Lexington Avenue-59th Street (4, 5, 6, N, R, W) Subway Station 12-173
Table 12.100: With-Action Stair Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-175
Table 12.101: With-Action Escalator Analysis at the Fifth Avenue-53rd Street Subway (E, M) Station 12-175
Table 12.102: With-Action Subway Line Haul Analysis 12-177
Table 12.103: With-Action Stair Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-180
Table 12.104: With-Action Escalator Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-180
Table 12.105: With-Action Passageway Analysis at the Grand Central Terminal - 47th Street Crosspassage 12-181
Table 12.106: Existing Sidewalk Conditions in the AM Peak Hour 12-183
Table 12.107: Existing Sidewalk Conditions in the Midday Peak Hour 12-185
Table 12.108: Existing Sidewalk Conditions in the PM Peak Hour 12-187
Table 12.109: Existing Crosswalk Conditions in the AM Peak Hour 12-190
Table 12.110: Existing Crosswalk Conditions in the Midday Peak Hour 12-191
Table 12.111: Existing Crosswalk Conditions in the PM Peak Hour 12-192
Table 12.112: Existing Corner Conditions 12-193
Table 12.113: No-Action Sidewalk Conditions in the AM Peak Hour 12-197
Table 12.114: No-Action Sidewalk Conditions in the Midday Peak Hour 12-199
Table 12.115: No-Action Sidewalk Conditions in the PM Peak Hour 12-201
Table 12.116: No-Action Crosswalk Conditions in the AM Peak Hour 12-203
Table 12.117: No-Action Crosswalk Conditions in the Midday Peak Hour 12-204
Table 12.118: No-Action Crosswalk Conditions in the PM Peak Hour 12-205
Table 12.119: No-Action Corner Conditions 12-207
Table 12.120: With-Action Sidewalk Conditions in the AM Peak Hour 12-214
Table 12.121: With-Action Sidewalk Conditions in the Midday Peak Hour 12-216
Table 12.122: With-Action Sidewalk Conditions in the PM Peak Hour 12-218
Table 12.123: With-Action Crosswalk Conditions in the AM Peak Hour 12-221
Table 12.124: With-Action Crosswalk Conditions in the Midday Peak Hour 12-222
Table 12.125: With-Action Crosswalk Conditions in the PM Peak Hour 12-223
Table 12.126: With-Action Corner Conditions 12-225
Table 12.127: Summary of Motor Vehicle Crash Data, 2012-2014 12-230
Table 12.128: Existing Off-Street Parking Facilities in Study Area 12-239
Table 12.129: Parking Regulation Code Definitions 12-243
Table 12.130: No-Action Condition Off-Street Parking Capacity, Demand, and Utilization 12-249
Table 12.131: With-Action Condition Net Incremental Weekday Hourly Parking Accumulation by Land Use 12-250
Table 12.132: With-Action Condition Off-Street Parking Capacity, Demand, and Utilization 12-251

Chapter 13: Air Quality

Table 13.1: National Ambient Air Quality Standards 13-6
Table 13.2: NYSDEC Air Guideline Concentrations for Non-Criteria Pollutants 13-9
Table 13.3: Background Concentrations for Intersection Analysis 13-13
Table 13.4: Intersection Analysis Sites 13-14
Table 13.5: Cluster Sites for Cumulative HVAC Analysis 13-16
Table 13.6: Background Concentrations for Stationary Sources Analysis 13-22

Table 13.7: Ambient Background Concentrations 13-23
Table 13.8: No-Action Maximum Predicted CO Concentrations (ppm) 13-24
Table 13.9: No-Action Maximum Predicted 24-Hour PM_{10} Concentrations ($\mu g/m^3$) 13-24
Table 13.10: With-Action Maximum Predicted CO Concentrations (ppm) 13-25
Table 13.11: With-Action Maximum Predicted 24-Hour PM_{10} Concentrations ($\mu g/m^3$) 13-26
Table 13.12: Maximum Predicted 24-Hour $PM_{2.5}$ Incremental Concentrations ($\mu g/m^3$) 13-26
Table 13.13: Maximum Predicted Annual $PM_{2.5}$ Incremental Concentrations ($\mu g/m^3$) 13-26
Table 13.14: HVAC Screening Analysis Results 13-28
Table 13.15: Existing Active Industrial Sources Permit Information 13-32
Table 13.16: Maximum Predicted Impacts on Projected and Potential Sites from Industrial Sources 13-33
Table 13.16: Maximum Predicted Impacts on Projected and Potential Sites from Industrial Sources (Continued) 13-34
Table 13.17: Cancer Risk (CR) and Chronic Non-Cancer Hazard Quotients (HQ) and Total Hazard Index (HI) of the Toxic Pollutants 13-36
Table 13.18: Acute Quotients (AHQ) and Total Hazard Index (AHI) of the Toxic Pollutants 13-37
Table 13.19: Emission Rates & Stack Parameters for Existing Power Plant Building 13-37
Table 13.20: Maximum Predicted Concentration ($\mu g/m^3$) from Existing Power Plant Building 13-38

Chapter 14: Greenhouse Gas Emissions

Table 14.1: Global Warming Potential for Primary Greenhouse Gases 14-3
Table 14.2: Operational Emissions 14-4
Table 14.3: Proposed Action (RWCDS) Annual Vehicle Miles Traveled (miles per year) 14-5
Table 14.4: Mobile Source Emissions 14-5
Table 14.5: Total GHG Emissions 14-6

Chapter 18: Construction

Table 18.1: Quarterly Peak Numbers of Daily Construction Workers and Delivery Trucks (16 Projected Development Sites with New Construction) 18-8
Table 18.2: Total Daily Vehicle Trips During Construction by Quarter 18-11
Table 18.3: 2032 First Quarter Construction-Vehicle Trip Projections (in PCEs) 18-12
Table 18.4: 2032 First Quarter Construction Weekday AM Transit Trips 18-14
Table 18.5: 2032 First Quarter Construction Weekday PM Transit Trips 18-14
Table 18.6: 2032 First Quarter Construction Weekday AM Pedestrian Trips 18-16
Table 18.7: 2032 First Quarter Construction Weekday PM Pedestrian Trips 18-16
Table 18.8: Summary of Significant Adverse Traffic Impacts 18-21
Table 18.9: Ambient Background Concentrations 18-28
Table 18.10 Maximum Predicted Total Concentrations for Construction Activities 18-29
Table 18.11 Construction Equipment Noise Emission Levels (dBA) 18-32
Table 18.12: Construction Noise Receptor Locations 18-35
Table 18.13: Construction Noise Analysis Results (dBA) 18-37
Table 18.14: Vibration Source Levels for Construction Equipment 18-42

Chapter 19: Mitigation

Table 19.1: Summary of Movements/Intersections with Significant Adverse Traffic Impacts 19-4

Table 19.2: Summary of Locations with Significant Adverse Traffic Impacts 19-5
Table 19.3: Unmitigated Pedestrian Impacts 19-9
Table 19.4: AM Proposed Traffic Mitigation Measures 19-17
Table 19.5: Midday Proposed Traffic Mitigation Measures 19-21
Table 19.6: PM Proposed Traffic Mitigation Measures 19-25
Table 19.7: AM Level of Service Analysis with and without Proposed Mitigation 19-30
Table 19.8: Midday Level of Service Analysis with and without Proposed Mitigation 19-40
Table 19.9: PM Level of Service Analysis with and without Proposed Mitigation 19-49
Table 19.10: Action-With-Mitigation, Sidewalk Conditions 19-62
Table 19.11: Action-With-Mitigation, AM Peak Hour Crosswalk Conditions 19-65
Table 19.12: Action-With-Mitigation: Midday Peak Hour Crosswalk Conditions 19-66
Table 19.13: Action-With-Mitigation: PM Peak Hour Crosswalk Conditions 19-67
Table 19.14: Action-With-Mitigation: AM Peak Hour Corner Conditions 19-69
Table 19.15: Action-With-Mitigation: Midday and PM Peak Hour Corner Conditions 19-70
Table 19.16: Maximum Predicted PM2.5 Concentrations (µg/m3) with Traffic Mitigation 19-71
Table 19.17: AM Proposed Traffic Mitigation Measures - Construction 19-73
Table 19.18: PM Proposed Traffic Mitigation Measures - Construction 19-73
Table 19.19: AM Level of Service Analysis with and without Proposed Mitigation - Construction 19-74
Table 19.20: PM Level of Service Analysis with and without Proposed Mitigation - Construction 19-75

Chapter 20: Alternatives

Table 20.1: Comparison of Proposed Action and Lesser Density Alternative FARs by Subarea **20-4**
Table 20.2: Summary of Level of Service by Movement – No-Action Alternative vs. Proposed Action **20-12**
Table 20.3: Summary of Lesser Density Alternative Development Scenario **20-25**
Table 20.4: Summary of Lesser Density Alternative Population and Employment **20-25**
Table 20.5: Summary of No-Action to With-Action Incremental Development – Proposed Action vs. Lesser Density Alternative **20-25**
Table 20.6: Net Difference in Person Trips between the Lesser Density Alternative and the Proposed Action **20-33**
Table 20.7: Net Difference in Vehicle Trips between the Lesser Density Alternative and the Proposed Action **20-33**
Table 20.8: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Lesser Density Alternative and Proposed Action **20-35**
Table 20.9: Number of Subway Station Elements with Significant Adverse Transit Impacts – Comparison of Lesser Density Alternative and Proposed Action **20-36**
Table 20.10: Number of Locations with Significant Adverse Pedestrian Impacts – Comparison of Lesser Density Alternative and Proposed Action **20-37**

Chapter 21: Conceptual Analysis

Table 21.1: Comparison of Special Permit Scenario to With-Action RWCDS 21-5
Table 21.2: Conceptual Analysis - Special Permit Scenario 21-8
Table 21.3: Conceptual Analysis - Special Permit Scenario Increment 21-9
Table 21.4: Net Difference in Person Trips between the Special Permit Scenario and the Proposed Action 21-17
Table 21.5: Net Difference in Vehicle Trips between the Special Permit Scenario and the Proposed Action 21-17
Table 21.6: Number of Intersections and Approaches with Significant Adverse Traffic Impacts – Comparison of Special Permit Scenario and Proposed Action 21-19

Table 21.7: Off-Street Parking Capacity, Demand, and Utilization – Comparison of Special Permit Scenario and Proposed Action 21-21

List of Figures

Executive Summary

Following Page:

Figure S-1: Proposed Rezoning Area S-1
Figure S-2: Proposed Subdistricts S-10
Figure S-3: Public Realm Improvements S-12
Figure S-4: Pedestrian Plaza Illustration S-1 4
Figure S-5: Park Avenue Improvements S-14
Figure S-6: Existing Zoning S-16
Figure S-7: Proposed Zoning Amendment S-17
Figure S-8: Proposed Rezoning Area RWDCS Sites S-17

Chapter 1: Project Description

Figure 1-1: Proposed Rezoning Area 1-1
Figure 1-2: Proposed Subdistricts 1-14
Figure 1-3: Public Realm Improvements 1-16
Figure 1-4: Pedestrian Plaza Illustration 1-17
Figure 1-5: Park Avenue Improvements 1-17
Figure 1-6: Existing Zoning 1-21
Figure 1-7: Proposed Zoning Amendments 1-21
Figure 1-8: Proposed Rezoning Area RWCDS Sites 1-23

Chapter 2: Land Use

Figure 2-1: Land Use and Zoning Study and Analysis Areas (Primary and Secondary) 2-2
Figure 2-2: Coastal Zone Boundary 2-2
Figure 2-3: Primary Study Area Existing Land Use 2-4
Figure 2-4: Secondary Study Area Existing Land Use 2-6
Figure 2-5: Existing Zoning 2-10
Figure 2-6: Special Midtown District and Subdistricts 2-12
Figure 2-7: Historic Resources 2-18
Figure 2-8: Business Improvement Districts 2-18
Figure 2-9: No Build Development Projects 2-20
Figure 2-10: Proposed Zoning Amendments 2-24
Figure 2-11: Proposed FAR Subareas 2-24

Chapter 3: Socioeconomic Conditions

Figure 3-1: Socioeconomics Study Area 3-6
Figure 3-2: Office Submarket Boundaries 3-16

Figure 3.3: Office Buildings by Year Built....3-18
Figure 3.4: Office Buildings by Floorspace....3-19
Figure 3.5: Hotel Locations....3-31

Chapter 4: Open Space

Figure 4-1: Open Space Study Area....4-5
Figure 4-2: Existing Open Space Inventory....4-11
Figure 4-3: Open Space Resources in the No-Action Condition....4-25
Figure 4-4: Open Space Resources Observed Utilization Levels....4-31

Chapter 5: Shadows

Figure 5-1: Open Spaces and Historic Resources within the Maximum Shadow Radius (Tiers 1 and 2)....5-3
Figure 5-2a: P3 December Detailed Shadows Analysis....5-7
Figure 5-2b: P3 March Detailed Shadows Analysis....5-7
Figure 5-2c: P3 May Detailed Shadows Analysis....5-7
Figure 5-2d: P3 June Detailed Shadows Analysis....5-7
Figure 5-3a: P5 March Detailed Shadows Analysis....5-7
Figure 5-3b: P5 May Detailed Shadows Analysis....5-7
Figure 5-3c: P5 June Detailed Shadows Analysis....5-7
Figure 5-4a: P15 December Detailed Shadows Analysis....5-7
Figure 5-4b: P15 March Detailed Shadows Analysis....5-7
Figure 5-4c: P15 May Detailed Shadows Analysis....5-7
Figure 5-4d: P15 May Detailed Shadows Analysis....5-7
Figure 5-5: P25N May Detailed Shadows Analysis....5-7
Figure 5-6a: P27 March Detailed Shadows Analysis....5-7
Figure 5-6b: P27 May Detailed Shadows Analysis....5-7
Figure 5-6c: P27 June Detailed Shadows Analysis....5-7
Figure 5-7a: P28 March Detailed Shadows Analysis....5-7
Figure 5-7b: P28 May Detailed Shadows Analysis....5-7
Figure 5-7c: P28 June Detailed Shadows Analysis....5-7
Figure 5-8: P30 May Detailed Shadows Analysis....5-7
Figure 5-9a: P31 December Detailed Shadows Analysis....5-7
Figure 5-9b: P 31 March Detailed Shadows Analysis....5-7
Figure 5-9c: P31 May Detailed Shadows Analysis....5-7
Figure 5-10: POPS No. 2 Detailed Shadow Analysis....5-7
Figure 5-11: POPS No. 3 Detailed Shadow Analysis....5-7
Figure 5-12: POPS No. 4 Detailed Shadow Analysis....5-7
Figure 5-13: POPS No. 5 Detailed Shadows Analysis....5-7
Figure 5-14: POPS No. 6 Detailed Shadows Analysis....5-7
Figure 5-15: POPS No. 8 Detailed Shadows Analysis....5-7
Figure 5-16: POPS No. 9 Detailed Shadows Analysis....5-7
Figure 5-17: POPS No. 10 Detailed Shadows Analysis....5-7
Figure 5-18: POPS No. 11 Detailed Shadows Analysis....5-7
Figure 5-19: POPS No. 12 Detailed Shadows Analysis....5-7

Figure 5-20: POPS No. 13 Detailed Shadows Analysis 5-7
Figure 5-21: POPS No. 15 Detailed Shadows Analysis 5-7
Figure 5-22: POPS No. 16 Detailed Shadows Analysis 5-7
Figure 5-23: POPS No. 17 Detailed Shadows Analysis 5-7
Figure 5-24: POPS No. 18 Detailed Shadows Analysis 5-7
Figure 5-25: POPS No. 19 Detailed Shadows Analysis 5-7
Figure 5-26: POPS No. 20 Detailed Shadows Analysis 5-7
Figure 5-27: POPS No. 21 Detailed Shadows Analysis 5-7
Figure 5-28: POPS No. 22 Detailed Shadows Analysis 5-7
Figure 5-29: POPS No. 23 Detailed Shadows Analysis 5-7
Figure 5-30: POPS No. 24 Detailed Shadows Analysis 5-7
Figure 5-31: POPS No. 25 Detailed Shadows Analysis 5-7
Figure 5-32: POPS No. 26 Detailed Shadows Analysis 5-7
Figure 5-33: POPS No. 27 Detailed Shadows Analysis 5-7
Figure 5-34: POPS No. 28 Detailed Shadows Analysis 5-7
Figure 5-35: POPS No. 30 Detailed Shadows Analysis 5-7
Figure 5-36: POPS No. 31 Detailed Shadows Analysis 5-7
Figure 5-37: POPS No. 32 Detailed Shadows Analysis 5-7
Figure 5-38: POPS No. 33 Detailed Shadows Analysis 5-7
Figure 5-39: POPS No. 48 Detailed Shadows Analysis 5-7
Figure 5-40: POPS No. 62 Detailed Shadows Analysis 5-7
Figure 5-41: POPS No. 63 Detailed Shadows Analysis 5-7
Figure 5-42: POPS No. 66 Detailed Shadows Analysis 5-7
Figure 5-43: POPS No. 68 Detailed Shadows Analysis 5-7
Figure 5-44: POPS No. 70 Detailed Shadows Analysis 5-7
Figure 5-45: POPS No. 72 Detailed Shadows Analysis 5-7
Figure 5-46: POPS No. 82 Detailed Shadows Analysis 5-7
Figure 5-47: POPS No. 83 Detailed Shadows Analysis 5-7
Figure 5-48: POPS No. 84 Detailed Shadows Analysis 5-7
Figure 5-49: POPS No. 85 Detailed Shadows Analysis 5-7
Figure 5-50: POPS No. 103 Detailed Shadows Analysis 5-7
Figure 5-51: POPS No. 143 Detailed Shadows Analysis 5-7
Figure 5-52: H1 December Detailed Shadows Analysis 5-7
Figure 5-53a: H2 March Detailed Shadows Analysis 5-7
Figure 5-53b: H2 May Detailed Shadows Analysis 5-7
Figure 5-7a: H3 May Detailed Shadows Analysis 5-7
Figure 5-7b: H3 June Detailed Shadows Analysis 5-7
Figure 5-55a: H5 May Detailed Shadows Analysis 5-7
Figure 5-55b: H5 June Detailed Shadows Analysis 5-7
Figure 5-56a: H6 December Detailed Shadows Analysis 5-7
Figure 5-56b: H6 March Detailed Shadows Analysis 5-7
Figure 5-56c: H6 May Detailed Shadows Analysis 5-7
Figure 5-56d: H6 June Detailed Shadows Analysis 5-7
Figure 5-57: H12 May Detailed Shadows Analysis 5-7
Figure 5-58a: H14 December Detailed Shadows Analysis 5-7
Figure 5-58b: H14 March Detailed Shadows Analysis 5-7
Figure 5-58c: H14 June Detailed Shadows Analysis 5-7
Figure 5-59a: H15 May Detailed Shadows Analysis 5-7

Figure 5-59b: H15 June Detailed Shadows Analysis 5-7
Figure 5-60: H17 December Detailed Shadows Analysis 5-7
Figure 5-61a: H18 March Detailed Shadows Analysis Base 5-7
Figure 5-61b: H18 May Detailed Shadows Analysis Base 5-7
Figure 5-62a: H19 March Detailed Shadows Analysis Base 5-7
Figure 5-62b: H19 May Detailed Shadows Analysis Base 5-7
Figure 5-62c: H19 June Detailed Shadows Analysis Base 5-7
Figure 5-63a: H20 December Detailed Shadows Analysis 5-7
Figure 5-63b: H20 March Detailed Shadows Analysis 5-7
Figure 5-63c: H20 May Detailed Shadows Analysis 5-7
Figure 5-63d: H20 June Detailed Shadows Analysis 5-7
Figure 5-64: H21 Dec Detailed Shadows Analysis Base 5-7
Figure 5-65a: H22 Dec Detailed Shadows Analysis Base 5-7
Figure 5-65b: H22 May Detailed Shadows Analysis Base 5-7
Figure 5-65c: H22 June Detailed Shadows Analysis Base 5-7

Chapter 6: Historic and Cultural Resources

Figure 6-1: Historic Resources Study Area and RWCDS Sites 6-1
Figure 6-2: Designated Historic Districts 6-7
Figure 6-3: Representative Photographs of Designated Historic Districts and Resources 6-7
Figure 6-4: Designated Historic Landmarks 6-7
Figure 6-5: Eligible Historic Districts and Landmarks 6-7
Figure 6-6: Representative Photographs of Eligible Historic Resources in the Project Area 6-7
Figure 6-7: Designated Historic Districts and Landmarks, and RWCDS Sites 6-7
Figure 6-8: Eligible Historic Districts and Landmarks, and RWCDS Sites 6-7

Chapter 7: Urban Design and Visual References

Figure 7-1: Urban Design and Visual Resources Primary Study Area - Aerial View 7-5
Figure 7-2: Urban Design Primary and Secondary Study Areas 7-6
Figure 7-3: Existing Density in Primary and Secondary Study Areas 7-8
Figure 7-4: Existing Building Height (Number of Floors) in Primary and Secondary Study Areas 7-8
Figure 7-5a: Views of the Built Context within the Primary Study Area Key Map 7-8
Figure 7-5b: Views of the Built Context within the Primary Study Area 7-8
Figure 7-6a: Views of the Built Context within the Secondary Study Area Key Map 7-22
Figure 7-6b: Views of the Built Context within the Secondary Study Area 7-22
Figure 7-7: Development and Transportation Projects in the Future without the Proposed Action 7-33
Figure 7-8: Urban Design Primary and Secondary Study Areas 7-44
Figure 7-9a: Public Realm Improvements 7-50
Figure 7-9b: Pedestrian Plaza Illustration 7-50
Figure 7-9c: Park Avenue Improvements 7-50
Figure 7-10: Visual Resources and Photo Key for Visual Resources Figures 7-55
Figure 7-11: Visual Resources Photographs 7-55

Chapter 9: Water and Sewer Infrastructure

Figure 9-1: Subcatchment Areas Map 9-6

Chapter 12: Transportation

Figure 12-1: Proposed Rezoning Area RWCDS Sites 12-1
Figure 12-2: Traffic Analysis Locations 12-16
Figure 12-3: Study Area Subway Stations 12-16
Figure 12-4: Study Area Local Bus Routes 12-18
Figure 12-5: Study Area Express Bus Routes 12-18
Figure 12-6: Pedestrian Study Areas 12-22
Figure 12-7a: 2016 Existing Traffic Volumes Weekday AM Peak Hour 12-35
Figure 12-7b: 2016 Existing Traffic Volumes Weekday AM Peak Hour 12-35
Figure 12-8a: 2016 Existing Traffic Volumes Weekday Midday Peak Hour 12-35
Figure 12-8b: 2016 Existing Traffic Volumes Weekday Midday Peak Hour 12-35
Figure 12-9a: 2016 Existing Traffic Volumes Weekday PM Peak Hour 12-35
Figure 12-9b: 2016 Existing Traffic Volumes Weekday PM Peak Hour 12-35
Figure 12-10a: 2036 No-Action Traffic Volumes Weekday AM Peak Hour 12-62
Figure 12-10b: 2036 No-Action Traffic Volumes Weekday AM Peak Hour 12-62
Figure 12-11a: 2036 No-Action Traffic Volumes Weekday Midday Peak Hour 12-62
Figure 12-11b: 2036 No-Action Traffic Volumes Weekday Midday Peak Hour 12-62
Figure 12-12a: 2036 No-Action Traffic Volumes Weekday PM Peak Hour 12-62
Figure 12-12b: 2036 No-Action Traffic Volumes Weekday PM Peak Hour 12-62
Figure 12-13a: Project Generated Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-13b: Project Generated Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-14a: Project Generated Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-14b: Project Generated Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-15a: Project Generated Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-15b: Project Generated Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-16a: 2036 With-Action Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-16b: 2036 With-Action Traffic Volumes Weekday AM Peak Hour 12-79
Figure 12-17a: 2036 With-Action Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-17b: 2036 With-Action Traffic Volumes Weekday Midday Peak Hour 12-79
Figure 12-18a: 2036 With-Action Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-18b: 2036 With-Action Traffic Volumes Weekday PM Peak Hour 12-79
Figure 12-19: Impacted Intersections Weekday AM Peak Hour 12-98
Figure 12-20: Impacted Intersections Weekday Midday Peak Hour 12-98
Figure 12-21: Impacted Intersections Weekday PM Peak Hour 12-98
Figure 12-22: Grand Central 42nd Street Subway Station Complex—Lexington Avenue Line and Shuttle Mezzanine 12-100
Figure 12-23: Grand Central 42nd Street Subway Station Complex—Flushing Line 12-101
Figure 12-24: 42nd Street-Bryant Park/Fifth Avenue Subway Station Complex 12-106
Figure 12-25: 47th-50th Streets-Rockefeller Center Subway Station 12-110
Figure 12-26: 51st Street/Lexington Avenue-53rd Street Subway Station Complex 12-114
Figure 12-27: Lexington Avenue-59th Street Subway Station 12-118
Figure 12-28: Fifth Avenue-53rd Street Subway Station 12-120

Figure 12-29: Grand Central Terminal 47th Street Crosspassage 12-123
Figure 12-30: Grand Central Terminal 47th Street Crosspassage in No-Action Condition 12-147
Figure 12-31: Off-Street Parking Facilities 12-239
Figure 12-32a: Off-Street Parking Regulations 12-243
Figure 12-32b: Off-Street Parking Regulations 12-243

Chapter 13: Air Quality

Figure 13-1: Air Quality Mobile Sources Analysis Sites 13-14

Chapter 15: Noise

Figure 15-1: Noise Receptor Locations 15-6

Chapter 17: Neighborhood Character

Figure 17-1: Study and Analysis Areas (Primary and Secondary) ..... Figure 17-3

Chapter 18: Construction

Figure 18-1a: Construction Schedule: 2019-2028 18-6
Figure 18-1b: Construction Schedule: 2026-2036 18-6
Figure 18-2: Traffic Analysis Locations 18-21
Figure 18-3: Construction Air Quality Analysis Clusters 18-26
Figure 18-4: Projected Peak Daily PM2.5 Construction Emissions Profile by Quarter 18-26
Figure 18-5: Projected Annual PM2.5 Construction Emissions Profile 18-26
Figure 18-6: Noise Monitoring and Receptor Sites 18-35
Figure 18-7: Worst Case Extent of Construction Noise Impact 18-40

Chapter 19: Mitigation

Figure 19-1: With-Action Intersection Mitigation Weekday AM Peak Hour 19-29
Figure 19-2: With-Action Intersection Mitigation Weekday Midday Peak Hour 19-29
Figure 19-3: With-Action Intersection Mitigation Weekday PM Peak Hour 19-29

Chapter 20: Alternatives

Figure 20-1: Lesser Density Alternatives Subdistricts and Sites 20-4

Chapter 21: Conceptual Analysis

Figure 21-1: Conceptual Special Permit Scenario Sites 21-4