500 Kent Avenue
EIS

Final Environmental Impact Statement (FEIS)

CEQR No. 21DCP139K
ULURP Nos.: C230293ZMK
C230294ZSK
C230296ZSK
N230295ZCK

Lead Agency:
City Planning Commission, City of New York
Daniel R. Garodnick, Chair

June 14th, 2024

500 Kent Avenue EIS

Final Environmental Impact Statement (DEIS)

Project Location:	Brooklyn, New York Community District 2
Type of Action:	Type I
CEQR No.:	21DCP139K
ULURP Nos.:	ULURP Nos.:C230293ZMK C230294ZSK C230296ZSK N230295ZCK
Lead Agency:	City Planning Commission, City of New York Daniel R. Garodnick, Chair
Lead Agency Contact:	Stephanie Shellooe, AICP Environmental Assessment and Review Division New York City Department of City Planning 120 Broadway New York, New York, 10271
Project Applicant:	500 Kent LLC and United Jewish Organizations of Williamsburg, Inc.
Prepared by:	Philip Habib & Associates 432 Park Avenue South, Floor 6 New York, NY 10016 AKRF, Inc. 440 Park Avenue South New York, NY 10016
Acceptance Date:	June 14th, 2024

A public hearing on the Draft Environmental Impact Statement (DEIS) was held on May 15th, 2024. Written comments on the DEIS were received and considered by the Lead Agency until May 28th, 2024. The FEIS is available on the website of the New York City Department of City Planning, via the 500 Kent Avenue project page on ZAP: https//zap.planning.nyc.gov/projects/2020K0289, select Public Documents, then "FEIS_21DCP139K".

Foreword **Foreword-1**

Executive Summary **ES-1**
A. Introduction ES-1
B. Existing Conditions ES-2
Description of the Project Site ES-2
C. Description of the Proposed Actions ES-2
Zoning Map Amendment ES-3
Bulk Modifications on Waterfront Block Special Permit ES-3
Public Parking Garage Special Permit (ZR 74-52) ES-4
Waterfront Zoning Certification (ZR 62-81) ES-4
D. Purpose and Need for the Proposed Action ES-5
E. Description of the Proposed Project ES-6
F. Analysis Framework for Environmental Review ES-6
Analysis Year ES-6
Reasonable Worst-Case Development Scenario (RWCDS) ES-7
Future Without the Proposed Action (No-Action Condition) ES-7
Future With the Proposed Action (With-Action Condition) ES-8
City Environmental Quality Review (CEQR) ES-8
G. Probable Impacts of the Proposed Action ES-10
Land Use, Zoning, and Public Policy ES-10
Socioeconomic Conditions ES-10
Open Space ES-12
Shadows ES-13
Historic and Cultural Resources ES-13
Archaeological Resources ES-13
Architectural Resources ES-14
Urban Design and Visual Resources ES-15
Natural Resources ES-16
Hazardous Materials ES-16
Water and Sewer Infrastructure ES-17
Water Supply ES-17
Sanitary (Dry Weather) Flows ES-17
Stormwater (Wet Weather) Flows ES-18
Energy ES-18
Transportation ES-18
Traffic ES-18
Transit ES-19
Pedestrians ES-20
Citywide Ferry Service ES-20
Vehicular and Pedestrian Safety ES-20
Parking ES-21
Air Quality ES-21
Greenhouse Gas Emissions ES-22
Greenhouse Gas Emissions ES-22
Resilience to Climate Change ES-22
Noise ES-23
Public Health ES-23
Neighborhood Character ES-24
Construction ES-24
H. Mitigation ES-26
Transportation ES-26
Traffic ES-26

Pedestrians ES-26
Construction ES-27
I. Alternatives ES-27
No-Action Alternative ES-28
No Significant Adverse Impacts Alternative ES-28
J. Unavoidable Adverse Impacts ES-28
Transportation ES-29
Construction ES-29
K. Growth-Inducing Aspects ES-30
L. Irreversible and Irretrievable Commitments of Resources ES-30

Chapter 1: Project Description 1-1
A. Introduction 1-1
B. Background and Existing Conditions 1-2
Proposed Rezoning Area (Project Site) 1-2
Zoning 1-2
Brooklyn Navy Yard Industrial Business Zone (IBZ) 1-3
Neighborhood Context 1-3
C. Description of the Proposed Action 1-4
Zoning Map Amendment 1-4
Bulk Modifications on Waterfront Block Special Permits (ZR 62-837) 1-4
Public Parking Garage Special Permit (ZR 74-52) 1-5
Waterfront Zoning Certification (ZR 62-81) 1-6
Restrictive Declaration and (E) Designation 1-6
D. Purpose and Need for the Proposed Action 1-6
E. Description of the Proposed Project 1-7
F. Analysis Framework and Reasonable Worst Case Development Scenario (RWCDS) 1-8
Analysis Year 1-8
Reasonable Worst-Case Development Scenario (RWCDS) 1-9
Future Without the Proposed Action (No-Action Condition) 1-9
Future with the Proposed Action (With-Action Condition) 1-9
G. Public Review Process 1-10
Uniform Land Use Review Process (ULURP) 1-10
City Environmental Quality Review (CEQR) 1-11

Chapter 2: Land Use, Zoning, and Public Policy 2-1
A. Introduction 2-1
B. Principal Conclusions 2-2
C. Methodology 2-2
Analysis Year 2-3
Study Area Definition 2-3
Data Sources 2-3
D. Existing Conditions 2-4
Land Use 2-4
Primary Study Area 2-4
Secondary Study Area (Quarter-Mile Radius) 2-5
Zoning 2-7
Primary Study Area Zoning 2-7
Secondary Study Area (Quarter-Mile Radius) Zoning 2-7
Public Policy 2-9
Public Policies Applicable to the Project Site and/or the Study Area 2-9
Legislative and Regulatory Background 2-11
New York City Panel on Climate Change: Projections 2-12
E. Future Without the Proposed Action 2-13
Land Use 2-13
Primary Study Area 2-13
Secondary Study Area (Quarter-Mile Radius) 2-13

Zoning....2-14
Primary Study Area....2-14
Secondary Study Area (Quarter-Mile Radius)....2-14
Public Policy....2-14
F. Future With the Proposed Action....2-15
Land Use....2-15
Primary Study Area....2-15
Secondary Study Area (Quarter-Mile Radius)....2-16
Assessment....2-16
Zoning....2-16
Secondary Study Area (Quarter-Mile Radius)....2-18
Assessment....2-18
Public Policy....2-19
Consistency with Applicable WRP Policies....2-21
Flood Insurance Rate Maps and Base Design Flood Elevations....2-26
Project Site Location in PFIRM 100-year Floodplain....2-27
Detailed Assessment....2-27
Identify Vulnerabilities and Consequences....2-28
Project Site....2-28
Identify Adaptive Strategies....2-29
Assess Policy Consistency....2-29
Conclusion.... 2-33

Chapter 3: Socioeconomic Conditions....3-1
A. Introduction....3-1
B. Principal Conclusions....3-1
Direct Residential Displacement....3-2
Indirect Residential Displacement....3-2
Direct Business Displacement....3-2
Indirect Business Displacement....3-2
Adverse Effects on Specific Industries....3-3
C. Methodology....3-3
Determining Whether a Socioeconomic Assessment is Appropriate....3-4
Analysis Format....3-5
Study Area Definition....3-6
Data Sources....3-6
D. Preliminary Assessment....3-7
Indirect Business and Institutional Displacement....3-7
Profile of Existing Employment and Business in the Study Area....3-8
Real Estate Trends....3-12
Future Without the Proposed Action....3-13
Future With the Proposed Action....3-13
Assessment....3-16

Chapter 4: Open Space....4-1
A. Introduction....4-1
B. Principal Conclusions....4-1
Direct Effects....4-1
Indirect Effects....4-2
C. Methodology....4-2
Direct Effects....4-2
Indirect Effects....4-2
Study Areas....4-3
Analysis Framework....4-4
Impact Assessment....4-5
D. Existing Conditions....4-6
Study Area Population....4-6

Inventory of Publicly Accessible Open Space....4-6
Non-Residential (Quarter-mile Study Area)....4-7
Assessment of Open Space Adequacy....4-11
Study Area....4-11
Quantitative Assessment....4-11
Qualitative Assessment....4-12
E. Future Without the Proposed Action (No-Action Condition)....4-12
Study Area Population....4-12
Open Space Resources....4-13
Assessment of Open Space Adequacy....4-13
Non-Residential (Quarter-mile Study Area)....4-13
F. Future With the Proposed Action (With-Action Condition)....4-14
Direct Effects....4-14
Indirect Effects....4-14
Study Area Population....4-14
Open Space Resources....4-15
Assessment of Open Space Adequacy....4-15
Non-Residential (Quarter-mile Study Area)....4-15
Determining Impact Significance....4-16
Non-Residential (Quarter-mile Study Area)....4-16

Chapter 5: Shadows....5-1
A. Introduction....5-1
B. Principal Conclusions....5-1
C. Methodology....5-1
D. Preliminary Screening....5-4
Tier I Screening Assessment....5-4
Tier II Screening Assessment....5-4
Tier III Screening Assessment....5-4
E. Detailed Assessment....5-6
Resources of Concern....5-6
Roberto Clemente Ballfield....5-6
Epiphany Playground....5-6
NYCHA Independence Towers Grounds 1 and 2....5-7
East River....5-7
Shadows Analysis....5-7
March 21st/September 21st....5-8
May 6th/August 6th....5-9
June 21st....5-10
December 21st....5-11
Assessment....5-12
Roberto Clemente Ballfield....5-12
Epiphany Playground....5-13
NYCHA Independence Towers Grounds I....5-13
East River....5-13
Project Generated Open Space....5-14

Chapter 6: Historic and Cultural Resources....6-1
A. Introduction....6-1
B. Principal Conclusions....6-1
Archaeological Resources....6-1
Architectural Resources....6-2
Direct (Physical) Impacts....6-2
Indirect (Contextual) Impacts....6-2
Construction-Related Impacts....6-3
Shadows Impacts....6-3
C. Development Background....6-3

D. Archaeological Resources 6-6
Existing Conditions 6-6
Future Without the Proposed Action (No-Action Condition)....6-7
Future With the Proposed Action (With-Action Condition)....6-8
Assessment 6-8
E. Architectural Resources....6-8
Criteria & Regulations....6-8
Existing Conditions 6-9
Project Site....6-9
400-foot Study Area 6-9
Brooklyn Navy Yard Historic District....6-9
Future Without the Proposed Action (No-Action Condition)....6-10
Anticipated Developments in the No-Action Condition....6-11
Future With the Proposed Action (With Action Condition) 6-12
Direct (Physical) Impacts 6-12
Indirect (Contextual) Impacts 6-13
Construction-Related Impacts....6-14
Shadows Impacts 6-14

Chapter 7: Urban Design and Visual Resources....7-1
A. Introduction 7-1
B. Principal Conclusions 7-2
Urban Design....7-2
Visual Resources 7-2
C. Methodology....7-2
Wind Screening 7-3
Definition of Study Area 7-3
D. Preliminary Assessment 7-4
E. Existing Conditions 7-4
Primary Study Area (Project Area)....7-4
Secondary Study Area 7-5
Sub-areas 7-6
Streets and Streetscapes....7-6
Buildings....7-8
Open Space....7-8
Natural Features....7-10
View Corridors and Visual Resources....7-10
F. Future Without the Proposed Action 7-11
Primary Study Area (Project Area)....7-11
Secondary Study Area 7-11
G. Future With the Proposed Action (With-Action Condition) 7-12
Project Area 7-12
Assessment 7-12
Secondary Study Area 7-13
Assessment 7-13
Visual Resources 7-14

Chapter 8: Natural Resources 8-1
A. Introduction 8-1
B. Principal Conclusions 8-1
C. Methodology....8-2
Study Area and Data Sources 8-2
D. Regulatory Context....8-3
Federal 8-3
New York State 8-4
Local....8-5
E. Existing Conditions 8-6

Groundwater and Aquifers 8-6
Floodplains 8-7
Surface Waters and Wetlands 8-7
Water Quality 8-8
Aquatic Biota 8-8
Wildlife 8-9
Threatened, Endangered and Special Concern Species and Significant Habitat Areas 8-9
F. Future Without the Proposed Action (No-Action Condition) 8-10
Groundwater and Floodplain 8-10
Water Quality and Aquatic Biota 8-10
Terrestrial Ecological Communities, Vegetation and Wildlife 8-10
G. Future With the Proposed Action (With-Action Condition) 8-10
Water Quality 8-11
Groundwater 8-11
Floodplains 8-12
Wetlands and Aquatic Resources 8-12
Terrestrial and Ecological Communities and Vegetation 8-14
Wildlife 8-14
Threatened, Endangered, and Special Concern Species and Significant Habitat Areas 8-15

Chapter 9: Hazardous Materials 9-1
A. Introduction 9-1
B. Principal Conclusions 9-1
C. Transportation 9-2
D. Existing Conditions 9-2
Current and Historic Site Use 9-2
Remedial Program 9-3
Confirmation of Remediation 9-4
Requirements for New Construction 9-5
Periodic Review Report 9-5
E. Future Without the Proposed Action (No-Action Condition) 9-5
F. Future With the Proposed Action (With-Action Condition) 9-6

Chapter 10: Water and Sewer Infrastructure 10-1
A. Introduction 10-1
Existing On-site Stormwater Management Requirements and Unified Stormwater Rule 10-1
B. Principal Conclusions 10-2
Water Supply 10-2
Sanitary (Dry Weather) Flows 10-3
Stormwater (Wet Weather) Flows 10-3
C. Methodology 10-4
D. Existing Conditions 10-5
Water Supply 10-5
Sewer System 10-5
Sanitary Flows (Dry Weather) 10-8
Stormwater Flows (Wet Weather) 10-8
E. The Future Without the Proposed Action (No-Action Condition) 10-8
Water Supply 10-9
Sewer System 10-9
Sanitary Flows (Dry Weather) 10-9
Stormwater Flows (Wet Weather) 10-10
F. The Future with the Proposed Action (With-Action Condition) 10-11
Water Supply 10-11
Sewer System 10-12
Sanitary Flows (Dry Weather) 10-12
Stormwater Flows (Wet Weather) 10-13

Chapter 11: Energy **11-1**
A. Introduction 11-1
B. Principal Conclusions 11-1
C. Methodology 11-2
D. Existing Conditions 11-2
Energy Supply and Transmission 11-2
Recent Energy Conservation Directives 11-4
Existing Demand 11-5
E. Future Without the Proposed Action (No-Action Condition) 11-5
Energy Supply and Transmission 11-5
No-Action Demand 11-5
F. Future With the Proposed Action (With Action Condition) 11-6
Energy Supply and Transmission 11-6
With-Action Demand 11-6

Chapter 12: Transportation **12-1**
A. Introduction 12-1
B. Principal Conclusions 12-2
Traffic 12-2
Transit 12-3
Subway 12-3
Bus 12-3
Pedestrians 12-4
Citywide Ferry Service 12-4
Vehicular and Pedestrian Safety 12-4
Parking 12-5
C. Preliminary Analysis Methodology 12-5
D. Level I Screening Assessment 12-5
Background 12-5
Transportation Planning Factors 12-6
Travel Demand Forecast 12-6
Traffic 12-8
Transit 12-8
Citywide Ferry Service 12-8
Pedestrians 12-8
E. Level 2 Screening Assessment 12-11
Vehicular Traffic 12-11
Transit 12-11
Subway Stations 12-11
Subway Line Haul 12-12
Bus 12-13
Pedestrians 12-14
Parking 12-15
F. Transportation Analyses Methodologies 12-16
Traffic 12-16
Analysis Methodology 12-16
Significant Impact Criteria 12-17
Transit 12-17
Analysis Methodology 12-17
Significant Impact Criteria 12-19
Pedestrians 12-19
Analysis Methodology 12-19
Significant Impact Criteria 12-20
Vehicular and Pedestrian Safety Evaluation 12-21
G. Traffic 12-23
Existing Conditions 12-23
Study Area Street Network 12-23

Bus Routes....12-24
Truck Routes....12-24
Traffic Conditions....12-25
Intersection Capacity Analysis....12-25
The Future Without the Proposed Action (No-Action Condition)....12-25
Future No-Action Traffic Growth....12-25
Intersection Capacity Analysis....12-25
The Future with the Proposed Action (With-Action Condition)....12-26
Future With-Action Traffic Growth....12-26
Intersection Capacity Analysis....12-26
H. Transit....12-26
Existing Conditions....12-26
Subway Stations....12-26
Bus Service....12-27
The Future Without the Proposed Action (No-Action Condition)....12-28
Subway Stations....12-28
Bus Service....12-29
The Future with the Proposed Action (With-Action Condition)....12-30
Subway Stations....12-30
Bus Service....12-31
I. Pedestrians....12-32
Existing Conditions....12-32
Sidewalks....12-32
Crosswalks....12-32
Corner Areas....12-33
Future Without the Proposed Action (No-Action Condition)....12-34
Sidewalks....12-34
Crosswalks....12-34
Corner Areas....12-34
Future with the Proposed Action (With-Action Condition)....12-35
Sidewalks....12-36
Crosswalks....12-36
Corner Areas....12-38
J. Vehicular and Pedestrian Safety Evaluation....12-38
Recent DOT Initiatives....12-38
Study Area High Crash Locations....12-39

Chapter 13: Air Quality....13-1
A. Introduction....13-1
B. Principal Conclusions....13-1
Mobile Sources....13-1
Stationary Sources....13-1
C. Mobile Sources....13-1
Methodology for Predicting Pollutant Concentrations....13-2
Intersection Analysis....13-2
Vehicle Emissions....13-2
Engine Emissions....13-2
Road Dust....13-3
Traffic Data....13-3
Dispersion Model for Microscale Analyses....13-3
Meteorology....13-4
Analysis Year....13-4
Background Concentrations....13-4
Analysis Site....13-5
Receptor Placement....13-5
Parking Analysis....13-5
Future Without the Proposed Action (No-Action Condition)....13-6

Intersection Analysis 13-6
Future With the Proposed Action (With-Action Condition)....13-7
Intersection Analysis 13-7
Parking Analysis....13-7
D. Stationary Sources....13-8
Introduction 13-8
Large Emission Source Analysis 13-9
Industrial Source Analysis....13-9
Large Emission Source Analysis 13-9
Kent Village Stack Parameters 13-10
Relevant Air Pollutants....13-10
Applicable Air Quality Standards and Significant Impact Criteria....13-11
NO_2 NAAQS 13-11
$PM_{2.5}$ CEQR De Minimis Criteria 13-13
Dispersion Analysis....13-13
Site Geometry....13-13
Meteorological Data 13-14
Background Concentrations....13-14
Receptor Locations....13-14
Emission Rates 13-15
Results 13-16
Natural Gas....13-17
Fuel Oil....13-17
Conclusion....13-19

Chapter 14: Greenhouse Gas Emissions....14-1
A. Introduction 14-1
B. Principal Conclusions....14-2
Greenhouse Gas Emissions....14-2
Resilience to Climate Change....14-2
C. Greenhouse Gas Emissions 14-3
Pollutants of Concern 14-3
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions....14-4
Methodology....14-9
Building Operational Emissions 14-9
Mobile Source Emissions 14-10
Construction Emissions 14-10
Emissions form Solid Waste Management....14-11
Projected GHG Emissions from the RWCDS 14-11
Operational Emissions....14-11
Mobile Source Emissions 14-11
Summary of Emissions....14-12
Consistency with the GHG Reduction Goal....14-12
Elements of the RWCDS that Would Reduce GHG Emissions....14-13
D. Resilience to Climate Change 14-14
Projected Climate Conditions....14-15
Resilience of the Proposed Project to Climate Change....14-17

Chapter 15: Noise 15-1
A. Introduction 15-1
B. Principal Conclusions....15-2
C. Noise Fundamentals 15-2
"A"- Weighted Sound Level (dBA)....15-3
Community Response to Changes in Noise Levels 15-3
Noise Descriptors Used in Impact Assessment 15-4
D. Noise Standard And Criteria 15-5
New York City Noise Code....15-5

New York CEQR Technical Manual Noise Standards 15-6
E. Noise Prediction Methodology 15-6
General Methodology 15-6
Proportional Modeling 15-6
Play Area Noise 15-8
F. Existing Conditions 15-9
Selection of Noise Receptor Locations 15-9
Noise Monitoring 15-10
Equipment Used During Noise Monitoring 15-10
Existing Noise Levels at the Noise Receptor Locations 15-11
Measured Noise Levels 15-11
G. Future Without the Proposed Action (No-Action) 15-12
H. Future With the Proposed Action (With Action) 15-13
Mobile Source Noise 15-13
Play Area Noise 15-14
I. Attenuation Requirements 15-15
J. Other Noise Concerns 15-16
Mechanical Equipment 15-16
Train Noise 15-17
Aircraft Noise 15-17

Chapter 16: Public Health 16-1
A. Introduction 16-1
B. Principal Conclusions 16-1
C. Preliminary Screening 16-2

Chapter 17: Neighborhood Character 17-1
A. Introduction 17-1
B. Principal Conclusions 17-2
C. Methodology 17-2
Study Area 17-2
D. Preliminary Assessment 17-3
Defining Features 17-3
Proposed Project 17-3
Study Area and Surrounding Neighborhood 17-3
Assessment of the Potential to Affect the Defining Features of the Neighborhood 17-4
Land Use, Zoning, and Public Policy 17-4
Socioeconomic Conditions 17-5
Open Space 17-5
Shadows 17-6
Urban Design and Visual Resources 17-6
Transportation 17-8
Noise 17-8

Chapter 18: Construction 18-1
A. Introduction 18-1
B. Principal Conclusions 18-2
Transportation 18-2
C. Regulatory Framework 18-4
Governmental Coordination and Oversight 18-4
D. Construction Schedule and Activities 18-5
Project Site Context 18-5
Preliminary Construction Schedule 18-5
Hours of Work 18-6
Deliveries and Access 18-8
Sidewalk and Lane Closures 18-8
Number of Construction Workers and Materials Deliveries 18-8

E. Probable Impacts of the Proposed Action....18-9
Transportation....18-9
Traffic....18-9
Curb Lane Closures and Staging....18-13
Transit....18-14
Pedestrians....18-14
Parking....18-15
Air Quality....18-15
Determining the Significance of Air Quality Impacts....18-16
Emissions Reduction Measures....18-16
On-Site Construction Activity Assessment....18-18
Construction Air Quality Analysis Results....18-21
Noise....18-21
Sound Level Descriptors....18-22
Construction Noise Analysis Fundamentals....18-22
Construction Noise Analysis Methodology....18-23
Construction Mobile Source Analysis....18-24
Noise Receptor Sites....18-24
Construction Noise Modeling....18-25
Analysis Time Period Selection....18-27
Construction Noise Impacts Criteria....18-27
Evaluation of Construction Noise Levels....18-28
Noise Reduction Measures....18-28
Existing Noise Levels....18-29
Construction Noise Analysis Results....18-30
Conclusions....18-33
Vibration....18-33
Analysis Methodology....18-34
Construction Vibration Analysis Results....18-34
Other Technical Areas....18-35
Land Use and Neighborhood Character....18-35
Socioeconomic Conditions....18-36
Community Facilities....18-36
Open Space....18-36
Historic and Cultural Resources....18-37
Architectural....18-37
Archaeological....18-37
Hazardous Materials....18-37
Natural Resources....18-38
Water Quality....18-38
Groundwater....18-38
Floodplains....18-39
Aquatic Biotica....18-39

Chapter 19: Mitigation....19-1
A. Introduction....19-1
B. Principal Conclusions....19-1
Transportation....19-1
Traffic....19-1
Pedestrians....19-1
Construction....19-2
Traffic....19-2
C. Transportation....19-2
Traffic....19-2
Proposed Schedule for Traffic Mitigation Measures....19-5
Pedestrians....19-5
Crosswalks....19-5

Sidewalks....19-6
Corner Areas....19-6
D. Construction....19-8
Traffic....19-8

Chapter 20: Alternatives....20-1
A. Introduction....20-1
B. Principal Conclusions....20-1
No-Action Alternative....20-1
No Significant Adverse Impacts Alternative....20-2
C. No-Action Alternative....20-2
Land Use, Zoning, and Public Policy....20-3
Socioeconomic Conditions....20-3
Open Space....20-4
Shadows/Natural Resources....20-4
Historic and Cultural Resources....20-4
Urban Design and Visual Resources....20-5
Hazardous Materials....20-5
Water and Sewer Infrastructure....20-5
Energy....20-6
Transportation....20-6
Air Quality....20-8
Greenhouse Gas Emissions and Climate Change....20-8
Noise....20-8
Public Health....20-8
Neighborhood Character....20-9
Construction....20-9
D. No Significant Adverse Impact Alternative....20-9
Transportation....20-10
Traffic....20-10
Assessment....20-10

Chapter 21: Unavoidable Adverse Impacts....21-1
A. Introduction....21-1
B. Principal Conclusions....21-1
C. Transportation....21-2
Traffic....21-2
Pedestrians....21-2
Construction Traffic....21-3

Chapter 22: Growth-Inducing Aspects of the Proposed Action....22-1
A. Introduction....22-1
B. Principal Conclusions....22-2

Chapter 23: Irreversible and Irretrievable Commitments of Resources....23-1

Chapter 24: Response to Comments on the Draft Environmental Impact Statement....24-1
A. Introduction....24-1
B. List of Organizations and Individuals who Commented on the Draft Environmental Impact Statement....24-1
C. Comments and Responses on the Draft Environmental Impact Statement....24-2

Appendices:

Appendix A....Land Use Appendix
Appendix B....Historic Resources Appendix
Appendix C....Hazardous Materials Appendix

Appendix D ..... Transportation Appendix
Appendix E ..... Construction Noise Appendix
Appendix F ..... CPC Public Hearing Transcript Appendix

ES-1 Comparison of 2026 No-Action and With-Action Scenarios ES-7
ES-2 Number of Impacted Intersections and Lane Groups by Peak Hour ES-19
ES-3 Summary of Significantly Impacted Intersections ES-19
ES-4 Number of Impacted Intersections and Lane Groups by Peak Hour (Construction) ES-25
ES-5 Summary of Significantly Impacted Intersections (Construction) ES-25
ES-6 Summary of Lane Groups/Intersection with Significant Adverse Traffic Impacts ES-26
ES-7 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts (Construction) ES-27
1-1 Comparison of 2026 No-Action and With-Action Scenarios 1-9
2-1 Existing Land Uses within the Quarter-Mile Secondary Study Area 2-5
2-2 Study Area Zoning Districts 2-8
2-3 No-Action Developments Within a Quarter Mile of the Project Site 2-13
2-4 Comparison of 2026 No-Action and With-Action Scenarios 2-15
2-5 Comparison of Allowable Uses & Maximum FAR for Existing and Proposed Zoning 2-17
3-1 2018 Estimated Employment in the 0.25-Mile Study Area, Williamsburg, and Brooklyn 3-9
3-2 Comparison of 2013 & 2018 Estimated Private Employment in 0.25-Mile Study Area & Williamsburg 3-10
4-1 Existing Non-residential and Residential Populations 4-6
4-2 Study Area Open Space Resources 4-8
4-3 Existing Passive Open Space Ratio 4-11
4-4 No-Action Study Area Population 4-13
4-5 With-Action Study Area Population and Open Space Ratios 4-15
4-6 Passive Open Space Ratios Summary 4-16
5-1 Sunlight-Sensitive Resources Warranting Further Assessment Based on Tier 1 and 2 Screening 5-5
5-2 Tier III Assessment Results 5-6
5-3 Duration of Shadows on Sunlight Sensitive Resources 5-8
10-1 Existing Red Hook WRRF Average Daily Sewer Flows 10-7
10-2 Existing Newton Creek WRRF Average Daily Sewer Flows 10-7
10-3 Existing Project Site Surface Areas and Runoff Coefficients 10-8
10-4 Existing Project Site Stormwater and Sanitary Sewage Flow Volumes 10-8
10-5 No-Action Project Site Water Consumption and Wastewater Generation 10-9
10-6 No-Action Project Site Surface Areas and Runoff Coefficients 10-10
10-7 No-Action Project Site Stormwater and Sanitary Sewage Flow Volumes 10-10
10-8 No-Action Water Quality Treatment Volume 10-11
10-9 Peak Allowable Stormwater Discharge 10-11
10-10 Expected Water Demand on Project Site- No-action vs. With-Action Conditions 10-12
10-11 Project Site Runoff Coefficient- With Action Condition 10-14
10-12 Project Site Stormwater and Sanitary Sewage Flow Volumes- With Action vs. Existing Conditions 10-14
11-1 Existing Annual Energy Consumption for the Project Site 11-5
11-2 No-Action Annual Energy Consumption for the Project Site 11-5
11-3 With-Action Annual Energy Consumption for the Project Site 11-7
12-1 2024 RWCDS No-Action Land Uses 12-2
12-2 Number of Impacted Intersection and Lane Groups by Peak Hour 12-3
12-3 Summary of Significantly Impacted Intersections 12-3
12-4 Transportation Planning Factors 12-7
12-5 RWCDS Trave; Demand Forecast – Incremental Person Trips 12-9
12-6 RWCDS Travel Demand Forecast – Incremental Vehicle Trips 12-10
12-7 Travel Demand Forecast Summary 12-10
12-8 Subway Assignment Summary 12-12
12-9 Subway Assignments by Direction – J, M, Z Routes 12-13
12-10 Bus Assignment Summary 12-13
12-11 Bus Assignment by Direction – B62 and B67 Routes 12-14
12-12 Weekday Parking Accumulation 12-15
12-13 Intersection Level of Service Criteria 12-17
12-14 Level of Service Criteria for Subway Station Elements 12-18

12-15 Significant Impact Thresholds for Stairways and Passageways....12-19
12-16 Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Description....12-21
12-17 Significant Impact Criteria for Sidewalks with Platooned Flow in a Non-CBD Location....12-22
12-18 Significant Impact Criteria for Corners and Crosswalks in a Non-CBD Location....12-23
12-19 Existing Intersection Level of Service Analysis....12-25a
12-20 No-Action Intersection Level of Service Analysis....12-25b
12-21 With-Action Intersection Level of Service Analysis....12-26a
12-22 Existing Conditions Subway Station Stair Analysis....12-27
12-23 Existing Conditions Subway Station Fare Array Analysis....12-27
12-24 Bus Routes Serving the Project Site....12-27
12-25 Existing Local Bus Analysis....12-28
12-26 No-Action Stair Analysis at Analyzed Subway Stations....12-29
12-27 No-Action Fare Array Analysis at Analyzed Subway Stations....12-29
12-28 No-Action Local Bus Analysis....12-30
12-29 With-Action Stair Analysis at Analyzed Subway Stations....12-30
12-30 With-Action Fare Array Analysis at Analyzed Subway Stations....12-31
12-31 With-Action Local Bus Analysis....12-31
12-32 Existing Sidewalk Conditions....12-32
12-33 Existing Crosswalk Conditions....12-33
12-34 Existing Corner Conditions....12-33
12-35 No-Action Sidewalk Conditions....12-34
12-36 No-Action Crosswalk Conditions....12-35
12-37 No-Action Corner Conditions....12-35
12-38 With-Action Sidewalk Conditions....12-37
12-39 With Action Crosswalk Conditions....12-37
12-40 With-Action Corner Conditions....12-38
12-41 Summary of Motor Vehicle Crash Data 2017-2019....12-40
13-1 Maximum Background Pollutant Concentrations for Mobile Source Analysis....13-5
13-2 Maximum Predicted 24 Hour Average PM_{10} No-Action Concentrations ($\mu g/m^3$)....13-7
13-3 Maximum Predicted 24 Hour Average PM_{10} With Action Concentrations ($\mu g/m^3$)....13-7
13-4 Maximum Predicted 24 Hour Average $PM_{2.5}$ With Action and Incremental Concentrations ($\mu g/m^3$)....13-8
13-5 Maximum Predicted Annual Average $PM_{2.5}$ With Action and Incremental Concentrations ($\mu g/m^3$)....13-8
13-6 Applicable National Ambient Air Quality Standards and CEQR Significant Impacts Criteria....13-11
13-7 Estimated Pollutant Emission Rates with Natural Gas Under Air State Facility Permit #2610100458 ..13-16
13-8 Estimated Pollutant Emission Rates with Fuel Oil No.2 Under Air State Facility Permit #2610100458 13-16
13-9 Results of the Analysis with Downwash....13-18
13-10 Results of the Analysis without Downwash....13-19
14-1 Global Warming Potential for Primary Greenhouse Gases....14-5
14-2 Proposed Project's Annual Vehicle Miles Traveled....14-10
14-3 Annual Operational Emissions for the Proposed Project....14-11
14-4 Annual Mobile Source Emissions for the Proposed Project....14-12
14-5 Summary of Total Annual GHG Emissions from RWCDS....14-12
15-1 Common Noise Levels....15-3
15-2 Average Ability to Perceive Changes in Noise Levels....15-4
15-3 Noise Exposure Guidelines for Use in City Environmental Impact Review....15-5
15-4 Required Attenuation Values to Achieve Acceptable Interior Noise Levels....15-6
15-5 Highest Predicted Noise Levels Due to the Roberto Clemente Ballfield Only (in dBA)....15-9
15-6 Noise Receptor Locations....15-10
15-7 Existing Noise Levels (in dBA) at the Monitoring Locations....15-11
15-8 Adjusted Existing Noise Levels (dBA)....15-12
15-9 2026 No-Action Condition Noise Levels and Total PCE Values at Receptor Locations (in dBA)....15-13
15-10 2026 With Action Condition Noise Levels and Total PCE Values at Receptor Locations (in dBA)....15-14
15-11 Predicted Noise Levels on the Proposed Project due to the Roberto Clemente Ballfield (in dBA)....15-15
18-1 Number of Impacted Intersection and Land Groups by Peak Hour....18-3
18-2 Summary of Significantly Impacted Intersections....18-3
18-3 Construction Oversight in New York City....18-4

18-4 Anticipated Construction Schedule 18-7
18-5 Average Daily Workers and Trucks by Quarter 18-9
18-6 2026 (Q4-Q7) Construction Vehicle Trip Generation (Autos, Taxis and Trucks, in PCEs) 18-10
18-7 Level of Service Analysis Under Existing and 2026 (Q4-Q7) No-Action Conditions 18-12
18-8 Level of Service Analysis Under 2026 (Q4-Q7) No-Action and With-Action Conditions 18-13
18-9 Pollutants for Analysis and Averaging Periods 18-16
18-10 National Ambient Air Quality Standards (NAAQS) 18-17
18-11 Representative Monitored Ambient Air Quality Data 18-20
18-12 Maximum Pollutant Concentrations 18-22
18-13 Noise Receptors by Location and Land Use 18-26
18-14 Construction Noise Analysis Time Periods 18-27
18-15 Typical Construction Equipment Noise Emission Levels (dBA) 18-30
18-16 Existing Noise Levels (in dBA) 18-30
18-17 Construction Noise Analysis Results in dBA 18-31
18-18 Vibration Source Levels for Construction Equipment (dBA) 18-34
19-1 Summary of Lane Groups/Intersection with Significant Adverse Traffic Impacts 19-1
19-2 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts 19-2
19-3 Lane Groups with Significant Adverse Traffic Impacts 19-3
19-4 Proposed Traffic Mitigation Measure 19-3
19-5 Action with Mitigation Conditions at Impacted Lane Groups (Weekday AM and Midday) 19-4
19-6 Action with Mitigation Conditions at Impacted Lane Groups (Weekday PM) 19-4
19-7 Summary of Significant Pedestrian Impacts 19-5
19-8 Action with Mitigation Crosswalk Conditions – Weekday PM Peak Hour 19-5
19-9 Action with Traffic Mitigation Crosswalk Conditions 19-7
19-10 Action with Traffic Mitigation Corner Conditions 19-7
19-11 Lane Groups With Significant Adverse Construction Traffic Impacts 19-8
19-12 Proposed Traffic Mitigation Measures 19-9
19-13 Action with Mitigation Conditions at Impacted Lane Groups Under Construction Peak Period 19-10

LIST OF FIGURES

		Following Page
ES-1	Project Site Location	ES-2
ES-2	Zoning Map	ES-2
ES-3	Existing and Proposed Zoning	ES-3
ES-4	Zoning Lot Site Plan	ES-6
ES-5a	Zoning Axonometrics	ES-6
ES-5b	Illustrative Ground Floor Plan	ES-6
1-1	Project Location	1-1
1-2	Site Photos	1-2
1-3	Existing and Proposed Zoning	1-3
1-4	Brooklyn Navy Yard IBZ	1-3
1-5	Zoning Analysis	1-5
1-6	Zoning Lot Site Plan	1-8
1-7a	Zoning Axonometric	1-8
1-7b	Zoning Axonometric	1-8
1-8	Illustrative Ground Floor Plan	1-8
1-9	Parking Garage	1-8
2-1	Study Areas	2-1
2-2	Study Area Land Uses	2-5
2-3	Zoning Districts	2-7
2-4	Williamsburg 197-a Plan Area	2-9
2-5	Brooklyn Navy Yard IBZ	2-10
2-6	Costal Zone Boundary	2-11
2-7	No-Build Developments	2-13
2-8	Waiver Plan	2-17
2-9a	Zoning Sections	2-17
2-9b	Zoning Sections	2-17
2-10	Brooklyn Navy Yard SMIA	2-22
2-11	Priority Marine Activity Zones (PMAZ)	2-23
2-12	NPCC 100-Year Floodplain Projections	2-26
2-13	NPCC 500-Year Floodplain Projections	2-26
2-14	Ground Floor Plan with Elevations	2-28
2-15	Bird's Eye Aerial View	2-28
2-16	Building Elevations	2-28
2-17	1% Floodplain Graph + Sea Level Rise	2-28
2-18	Mean Higher High Water + Sea Level Rise	2-28
3-1	Socioeconomic Study Area	3-6
4-1	Open Space Study Area	4-3
4-2	WtPSA	4-4
4-3	Open Space Resources	4-7
5-1	Tier I & II Shadows Assessment	5-4
5-2a	Projected Development Site 1 Screening Analysis on Existing Land Uses	5-5
5-2b	Tier III Screening	5-5
5-3a	Incremental Shadows on March 21st/September 21st , 13:00 & 14:00 - Roberto Clemente Ballfield	5-14
5-3b	Incremental Shadows on March 21st/September 21st , 15:00 & 16:00 – Roberto Clemente Ballfield	5-14
5-3c	Incremental Shadows on March 21st/ September 21st , 8:00 & 9:00 – East River	5-14
5-3d	Incremental Shadows on March 21st/ September 21st , 10:00 & 11:00 – East River	5-14
5-4a	Incremental Shadows on May 6th/ August 6th, 13:00 & 14:00 – Roberto Clemente Ballfield	5-14
5-4b	Incremental Shadows on May 6th/ August 6th, 15:00 & 16:00 – Roberto Clemente Ballfield	5-14
5-4c	Incremental Shadows on May 6th/ August 6th , 17:00 – Roberto Clemente Ballfield	5-14
5-4d	Incremental Shadows on May 6th/August 6th, 7:00 & 8:00 – East River	5-14

5-4e Incremental Shadows on May 6th/ August 6th , 9:00 & 10:00- East River....5-14
5-4f Incremental Shadows on May 6th/ August 6th, 11:00 – East River....5-14
5-5a Incremental Shadows on June 21st, 12:30 & 13:30 – Roberto Clemente Ballfield....5-14
5-5b Incremental Shadows on June 21st, 14:30 & 15:30 – Roberto Clemente Ballfield....5-14
5-5c Incremental Shadows on June 21st, 16:30 & 17:30 - Roberto Clemente Ballfield....5-14
5-5d Incremental Shadows on June 21st, 17:45 & 18:00 – NYCHA Independence Towers Grounds 1....5-14
5-5e Incremental Shadows on June 21st, 6:00 & 7:00 – East River....5-14
5-5f Incremental Shadows on June 21st, 8:00 & 9:00 – East River....5-14
5-5g Incremental Shadows on June 21st, 10:00 & 11:00 – East River....5-14
5-6a Incremental Shadows on December 21st, 12:15 & 12:30 – Roberto Clemente Ballfield....5-14
5-6b Incremental Shadows on December 21st, 14:53 – Epiphany Playground....5-14
5-6c Incremental Shadows on December 21st, 9:00 & 10:00 – East River....5-14
5-6d Incremental Shadows on December 21st, 11:00 – East River....5-14
6-1 Historic Resources Map....6-1
6-2 Historic Resources Photographs....6-9
7-1 Aerial Map & Existing Conditions Photo Key....7-3
7-2a Primary Study Area- Streetscapes....7-4
7-2b Project Area- Buildings & Visual Resources....7-4
7-3 Secondary Study Area – Sub-Areas....7-6
7-4a Secondary Study Area – Streetscape....7-6
7-4b Secondary Study Area – Streetscape....7-6
7-4c Secondary Study Area – Buildings....7-6
7-4d Secondary Study Area – Visual Resources....7-6
7-5 Building Densities....7-8
7-6 Building Heights....7-8
7-7 Illustrative Street View, Looking West on Division Ave....7-13
7-8 Illustrative Street View, Looking West on Wythe Ave....7-13
7-9 Illustrative Street View, Looking North on Kent Ave....7-13
7-10 Illustrative Street View, Looking North on Railroad Ave....7-13
7-11 Illustrative Street View, Looking South on Kent Ave....7-13
7-12 Illustrative Street View, Looking North on Kent Ave....7-13
8-1 Natural Resources Study Area....8-2
8-2 Water Resources and Wetlands....8-6
8-3 Flood Zones....8-7
8-4 Aerial Imagery....8-8
8-5 NYS DEC Environmental Resource Mapper....8-9
8-6 Waterfront Public Open Space Sections....8-12
10-1 Existing DEP Water Mains....10-5
10-2 Existing Sanitary Sewer System....10-6
10-3 DEP Subcatchment Areas....10-6
12-1 Project Location and Transit Map....12-1
12-2 Zoning Lot Site Plan....12-1
12-3 Illustrative Ground Floor Plan....12-1
12-6a Project Increment Weekday AM/MD/PM Traffic Volumes....12-11
12-6b Project Increment Saturday Traffic Volumes....12-11
12-5 Pedestrian Analysis Locations....12-14
12-6a Existing Weekday AM/MD/PM Traffic Volumes....12-25
12-6b Existing Saturday Traffic Volumes....12-25
12-7a No-Action Weekday AM/MD/PM Traffic Volumes....12-25a
12-7b No-Action Saturday Traffic Volumes....12-25a
12-8a With-Action Weekday AM/MD/PM Traffic Volumes....12-26
12-8b With-Action Saturday Traffic Volumes....12-26
12-9 Marcy Avenue (J/M/Z) Subway Station Complex....12-26a
13-1 Kent Village Housing Complex and Stack Location....13-10
13-2 Kent Village Housing Stack and Proposed Building at 500 Kent Ave....13-19
15-1 Noise Monitor Locations....15-8

18-1 Project Increment Weekday AM/PM Construction Traffic Volumes 18-10
18-2 Existing Weekday AM/PM Construction Traffic Volumes 18-11
18-3 No Action Weekday AM/PM Construction Traffic Volumes.....18-11
18-4 With Action Weekday AM/PM Construction Traffic Volumes.....18-11