# Midtown South Mixed-Use Plan

## Draft Environmental Impact Statement (DEIS)



NYC PLANNING

New York City Department of City Planning
CEQR No. 24DCP094M
ULURP No. 250166 ZMM, N 250167 ZRM

Prepared by:

WSP

WSP, Inc.
One Penn Plaza, 4th Floor
250 West 34th Street
New York, NY 10119

January 17, 2025

# Midtown South Mixed-Use Plan

## Draft Environmental Impact Statement (DEIS)

## January 17, 2025

**CEQR No.:** 24DCP094M

**ULURP No.:** 250166 ZMM, N 250167 ZRM

**Lead Agency:** New York Department of City Planning, on behalf of the City Planning Commission, City of New York

**Lead Agency Contact:** Stephanie Shellooe, AICP
Director, Environmental Assessment and Review Division
120 Broadway, 31st Floor
New York, New York, 10271-3100

**Prepared by:** WSP, Inc. with
Philip Habib & Associates; Historical Perspectives Inc.;
HMMH; VHB, Inc.; and BJH Advisors

**Prepared for:** New York Department of City Planning
Erik Botsford, Director
Manhattan Office

and

Glen A. Price III
Director, Studies Implementation

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Writing comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing. The DEIS is available on the website of the New York City Department of City Planning, via the Midtown South Mixed-Use Plan project page on ZAP: https://zap.planning.nyc.gov/projects/2024M0142.

To view the Midtown South Mixed-Use Plan DEIS, navigate to the project page in ZAP, linked above, and select Public Documents, then “DEIS_24DCP094M”

# TABLE OF CONTENTS

Executive Summary ..... ES-1

Chapter 1: Project Description ..... 1-1
Introduction ..... 1-1
Required Approvals ..... 1-3
Background to the Proposed Actions ..... 1-4
Community Engagement and Interagency Participation ..... 1-4
Midtown South Mixed-Use Plan Area History ..... 1-6
Affected Area History ..... 1-6
Neighborhood Context ..... 1-13
Affected Area ..... 1-13
Previous Planning Efforts and Past Actions ..... 1-17
Existing Zoning ..... 1-18
Rezoning Area ..... 1-18
Surrounding Area ..... 1-22
Purpose and Need for the Proposed Actions ..... 1-24
Description of Proposed Actions ..... 1-27
Proposed Zoning Map Amendments ..... 1-28
Proposed Zoning Text Amendments ..... 1-29
Framework for Environmental Review ..... 1-34
Reasonable Worst-Case Development Scenario ..... 1-34
Development Site Criteria ..... 1-34
Projected and Potential Development Sites ..... 1-36
Development Scenario Parameters ..... 1-38
Public Review Process for the Proposed Actions ..... 1-41
Uniform Land Use Review Procedure ..... 1-42
New York City Environmental Quality Review ..... 1-42

Chapter 2: Land Use, Zoning, and Public Policy ..... 2-1
Introduction ..... 2-1
Principal Conclusions ..... 2-4

Methodology ..... 2-4
Study Areas ..... 2-5
Existing Conditions ..... 2-6
Land Use ..... 2-6
Zoning ..... 2-19
Public Policy ..... 2-30
No-Action Condition ..... 2-37
Land Use ..... 2-37
Zoning ..... 2-41
Public Policy ..... 2-42
With-Action Condition ..... 2-42
Land Use ..... 2-42
Zoning ..... 2-45
Assessment ..... 2-51
Public Policy ..... 2-52

Chapter 3: Socioeconomic Conditions ..... 3-1
Introduction ..... 3-1
Principal Conclusions ..... 3-2
Direct Residential Displacement ..... 3-2
Direct Business Displacement ..... 3-2
Indirect Residential Displacement ..... 3-4
Indirect Business Displacement ..... 3-5
Adverse Effects on Specific Industries ..... 3-6
Proposed Actions ..... 3-7
Methodology ..... 3-8
Determining Whether a Socioeconomic Assessment Is Appropriate ..... 3-8
Study Area Definition ..... 3-10
Data Sources ..... 3-13
Preliminary Assessments ..... 3-15
Direct Business Displacement ..... 3-16
Indirect Residential Displacement ..... 3-41
Indirect Business Displacement ..... 3-55
Adverse Effects on Specific Industries ..... 3-66

Chapter 4: Community Facilities and Services ..... 4-1
Introduction ..... 4-1
Principal Conclusions ..... 4-2
Direct Effects ..... 4-2
Indirect Effects ..... 4-2
Methodology ..... 4-4
Direct Effects ..... 4-4
Indirect Effects ..... 4-4
Public Schools ..... 4-5
Libraries ..... 4-5
Childcare Services ..... 4-6
Police, Fire, and Health Care Services ..... 4-6
Indirect Effects on Public Schools ..... 4-7
Methodology ..... 4-7
Existing Conditions ..... 4-8
No-Action Condition ..... 4-13
With-Action Condition ..... 4-15
Indirect Effects on Public Libraries ..... 4-17
Methodology ..... 4-17
Existing Conditions ..... 4-20
No-Action Condition ..... 4-31
With-Action Condition ..... 4-31
Indirect Effects on Publicly Funded Childcare Centers ..... 4-33
Methodology ..... 4-33
Existing Conditions ..... 4-34
No-Action Condition ..... 4-36
With-Action Condition ..... 4-37

Chapter 5: Open Space ..... 5-1
Introduction ..... 5-1
Principal Conclusions ..... 5-2
Methodology ..... 5-3

Direct Effects ..... 5-3
Indirect Effects ..... 5-3
Analysis Framework ..... 5-3
Study Areas ..... 5-4
Open Space User Populations ..... 5-5
Inventory of Open Space Resources ..... 5-5
Adequacy of Open Space Resources ..... 5-7
Detailed Analysis ..... 5-7
NYC Parks Walk to a Park Initiative ..... 5-8
Existing Conditions ..... 5-8
No-Action Condition ..... 5-28
With-Action Condition ..... 5-29

Chapter 6: Shadows ..... 6-1
Introduction ..... 6-1
Principal Conclusions ..... 6-1
Methodology ..... 6-1
Preliminary Screening Assessment ..... 6-4
Tier 1 Screening Assessment ..... 6-6
Tier 2 Screening Assessment ..... 6-6
Tier 3 Screening Assessment ..... 6-8
Detailed Analysis of Shadow Impacts ..... 6-11
Shadows Analysis ..... 6-11
Sunlight Sensitive Resources ..... 6-14

Chapter 7: Historic and Cultural Resources ..... 7-1
Introduction ..... 7-1
Principal Conclusions ..... 7-1
Archaeological Resources ..... 7-2
Architectural Resources ..... 7-2
Development Background ..... 7-4
Methodology ..... 7-6
Archaeological Resources ..... 7-7

Architectural Resources ..... 7-7
Existing Conditions ..... 7-7
No-Action Condition ..... 7-112
Archaeological Resources ..... 7-113
Architectural Resources ..... 7-113
With-Action Condition ..... 7-113
Overview ..... 7-113
Impacts Assessment ..... 7-114
Archaeological Resources ..... 7-114
Architectural Resources ..... 7-114

Chapter 8: Urban Design and Resources ..... 8-1
Introduction ..... 8-1
Principal Conclusions ..... 8-1
Methodology ..... 8-2
Study Area Definition ..... 8-3
Existing Conditions ..... 8-6
Primary Study Area ..... 8-6
Secondary Study Area ..... 8-32
No-Action Condition ..... 8-49
Primary Study Area ..... 8-49
Secondary Study Area ..... 8-52
With-Action Condition ..... 8-52
Primary Study Area (Project Area) ..... 8-53
Secondary Study Area ..... 8-54

Chapter 9: Hazardous Materials ..... 9-1
Introduction ..... 9-1
Principal Conclusions ..... 9-1
Methodology ..... 9-2
Sanborn Fire Insurance Map Review ..... 9-3
Database Review ..... 9-3
Site Reconnaissance ..... 9-4

Limitations ..... 9-4
Existing Conditions, Topography, and Hydrogeology ..... 9-5
Overview of Historical Uses General Area History ..... 9-5
Hazardous Materials Analysis ..... 9-7
Hazardous Materials Implications ..... 9-19
Subsurface Disturbance ..... 9-19
No-Action Condition ..... 9-19
With-Action Condition ..... 9-20
Conclusion ..... 9-21

Chapter 10: Water and Sewer Infrastructure ..... 10-1
Introduction ..... 10-1
Principal Conclusions ..... 10-1
Water Supply ..... 10-1
Wastewater Treatment ..... 10-1
Stormwater and Drainage Management ..... 10-2
Methodology ..... 10-2
Regulatory Context ..... 10-3
Preliminary Analysis ..... 10-3
Existing Conditions ..... 10-3
No-Action Condition ..... 10-10
With-Action Condition ..... 10-10

Chapter 11: Solid Waste and Sanitation Services ..... 11-1
Introduction ..... 11-1
Principal Conclusions ..... 11-1
Methodology ..... 11-2
Existing Conditions ..... 11-2
Description of Current Solid Waste Sanitation Services ..... 11-2
Local Law 199 ..... 11-4
Solid Waste Generation on Projected Development Sites ..... 11-4
No-Action Condition ..... 11-5
With-Action Condition ..... 11-6

Conclusion ..... 11-8

Chapter 12: Energy ..... 12-1
Introduction ..... 12-1
Principal Conclusions ..... 12-1
Methodology ..... 12-2
Existing Conditions ..... 12-2
Energy Supply and Transmission ..... 12-2
Recent Energy Conservation Directives ..... 12-3
Existing Demand ..... 12-4
No-Action Condition ..... 12-4
With-Action Condition ..... 12-4

Chapter 13: Transportation ..... 13-1
Introduction ..... 13-1
Principal Conclusions ..... 13-4
Traffic ..... 13-4
Transit ..... 13-6
Pedestrians ..... 13-6
Vehicular and Pedestrian Safety ..... 13-6
Parking ..... 13-8
Preliminary Analysis Methodology ..... 13-9
Level 1 Screening Assessment ..... 13-9
Background ..... 13-10
Transportation Planning Factors ..... 13-10
Travel Demand Forecast ..... 13-10
Level 2 Screening Assessment ..... 13-16
Vehicular Traffic ..... 13-16
Transit ..... 13-17
Pedestrians ..... 13-21
Parking ..... 13-21
Transportation Analyses Methodologies ..... 13-21
Traffic ..... 13-21

Transit ..... 13-23
Pedestrians ..... 13-25
Vehicular and Pedestrian Safety Evaluation ..... 13-28
Parking ..... 13-29
Traffic ..... 13-29
Existing Conditions ..... 13-29
The Future without the Proposed Actions (No-Action Condition) ..... 13-37
The Future with the Proposed Actions (With-Action Condition) ..... 13-44
Transit ..... 13-50
Existing Conditions ..... 13-50
The Future without the Proposed Actions (No-Action Condition) ..... 13-55
The Future with the Proposed Actions (With-Action Condition) ..... 13-61
Pedestrians ..... 13-65
Existing Conditions ..... 13-65
The Future without the Proposed Actions (No-Action Condition) ..... 13-72
The Future with the Proposed Actions (With-Action Condition) ..... 13-78
Vehicular and Pedestrian Safety Evaluation ..... 13-85
Recent DOT Initiatives ..... 13-85
Study Area High Crash Locations ..... 13-86
Parking ..... 13-98

Chapter 14: Air Quality ..... 14-1
Introduction ..... 14-1
Principal Conclusions ..... 14-1
Pollutants for Analysis ..... 14-2
Carbon Monoxide ..... 14-2
Nitrogen Oxides, VOCS, and Ozone ..... 14-2
Lead ..... 14-3
Respirable Particulate Matter - $PM_{10}$ AND $PM_{2.5}$ ..... 14-3
Sulfur Dioxide ..... 14-4
Noncriteria Pollutants ..... 14-4
Air Quality Regulations, Standards, and Benchmarks National and State Air Quality Standards ..... 14-4
NAAQS Attainment Status and State Implementation Plans ..... 14-5

Determining the Significance of Air Quality Impacts ..... 14-7
CO de minimis Criteria ..... 14-7
$PM_{2.5}$ de minimis Criteria ..... 14-7
Non-Criteria Pollutant Thresholds ..... 14-8
Methodology for Predicting Pollutant Concentrations ..... 14-8
Mobile Sources ..... 14-8
Stationary Sources ..... 14-11
Additional Sources (Large and Major Sources) ..... 14-25
The Future without the Proposed Actions (No-Action Condition) ..... 14-26
Mobile Sources ..... 14-26
Stationary Sources ..... 14-26
The Future without the Proposed Actions (With-Action Condition) ..... 14-26
Mobile Sources ..... 14-26
Stationary Sources ..... 14-28

Chapter 15: Greenhouse Gas Emissions and Climate Change ..... 15-1
Introduction ..... 15-1
Principal Conclusions ..... 15-2
Greenhouse Gas Emissions ..... 15-2
Pollutants of Concern ..... 15-2
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions ..... 15-3
New York State Climate Leadership and Community Protection Act ..... 15-3
New York City Initiatives ..... 15-4
Other Benchmarks ..... 15-5
Methodology ..... 15-5
Greenhouse Gas Emissions ..... 15-5
Climate Change Initiatives ..... 15-7
Climate Change ..... 15-8
Projected GHG Emissions from the Proposed Actions ..... 15-9
Operational Emissions ..... 15-9
Mobile Source Emissions ..... 15-9
Summary ..... 15-10
Consistency with GHG Reduction Goal ..... 15-10

Chapter 16: Noise ..... 16-1
Introduction ..... 16-1
Principal Conclusions ..... 16-1
Acoustical Fundamentals ..... 16-2
"A" Weighted Sound Level ..... 16-2
Noise Descriptors used in Impact Assessment ..... 16-3
Noise Exposure Standards and Criteria ..... 16-4
New York City Noise Control Code ..... 16-6
Environmental Conditions for Buildings In MX Districts ..... 16-7
Noise from Manufacturing Use in the Same Building ..... 16-7
Existing Noise Levels ..... 16-8
Selection of Noise Receptor Locations ..... 16-8
Noise Monitoring ..... 16-10
Equipment Used During Noise Monitoring ..... 16-11
Existing Noise Levels At Noise Receptor Locations ..... 16-11
Methodology ..... 16-14
Traffic Noise ..... 16-14
Train Noise ..... 16-15
Aircraft Noise ..... 16-15
Stationary Noise ..... 16-15
The Future without the Proposed Actions (No-Action Condition) ..... 16-16
Noise Impact Identification ..... 16-16
The Future with the Proposed Actions (With-Action Condition) ..... 16-19
Noise Impact Identification ..... 16-19
Noise Attenuation Measures ..... 16-23
Noise Impacts at Residential Conversion ..... 16-25
Mechanical Equipment ..... 16-26

Chapter 17: Public Health ..... 17-1
Introduction ..... 17-1
Principal Conclusions ..... 17-1
Methodology ..... 17-1

Preliminary Screening ..... 17-2
Hazarous Materials ..... 17-2
Air Quality ..... 17-3
Noise ..... 17-3
Construction Air Quality ..... 17-5
Construction Noise ..... 17-5

Chapter 18: Neighborhood Character ..... 18-1
Introduction ..... 18-1
Principal Conclusions ..... 18-2
Methodology ..... 18-3
Study Areas ..... 18-3
Primary Study Area ..... 18-4
Secondary Study Area ..... 18-4
Preliminary Assessment ..... 18-7
Existing Conditions Defining Features ..... 18-7
Assessment of the Potential to Affect Defining Features of the Neighborhood ..... 18-13

Chapter 19: Construction ..... 19-1
Introduction ..... 19-1
Principal Conclusions ..... 19-2
Transportation ..... 19-2
Air Quality ..... 19-4
Noise ..... 19-5
Other Analyses ..... 19-6
Regulatory Framework ..... 19-7
Governmental Coordination and Oversight ..... 19-7
Conceptual Construction Schedule and Activities ..... 19-8
Typical Construction Activities ..... 19-9
Estimate of Construction Workers and Construction Period Trucks ..... 19-10
Determining Peak Year for Cumulative Construction and Operational Effects ..... 19-11
Construction Work Hours ..... 19-11
Construction Staging Areas, Sidewalk and Lane Closures ..... 19-14

Preliminary Assessment ..... 19-14
Transportation ..... 19-15
Air Quality ..... 19-15
Noise and Vibration ..... 19-16
Other Technical Areas ..... 19-17
Detailed Analyses ..... 19-21
Transportation ..... 19-21
Air Quality ..... 19-28
Noise and Vibration ..... 19-38

Chapter 20: Alternatives ..... 20-1
Introduction ..... 20-1
Principal Conclusions ..... 20-1
No-Action Alternative ..... 20-1
No Unmitigated Significant Adverse Impacts Alternative ..... 20-2
No-Action Alternative ..... 20-2
Introduction ..... 20-2
Land Use, Zoning, and Public Policy ..... 20-3
Socioeconomic Conditions ..... 20-3
Community Facilities ..... 20-4
Open Space ..... 20-4
Shadows ..... 20-4
Historic and Cultural Resources ..... 20-4
Urban Design and Visual Resources ..... 20-5
Hazardous Materials ..... 20-5
Water and Sewer Infrastructure ..... 20-5
Solid Waste and Sanitation ..... 20-5
Energy ..... 20-5
Transportation ..... 20-5
Air Quality ..... 20-7
Greenhouse Gas Emissions and Climate Change ..... 20-7
Noise ..... 20-8
Public Health ..... 20-8
Neighborhood Character ..... 20-8

Construction ..... 20-8
No Unmitigated Significant Adverse Impacts Alternative ..... 20-8
Open Space ..... 20-8
Shadows ..... 20-8
Historic Resources ..... 20-8
Hazardous Materials ..... 20-11
Transportation ..... 20-12
Air Quality ..... 20-12
Noise ..... 20-13
Construction ..... 20-14

Chapter 21: Mitigation ..... 20-1
Introduction ..... 20-1
Principal Conclusions ..... 21-1
Open Space ..... 21-1
Shadows ..... 21-2
Historic and Cultural Resources ..... 21-2
Hazarous Materials ..... 21-4
Transportation ..... 21-5
Air Quality ..... 21-7
Construction ..... 21-7
Open Space ..... 21-8
Shadows ..... 21-9
Historic Resources ..... 21-11
Architectural Resources ..... 21-11
Hazarous Materials ..... 21-12
Transportation ..... 21-13
Traffic ..... 21-13
Pedestrians ..... 21-25
Air Quality ..... 21-35
Noise ..... 21-36
Construction ..... 21-36
Transportation ..... 21-36

Air Quality ..... 21-37
Noise ..... 21-37

Chapter 22: Unavoidable Significant Adverse Impacts ..... 22-1
Introduction ..... 22-1
Open Space ..... 22-1
Shadows ..... 22-2
Historic Resources ..... 22-2
Architectural Resources ..... 22-2
Hazardous Materials ..... 22-4
Transportation ..... 22-4
Traffic ..... 22-4
Pedestrians ..... 22-6
Air Quality ..... 22-7
Noise ..... 22-8
Construction ..... 22-8

Chapter 23: Growth Inducing Aspects ..... 23-1

Chapter 24: Irreversible and Irretrievable Commitments of Resources ..... 24-1

Chapter 25: Conceptual Analysis ..... 25-1
Introduction ..... 25-1
Principal Conclusions ..... 25-1
Description of the Zoning Mechanism ..... 25-2
Special Permit for Covered Pedestrian Space ..... 25-2
Authorization for Additional Floor Area for Mass Transit Station Improvements ..... 25-2
Methodology and Analysis Framework ..... 25-2
Conceptual Development Site 1 (Block 831, Lots 19, 55, 59, and 61) ..... 25-5
Conceptual Development Site 2 (Block 838, Lots 65, 66, 68, 69) ..... 25-5
Incremental Development ..... 25-6
Analysis Framework ..... 25-6

Conceptual Environmental Impact Analysis ..... 25-6
Land Use, Zoning, and Public Policy ..... 25-6
Socioeconomic Conditions ..... 25-7
Community Facilities and Services ..... 25-9
Open Space ..... 25-9
Shadows ..... 25-10
Historic and Cultural Resources ..... 25-10
Urban Design and Visual Resources ..... 25-11
Hazardous Materials ..... 25-11
Water and Sewer Infrastructure ..... 25-11
Solid Waste and Sanitation Services ..... 25-12
Energy ..... 25-13
Transportation ..... 25-13
Air Quality ..... 25-13
Greenhouse Gas Emissions and Climate Change ..... 25-14
Noise ..... 25-14
Public Health ..... 25-14
Neighborhood Character ..... 25-15
Construction ..... 25-15

# LIST OF APPENDICES

**Appendix A: RWCDS Tables**

**Appendix B: Draft Proposed Zoning Text Amendments and Zoning Map Amendments**

**Appendix C: Historic Resources**

**Appendix D: Hazardous Materials**

**Appendix E: Transportation**

**Appendix F: Air Quality**

**Appendix G: Noise**

**Appendix H: Construction**

# LIST OF TABLES

Table ES-1: Proposed Zoning Disdtricts ..... ES-28
Table ES-2: 2034 RWCDS No-Action and With-Action Land Uses ..... ES-41
Table ES-3: Number of Impacted Intersections and Lane Groups by Peak Hour .. ES-59
Table ES-4: Summary of Significantly Impacted Intersections ..... ES-60
Table ES-5: Summary of Significant Pedestrian Impacts ..... ES-62
Table ES-6: High Crash Locations ..... ES-63
Table ES-7: Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts ..... ES-76
Table ES-8: Lane Groups with Unmitigated Significant Adverse Traffic Impacts ... ES-77
Table ES-9: Summary of Significant Pedestrian Impacts ..... ES-77

Table 1-1: Proposed Zoning Districts ..... 1-28
Table 1-2: 2034 RWCDS No-Action and With-Action Land Uses ..... 1-41

Table 2-1a: Existing Land Uses in the Primary Study Area ..... 2-8
Table 2-1b: Existing Land Uses in the Northwest Quadrant ..... 2-10
Table 2-1c: Existing Land Uses in the Northeast Quadrant ..... 2-11
Table 2-1d: Existing Land Uses in the Southeast Quadrant ..... 2-13
Table 2-1e: Existing Land Uses in the Southwest Quadrant ..... 2-14
Table 2-2a: Existing Land Uses in the Secondary Study Area ..... 2-15
Table 2-2b: Existing Land Uses in the Midtown Secondary Study Area Subarea ..... 2-16
Table 2-2c: Existing Land Uses in the Chelsea Secondary Study Area Subarea ..... 2-18
Table 2-2d: Existing Land Uses in the Flatiron/NoMad Secondary Study Area Subarea ..... 2-19
Table 2-3: Summary of Existing Zoning and Allowable Densities in the Primary Study Area ..... 2-21
Table 2-4: Existing Zoning Districts within the Secondary Study Area ..... 2-26
Table 2-5: Development Projects in the Fugure without the Proposed Actions ..... 2-40
Table 2-6: 2034 RWCDS No-Action and With-Action Land Uses at the 61 Projected and Potential Development Sites and Conversion Sites ..... 2-44

Table 3-1: Potentially Displaced Businesses in Descending Order by Sector ..... 3-3
Table 3-2: Private Sector Employees in 0.5-Mile Study Area Compared to Borough and NYC, 2023 Q3 ..... 3-18
Table 3-3: Private Sector Firms in 0.5-Mile Study Area Compared to Borough and NYC, 2023 Q3 ..... 3-22
Table 3-4: Private Businesses and Employment Potentially Displaced by the Proposed Actions ..... 3-26
Table 3-5: List of Garment Industry Businesses Offering Similar Services Within the 0.5-Mile Study Area ..... 3-40
Table 3-6: Household Income Characteristics (2006-2010, 2018-2022 ACS) ..... 3-42
Table 3-7: Distribution of Household Incomes (2018-2022) ..... 3-43
Table 3-8: Percentage of Families with Income Below the Poverty Level in the Past 12 Months (2018-2022) ..... 3-43
Table 3-9: 2024 New York City Area Median Income (AMI) ..... 3-44
Table 3-10: 2023 New York City Affordable Monthly Rents by Area Median Income (AMI) ..... 3-44
Table 3-11: Average and Median Gross Rents ..... 3-45
Table 3-12: Median Asking Rents, 2018-2023 ..... 3-46
Table 3-13: Median Asking Rents, January-December 2023 ..... 3-47
Table 3-14: Household Income by Unit Type (based on 30% expense on rent) ..... 3-47
Table 3-15: Market-Rate Units by Number of Bedrooms in Study Area (Rental units only) ..... 3-48
Table 3-16: Weighted Average Income of With-Action Market-Rate Renters ..... 3-49
Table 3-17: Weighted Average Income of Total With-Action Population ..... 3-49
Table 3-18: Study Area, Manhattan, New York City Residential Population (2010-2023) ..... 3-51
Table 3-19: Projected Background Study Area Growth Under the No-Action Condition ..... 3-52
Table 3-20: Summary of No-Action Condition of 0.5-Mile Study Area ..... 3-53
Table 3-21: Summary of With-Action Condition of 0.5-Mile Study Area ..... 3-53
Table 3-22: Change in Median Asking Rents in Study Area, 2018-2023 ..... 3-55
Table 3-23: Existing Land Uses and Incremental Land Uses udner No-Action and With-Action Conditions ..... 3-57
Table 3-24: Summary of Trends in Greater Midtown 2014-2024 YTD ..... 3-58
Table 3-25: Study Area Retail Trends 2014-2024 Year to Date (YTD) ..... 3-61

Table 3-26: Study Area Office Trends 2014-2024 Year to Date (YTD) ..... 3-63
Table 3-27: Garment Industry Statistics, Manhattan, 2013-2023 ..... 3-67
Table 3-27: Garment Industry Statistics, New York City, 2013-2023 ..... 3-67

Table 4-1: Preliminary Screening Analysis Criteria ..... 4-5
Table 4-2: Projected Development Sites and Conversion Area - Associated Number of Projected Incremental Students by Respective CSD Sub-District ..... 4-7
Table 4-3: Study Area Elementary School Enrollment, Capacity, and Utilization for 2022-2023 Academic Year ..... 4-11
Table 4-4: Study Area Intermediate School Enrollment, Capacity, and Utiliation for 2022-2023 Academic Year ..... 4-12
Table 4-5: Manhattan High School Enrollment, Capacity, and Utilization for the 2022-2023 Academic Year ..... 4-12
Table 4-6: Estimated No-Action Elementary School Enrollment, Capacity, and Utilization ..... 4-14
Table 4-7: Estimated No-Action Intermediate School Enrollment, Capacity, and Utilization ..... 4-14
Table 4-8: Estimated No-Action High School Enrollment, Capacity, and Utilization ..... 4-14
Table 4-9: Estimated Number of Students Introduced in the Affected Area in the With-Action Condition ..... 4-15
Table 4-10: Estimated With-Action Elementary School Enrollment, Capacity, and Utilization ..... 4-15
Table 4-11: Estimated With-Action Intermediate School Enrollment, Capacity, and Utilization ..... 4-17
Table 4-12: Estimated With-Action High School Enrollment, Capacity, and Utilization ..... 4-17
Table 4-13: Public Library Analysis Criteria ..... 4-18
Table 4-14: Public Libraries Serving the Affected Area ..... 4-20
Table 4-15: Catchment Area Population: No-Action Condition ..... 4-31
Table 4-16: Catchment Area Population: With-Action Condition ..... 4-32
Table 4-17: Publicily Funded Child Care Centers Analysis Criteria ..... 4-34
Table 4-18: Publicly Funded Child Care Centers – Existing Conditions ..... 4-35
Table 4-19: No-Action Publicly Funded Child Care Enrollment ..... 4-37

Table 4-20: Multipliers for Estimating the Number of Children Eligible for Publicly Funded Childcare and Head Start ..... 4-37
Table 4-21: Publicily Funded Childcare Centers Analysis ..... 4-37

Table 5-1: Open Space Study Area Residential Population ..... 5-10
Table 5-2: Residential Study Area Population Age Distribution ..... 5-11
Table 5-3: Open Space Inventory ..... 5-13
Table 5-4: Adequacy of Open Space Resources in the Residential Study Area: Existing Conditions ..... 5-26
Table 5-5: Adequacy of Open Space Resources in the Residential Study Area: No-Action Condition ..... 5-28
Table 5-6: With-Action Open Space Study Area Population ..... 5-29
Table 5-7: Adequacy of Open Space Resources in the Residential Study Area: With-Action Condition ..... 5-29
Table 5-8: Impact Determination ..... 5-30

Table 6-1: RWCDS Sites Warranting Preliminary Shadow Analyses ..... 6-6
Table 6-2: Sunlight-Sensitive Resources Warranting Further Analysis Based on Tier I and II Screening ..... 6-7
Table 6-3: Tier III Assessment Results ..... 6-9
Table 6-4: Duraiton of Shadows on Sunlight-Sensitive Resources (Increment compared to No-Action Condition) ..... 6-12

Table 7-1: Historic Districts and Individual Historic Resources in Study Area ..... 7-11
Table 7-2: Projected and Potential Development Sites Containing Historic Resources ..... 7-98
Table 7-3: RWCDS Projected/Potential Development Sites Containing or Located Proximate to Designated/Eligible Historic Resources ..... 7-123

Table 9-1: Hazardous Materials – Projected and Potential Development Sites ..... 9-9

Table 10-1: Existing Water Consumption and Wastewater Generation ..... 10-5

Table 10-2: Existing North River and Newtown Creek WRRF Average Daily Sewer Flows ..... 10-7
Table 10-3: Existing Wastewater Generation by Subcatchment Area ..... 10-7
Table 10-4: Existing Surface Coverage by WRRF Drainage Area ..... 10-9
Table 10-5: Existing Condition Flow Volume Matrix ..... 10-10
Table 10-6: With-Action Condition Water Consumption and Wastewater Generation ..... 10-11
Table 10-7: Incremental Wastewater Generation by WRRF Area ..... 10-12
Table 10-8: With-Action Condition Surface Coverage by Subcatchment Area ..... 10-13
Table 10-9: With-Action Condition Flow Volume Matrix ..... 10-13

Table 11-1: Existing Solid Wate Generation on Projected Development Sites and Conversion Area ..... 11-5
Table 11-2: With-Action Solid Wate Generation on Projected Development Sites and Conversion Area ..... 11-7
Table 11-3: Comparison of Weekly Solid Wate Generation on Projected Development Sites and Conversion Area ..... 11-8

Table 12-1: Existing Annual Energy Consumption for the Projected Development Sites and Conversion Area ..... 12-4
Table 12-2: With-Action Annual Energy Consumption for the Projected Development Sites and Conversion Area ..... 12-6

Table 13-1: 2034 RWCDS No-Action and With-Action Land Uses Assumed for Transportation Analyses ..... 13-2
Table 13-2: 2034 RWCDS No-Action and With-Action Commercial to Residential Conversions Assumed for Transportation Analyses ..... 13-3
Table 13-3: 2034 RWCDS No-Action and With-Action Land Uses on Projected Development Sites (with Residential Conversion) Assumed for Transportation Analyses ..... 13-4
Table 13-4: Number of Impacted Intersections and Lane Groups by Peak Hour ..... 13-5
Table 13-5: Summary of Significantly Impacted Intersections ..... 13-5
Table 13-6: Summary of Significant Pedestrian Impacts ..... 13-7
Table 13-7: High Crash Locations ..... 13-8

Table 13-8: Transportation Planning Factors ..... 13-12
Table 13-9: RWCDS Travel Demand Forecast ..... 13-13
Table 13-10: RWCDS Net Incremental Vehicle Trips by Projected Development Site ..... 13-15
Table 13-11: Summary of Net Incremental Peak Hour Trips Generated under the RWCDS ..... 13-16
Table 13-12: RWCDS Net Incremental Peak Hour Subway Trips by Station ..... 13-19
Table 13-13: RWCDS Net Incremental Peak Hour Subway Trips by Route ..... 13-20
Table 13-14: Intersection Level of Service Criteria ..... 13-23
Table 13-15: Level of Service Criteria for Subway Station Elements ..... 13-24
Table 13-16: Significant Impact Thresholds for Stairways and Passageways ..... 13-25
Table 13-17: Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions ..... 13-26
Table 13-18: Significant Impact Criteria for Sidewalks in a CBD Location ..... 13-27
Table 13-19: Significant Impact Criteria for Corners and Crosswalks in a CBD Location ..... 13-28
Table 13-20: Existing Level of Service at Analyzed Intersections ..... 13-35
Table 13-21: No-Action Level of Service at Analyzed Intersections ..... 13-40
Table 13-22: With-Action Level of Service at Analyzed Intersections ..... 13-46
Table 13-23: Existing Conditions Subway Station Stair Analysis ..... 13-53
Table 13-24: Existing Conditions Subway Station Fare Array Analysis ..... 13-55
Table 13-25: Existing Conditions Escalator Analysis at the 34th Street-Herald Square Station Complex ..... 13-55
Table 13-26: No-Action Subway Station Stair Analysis ..... 13-58
Table 13-27: No-Action Subway Statation Fare Analysis ..... 13-60
Table 13-28: No-Action Escalator Analysis at the 34th Street-Herald Square Station Complex ..... 13-60
Table 13-29: With-Action Subway Station Stair Analysis ..... 13-63
Table 13-30: With-Action Subway Station Fare Array Analysis ..... 13-65
Table 13-31: With-Action Escalator Analysis at the 34th Street-Herald Square Station Complex ..... 13-65
Table 13-32: Existing Sidewalk Conditions ..... 13-67
Table 13-33: Existing Crosswalk Conditions ..... 13-69
Table 13-34: Existing Corner Conditions ..... 13-70

Table 13-35: No-Action Sidewalk Conditions ..... 13-73
Table 13-36: No-Action Crosswalk Conditions ..... 13-75
Table 13-37: No-Action Corner Conditions ..... 13-76
Table 13-38: With-Action Sidewalk Conditions ..... 13-80
Table 13-39: With-Action Crosswalk Conditions ..... 13-82
Table 13-40: With-Action Corner Conditions ..... 13-83
Table 13-41: Crash Data Summary 2017-2019 ..... 13-88
Table 13-42: With-Action Net Incremental Weekday Hourly Parking Demand by Land Use ..... 13-100
Table 13-43: With-Action Net Incremental Saturday Hourly Parking Demand by Land Use ..... 13-101

Table 14-1: National Ambient Air Quality Standards ..... 14-5
Table 14-2: Background Concentrations ..... 14-11
Table 14-3: Addresses of Individual Potential and Projected Development Sites Analyzed using AERMOD (Total 26 sites) ..... 14-13
Table 14-4: Maximum Background Pollutant Concentrations ..... 14-18
Table 14-5: Sites included in Clusters ..... 14-19
Table 14-6: Light Industrial Sources in the Study Area ..... 14-22
Table 14-7: Estimated Emission Rates from Light Industrial Sources ..... 14-23
Table 14-8: Screening of Pollutants from Light Industrial Sources ..... 14-24
Table 14-9: Large and Major Sources within 1,000 feet of the Study Area ..... 14-25
Table 14-10: Estimates Emission Rates from Large Sources ..... 14-25
Table 14-11: Maximum Predicted 1-Hour and 8-Hour CO No-Action Concentrations ..... 14-26
Table 14-12: Maximum Predicted 1-Hour and 8-Hour Average CO With-Action Concentrations (ppm) ..... 14-27
Table 14-13: 2034 Maximum Predicted 24-Hour Average PM2.5 Incremental and Total Concentrations (ug/m3) ..... 14-27
Table 14-14: 2034 Maximum Predicted Annual Average PM2.5 Incremental and Total Concentrations (ug/m3) ..... 14-27
Table 14-15: Heating and Hot Water System Analysis Summary ..... 14-28
Table 14-16: Heating and Hot Water System Analysis – Results for Projected Development Sites ..... 14-29

Table 14-17: Heating and Hot Water System Analysis – Results for Potential Development Sites ..... 14-33
Table 14-18: Heating and Hot Water System Analysis – Results for Cluster Analysis ..... 14-33
Table 14-19: Industrial Source Detailed Analysis Results ..... 14-34
Table 14-20: Estimated Maximum Hazard Index ..... 14-35
Table 14-21: Estimated Maximum Cancer Risk ..... 14-35
Table 14-22: Large Source Detailed Analysis Results ..... 14-36

Table 15-1: Global Warming Potential for Primary Greenhouse Gases ..... 15-3
Table 15-2: Incremental Vehicle Miles Traveled per Year ..... 15-7
Table 15-3: Annual Operational Emissions - RWCDS ..... 15-9
Table 15-4: Annual Mobile Source Emissions for 2034 – CO2 Emissions (metric tons/year) ..... 15-10
Table 15-5: Total Annual GHG Emissions from the Proposed Actions ..... 15-10

Table 16-1: Typical Noise Values ..... 16-2
Table 16-2: CEQR Noise Exposure Guidelines for Use in City Environmental Impact Review ..... 16-5
Table 16-3: Required Attenuation Values to Achieve Acceptable Interior Noise Levels ..... 16-6
Table 16-4: New York City Noise Code ..... 16-7
Table 16-5: Noise Receptor Locations ..... 16-10
Table 16-6: Measured Existing Noise Lvels (in dBA) ..... 16-12
Table 16-7: 2034 No-Action Condition Noise Levels where traffic is dominant source of noise (dBA) ..... 16-16
Table 16-8: 2034 With-Action Condition Noise Levels where traffic is dominant source of noise (dBA) ..... 16-20
Table 16-9: Required Attenuation at Noise Measurement Locations ..... 16-24

Table 19-1: Construction oversight in New York City ..... 19-8

Table 19-2: Average Incremental Number of Daily Construction Workers and Trucks by Year and Quarter ..... 19-11
Table 19-3: 2028 (Second Quarter) Peak Incremental Construction Vehicle Trip Projects (in PCEs) ..... 19-22
Table 19-4: Comparison of 2028 (Second Quarter) Incremental Construction and Operational Vehicle Trips with 2034 Operational Vehicle Trips ..... 19-23
Table 19-5: 2028 (Second Quarter) Construction Worker Parking Accumulation ..... 19-28
Table 19-6: Pollutant for Analysis and Averaging Periods ..... 19-29
Table 19-7: Short-term Project Emission Intensity for PM2.5 (lb/day) ..... 19-31
Table 19-8: Short-term Project Emission Intensity for PM10 (lb/day) ..... 19-31
Table 19-9: Rolling 12-month Annual Project Emission Intensity for PM2.5 (lb/day) ..... 19-31
Table 19-10: Rolling 12-month Annual Project Emission Intensity for NO2 (lb/day) ..... 19-32
Table 19-11: Short-term Project Emission Intensity for CO (lb/day) ..... 19-32
Table 19-12: Maximum Pollutant Concentrations Resulting from Construction Activities on Projected Development Site 46 ..... 19-36
Table 19-13: Maximum Pollutant Concentrations Resulting from Construction Activities on Projected Development Site 49 ..... 19-36
Table 19-14: Maximum Pollutant Concentrations Resulting from Construction Activities on Combined Projected Development Sites 46 and 49 ..... 19-37
Table 19-15: Maximum Pollutant Concentrations Resulting from Construction Activities on Combined Projected Development Sites 51 and 52 ..... 19-37
Table 19-16: FTA Construction Vibration Damage Criteria ..... 19-41
Table 19-17: FTA Construction Vibration Annoyance Criteria ..... 19-42
Table 19-18: Typical Construction Equipment Noise Emission Levels (dBA) ..... 19-43
Table 19-19: FTA Construction Equipment Vibration Source Levels ..... 19-50
Table 19-20: Projected Development Site 49 Noise Analysis Results Leq (dBA) ..... 19-51
Table 19-21: Projected Development Site 52 Noise Analysis Results Leq (dBA) ..... 19-51
Table 19-22: Projected Development Site 46 Noise Analysis Results Leq (dBA) ..... 19-56
Table 19-23: Projected Development Site 35 Noise Analysis Results Leq (dBA) ..... 19-59

Table 21-1: Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts ..... 21-5
Table 21-2: Lane Groups with Unmitigated Significant Adverse Traffic Impacts ..... 21-6

Table 21-3: Summary of Significant Pedestrian Impacts ..... 21-6
Table 21-4: Proposed Traffic Mitigation Measures ..... 21-15
Table 21-5: Action-With-Mitigation Conditions at Impacted Land Groups - AM ..... 21-17
Table 21-6: Action-With-Mitigation Conditions at Impacted Land Groups - MD ..... 21-19
Table 21-7: Action-With-Mitigation Conditions at Impacted Land Groups - PM ..... 21-21
Table 21-8: Action-With-Mitigation Conditions at Impacted Land Groups - SAT ..... 21-23
Table 21-9: Summary of Significant Pedestrian Impacts ..... 21-27
Table 21-10: Action-With-Mitigation Sidewalk Conditions ..... 21-28
Table 21-11: Action-With-Mitigation Crosswalk Conditions ..... 21-30
Table 21-12: Action-With-Mitigation Corner Conditions ..... 21-30
Table 21-13: Action-With-Traffic Mitigation Crosswalk Conditions ..... 21-31
Table 21-14: Action-With-Traffic Mitigation Corner Conditions ..... 21-32

Table 25-1: Development under Future Discretionary Actions Scenario ..... 25-3
Table 25-2: Incremental Development under Future Discretionary Actions Scenario ..... 25-3

# LIST OF FIGURES

Figure ES-1: Existing Zoning ..... ES-25
Figure ES-2: Projected and Potential Development Sites ..... ES-49
Figure ES-3: Proposed Zoning ..... ES-30
Figure ES-4: Projected and Potential Development Sites ..... ES-38

Figure 1-1: Project Location ..... 1-5
Figure 1-2: Existing Zoning ..... 1-21
Figure 1-3: Proposed Zoning ..... 1-30
Figure 1-4: Projected and Potential Development Sites ..... 1-37

Figure 2-1: Land Use, Zoning, and Public Policy Study Area ..... 2-3
Figure 2-2: Existing Land Use ..... 2-9
Figure 2-3: Existing Zoning ..... 2-23
Figure 2-4: NYC FRESH Zoning Boundaries ..... 2-33
Figure 2-5: Business Improvement Districts ..... 2-35
Figure 2-6: No-Build Developments in the Primary and Secondary Study Areas ..... 2-39
Figure 2-7: Proposed Zoning Map Amendment ..... 2-46

Figure 3-1: Socioeconomic Study Area ..... 3-12

Figure 4-1: Public Schools ..... 4-10
Figure 4-2a: Public Libraries within a 0.75-mile Radius of the Affected Area ..... 4-19
Figure 4-2b: 53rd Street Library Catchment Area ..... 4-21
Figure 4-2c: Andrew Heiskell Braille and Talking Book Library Catchment Area ..... 4-22
Figure 4-2d: Columbus Library Catchment Area ..... 4-23
Figure 4-2e: Epiphany Library Catchment Area ..... 4-24
Figure 4-2f: Jefferson Market Library Catchment Area ..... 4-25
Figure 4-2g: Kips Bay Library Catchment Area ..... 4-26
Figure 4-2h: Stravros Niarchos Foundation Library Catchment Area ..... 4-27

Figure 4-2i: Muhlenberg Library Catchment Area ..... 4-28
Figure 4-2j: Stephen A. Schwarzman Library Catchment Area ..... 4-29
Figure 4-3: Existing Childcare Facilities ..... 4-38

Figure 5-1: Open Space Study Area ..... 5-6
Figure 5-2: Walk to a Park Service Area ..... 5-9
Figure 5-3: Open Space Resources in the Study Area ..... 5-25

Figure 6-1: Tier I and II Shadow Screening ..... 6-5
Figure 6-2: Bryant Park – March 21/September 21 ..... 6-30
Figure 6-3: Bryant Park – March 21/September 21 ..... 6-31
Figure 6-4: Bryant Park – May 6/August 6 ..... 6-32
Figure 6-5: Bryant Park – May 6/August 6 ..... 6-33
Figure 6-6: Bryant Park – June 21 ..... 6-34
Figure 6-7: Bryant Park – December 21 ..... 6-35
Figure 6-8: Madison Square Park – May 6/August 6 ..... 6-36
Figure 6-9: Madison Square Park – June 21 ..... 6-37
Figure 6-10: Penn South Playground – June 21 ..... 6-38
Figure 6-11: Penn South – March 21/September 21 ..... 6-39
Figure 6-12: Penn South – March 21/September 21 ..... 6-40
Figure 6-13: Penn South – May 6/August 6 ..... 6-41
Figure 6-14: Penn South – May 6/August 6 ..... 6-42
Figure 6-15: Penn South – June 21 ..... 6-43
Figure 6-16: Moynihan Train Hall Steps – December 21 ..... 6-44
Figure 6-17: Moynihan Train Hall Steps – December 21 ..... 6-45
Figure 6-18: 525 Eighth Avenue POPS – December 21 ..... 6-46
Figure 6-19: Broadway Plazas (35th – 42nd Streets) – March 21/September 21 ..... 6-47
Figure 6-20: Broadway Plazas (35th – 42nd Streets) – May 6/August 6 ..... 6-48
Figure 6-21: Broadway Plazas (35th – 42nd Streets) – June 21 ..... 6-49
Figure 6-22: 776 Sixth Avenue POPS – March 21/September 21 ..... 6-50
Figure 6-23: 776 Sixth Avenue POPS – May 6/August 6 ..... 6-51
Figure 6-24: 835 Sixth Avenue POPS – March 21/September 21 ..... 6-52

Figure 6-25: 420 Fifth Avenue POPS – March 21/September 21 ..... 6-53
Figure 6-26: 420 Fifth Avenue POPS – May 6/August 6 ..... 6-54
Figure 6-27: 420 Fifth Avenue POPS – June 21 ..... 6-55
Figure 6-28: 41 Madison Avenue POPS – June 21 ..... 6-56
Figure 6-29: Grace Plaza – December 21 ..... 6-57
Figure 6-30: Greeley Square – December 21 ..... 6-58
Figure 6-31: 1185 Broadway POPS – March 21/September 21 ..... 6-59
Figure 6-32: 1185 Broadway POPS – March 21/September 21 ..... 6-60
Figure 6-33: 1185 Broadway POPS – May 6/August 6 ..... 6-61
Figure 6-34: 1185 Broadway POPS – May 6/August 6 ..... 6-62
Figure 6-35: 1185 Broadway POPS – May 6/August 6 ..... 6-63
Figure 6-36: 1185 Broadway POPS – June 21 ..... 6-64
Figure 6-37: 1185 Broadway POPS – June 21 ..... 6-65
Figure 6-38: Broadway between 25th and 28th Streets – March 21/September 21 .... 6-66
Figure 6-39: Broadway between 25th and 28th Streets – May 6/August 6..... 6-67
Figure 6-40: Broadway between 25th and 28th Streets – May 6/August 6..... 6-68
Figure 6-41: Broadway between 25th and 28th Streets – June 21..... 6-69
Figure 6-42: Broadway between 25th and 28th Streets – June 21..... 6-70
Figure 6-43: Broadway between 29th and 32nd Streets – March 21/September 21 ... 6-71
Figure 6-44: Broadway between 29th and 32nd Streets – March 21/September 21 ... 6-72
Figure 6-45: Broadway between 29th and 32nd Streets – May 6/August 6..... 6-73
Figure 6-46: Broadway between 29th and 32nd Streets – May 6/August 6..... 6-74
Figure 6-47: Broadway between 29th and 32nd Streets – June 21..... 6-75
Figure 6-48: Broadway between 29th and 32nd Streets – June 21..... 6-76
Figure 6-49: Broadway between 29th and 32nd Streets – June 21..... 6-77
Figure 6-50: Broadway between 29th and 32nd Streets – June 21..... 6-78
Figure 6-51: Broadway between 29th and 32nd Streets – December 21 ..... 6-79
Figure 6-52: Herald Square – March 21/September 21..... 6-80
Figure 6-53: Marble Collegiate Church – March 21/September 21 ..... 6-81
Figure 6-54: Marble Collegiate Church – March 21/September 21 ..... 6-82
Figure 6-55: Marble Collegiate Church – May 6/August 6..... 6-83
Figure 6-56: Marble Collegiate Church – May 6/August 6..... 6-84

Figure 6-57: Marble Collegiate Church – June 21 ..... 6-85
Figure 6-58: Marble Collegiate Church – June 21 ..... 6-86
Figure 6-59: Marble Collegiate Church – December 21 ..... 6-87
Figure 6-60: Millinery Center Synagogue – March 21/September 21 ..... 6-88
Figure 6-61: Millinery Center Synagogue – June 21 ..... 6-89
Figure 6-62: Millinery Center Synagogue – December 21 ..... 6-90
Figure 6-63: St. John the Baptist Roman Catholic Church – March 21/September 21 ..... 6-91
Figure 6-64: St. John the Baptist Roman Catholic Church – March 21/September 21 ..... 6-92
Figure 6-65: St. John the Baptist Roman Catholic Church – March 21/September 21 ..... 6-93
Figure 6-66: St. John the Baptist Roman Catholic Church – May 6/August 6 ..... 6-94
Figure 6-67: St. John the Baptist Roman Catholic Church – May 6/August 6 ..... 6-95
Figure 6-68: St. John the Baptist Roman Catholic Church – May 6/August 6 ..... 6-96
Figure 6-69: St. John the Baptist Roman Catholic Church – June 21 ..... 6-97
Figure 6-70: St. John the Baptist Roman Catholic Church – June 21 ..... 6-98
Figure 6-71: St. John the Baptist Roman Catholic Church – June 21 ..... 6-99
Figure 6-72: St. John the Baptist Roman Catholic Church – December 21 ..... 6-100
Figure 6-73: St. John the Baptist Roman Catholic Church – December 21 ..... 6-101
Figure 6-74: St. Francis of Assisi Roman Catholic Church – March 21/September 21… ..... 6-102
Figure 6-75: St. Francis of Assisi Roman Catholic Church – March 21/September 21… ..... 6-103
Figure 6-76: St. Francis of Assisi Roman Catholic Church – March 21/September 21… ..... 6-104
Figure 6-77: St. Francis of Assisi Roman Catholic Church – May 6/August 6 ..... 6-105
Figure 6-78: St. Francis of Assisi Roman Catholic Church – May 6/August 6 ..... 6-106
Figure 6-79: St. Francis of Assisi Roman Catholic Church – June 21 ..... 6-107
Figure 6-80: St. Francis of Assisi Roman Catholic Church – June 21 ..... 6-108
Figure 6-81: Trinity Chapel – March 21/September 21 ..... 6-109
Figure 6-82: Trinity Chapel – March 21/September 21 ..... 6-110
Figure 6-83: Trinity Chapel – May 6/August 6 ..... 6-111
Figure 6-84: Trinity Chapel – May 6/August 6 ..... 6-112

Figure 6-85: Trinity Chapel – May 6/August 6 ..... 6-113
Figure 6-86: Trinity Chapel – June 21 ..... 6-114
Figure 6-87: Trinity Chapel – June 21 ..... 6-115
Figure 6-88: Trinity Chapel – June 21 ..... 6-116

Figure 7-1: Architectural Resources in the Northeast and Northwest Quadrants and Study Area ..... 7-9
Figure 7-2: Architectural Resources in the Southeast and Southwest Quadrants and Study Area ..... 7-10
Figure 7-3: Projected/Potential Development Sites within 90 Feet of Historic Resources ..... 7-120

Figure 8-1: Urban Design Study Area ..... 8-5
Figure 8-2: Built Density ..... 8-7
Figure 8-3: Building Height ..... 8-8
Figure 8-4: Photo Locations ..... 8-9
Figure 8-5: Northwest Quadrant Streetscape ..... 8-12
Figure 8-6: Northwest Quadrant Buildings ..... 8-13
Figure 8-7: Northwest Quadrant Open Space ..... 8-14
Figure 8-8: Northwest Quadrant Visual Resources ..... 8-16
Figure 8-9: Northeast Quadrant Streetscape ..... 8-17
Figure 8-10: Northeast Quadrant Buildings ..... 8-19
Figure 8-11: Northeast Quadrant Visual Resources ..... 8-20
Figure 8-12: Southeast Quadrant Streetscape ..... 8-22
Figure 8-13: Southeast Quadrant Buildings ..... 8-23
Figure 8-14: Southeast Quadrant Open Space ..... 8-26
Figure 8-15: Southeast Quadrant Visual Resources ..... 8-27
Figure 8-16: Southwest Quadrant Streetscape ..... 8-29
Figure 8-17: Southwest Quadrant Buildings ..... 8-30
Figure 8-18: Southwest Quadrant Open Space ..... 8-31
Figure 8-19: Southwest Quadrant Visual Resources ..... 8-34
Figure 8-20: Midtown Streetscape ..... 8-35
Figure 8-21: Midtown Buildings ..... 8-37

Figure 8-22: Midtown Open Space ..... 8-38
Figure 8-23: Midtown Visual Resources ..... 8-40
Figure 8-24: Chelsea Streetscape ..... 8-41
Figure 8-25: Chelsea Buildings ..... 8-44
Figure 8-26: Chelsea Open Space and Visual Resources ..... 8-45
Figure 8-27: Flatiron/NoMad Streetscape ..... 8-47
Figure 8-28: Flatiron/NoMad Buildings ..... 8-48
Figure 8-29: Flatiron/NoMad Open Space ..... 8-50
Figure 8-30: Flatiron/NoMad Visual Resources ..... 8-51
Figure 8-31: No-Action v. With-Action View – West 23rd Street between Fifth and Sixth Avenues ..... 8-55
Figure 8-32: No-Action v. With-Action View – West 29th Street between Seventh and Eighth Avenues ..... 8-56
Figure 8-33: No-Action v. With-Action View – West 37th Street between Fifth and Sixth Avenues ..... 8-57
Figure 8-34: No-Action v. With-Action View – West 29th Street between Fifth Avenue and Broadway ..... 8-58
Figure 8-35: No-Action v. With-Action View – West 36th Street between Seventh and Eighth Avenues ..... 8-59

Figure 9-1: Hazardous Materials Risk Sites – Northwest Quadrant ..... 9-15
Figure 9-2: Hazardous Materials Risk Sites – Northeast Quadrant ..... 9-16
Figure 9-3: Hazardous Materials Risk Sites – Southeast Quadrant ..... 9-17
Figure 9-4: Hazardous Materials Risk Sites – Southwest Quadrant ..... 9-18

Figure 10-1: WRRF Subcatchment Areas ..... 10-8

Figure 13-1: Project Location ..... 13-1
Figure 13-2a: AM Peak Hour Incremental Traffic Volumes ..... 13-16
Figure 13-2b: MD Peak Hour Incremental Traffic Volumes ..... 13-16
Figure 13-2c: PM Peak Hour Incremental Traffic Volumes ..... 13-16
Figure 13-2d: SAT MD Peak Hour Incremental Traffic Volumes ..... 13-16
Figure 13-3: Subway Map ..... 13-17

Figure 13-4: Proposed Analyzed Pedestrian Elements ..... 13-21
Figure 13-5: Bike Routes and Citi Bike Stations ..... 13-30
Figure 13-6a: AM Peak Hour Existing Traffic Volumes ..... 13-33
Figure 13-6b: MD Peak Hour Existing Traffic Volumes ..... 13-33
Figure 13-6c: PM Peak Hour Existing Traffic Volumes ..... 13-33
Figure 13-6d: SAT MD Peak Hour Existing Traffic Volumes ..... 13-33
Figure 13-7: No-Build Development Sites ..... 13-39
Figure 13-8a: AM Peak Hour No-Action Traffic Volumes ..... 13-39
Figure 13-8b: MD Peak Hour No-Action Traffic Volumes ..... 13-39
Figure 13-8c: PM Peak Hour No-Action Traffic Volumes ..... 13-39
Figure 13-8d: SAT MD Peak Hour No-Action Traffic Volumes ..... 13-39
Figure 13-9a: AM Peak Hour With-Action Traffic Volumes ..... 13-45
Figure 13-9b: MD Peak Hour With-Action Traffic Volumes ..... 13-45
Figure 13-9c: PM Peak Hour With-Action Traffic Volumes ..... 13-45
Figure 13-9d: SAT MD Peak Hour With-Action Traffic Volumes ..... 13-45
Figure 13-10a: 34th St. – Herald Square Subway Station – IND (B/D/F/M) Platform ..... 13-50
Figure 13-10b: 34th St. – Herald Square Subway Station – BMT (N/R/Q/W) Platform ..... 13-50
Figure 13-10c: 34th St. – Herald Square Subway Station – Lower/Intermediate Mezzanine ..... 13-50
Figure 13-10d: 34th St. – Herald Square Subway Station – Upper Mezzanine ..... 13-50

Figure 14-1: Individual Potential and Projected Sites Screened (Total 68 Sites) ..... 14-14
Figure 14-2: Individual Potential and Projected Sites Screened (North) (Total 28 Sites) ..... 14-15
Figure 14-3: Individual Potential and Projected Sites Screened (South) (Total 40 Sites) ..... 14-16

Figure 16-1: Noise Measurement Locations ..... 16-9

Figure 18-1: Neighborhood Character Study Area Neighborhoods ..... 18-6

Figure 19-1: Conceptual Construction Schedule ..... 19-13

Figure 19-2: Maximum 24-Hour and Rolling 12-Month Average PM2.5 Construction Emissions Profile for Development Sites 46 & 49 ..... 19-30

Figure 19-3: Maximum 24-Hour and Rolling 12-Month Average PM2.5 Construction Emissions Profile for Development Sites 51 & 52 ..... 19-30

Figure 19-4: Noise Measurement Locations and Representative Noise Measurement Assignments for Determining Impact Criteria ..... 19-49

Figure 19-5: Potential Very Objectionable Construction Noise Impacts ..... 19-63

Figure 19-6: Potential Objectionable Construction Noise Impacts ..... 19-64

Figure 25-1: Conceptual Development Sites ..... 25-4