

SOHO/NOHO NEIGHBORHOOD PLAN

Draft Environmental Impact Statement
CEQR # 21DCP059M

prepared by:
New York City Department of City Planning
120 Broadway, 31st Floor
New York, NY 10271

with assistance of:
AKRF
440 Park Ave South, 7th Floor
New York, NY 10016

and
Philip Habib and Associates
102 Madison Avenue 11th floor
New York, NY 10016

May 2021

SoHo/NoHo Neighborhood Plan
DRAFT ENVIRONMENTAL IMPACT STATEMENT (DEIS)

May 17, 2021

CEQR No.:	21DCP059M
ULURP Nos.	SoHo/NoHo Neighborhood Plan 210422 ZMM, N210423 ZRM
Project Location:	Manhattan, New York Community District 2
Lead Agency:	City Planning Commission, City of New York Marisa Lago, Chair
Lead Agency Contact:	Olga Abinader, Director Environmental Assessment and Review Division NYC Department of City Planning 120 Broadway, 31st floor New York, NY 10271-3100 (212) 720-3493
Prepared for:	New York City Department of City Planning Edith Hsu-Chen Manhattan Office Glen A. Price III, Director Studies Implementation New York City Department of City Planning
Prepared by:	AKRF, Inc. Philip Habib & Associates

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

The DEIS is available on the website of the New York City Department of City Planning: http://www1.nyc.gov/site/planning/applicants/eis-documents.page

Table of Contents

Executive Summary **S-1**

1: Project Description **1-1**
A. Introduction 1-1
B. Required Approvals 1-2
C. Background to the Proposed Actions 1-2
Project Area History 1-2
Community Engagement and Interagency Participation 1-4
Project Area 1-6
D. Existing Zoning 1-9
Project Area 1-9
Surrounding Area 1-10
E. Purpose and Need for the Proposed Actions 1-12
Replace Outdated Manufacturing Districts With Mixed-Use Regulations 1-12
Introduce Residential Use and Promote Equity in Housing 1-14
Support Arts and Culture 1-14
Facilitate Superior Urban Design and Appropriate Building Forms 1-15
F. Description of the Proposed Actions 1-15
Zoning Map Amendment 1-16
Zoning Text Amendments 1-18
Waterfront Revitalization Program 1-24
G. Analysis Framework 1-24
Reasonable Worst-Case Development Scenario 1-24
The Future With the Proposed Actions (With Action Condition) 1-25
Criteria for Determining Development Sites 1-26
H. Public Review Process 1-29
Uniform Land Use Review Procedure 1-30
New York City Environmental Quality Review 1-30

2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
Principal Conclusions 2-1
B. Methodology 2-3
Study Areas 2-3
C. Existing Conditions 2-4
Land Use 2-4
Zoning 2-15
Public Policy 2-18
D. The Future Without the Proposed Actions (No Action Condition) 2-25
Land Use 2-25

Zoning....2-26
Public Policy....2-28
E. The Future With the Proposed Actions (With Action Condition)....2-28
Land Use....2-28
Zoning....2-38
Public Policy....2-50

3: Socioeconomic Conditions....3-1
A. Introduction....3-1
Principal Conclusions....3-1
B. Methodology....3-4
Determining Whether A Socioeconomic Assessment Is Appropriate....3-5
Analysis Format....3-8
Study Area Definition....3-8
Data Sources....3-9
C. Preliminary Assessment....3-11
Direct Business Displacement....3-11
Indirect Residential Displacement....3-19
Indirect Business Displacement....3-30
Adverse Effects On Specific Industries....3-33
D. Detailed Indirect Residential Displacement Analysis....3-34
Existing Conditions and Trends....3-34
The Future Without the Proposed Actions (No Action Condition)....3-43
The Future With the Proposed Actions (With Action Condition)....3-44

4: Community Facilities and Services....4-1
A. Introduction....4-1
Principal Conclusions....4-1
B. Preliminary Screening....4-3
Direct Effects....4-3
Indirect Effects....4-3
C. Potential Indirect Effects On Public Elementary and Intermediate Schools....4-4
Methodology....4-4
Existing Conditions....4-5
The Future Without the Proposed Actions....4-6
The Future With the Proposed Actions....4-7
D. Potential Indirect Effects On Public Libraries....4-9
Methodology....4-9
Existing Conditions....4-9
The Future Without the Proposed Actions....4-12
The Future With the Proposed Actions....4-12
E. Potential Indirect Effects On Early Childhood Programs....4-14
Methodology....4-14
Existing Conditions....4-16
The Future Without the Proposed Actions....4-16
The Future With the Proposed Actions....4-17
F. Health Care Facilities....4-18
Methodology....4-18

Existing Conditions 4-18
G. Police and Fire Services 4-26
Methodology 4-26
Existing Conditions 4-26

5: Open Space 5-1
A. Introduction 5-1
Principal Conclusions 5-1
B. Methodology 5-2
Direct Effects 5-2
Indirect Effects 5-3
C. Existing Conditions 5-5
Study Area Population 5-5
Inventory of Publicly Accessible Open Spaces 5-7
Assessment of Open Space Adequacy 5-15
D. The Future Without the Proposed Actions (No Action Condition) 5-17
Open Space Resources 5-17
Assessment of Open Space Adequacy 5-18
E. The Future With the Proposed Actions (With Action Condition) 5-19
Direct Effects 5-19
Indirect Effects 5-20
Open Space Resources 5-20
Assessment of Open Space Adequacy 5-20
Determining Impact Significance 5-21

6: Shadows 6-1
A. Introduction 6-1
Principal Conclusions 6-1
B. Definitions and Methodology 6-1
Definitions 6-2
Methodology 6-2
C. Preliminary Screening Assessment 6-3
Tier 1 Screening Assessment 6-3
Tier 2 Screening Assessment 6-4
Tier 3 Screening Assessment 6-4
D. Detailed Shadow Analysis 6-7
Determination of Impact Significance 6-7
Summary of Analysis Results 6-8
Assessment of Shadow Impacts By Resource 6-11
E. Conclusions 6-19

7: Historic and Cultural Resources 7-1
A. Introduction 7-1
B. Principal Conclusions 7-1
Archaeological Resources 7-1
Architectural Resources 7-2
C. Development Background 7-7
The Indigenous Occupation of the Project Area 7-7

Early Colonial Occupation of the Project Area 7-7
Agricultural Uses in the 18th and 19th Centuries 7-7
The Expansion of Urban Development and the Formation of Neighborhoods in the 19th Century 7-8
Late 19th Century Industrialization 7-8
D. Methodology 7-9
Archaeological Resources 7-9
Architectural Resources 7-10
E. Existing Conditions 7-13
Archaeological Resources 7-13
Architectural Resources 7-15
F. The Future Without the Proposed Actions 7-43
Archaeological Resources 7-43
Architectural Resources 7-44
G. The Future With the Proposed Actions 7-45
Overview 7-45
Archaeological Resources 7-45
Architectural Resources 7-56

8: Urban Design and Visual Resources 8-1
A. Introduction 8-1
B. Principal Conclusions 8-1
C. Methodology 8-3
D. Existing Conditions 8-5
Primary Study Area 8-5
Secondary Study Area 8-19
E. The Future Without the Proposed Actions (No Action Condition) 8-21
Primary Study Area 8-21
Secondary Study Area 8-22
F. The Future With the Proposed Actions (With Action Condition) 8-23
Primary Study Area 8-23
Secondary Study Area 8-36

9: Natural Resources 9-1
A. Introduction 9-1
Principal Conclusions 9-1
B. Methodology 9-2
Study Area 9-2
Existing Conditions 9-2
Future Without the Proposed Actions (No Action Condition) 9-2
Future With the Proposed Actions (With Action Condition) 9-2
Regulatory Context 9-2
C. Existing Conditions 9-3
Floodplains 9-4
Groundwater 9-4
Terrestrial Resources 9-4
Threatened, Endangered, and Special Concern Species and Significant Natural Communities 9-6

D. The Future Without the Proposed Actions 9-6
E. The Future With the Proposed Actions 9-7
Floodplains 9-7
Groundwater 9-7
Terrestrial Resources 9-7
Threatened, Endangered, and Special Concern Species and Significant Natural Communities 9-8
F. References 9-9

10: Hazardous Materials 10-1
A. Introduction 10-1
Principal Conclusions 10-1
B. Methodology 10-2
Sanborn Fire Insurance Map Review 10-2
Database Review 10-2
Site Reconnaissance 10-3
C. Existing Conditions 10-3
Topography and Hydrogeology 10-3
Regulatory Database Records 10-3
Overview of Historical Uses 10-4
D. The Future Without the Proposed Actions 10-13
E. The Future With the Proposed Actions 10-13
F. Conclusion 10-15

11: Water and Sewer Infrastructure 11-1
A. Introduction 11-1
Principal Conclusions 11-1
B. Methodology 11-2
C. Preliminary Analysis 11-3
Existing Conditions 11-3
The Future Without the Proposed Actions 11-5
The Future With the Proposed Actions 11-6
Stormwater Best Management Practices 11-10

12: Solid Waste 12-1
A. Introduction 12-1
Principal Conclusions 12-1
B. Methodology 12-2
C. Existing Conditions 12-2
Solid Waste Generation on Projected Development Sites 12-4
D. The Future Without the Proposed Actions 12-5
Other City Initiatives 12-5
E. The Future With the Proposed Actions 12-6

13: Energy 13-1
A. Introduction 13-1
Principal Conclusions 13-1
B. Methodology 13-2

C. Existing Conditions 13-2
Energy Supply and Transmission 13-2
Recent Energy Conservation Directives 13-3
Existing Demand 13-4
D. The Future Without the Proposed Actions 13-4
E. The Future With the Proposed Actions 13-5

14: Transportation 14-1
A. Introduction 14-1
B. Principal Conclusions 14-3
Traffic 14-3
Transit 14-3
Pedestrians 14-4
Street User Safety 14-4
Parking 14-5
C. Preliminary Analysis Methodology 14-6
D. Level 1 Screening Assessment 14-6
Background 14-6
Transportation Planning Factors 14-7
Travel Demand Forecast 14-7
E. Level 2 Screening Assessment 14-11
Vehicular Traffic 14-11
Transit 14-12
Pedestrians 14-14
Parking 14-15
F. Transportation Analyses Methodologies 14-15
Transit 14-15
Pedestrians 14-17
Vehicular and Pedestrian Safety Evaluation 14-20
Parking 14-21
G. Transit 14-21
Existing Conditions 14-21
The Future Without the Proposed Actions (No Action Condition) 14-26
The Future With the Proposed Actions (With Action Condition) 14-28
H. Pedestrians 14-31
Existing Conditions 14-31
The Future Without the Proposed Actions (No Action Condition) 14-33
The Future With the Proposed Actions (With Action Condition) 14-35
I. Street User Safety 14-37
Recent Dot Initiatives 14-37
Study Area High Crash Locations 14-39
J. Parking 14-41

15: Air Quality 15-1
A. Introduction 15-1
Principal Conclusions 15-1
B. Pollutants for Analysis 15-2
Carbon Monoxide 15-2

Nitrogen Oxides, VOCs, and Ozone 15-2
Lead 15-3
Respirable Particulate Matter—PM_{10} and $PM_{2.5}$ 15-3
Sulfur Dioxide 15-4
Noncriteria Pollutants 15-4
C. Air Quality Regulations, Standards, and Benchmarks 15-4
National and State Air Quality Standards 15-4
Naaqs Attainment Status and State Implementation Plans 15-6
Determining the Significance of Air Quality Impacts 15-7
D. Methodology for Predicting Pollutant Concentrations 15-9
Mobile Sources 15-9
Stationary Sources 15-9
E. Existing Conditions 15-16
F. The Future Without the Proposed Actions (No Action Condition) 15-17
G. The Future With the Proposed Actions (With Action Condition) 15-17
Mobile Sources 15-17
Stationary Sources 15-18

16: Greenhouse Gas Emissions and Climate Change 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Greenhouse Gas Emissions 16-2
Pollutants of Concern 16-2
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 16-3
Methodology 16-6
Projected GHG Emissions 16-9
Consistency With the Citywide GHG Reduction Goals 16-10
C. Resilience to Climate Change 16-11
Development of Policy to Improve Climate Change Resilience 16-12
Resilience of the Proposed Project to Climate Change 16-13

17: Noise 17-1
A. Introduction 17-1
Principal Conclusions 17-1
B. Acoustical Fundamentals 17-1
"A"-Weighted Sound Level (dBA) 17-1
Noise Descriptors Used in Impact Assessment 17-2
C. Noise Standards and Criteria 17-3
New York Ceqr Technical Manual Noise Standards 17-3
D. Existing Noise Levels 17-4
Selection of Noise Receptor Locations 17-4
Noise Monitoring 17-5
Existing Noise Levels At Noise Receptor Locations 17-5
E. Noise Prediction Methodology 17-7
F. Noise Attenuation Measures 17-7
G. Mechanical Equipment 17-11

18: Public Health 18-1
A. Introduction 18-1
Principal Conclusions 18-1
B. Public Health Assessment—Construction Noise 18-1
Assessment 18-2

19: Neighborhood Character 19-1
A. Introduction 19-1
Principal Conclusions 19-1
B. Methodology 19-2
Study Areas 19-3
C. Preliminary Assessment 19-3
Defining Features 19-4
Primary Study Area 19-8
Secondary Study Area 19-13
Assessment of the Potential to Affect the Defining Features of the Neighborhood 19-15

20: Construction 20-1
A. Introduction 20-1
Principal Conclusions 20-1
Governmental Coordination and Oversight 20-5
B. Conceptual Construction Phasing and Schedule 20-6
C. Construction Description 20-7
General Construction Stages 20-7
General Construction Practices 20-8
Number of Construction Workers and Material Deliveries 20-9
D. The Future Without the Proposed Actions (No Action Condition) 20-10
E. The Future With the Proposed Actions (With Action Condition) 20-10
Transportation 20-11
Air Quality 20-18
Noise 20-23
Vibration 20-44
Other Technical Areas 20-46

21: Mitigation 21-1
A. Introduction 21-1
Principal Conclusions 21-1
B. Open Space 21-3
C. Shadows 21-3
Most Precious Blood Church 21-3
Merchant's House Museum Rear Garden 21-4
Grand Canal Court 21-4
Greenstreet Between Thompson Street and Canal Street 21-5
Petrosino Square 21-5
Bowery & East 4th Street Planned Open Space 21-5
D. Historic and Cultural Resources 21-6
Archaeological Resources 21-6
Architectural Resources 21-6

E. Transportation 21-7
Transit 21-7
Pedestrians 21-8
F. Construction 21-8

22: Alternatives 22-1
A. Introduction 22-1
B. Principal Conclusions 22-1
No Action Alternative 22-1
No Unmitigated Significant Adverse Impacts Alternative 22-1
C. No Action Alternative 22-2
Land Use, Zoning, and Public Policy 22-2
Socioeconomic Conditions 22-2
Community Facilities and Services 22-3
Open Space 22-5
Shadows 22-5
Historic and Cultural Resources 22-5
Natural Resources 22-6
Hazardous Materials 22-6
Water and Sewer Infrastructure 22-7
Solid Waste and Sanitation Services 22-7
Energy 22-7
Transportation 22-8
Air Quality 22-9
Greenhouse Gas Emissions and Climate Change 22-10
Noise 22-10
Public Health 22-10
Neighborhood Character 22-10
Construction 22-10
D. No Unmitigated Significant Adverse Impacts Alternative 22-11
Open Space 22-11
Shadows 22-11
Historic and Cultural Resources 22-14
Transportation 22-15
Construction 22-16

23: Unavoidable Adverse Impacts 23-1
A. Introduction 23-1
B. Open Space 23-1
C. Shadows 23-1
Merchant's House Museum Rear Garden 23-2
Grand Canal Court 23-2
Greenstreet Between Thompson Street and Canal Street 23-3
Petrosino Square 23-3
Bowery & East 4th Street Planned Open Space 23-3
D. Historic and Cultural Resources 23-4
Archaeological Resources 23-4
Architectural Resources 23-4

E. Transportation 23-4
Transit 23-4
Pedestrians 23-5
F. Construction 23-5
Noise 23-5

24: Growth-Inducing Aspects of the Proposed Actions 24-1

25: Irreversible and Irretrievable Commitments of Resources 25-1

LIST OF APPENDICES

Appendix A: Project Description
A-1: Proposed Zoning Text Amendments
A-2: Reasonable Worst-Case Development Scenario
A-3: Blocks and Lots in Rezoning Area

Appendix B-1: Waterfront Revitalization Program

Appendix B-2: WRP, CAF, and WRP Policy Analysis

Appendix C: Historic Resources
C-1: Historic and Cultural Resources Correspondence
C-2: Phase 1A Study

Appendix D: Hazardous Materials

Appendix E: TPF-TDF Memo

Appendix F: Proposed Air Quality (E) Designations

Appendix G: Noise

Appendix H: Construction

List of Tables

S-1 Proposed Use and Floor Area Regulations S-21
S-2 Proposed Base Heights and Maximum Building Heights S-22
S-3 Rwcds No Action and With Action Land Uses S-25
S-4 Summary of Significant Pedestrian Impacts S-49
S-5 High Crash Locations S-50
1-1 Proposed Use and Floor Area Regulations 1-22
1-2 Proposed Base Heights and Maximum Building Heights 1-22
1-3 RWCDS No Action and With Action Land Uses 1-26
2-1 Existing Land Uses Within Primary Study Area 2-4
2-2 Existing Land Uses Within Soho East 2-5
2-3 Existing Land Uses Within Soho West Subarea 2-6
2-4 Existing Land Uses Within Noho-Bowery Subarea 2-7
2-5 Existing Land Uses Within Canal Street Subarea 2-8
2-6 Existing Land Uses Within Broadway and Houston Street Subarea 2-9
2-7 Existing Land Uses Within Soho Historic Core Subarea 2-10
2-8 Existing Land Uses Within Noho Historic Core Subarea 2-11
2-9 Existing Zoning Districts Within the Secondary Study Area 2-17
2-10 Development Projects in the Future Without the Proposed Actions 2-25
2-11 RWCDS No Action and With Action Land Uses 2-29
2-12 Proposed Use and Floor Area Regulations 2-44
2-13 Proposed Base Heights and Maximum Building Heights 2-44
3-1 2018 Employment in Study Area, Manhattan, and New York City 3-12
3-2 Businesses and Employment Potentially Displaced By the Proposed Actions 3-14
3-3 Household Income Characteristics (2006-2010, 2014-2018 ACS) 3-21
3-4 Potential Rent-Protected Units in Study Area 3-22
3-5 Average and Median Gross Rents 3-23
3-6 Average and Median Market Rents in the Study Area 3-23
3-7 2021 New York City Area Median Income (AMI) 3-24
3-8 2021 New York City Affordable Monthly Rents By Area Median Income (AMI) 3-25
3-9 Market Rate Units By Number of Bedrooms 3-25
3-10 Weighted Average Income of With-Action Market-Rate Renters 3-26
3-11 Weighted Average Income of Total With Action Population 3-26
3-12 Study Area and Subarea Population Estimates and Projections Existing Conditions and Future Without the Proposed Actions 3-28
3-13 With Action Condition Population 3-29
3-14 Existing Land Uses and Incremental Land Uses Under the Proposed Actions RWCDS 3-31
3-15 Household Income Characteristics (2006-2010, 2014-2018 ACS) 3-35
3-16 Household Income Distribution 2018 3-35
3-17 Percentage of Population Living Below Poverty Level 3-36
3-18 Housing Units, Vacancy, and Tenure 3-36
3-19 2018 Housing Units By Year Structure Built 3-37

3-20 Units in Structure 3-38
3-21 Renter-Occupied Housing Units By Gross Rent As Percentage of Household Income 3-38
3-22 Average Market Rents 3-39
3-23 Certificates of Occupancy and Residential Demolitions 2013-2020 3-40
3-24 Low-Income Renter Households: Subarea A 3-41
3-25 Allocation of Low-Income Households: Subarea A 3-42
3-26 Low-Income Renter Households: Subarea B 3-42
3-27 Allocation of Low-Income Households: Subarea B 3-43
3-28 Planned Projects in Subareas 3-44
4-1 Preliminary Screening Analysis Criteria: Manhattan 4-3
4-2 Study Area Elementary Schools 4-5
4-3 Study Area Intermediate Schools 4-6
4-4 Projected Estimated Number of New Students Introduced By Development in the No Action Condition 4-7
4-5 Projected Estimated Number of New Students Introduced By Development in the With Action Condition 4-7
4-6 Estimated Public School Enrollment, Capacity, and Utilization: With Action Condition 4-8
4-7 Public Libraries Serving the Study Area 4-10
4-8 Catchment Area Population: No Action Condition 4-12
4-9 Catchment Area Population: With Action Condition 4-14
4-10 Publicly Funded Early Childhood Programs Serving the Study Area 4-16
4-11 Estimated Public Child Care Facility Enrollment, Capacity, and Utilization 4-17
4-12 Hospitals Serving the Project Area 4-18
4-13 Outpatient Facilities Serving the Project Area 4-20
4-14 Police Precincts Serving the Project Area 4-26
4-15 Firehouses Serving the Project Area 4-27
5-1 Study Area Residential Population 5-6
5-2 Study Area Population Age Distribution 5-7
5-3 Study Area Quantified Open Space Resources 5-8
5-4 Open Spaces Included in the Qualitative Assessment 5-13
5-5 Adequacy of Open Space Resources in the Study Area: Existing Conditions 5-16
5-6 Additional Publicly Accessible Open Space Introduced in the No Action Condition 5-17
5-7 Adequacy of Open Space Resources in the Study Area: No Action Condition 5-18
5-8 With Action Open Space Study Area Population 5-20
5-9 Adequacy of Open Space Resources in the Study Area: With Action Condition 5-20
5-10 Open Space Ratio Summary 5-21
6-1 Tier 3 Assessment 6-6
6-2 Incremental Shadow Durations 6-9
7-1 Development Sites Included in the Phase 1a Study Area 7-11
7-2 Determinations of Archaeological Sensitivity 7-15
7-3 Architectural Resources 7-16
7-4 Impacts on Architectural Resources 7-47
7-5 Projected and Potential Development Sites On or Adjacent to An Architectural Resource: No Action and With Action Condition Impacts 7-60
9-1 Birds Documented During the 2000–2005 New York State Breeding Bird Atlas in Blocks 5850a and 5750b 9-5
10-1 Assessment of Projected and Potential Development Sites 10-5

11-1 Existing Water Consumption 11-3
11-2 Existing Wastewater Generation on the Projected Development Sites by Subcatchment Area 11-4
11-3 Existing Surface Coverage 11-5
11-4 With Action Condition Water Consumption 11-7
11-5 With Action Condition Wastewater Generation on the Projected Development Sites by Subcatchment Area 11-7
11-6 With Action Surface Coverage 11-8
11-7 Flow Volume Matrix: Existing and With Action Volume Comparison 11-9
12-1 Existing Solid Waste Generation on Projected Development Sites 12-4
12-2 No Action Solid Waste Generation on Projected Development Sites 12-5
12-3 With-Action Solid Waste Generation on Projected Development Sites 12-7
12-4 Comparison of Weekly Solid Waste Generation on Projected Development Sites (Existing, No Action, With Action Conditions) 12-7
13-1 Existing Annual Energy Consumption for the Projected Development Sites 13-4
13-2 No Action Annual Energy Consumption for the Projected Development Sites 13-5
13-3 With Action Annual Energy Consumption for the Projected Development Sites 13-5
14-1 2031 RWCDS No Action and With Action Land Uses for the Transportation Analyses 14-2
14-2 Summary of Significant Pedestrian Impacts 14-4
14-3 High Crash Locations 14-5
14-4 Transportation Planning Factors 14-8
14-5 RWCDS Travel Demand Forecast 14-9
14-6 RWCDS Net Incremental Vehicle Trips by Projected Development Site 14-10
14-7 Summary of Net Incremental Peak Hour Trips Generated Under the RWCDS 14-11
14-8 RWCDS Net Incremental Peak Hour Subway Trips by Station 14-13
14-9 Level of Service Criteria for Subway Station Elements 14-16
14-10 Significant Impact Thresholds for Stairways and Passageways 14-17
14-11 Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions 14-18
14-12 Significant Impact Criteria for Sidewalks With Platooned Flow in a CBD Location 14-19
14-13 Significant Impact Criteria for Corners and Crosswalks in a CBD Location 14-20
14-14 Existing Conditions Subway Station Stair Analysis 14-24
14-15 Existing Conditions Subway Station Fare Array Analysis 14-24
14-16 Existing Conditions Subway Line Haul Analysis 14-25
14-17 No Action Subway Station Stair Analysis 14-26
14-18 No Action Subway Station Fare Array Analysis 14-27
14-19 No Action Subway Line Haul Analysis 14-28
14-20 With Action Subway Station Stair Analysis 14-29
14-21 With Action Subway Station Fare Array Analysis 14-29
14-22 With Action Subway Line Haul Analysis 14-31
14-23 Existing Sidewalk Conditions 14-32
14-24 Existing Corner Conditions 14-33
14-25 Existing Crosswalk Conditions 14-33
14-26 No Action Sidewalk Conditions 14-34
14-27 No Action Corner Conditions 14-34
14-28 No Action Crosswalk Conditions 14-35
14-29 With Action Sidewalk Conditions 14-36
14-30 With Action Corner Conditions 14-36

14-31 With Action Crosswalk Conditions 14-37
14-32 Summary of Motor Vehicle Crash Data 2016-2018..... 14-39
14-33 RWCDS Net Incremental Weekday Hourly Parking Accumulation by Land Use 14-41
14-34 Existing Off-Street Public Parking Facilities on Projected Development Sites..... 14-42
15-1 National Ambient Air Quality Standards (NAAQS)..... 15-5
15-2 Industrial Source Analysis: Relevant Dec Air Guideline Concentrations..... 15-8
15-3 Maximum Background Pollutant Concentrations 15-12
15-4 Cluster Analysis Sites..... 15-13
15-5 Industrial Sources Within 400 Feet of a Projected or Potential Development Site.... 15-14
15-6 Modeled Emission Rates of Existing Industrial Sources 15-14
15-7 Stack Parameters and Emission Rates from Manhattan Criminal Court..... 15-16
15-8 Stack Parameters and Emission Rates from the NYU Cogeneration Plant..... 15-16
15-9 Representative Monitored Ambient Air Quality Data..... 15-17
15-10 Heating and Hot Water System Analysis Summary..... 15-19
15-11 Heating and Hot Water System Analysis—Results for Projected Development Sites... 15-21
15-12 Heating and Hot Water System Analysis—Results for Potential Development Sites 15-22
15-13 Cumulative Heating and Hot Water System Analysis Maximum Pollutant Concentrations – Screening Results ($\mu g/m^3$)..... 15-25
15-14 Maximum Modeled Impacts On Projected and Potential Sites from Industrial Sources 15-25
15-15 Estimated Maximum Hazard Index..... 15-25
15-16 Maximum Modeled Pollutant Concentrations on the Proposed Project ($\mu g/m^3$)—Manhattan Criminal Court..... 15-26
15-17 Maximum Modeled Pollutant Concentrations on the Proposed Project ($\mu g/m^3$)—NYU Cogeneration Plant..... 15-26
16-1 GWP for Major GHGs 16-3
16-2 Vehicle Miles Traveled Per Year—RWCDS..... 16-8
16-3 Annual Building Operational Emissions—RWCDS..... 16-9
16-4 Annual Mobile Source Emissions—RWCDS (Metric Tons CO_2e, 2031)..... 16-9
16-5 Summary of Annual GHG Emissions—RWCDS (Metric Tons CO_2e)..... 16-10
17-1 Common Noise Levels..... 17-2
17-2 Noise Exposure Guidelines for Use in City Environmental Impact Review 17-3
17-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 17-4
17-4 Proposed Noise Measurement Locations 17-4
17-5 Existing Noise Levels (in dBA) 17-5
17-6 Playground Boundary Noise $L_{eq(1)}$ Noise Levels (in dBA)..... 17-7
17-7 Required Attenuation at Noise Measurement Locations (in Dba) 17-8
17-8 Required Attenuation at Development Sites (in dBA)..... 17-8
20-1 Summary of Primary Agency Construction Oversight 20-6
20-2 Average Number of Daily Construction Workers and Trucks By Year and Quarter. 20-10
20-3 2028 (First Quarter) Peak Incremental Construction Vehicle Trip Projections (in PCEs).. 20-12
20-4 Comparison of 2028 (First Quarter) Peak Incremental Construction Vehicle Trips With 2031 Operational Vehicle Trips (in PCEs)..... 20-12
20-5 2029 (First Quarter) Peak Incremental Construction Vehicle Trip Projections (in PCEs).. 20-14
20-6 2029 (First Quarter) Incremental Peak Hour Construction and Operational Traffic Volumes (in PCEs)..... 20-14
20-7 2028 (First Quarter) and 2029 (First Quarter) Construction Worker Parking Accumulation..... 20-17

20-8 Pollutants for Analysis and Averaging Periods 20-18
20-9 Maximum Predicted Pollutant Concentrations from Construction Site Sources—Peak Analysis Periods ($\mu g/m^3$) 20-22
20-10 Construction Activities At Projected Development Sites 20-29
20-11 Typical Construction Equipment Noise Emission Levels (dBA) 20-30
20-12 Projected Development Site 5 Noise Analysis Results in dBA 20-32
20-13 Projected Development Site 9 Noise Analysis Results in dBA 20-38
20-14 Vibration Source Levels for Construction Equipment 20-45
21-1 Minimum Required Subway Stairway Widening to Mitigate Impacts at the Canal Street (A/C/E) Station 21-7

List of Figures

following page:

S-1 Aerial S-1
S-2 Project Location S-2
S-3 Existing Zoning S-9
S-4 Proposed Zoning S-16
S-5 Projected and Potential Development Sites S-25
1-1 Aerial 1-1
1-2 Project Location 1-1
1-3 Existing Zoning 1-9
1-4 Proposed Zoning 1-16
1-5 Projected and Potential Development Sites 1-25
2-1 Project Location and Secondary Study Area 2-1
2-2 Primary Study Area Subareas 2-3
2-3 Existing Land Use 2-4
2-4 Existing Zoning 2-14
2-5 Coastal Zone Boundary 2-23
2-6 Business Improvement Districts 2-23
2-7 Planned No Build Developments 2-25
2-8 Proposed Zoning 2-40
3-1 Socioeconomic Study Area 3-8
3-2 Socioeconomic Subareas 3-8
3-3 Average Household Income 3-21
4-1 Public Schools Serving the Study Area 4-4
4-2 Public Libraries Serving the Study Area 4-10
4-3 Publicly Funded Early Childhood Programs 4-16
4-4 Health Care Facilities 4-18
4-5 Police Precincts 4-26
4-6 Fire Engine Companies 4-26
5-1 Open Space Study Area 5-4
5-2 Open Space Study Area and Resources 5-7
5-3 Additional Open Spaces in the Study Area 5-7
6-1 Tier 1 and Tier 2 Assessments 6-19
6-2 Tier 3 Assessment: December 21 6-19
6-3 Tier 3 Assessment: March 21 / September 21 6-19
6-4 Tier 3 Assessment: May 6 / August 6 6-19
6-5 Tier 3 Assessment: June 21 6-19
6-6 Detailed Analysis: December 21 6-19
6-7 Detailed Analysis: December 21 6-19
6-8 Detailed Analysis: December 21 6-19
6-9 Detailed Analysis: December 21 6-19

6-10 Detailed Analysis: December 21 6-19
6-11 Detailed Analysis: March 21 / September 21 6-19
6-12 Detailed Analysis: March 21 / September 21 6-19
6-13 Detailed Analysis: March 21 / September 21 6-19
6-14 Detailed Analysis: March 21 / September 21 6-19
6-15 Detailed Analysis: March 21 / September 21 6-19
6-16 Detailed Analysis: March 21 / September 21 6-19
6-17 Detailed Analysis: May 6 / August 6 6-19
6-18 Detailed Analysis: May 6 / August 6 6-19
6-19 Detailed Analysis: May 6 / August 6 6-19
6-20 Detailed Analysis: May 6 / August 6 6-19
6-21 Detailed Analysis: May 6 / August 6 6-19
6-22 Detailed Analysis: May 6 / August 6 6-19
6-23 Detailed Analysis: June 21 6-19
6-24 Detailed Analysis: June 21 6-19
6-25 Detailed Analysis: June 21 6-19
6-26 Detailed Analysis: June 21 6-19
6-27 Detailed Analysis: June 21 6-19
6-28 Detailed Analysis: June 21 6-19
6-29 Detailed Analysis: December 21 6-19
6-30 Detailed Analysis: December 21 6-19
6-31 Detailed Analysis: December 21 6-19
6-32 Detailed Analysis: December 21 6-19
6-33 Detailed Analysis: March 21 / September 21 6-19
6-34 Detailed Analysis: March 21 / September 21 6-19
6-35 Detailed Analysis: March 21 / September 21 6-19
6-36 Detailed Analysis: May 6 / August 6 6-19
6-37 Detailed Analysis: May 6 / August 6 6-19
6-38 Detailed Analysis: May 6 / August 6 6-19
6-39 Detailed Analysis: June 21 6-19
6-40 Detailed Analysis: June 21 6-19
6-41 Detailed Analysis: December 21 6-19
6-42 Detailed Analysis: December 21 6-19
6-43 Detailed Analysis: December 21 6-19
6-44 Detailed Analysis: December 21 6-19
6-45 Detailed Analysis: March 21 / September 21 6-19
6-46 Detailed Analysis: March 21 / September 21 6-19
6-47 Detailed Analysis: March 21 / September 21 6-19
6-48 Detailed Analysis: March 21 / September 21 6-19
6-49 Detailed Analysis: May 6 / August 6 6-19
6-50 Detailed Analysis: May 6 / August 6 6-19
6-51 Detailed Analysis: June 21 6-19
6-52 Detailed Analysis: June 21 6-19
6-53 Detailed Analysis: December 21 6-19
6-54 Detailed Analysis: March 21 / September 21 6-19
6-55 Detailed Analysis: March 21 / September 21 6-19
6-56 Detailed Analysis: May 6 / August 6 6-19
6-57 Detailed Analysis: May 6 / August 6 6-19

6-58 Detailed Analysis: May 6 / August 6 6-19
6-59 Detailed Analysis: June 21 6-19
6-60 Detailed Analysis: June 21 6-19
6-61 Detailed Analysis: June 21 6-19
6-62 Detailed Analysis: March 21 / September 21 6-19
6-63 Detailed Analysis: May 6 / August 6 6-19
6-64 Detailed Analysis: May 6 / August 6 6-19
6-65 Detailed Analysis: June 21 6-19
6-66 Detailed Analysis: June 21 6-19
6-67 Detailed Analysis: June 21 6-19
6-68 Duarte Square Site Plan 6-19
7-1a Project Location 7-10
7-1b Areas of Archaeological Sensitivity 7-10
7-2 Architectural Resources 7-15
7-3 Architectural Resources 7-15
7-4 Architectural Resources 7-15
7-5 Architectural Resources 7-15
7-6 Architectural Resources 7-15
7-7 Architectural Resources 7-15
7-8 Architectural Resources 7-15
7-9 Architectural Resources 7-15
7-10 Architectural Resources 7-15
7-11 Architectural Resources 7-15
7-12 Architectural Resources 7-15
7-13 Architectural Resources 7-15
7-14 Architectural Resources 7-15
7-15 Architectural Resources 7-15
7-16 Architectural Resources 7-15
7-17 Architectural Resources 7-15
7-18 Architectural Resources 7-15
7-19 Architectural Resources 7-15
7-20 Architectural Resources 7-15
7-21 Architectural Resources 7-15
7-22 Architectural Resources 7-15
7-23 Architectural Resources 7-15
7-24 Architectural Resources 7-15
7-25 Architectural Resources 7-15
7-26 Architectural Resources 7-15
7-27 Architectural Resources 7-15
7-28 Architectural Resources 7-15
7-29 Architectural Resources 7-15
7-30 Architectural Resources 7-15
7-31 Architectural Resources 7-15
7-32 Architectural Resources 7-15
7-33 Architectural Resources 7-15
7-34 Architectural Resources 7-15
7-35 Architectural Resources 7-15
7-36 Architectural Resources 7-15

7-37 Architectural Resources 7-15
7-38 Architectural Resources 7-15
7-39 Architectural Resources 7-15
7-40 Architectural Resources 7-15
7-41 Architectural Resources 7-15
8-1 Urban Design and Visual Resources Study Area Subareas 8-1
8-2 Urban Design and Visual Resources Aerial Map 8-1
8-3 Urban Design and Visual Resources Photograph Key Map 8-5
8-4a Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4b Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4c Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4d Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4e Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4f Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4g Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4h Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4i Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4j Existing Conditions: Broadway and Houston Street Subarea 8-5
8-4k Existing Conditions: Canal Street Subarea 8-9
8-4l Existing Conditions: Canal Street Subarea 8-9
8-4m Existing Conditions: Canal Street Subarea 8-9
8-4n Existing Conditions: SoHo Historic Core Subarea 8-11
8-4o Existing Conditions: SoHo Historic Core Subarea 8-11
8-4p Existing Conditions: SoHo Historic Core Subarea 8-11
8-4q Existing Conditions: SoHo Historic Core Subarea 8-11
8-4r Existing Conditions: SoHo Historic Core Subarea 8-11
8-4s Existing Conditions: SoHo Historic Core Subarea 8-11
8-4t Existing Conditions: SoHo Historic Core Subarea 8-11
8-4u Existing Conditions: SoHo West Subarea 8-13
8-4v Existing Conditions: SoHo West Subarea 8-13
8-4w Existing Conditions: SoHo West Subarea 8-13
8-4x Existing Conditions: SoHo West Subarea 8-13
8-4y Existing Conditions: SoHo East Subarea 8-15
8-4z Existing Conditions: SoHo East Subarea 8-15
8-4aa Existing Conditions: SoHo East Subarea 8-15
8-4ab Existing Conditions: NoHo Historic Core Subarea 8-16
8-4ac Existing Conditions: NoHo Historic Core Subarea 8-16
8-4ad Existing Conditions: NoHo Historic Core Subarea 8-16
8-4ae Existing Conditions: NoHo-Bowery Subarea 8-17
8-4af Existing Conditions: NoHo-Bowery Subarea 8-17
8-4ag Existing Conditions: NoHo-Bowery Subarea 8-17
8-4ah Existing Conditions: Secondary Study Area 8-19
8-4ai Existing Conditions: Secondary Study Area 8-19
8-4aj Existing Conditions: Secondary Study Area 8-19
8-4ak Existing Conditions: Secondary Study Area 8-19
8-4al Existing Conditions: Secondary Study Area 8-19
8-4am Existing Conditions: Secondary Study Area 8-19
8-4an Existing Conditions: Secondary Study Area 8-19

8-4ao Existing Conditions: Secondary Study Area 8-19
8-5 No Action and With Action Conditions Photograph Views 8-23
8-6a Comparison Massings: Broadway and Houston Street Subarea: View south on Broadway from Spring Street 8-23
8-6b Comparison Massings: Canal Street Subarea: View northwest on Canal Street from Between Broadway and Mercer Street 8-23
8-6c Comparison Massings: SoHo Core [Preservation] Subarea: View south on West Broadway from Spring Street 8-23
8-6d Comparison Massings: SoHo Core [Preservation] Subarea: View west on Grand Street from Wooster Street 8-23
8-6e Comparison Massings: SoHo Core [Preservation] Subarea: View south on Wooster Street from Prince Street 8-23
8-6f Comparison Massings: SoHo Core [Preservation] Subarea: View southwest on Lafayette Street from Spring Street 8-23
8-6g Comparison Massings: SoHo West Subarea: View northwest on Canal Street from Church Street 8-23
8-6h Comparison Massings: SoHo West Subarea: View south on Centre Street from Grand Street 8-23
8-6i Comparison Massings: SoHo East Subarea: View south on Lafayette Street from between Grand Street and Broome Street 8-23
8-6j Comparison Massings: NoHo-Bowery Subarea: View south on Bowery from East 6th Street 8-23
9-1 FEMA Preliminary FIRM 2015 9-4
11-1 WRRF Subcatchment Areas 11-4
14-1 AM Peak Hour Project Increment Traffic Volumes 14-12
14-2 MD Peak Hour Project Increment Traffic Volumes 14-12
14-3 PM Peak Hour Project Increment Traffic Volumes 14-12
14-4 Saturday Peak Hour Project Increment Traffic Volumes 14-12
14-5 Subway Stations 14-12
14-6 Analyzed Pedestrian Elements 14-14
14-7 Canal Street (J/N/Q/R/W/Z/6) Subway Station Complex 14-22
14-8 Analyzed Elements at the Canal Street (6) Subway Station 14-22
14-9 Analyzed Elements at the Canal Street (A/C/E) Subway Station 14-23
15-1 Air Quality Cluster Analysis Potential Cluster Locations 15-12
17-1 Noise Measurement Locations 17-4
19-1 Neighborhood Character 19-3
20-1 Conceptual Construction Schedule 20-7
20-2 Construction Noise Impacts 20-43

✶