Halletts North

Draft Environmental Impact Statement (DEIS)



CEQR No. 21DCP138Q

ULURP Nos.: 220196ZMQ, 220197ZRQ, 220206MMQ, 220198ZSQ, N220353ZAQ, N220200ZAQ, N220202ZAQ, N220199ZCQ, N220164LDQ

Lead Agency:

City Planning Commission, City of New York

Dan Garodnick, Chair

March 25, 2022

Halletts North

Draft Environmental Impact Statement (DEIS)

Project Location:	Queens, New York Community District 1
Type of Action:	Type I
CEQR No.:	21DCP138Q
ULURP Nos.:	ULURP Nos.: 220196ZMQ, 220197ZRQ, 220206MMQ, 220198ZSQ, N220353ZAQ, N220200ZAQ, N220202ZAQ, N220199ZCQ, N220164LDQ
Lead Agency:	City Planning Commission, City of New York Dan Garodnick, Chair
Lead Agency Contact:	Stephanie Shellooe, AICP, Director Environmental Assessment and Review Division New York City Department of City Planning 120 Broadway, 31st Floor New York, New York, 10271
Project Applicant:	Astoria Owners, LLC
Prepared For:	New York City Department of City Planning Alexis Wheeler, Queens Office
Prepared by:	Philip Habib & Associates 102 Madison Avenue, Floor 11 New York, NY 10016
Acceptance Date:	March 25, 2022

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Writing comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing. The DEIS is available on the website of the New York City Department of City Planning, via the Halletts North project page on ZAP: https//zap.planning.nyc.gov/projects/2018Q0491

To view the Halletts North DEIS and Appendix, navigate to the project page in ZAP and select Public Documents, then “DEIS_21DCP138Q”.

TABLE OF CONTENTS

Executive Summary ES-1

A. Introduction ES-1
B. Existing Conditions ES-2
C. Description of the Proposed Actions ES-2
Proposed Zoning Map Changes ES-2
Proposed Zoning Text Amendment ES-3
City Map Amendment ES-3
Waterfront Special Permit ES-4
Waterfront Authorizations and Certifications ES-4
Additional Actions – Not Subject to City Planning Commission Approval ES-4
D. Purpose and Need for the Proposed Actions ES-4
E. Description of the Proposed Project ES-5
F. Analysis Framework for Environmental Review ES-6
Future without the Proposed Actions (No-Action Condition) ES-7
Future with the Proposed Actions (With-Action Condition) ES-7
Reasonable Worst-Case Development Scenario for Analysis Purposes ES-8
G. Probable Impacts of the Proposed Actions ES-9
Land Use, Zoning, and Public Policy ES-9
Socioeconomic Conditions ES-10
Community Facilities ES-10
Open Space ES-13
Shadows ES-14
Urban Design and Visual Resources ES-14
Natural Resources ES-15
Hazardous Materials ES-15
Water and Sewer Infrastructure ES-16
Transportation ES-17
Air Quality ES-20
Greenhouse Gas Emissions and Climate Change ES-20
Noise ES-21
Public Health ES-22
Neighborhood Character ES-22
Construction ES-23
H. Mitigation ES-27
Community Facilities ES-28
Open Space ES-28
Transportation ES-29
Noise ES-32
Construction ES-32
I. Alternatives ES-33
No-Action Alternative ES-33
No Unmitigated Significant Adverse Impacts Alternative ES-34
Lower Density Alternative ES-34
J. Unavoidable Adverse Impacts ES-35
Community Facilities ES-35
Open Space ES-36
Transportation ES-36
Noise ES-39

Construction ES-39
K. Growth-Inducing Aspects of the Proposed Actions ES-40
L. Irreversible and Irretrievable Commitments of Resources ES-41

Chapter 1: Project Description 1-1
A. Introduction 1-1
B. Existing Conditions 1-2
C. Purpose and Need for the Proposed Actions 1-3
D. Description of the Proposed Actions 1-4
Proposed Zoning Map Changes 1-4
Proposed Zoning Text Amendment 1-4
City Map Amendment 1-5
Waterfront Special Permit 1-5
Waterfront Authorizations and Certifications 1-5
Additional Actions – Not Subject to City Planning Commission Approval 1-5
E. Description of the Proposed Project 1-6
F. Analysis Framework and Reasonable Worst-Case Development Scenario (RWCDS) 1-7
Future without the Proposed Actions (No-Action Condition) 1-8
Future with the Proposed Actions (With-Action Condition) 1-8
Reasonable Worst-Case Development Scenario for Analysis Purposes 1-9
G. Public Review Process 1-10
Uniform Land Use Review Process (ULURP) 1-10
City Environmental Quality Review (CEQR) 1-11

Chapter 2: Land Use, Zoning, and Public Policy 2-1
A. Introduction 2-1
B. Principal Conclusions 2-2
C. Methodology 2-2
Analysis Year 2-3
Study Area Definition 2-3
D. Development History 2-4
E. Detailed Assessment 2-5
Existing Conditions 2-5
Future without the Proposed Actions (No-Action Condition) 2-12
Future with the Proposed Actions (With Condition) 2-13

Chapter 3: Socioeconomic Conditions 3-1
A. Introduction 3-1
B. Principal Conclusions 3-1
Direct Residential Displacement 3-1
Direct Business/Institutional Displacement 3-2
Indirect Residential Displacement 3-2
Indirect Business Displacement 3-3
C. Methodology 3-4
Determining Whether a Socioeconomic Assessment is Appropriate 3-4
Analysis Format 3-6
Study Area Definition 3-6
D. Preliminary Assessment 3-7
Indirect Residential Displacement 3-7
E. Detailed Assessment of Indirect Residential Displacement 3-8

Existing Conditions 3-9
The Future without the Proposed Actions (No-Action Condition) 3-18

The Future with the Proposed Actions (With Action Condition) 3-19
Indirect Residential Displacement Analysis 3-20

Chapter 4: Community Facilities 4-1
A. Introduction 4-1
B. Principal Conclusions 4-1
Public Schools 4-1
Libraries 4-3
Early Childhood Programs 4-3
Police, Fire, and Health Care Services 4-3
C. Preliminary Screening 4-4
Direct Effects 4-4
Indirect Effects 4-4
D. Indirect Effects on Public Schools 4-6
Methodology 4-6
Existing Conditions 4-8
The Future without the Proposed Actions (No-Action Condition) 4-10
The Future with the Proposed Actions (With-Action Condition) 4-12
E. Indirect Effects on Public Libraries 4-13
Methodology 4-13
Existing Conditions 4-14
The Future without the Proposed Actions (No-Action Condition) 4-14
The Future with the Proposed Actions (With-Action Condition) 4-15
F. Indirect Effects on Publicly Funded Child Care Centers 4-16
Methodology 4-16
Existing Conditions 4-17
The Future without the Proposed Actions (No-Action Condition) 4-17
The Future with the Proposed Actions (With-Action Condition) 4-18

Chapter 5: Open Space 5-1
A. Introduction 5-1
B. Principal Conclusions 5-1
C. Methodology 5-2
Study Area 5-2
Analysis Framework 5-3
D. Existing Conditions 5-4
Study Area Population 5-4
Inventory of Publicly Accessible Open Space 5-5
Assessment of Open Space Adequacy 5-10
E. The Future without the Proposed Actions (No-Action Condition) 5-11
Study Area Population 5-11
Open Space Resources 5-12
Assessment of Open Space Adequacy 5-13
F. The Future with the Proposed Actions (With-Action Condition) 5-13
Direct Effects 5-14
Indirect Effects 5-14

Chapter 6: Shadows 6-1
A. Introduction 6-1
B. Principal Conclusions 6-1
C. Methodology 6-1
D. Preliminary Screening 6-3
Tier 1 Screening Assessment 6-3
Tier 2 Screening Assessment 6-4

Tier 3 Screening Assessment 6-4
E. Detailed Assessment....6-5
Resources of Concern 6-5
Shadows Analysis....6-6
Assessment....6-9

Chapter 7: Urban Design and Visual Resources 7-1
A. Introduction....7-1
B. Principal Conclusions 7-1
Urban Design 7-1
Visual Resources 7-2
C. Methodology 7-2
Study Area 7-3
D. Preliminary Assessment....7-3
E. Detailed Analysis....7-4
Existing Conditions....7-4
The Future without the Proposed Actions (No-Action Condition) 7-7
The Future with the Proposed Actions (With-Action Condition)....7-9

Chapter 8: Natural Resources 8-1
A. Introduction....8-1
B. Principal Conclusions 8-1
C. Methodology 8-2
Study Area and Data Sources....8-3
D. Regulatory Context 8-3
E. Existing Conditions....8-6
F. The Future without the Proposed Actions (No-Action Condition) 8-9
Groundwater and Floodplain....8-9
Water Quality and Aquatic Biota 8-9
Terrestrial Ecological Communities, Vegetation, and Wildlife 8-10
G. The Future with the Proposed Actions (With-Action Condition)....8-10
Groundwater 8-10
Floodplains....8-10
Wetlands and Aquatic Resources 8-11
Terrestrial Ecological Communities and Vegetation....8-12
Wildlife....8-13
Threatened. Endangered, and Special Concern Species and Significant Habitat Areas 8-14
H. Conclusions....8-14

Chapter 9: Hazardous Materials....9-1
A. Introduction....9-1
B. Principal Conclusions 9-1
C. Methodology 9-2
D. Background....9-3
E. Existing Conditions....9-5
F. The Future without the Proposed Actions (No-Action Condition) 9-8
G. The Future with the Proposed Actions (With-Action Condition)....9-8

Chapter 10: Water and Sewer Infrastructure 10-1
A. Introduction....10-1
B. Principal Conclusions 10-1
Water Supply 10-1
Sanitary (Dry Weather) Flows....10-2
Stormwater (Wet Weather) Flows 10-2

C. Methodology 10-2
D. Existing Conditions 10-4
Water Supply 10-4
Wastewater 10-5
Stormwater and Drainage Management 10-6
Water Conservation and WPCP Load Reduction 10-7
E. The Future without the Proposed Actions (No-Action Condition) 10-8
Water Supply 10-8
Wastewater 10-9
Stormwater and Drainage Management 10-9
F. The Future with the Proposed Actions (With-Action Condition) 10-10
Water Supply 10-10
Wastewater 10-11
Stormwater and Drainage Management 10-11
Stormwater Best Management Practices (BMPs) 10-13
Proposed Actions and Associated Infrastructure Improvements 10-14

Chapter 11: Transportation 11-1
A. Introduction 11-1
B. Principal Conclusions 11-2
Traffic 11-2
Transit 11-2
Pedestrians 11-3
Street User Safety 11-4
Parking 11-4
C. Preliminary Analysis Methodology 11-5
D. Level 1 Screening Assessment 11-5
Transportation Planning Factors 11-5
Trip Generation 11-7
E. Level 2 Screening Assessment 11-10
Vehicular Traffic 11-10
Transit 11-10
Bus 11-12
Pedestrians 11-12
Parking 11-14
F. Transportation Analyses Methodologies 11-16
Traffic 11-16
Transit 11-18
Pedestrians 11-19
Street User Safety 11-23
Parking 11-24
G. Traffic 11-25
Existing Conditions 11-25
The Future without the Proposed Actions (No-Action Condition) 11-28
The Future with the Proposed Actions (With-Action Condition) 11-36
H. Transit 11-39
Existing Conditions 11-39
The Future without the Proposed Actions (No-Action Condition) 11-41
The Future with the Proposed Actions (With-Action Condition) 11-44
I. Pedestrians 11-47
Existing Conditions 11-47
The Future without the Proposed Actions (No-Action Condition) 11-49
The Future with the Proposed Actions (With-Action Condition) 11-51
J. Street User Safety 11-55

Recent DOT Initiatives 11-55
Study Area High Crash Locations 11-56
K. Parking 11-58
Existing Conditions 11-58
The Future without the Proposed Actions (No-Action Condition) 11-58
The Future with the Proposed Actions (With-Action Condition) 11-59

Chapter 12: Air Quality 12-1
A. Introduction 12-1
B. Principal Conclusions 12-2
C. Pollutants for Analysis 12-2
Carbon Monoxide 12-2
Nitrogen Oxides, VOCs, and Ozone 12-3
Lead 12-3
Respirable Particulate Matter – PM_{10} and $PM_{2.5}$ 12-3
Sulfur Dioxide 12-4
D. Air Quality Regulations, Standards, and Benchmarks 12-4
National and State Air Quality Standards 12-4
NAAQs Attainment Status and State Implementation Plans 12-6
Determining the Significance of Air Quality Impacts 12-7
E. Methodology for Predicting Pollutant Concentrations 12-8
Mobile Source Analysis 12-8
Stationary Sources 12-12
F. Existing Conditions 12-16
G. The Future without the Proposed Actions (No-Action Conditions) 12-17
Mobile Sources 12-17
Stationary Sources 12-17
H. The Future with the Proposed Actions (With-Action Conditions) 12-18
Mobile Sources 12-18
Stationary Sources 12-19
Industrial Sources 12-21

Chapter 13: Greenhouse Gas Emissions and Climate Change 13-1
A. Introduction 13-1
B. Principal Conclusions 13-1
Greenhouse Gas Emissions 13-2
Resilience to Climate Change 13-2
C. Greenhouse Gas Emissions 13-2
Pollutants of Concern 13-2
Policy, Regulations, Standards, and Benchmark for Reducing GHG Emissions 13-4
Methodology 13-7
Projected GHG Emissions from the Proposed Actions 13-9
Consistency with the GHG Reduction Goal 13-11
D. Resilience to Climate Change 13-13
Policy to Improve Climate Change Resilience 13-13
Projected Climate Conditions 13-13
Resilience to Climate Change 13-15

Chapter 14: Noise 14-1
A. Introduction 14-1
B. Principal Conclusions 14-2
C. Acoustical Fundamentals 14-2
"A"-Weighted Sound Level (dBA) 14-2
Noise Descriptors Used In Impact Assessment 14-3

D. Applicable Noise Codes and Impact Criteria....14-4
New York City Noise Code....14-4
New York CEQR Technical Manual Noise Standards....14-4
E. Noise Prediction Methodology....14-6
Proportional Modeling....14-6
Traffic Noise Modeling (TNM)....14-7
Play Area Noise....14-7
Building Attenuation Analysis Procedure....14-9
E. Existing Noise Levels....14-10
Noise Monitoring Locations....14-10
Equipment Used During Noise Monitoring....14-11
Existing Noise Levels at Noise Receptor Locations....14-11
F. The Future without the Proposed Actions (No-Action Conditions)....14-12
Mobile Source Noise Screening Analysis....14-12
G. The Future with the Proposed Actions (With-Action Conditions)....14-13
Mobile Source Noise Screening Analysis....14-13
H. Noise Attenuation Requirements....14-20
(E) Designation....14-21
I. Other Noise Concerns....14-22
Mechanical Equipment....14-22
Train Noise....14-22
Aircraft Noise....14-23

Chapter 15: Public Health....15-1
A. Introduction....15-1
B. Principal Conclusions....15-1
C. Public Health Assessment – Noise....15-1
Assessment....15-2
D. Public Health Assessment – Construction Noise....15-2
Assessment....15-3

Chapter 16: Neighborhood Character....16-1
A. Introduction....16-1
B. Principal Conclusions....16-1
C. Methodology....16-2
Study Area....16-3
D. Preliminary Assessment....16-3
Defining Features....16-3
Assessment of the Potential to Affect the Defining Feature of the Neighborhood....16-5

Chapter 17: Construction....17-1
A. Introduction....17-1
B. Principal Conclusions....17-2
Transportation....17-2
Air Quality....17-3
Noise....17-4
Other Technical Areas....17-4
C. Governmental Coordination and Oversight....17-6
D. Construction Schedule....17-7
E. Description of Construction Activities....17-9
General Construction Practices....17-9
Description of Construction Activities....17-9
Number of Construction Workers and Material Deliveries....17-11
F. Probable Impacts of the Proposed Actions....17-12

Transportation 17-12
Air Quality 17-23
Noise 17-28
Vibration 17-48
Other Technical Areas 17-50

Chapter 18: Mitigation 18-1
A. Introduction 18-1
B. Principal Conclusions 18-1
Community Facilities 18-1
Open Space 18-2
Transportation 18-3
Noise 18-5
Construction 18-6
C. Community Facilities and Services 18-8
Elementary Schools 18-8
Early Childhood Programs 18-9
D. Open Space 18-10
E. Transportation 18-10
Pedestrians 18-17
Transit 18-20
Street User Safety 18-23
Transportation Monitoring Plan (TMP) 18-24
F. Noise 18-25
G. Construction 18-26
Transportation – Traffic 18-26
Noise 18-30

Chapter 19: Alternatives 19-1
A. Introduction 19-1
B. Principal Conclusions 19-1
No-Action Alternative 19-1
No Unmitigated Significant Adverse Impacts Alternative 19-2
Lower Density Alternative 19-2
C. No-Action Alternative 19-3
Land Use, Zoning, and Public Policy 19-3
Socioeconomic Conditions 19-4
Community Facilities and Services 19-4
Open Space 19-4
Shadows/Natural Resources 19-5
Urban Design and Visual Resources 19-5
Hazardous Materials 19-5
Water and Sewer Infrastructure 19-6
Transportation 19-6
Air Quality 19-8
Greenhouse Gas Emissions and Climate Change 19-9
Noise 19-9
Public Health 19-9
Neighborhood Character 19-9
Construction 19-10
D. No Unmitigated Significant Adverse Impact Alternative 19-10
Community Facilities and Services 19-10
Open Space 19-11
Transportation 19-12

Noise 19-12
Construction 19-13
E. Lower Density Alternative 19-13
Description of the Lower Density Alternative 19-13
Lower Density Alternative Compared with the Proposed Actions 19-14

Chapter 20: Unavoidable Adverse Impacts 20-1
A. Introduction 20-1
B. Community Facilities 20-1
Public Elementary Schools 20-1
Early Childhood Programs 20-2
C. Open Space 20-2
D. Transportation 20-3
Traffic 20-3
Transit 20-4
E. Noise 20-5
F. Construction 20-6
Traffic 20-6
Noise 20-7

Chapter 21: Growth-Inducing Aspects of the Proposed Action 21-1

Chapter 22: Irreversible and Irretrievable Commitment of Resources 22-1

APPENDICES

Appendix A: **Project Description – CEQR Technical Manual Updates Sensitivity Study Technical Memorandum**
Appendix B: **Land Use, Zoning, and Public Policy – WRP Consistency Assessment Form**
Appendix C: **Urban Design and Visual Resources – Pedestrian Wind Study**
Appendix D: **Natural Resources – Agency Correspondence**
Appendix E: **Hazardous Materials – Brownfield Cleanup Program Certificate of Completion Appendix F:**

LIST OF TABLES

ES-1 With-Action Scenario – Projected Development Sites on Block 911 ..... ES-8
ES-2 Net Change in Land Uses as a Result of the Proposed Actions ES-9
ES-3 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts ES-30
ES-4 Lane Groups With Unmitigated Significant Adverse Traffic Impacts ES-30
ES-5 Summary of Lane Groups/Intersections with Significant Adverse Construction Traffic Impacts ES-33
ES-6 Lane Groups With Unmitigated Significant Adverse Construction Traffic Impacts ES-33
ES-7 Lane Groups With Unmitigated Significant Adverse Traffic Impacts ES-37
ES-8 Lane Groups With Unmitigated Significant Adverse Construction Traffic Impacts ES-40
1-1 With-Action Scenario – Projected Development Sites on Block 911 1-9
1-2 Net Change in Land Uses as a Result of the Proposed Actions 1-10
2-1 Existing Uses within the Rezoning Area 2-5
2-2 Land Uses within the Secondary Study Area 2-6
2-3 Secondary Study Area Existing Zoning Districts 2-8
2-4 No-Action Developments within the Secondary Study Area 2-12
2-5 Incremental Development on the Projected Development Sites 2-14
2-6 Summary of Proposed Zoning Districts and Regulations 2-15
3-1 Residential Population, 2006-2010 and 2014-2018 3-9
3-2 Household Characteristics, 2006-2010 and 2014-2018 3-9
3-3 Household Income Characteristics, 2010 and 2018 3-10
3-4 Household Income Distribution, 2018 3-10
3-5 Percentage of Population Living Below the Poverty Level 3-11
3-6 Housing Units and Vacancy, 2010 and 2020 3-11
3-7 Owner-Occupied and Renter-Occupied Units, 2010 and 2018 3-11
3-8 Housing Units by Year Structure Built, 2018 3-12
3-9 Median Home Value and Median Monthly Gross Rent, 2010 and 2018 3-12
3-10 Gross Rent as Percentage of Household Income, 2018 3-13
3-11 Northwest Queens Home Sale Prices, 2018-2021 3-13
3-12 Pre-Foreclosure Properties and Foreclosure Filing Rates for Study Area and Queens, 2010 3-14
3-13 Median Rental Rates for Astoria 3-14
3-14 New Residential Development 3-15
3-15 2020 Housing Units in Rent-Regulated Buildings 3-16
3-16 Renter-Occupied Housing Units in Study Area, 2018 3-16
3-17 Low-Income Renter Households 3-17
3-18 2019 Protected and Unprotected Renter-Occupied Housing Units in the Study Area 3-18
3-19 Population and Housing Growth – Future without the Proposed Actions 3-18
3-20 Population and Housing Growth – Future with the Proposed Actions 3-19
4-1 Preliminary Screening Analysis Criteria 4-4
4-2 Projected Development Sites and Associated Number of Projected Incremental Students 4-7
4-3 2019-2020 Public Elementary and Intermediate School Enrollment, Capacity, and Utilization in CSD 30, Sub-district 3 4-9
4-4 Queens Public High School Enrollment, Capacity, and Utilization for the 2019-2020 Academic Year 4-10
4-5 High Schools within a Mile Radius from the Project Site 4-10
4-6 2031 No-Action Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization in CSD 30, Sub-district 3 4-11
4-7 2031 With-Action Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization for CSD 30, Sub-district 3 4-12
4-8 2031 Estimated With-Action Queens High School Enrollment, Capacity, and Utilization 4-13
4-9 Existing Holdings-per-Resident Ratios at the Astoria Library 4-14
4-10 Anticipated No-Action Residential Development within the Astoria Library Catchment Areas 4-14

4-11 No-Action Holdings-per-Resident Ratios at Astoria Library 4-15
4-12 Anticipated With-Action Astoria Library Catchment Area Population Increases 4-15
4-13 With-Action Holdings-per-Resident Ratios for the Astoria Library 4-15
4-14 Study Area Publicly Funded Early Childhood Programs 4-17
4-15 Comparison of Budget Capacity, Enrollment, Available Slots, & Percent Utilization for Existing Conditions and the 2031 Future No-Action Conditions in the Study Area 4-18
4-16 Projected Number of Publicly Funded Child Care Pupils Generated by the Proposed Actions 4-18
4-17 Comparison of Budget Capacity, Enrollment, Available Slots, & Percent Utilization in the Study Area for the 2031 Future No-Action and With-Action Conditions 4-19
5-1 Study Area Residential Population Age Breakdown 5-5
5-2 Open Space Resources within the ½-Mile Open Space Study Area 5-8
5-3 Open Space Resources not included within the Quantitative Analysis 5-9
5-4 Existing Conditions: Adequacy of Open Space Resources 5-10
5-5 No-Action Developments Planned for Completion by 2031 within a ½-Mile Radius 5-12
5-6 No-Action Open Space Study Area Population 5-12
5-7 Adequacy of Open Space Resources: No-Action Condition 5-13
5-8 With-Action Open Space Study Area Population 5-14
5-9 Adequacy of Open Space Resources: With-Action Condition 5-15
5-10 Open Space Ratios Summary (Residential ½-Mile Study Area) 5-17
6-1 Sunlight-Sensitive Resources Warranting Further Assessment Based on Tier 1 and 2 Screening 6-4
6-2 Tier 3 Assessment Results 6-5
6-3 Duration of Shadows on Sunlight Sensitive Resources (Increment Compared to No-Action Condition) 6-6
10-1 Water Consumption and Wastewater Generation Rates 10-3
10-2 Summary of Sanitary and Storm Discharges and CSO Subcatchment Areas 10-4
10-3 Monthly Average Dry Weather 10-6
10-4 Existing Stormwater Runoff to the Bowery Bay WPCP 10-7
10-5 Existing Combined Stormwater Runoff and Wastewater Generation to the Bowery Bay WPCP 10-7
10-6 Water Consumption and Wastewater Generation in the Future without the Proposed Actions 10-9
10-7 Water Consumption and Wastewater Generation in the Future without and with the Proposed Actions 10-11
10-8 Combined Stormwater Runoff and Wastewater Generation Flow Volume to the Combined Sewer System – Future With-Action Condition 10-13
10-9 Combined Stormwater Runoff and Wastewater Generation Flow Volumes to the Combined Sewer System – Existing vs. Future With-Action Condition 10-13
11-1 Transportation Planning Factors 11-9
11-2 Travel Demand Forecast (Net Incremental Trips) 11-10
11-3 Project Generated Incremental Peak Hour Subway Assignments by Station 11-13
11-4 Project Generated Incremental Peak Hour Bus Trips by Route 11-14
11-5 With-Action Weekday Parking Accumulation Forecast – Projected Development Site 1 11-15
11-6 With-Action Saturday Parking Accumulation Forecast – Projected Development Site 1 11-16
11-7 With-Action Weekday Parking Accumulation Forecast – Projected Development Site 2 11-16
11-8 With-Action Saturday Parking Accumulation Forecast – Projected Development Site 2 11-17
11-9 Intersection Level of Service Criteria 11-18
11-10 Level of Service Criteria for Subway Station Elements 11-20
11-11 Significant Impact Thresholds for Stairways and Passageways 11-20
11-12 Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions 11-21
11-13 Significant Impact Criteria for Sidewalks with Platooned Flow in a non-CBD Location 11-23
11-14 Significant Impact Criteria for Corners and Crosswalks in a non-CBD Location 11-24
11-15 Existing Traffic Levels of Service 11-28
11-16 No-Action Developments 11-30
11-17 No-Action Traffic Levels of Service 11-35
11-18 With-Action Traffic Levels of Service 11-38
11-19 Existing Conditions Subway Station Stair Analysis 11-40

11-20 Existing Conditions Subway Station Fare Array Analysis 11-41
11-21 Existing Conditions Subway Line Haul Analysis 11-41
11-22 Existing Conditions Bus Analysis 11-42
11-23 No-Action Conditions Subway Station Stair Analysis 11-43
11-24 No-Action Conditions Subway Station Fare Array Analysis 11-43
11-25 No-Action Conditions Subway Line Haul Analysis 11-44
11-26 No-Action Conditions Bus Analysis 11-45
11-27 With-Action Conditions Subway Station Stair Analysis 11-46
11-28 With-Action Conditions Subway Station Fare Array Analysis 11-46
11-29 With-Action Conditions Subway Line Haul Analysis 11-47
11-30 With-Action Conditions Bus Analysis 11-48
11-31 Existing Sidewalk Conditions 11-49
11-32 Existing Corner Area Conditions 11-50
11-33 No-Action Sidewalk Conditions 11-51
11-34 No-Action Crosswalk Conditions 11-52
11-35 No-Action Corner Area Conditions 11-52
11-36 With-Action Sidewalk Conditions 11-54
11-37 With-Action Crosswalk Conditions 11-55
11-38 With-Action Corner Area Conditions 11-55
11-39 Summary of Motor Vehicle Crash Data 2016-2018 11-58
11-40 Existing Weekday Overnight Parking Capacity, Demand, and Utilization 11-59
11-41 No-Action Weekday Overnight Parking Capacity, Demand, and Utilization 11-60
11-42 With-Action Weekday Overnight Parking Capacity, Demand, and Utilization 11-61
12-1 National Ambient Air Quality Standards (NAAQS) 12-5
12-2 Maximum Background Pollutant Concentrations for Mobile Source Analysis 12-11
12-3 Exhaust Stack Parameters and Emission Rates – Proposed Buildings 12-14
12-4 Maximum Background Pollutant Concentrations 12-15
12-5 Representative Monitored Ambient Air Quality Data 12-16
12-6 Maximum Predicted 8-Hour Average CO No-Action Concentrations 12-17
12-7 Maximum Predicted 24-Hour Average PM10 No-Action Concentrations 12-17
12-8 2031 Maximum Predicted CO With-Action Concentrations (ppm) 12-18
12-9 Maximum Predicted 24-Hour Average PM10 With-Action Concentrations 12-18
12-10 Maximum Predicted 24-Hour Average PM2.5 Incremental Concentration 12-19
12-11 Maximum Predicted Annual Average PM2.5 Incremental Concentration 12-19
12-12 Maximum Modeled Pollutant Concentrations – Project-on-Project 12-20
12-13 Industrial Sources within 400 Feet of a Projected or Potential Development Site 12-21
12-14 PM2.5 Analysis Results of Industrial Source Analysis 12-21
12-15 Air Toxics Analysis Results of Industrial Source Analysis 12-22
13-1 Global Warming Potential for Primary Greenhouse Gases 13-4
13-2 Proposed Actions' Annual Vehicle Miles Traveled (miles per year) 13-8
13-3 Annual Operational Emissions – RWCDS Development Site 13-19
13-4 Annual Mobile Source Emissions for the Proposed Actions 13-10
13-5 Summary of Total Annual GHG Emissions for the Proposed Actions 13-10
14-1 Common Noise Levels 14-3
14-2 Noise Exposure Guidelines for Use in City Environmental Impact Review 14-5
14-3 Required Attenuation Values to Achieve Acceptable Interior Noise Level 14-5
14-4` Highest Predicted Noise Levels due to the Planned Publicly Accessible Play Area Only (in dBA) 14-9
14-5 Existing Noise Levels (dBA) 14-12
14-6 Adjusted Existing Noise Levls (dBA) 14-12
14-7 2031 No-Action Condition Noise Levels (dBA) 14-13
14-8 2031 With-Action Condition Noise Levels (dBA) 14-14
14-9 Off-Site Mobile Source Noise Analysis Results in dBA 14-16
14-10 Predicted Noise Levels on the Proposed Project due to the Proposed Play Area (in dBA) 14-20

17-1 Number of Impacted Intersections and Lane Groups by Peak Hour 17-2
17-2 Summary of Significantly Impacted Intersections 17-2
17-3 Construction Oversight – Governmental Agencies 17-7
17-4 Average Number of Daily Workers and Trucks by Quarter 17-11
17-5 2027 (Q3 & Q4) Peak Construction Vehicle Trip Projections (in PCEs) 17-12
17-6 2027 (Q3 & Q4) Hourly Construction + Incremental Operational Vehicle Trips (Autos, Taxis and Trucks in PCEs) 17-13
17-7 Existing Traffic Levels of Service – Construction Peak Hours 17-16
17-8 2027 (Q3 & Q4) No-Action Traffic Levels of Service – Construction Peak Hours 17-17
17-9 2027 (Q3 & Q4) With-Action Traffic Levels of Service – Construction Peak Hours 17-19
17-10 Maximum Pollutant Concentrations from Phase 1 Construction 17-27
17-11 Adjustment Factors Applied in the CadnaA model Receptors 17-30
17-12 Construction Equipment Used in Noise Analysis 17-31
17-13 Construction Noise Analysis Results (dBA) 17-34
17-14 Construction Noise Impact Determination 17-35
17-15 Project on Project Construction Noise Levels Results (dBA) 17-45
17-16 Construction Noise Impact Determination 17-45
17-17 Vibration Source Levels for Construction Equipment 17-47
18-1 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts 18-3
18-2 Lane Groups With Unmitigated Significant Adverse Traffic Impacts 18-4
18-3 Summary of Lane Groups/Intersections with Significant Adverse Construction Traffic Impacts 18-6
18-4 Lane Groups With Unmitigated Significant Adverse Construction Traffic Impacts 18-6
18-5 Proposed Traffic Mitigation Measures 18-12
18-6 Action-With-Mitigation Conditions at Impacted Lane Groups – Weekday AM Peak Hour 18-13
18-7 Action-With-Mitigation Conditions at Impacted Lane Groups – Weekday Midday Peak Hour 18-14
18-8 Action-With-Mitigation Conditions at Impacted Lane Groups – Weekday PM Peak Hour 18-15
18-9 Action-With-Mitigation Conditions at Impacted Lane Groups – Saturday Peak Hour 18-16
18-10 Pedestrian Impact Summary 18-17
18-11 Action-With-Mitigation Sidewalk Conditions 18-18
18-12 Action-With-Mitigation Crosswalk Conditions 18-19
18-13 Action-With-Mitigation Corner Conditions 18-19
18-14 Effects of Traffic Mitigation on Crosswalks 18-20
18-15 Effects of Traffic Mitigation on Corners 18-20
18-16 Action-With-Mitigation – Subway Station Stair Analysis 18-22
18-17 Effects of Subway Mitigation on Sidewalk 18-22
18-18 Action-With-Mitigation Local Bus Analysis 18-23
18-19 Lane Groups With Significant Adverse Construction Traffic Impacts 18-27
18-20 Proposed Construction Traffic Mitigation Measures 18-28
18-21 Construction Action-With-Mitigation Conditions at Impacted Lane Groups 18-29
19-1 Lower Density Alternative Compared to the Proposed Actions 19-13
19-2 Comparison of Weekday Peak Hour Incremental Person Trips by Mode – Proposed Actions vs. Lower Density Alternative 19-17
19-3 Comparison of Weekday Peak Hour Incremental Vehicle Trips by Mode – Proposed Actions vs. Lower Density Alternative 19-18
19-4 Comparison of AM LOS Proposed Actions vs. Lower Density Alternative 19-20
19-5 Comparison of Midday LOS Proposed Actions vs. Lower Density Alternative 19-21
19-6 Comparison of PM LOS Proposed Actions vs. Lower Density Alternative 19-22
19-7 Comparison of Saturday LOS Proposed Actions vs. Lower Density Alternative 19-23
19-8 Lower Density Alternative Proposed Mitigation Measures 19-24
19-9 Lower Density Alternative – Subway Station Stair Analysis 19-25
19-10 Lower Density Alternative-With-Mitigation – Subway Station Stair Analysis 19-26
19-11 Lower Density Alternative Local Bus Analysis (with Mitigation) 19-27

19-12 Comparison of Incremental Peak Hour Pedestrian Trips Proposed actions vs. Lower Density Alternative 19-28
19-23 Level-of-service for Impacted Sidewalks Proposed Development With-Action and Lower Density Alternative 19-29
19-24 Level-of-service for Impacted Crosswalks Proposed Development With-Action and Lower Density Alternative.....19-30
19-25 Level-of-service for Impacted Corners Proposed Development With-Action and Lower Density Alternative 19-30
20-1 Lane Groups With Unmitigated Significant Adverse Traffic Impacts 20-4
20-2 Lane Groups With Unmitigated Significant Construction Traffic Impacts.....20-6

LIST OF FIGURES

		Following Page
ES-1	Project Location	ES-1
ES-2	Existing and Proposed Zoning Map	ES-2
ES-3	Projected Development Site 1 – Proposed Ground Floor Plan	ES-5
ES-4	Proposed Waterfront Open Space	ES-5
ES-5	Projected Development Site 1 – Proposed Massing	ES-5
1-1	Project Location	1-1
1-2	Existing and Proposed Zoning Map	1-2
1-3a	Photo Key	1-2
1-3b	Project Area Existing Conditions 07/25/2019	1-2
1-3c	Project Area Existing Conditions 07/25/2019	1-2
1-4	Projected Development Site 1 – Proposed Ground Floor Plan	1-6
1-5	Projected Development Site 1 – Proposed Waterfront Open Space	1-6
2-1	Land Use Study Area	2-4
2-2	Land Use Map	2-5
2-3	Zoning Map	2-7
2-4	Coastal Zone Boundary	2-9
2-5	No-Action Developments	2-12
2-6	Existing and Proposed Zoning Map	2-15
2-7	FEMA Flood Hazard Zones	2-19
2-8	2020s Flood Zone Projections	2-20
2-9	2050s Flood Zone Projections	2-20
2-10	1% Floodplain Graph	2-20
2-11	Illustrative Building Section	2-20
2-12	Projected Development Site 1 – Proposed Ground Floor Plan	2-20
2-13	Mean Higher High Water Graph	2-21
3-1	Socioeconomic Conditions Study Area	3-7
4-1	Public Elementary & Intermediate Schools within the Study Area	4-8
4-2	Public High Schools within 1-Mile of Project Area	4-9
4-3	Libraries within the Study Area	4-13
4-4	Public Child Care Centers within the Study Area	4-17
5-1	Open Space Study Area	5-2
5-2	Quantitative and Qualitative Open Space Resources	5-6
5-3	Proposed Waterfront Open Space	5-16
6-1	Tier I & II Shadow Assessment	6-4
6-2a	Tier 3 Screening	6-5
6-2b	Tier 3 Screening	6-5
6-3a	Incremental Shadows on March 21st/September 21st – Whitey Ford Field	6-11
6-3b	Incremental Shadows on March 21st/September 21st – Whitey Ford Field	6-11
6-4a	Incremental Shadows on March 21st/September 21st – East River	6-11
6-4b	Incremental Shadows on March 21st/September 21st – East River	6-11
6-4c	Incremental Shadows on March 21st/September 21st – East River	6-11
6-4d	Incremental Shadows on March 21st/September 21st – East River	6-11
6-4e	Incremental Shadows on March 21st/September 21st – East River	6-11
6-5a	Incremental Shadows on May 6th/August 6th – Whitey Ford Field	6-11
6-5b	Incremental Shadows on May 6th/August 6th – Whitey Ford Field	6-11

6-6a Incremental Shadows on May 6th/August 6th – East River 6-11
6-6b Incremental Shadows on May 6th/August 6th – East River 6-11
6-6c Incremental Shadows on May 6th/August 6th – East River 6-11
6-6d Incremental Shadows on May 6th/August 6th – East River 6-11
6-6e Incremental Shadows on May 6th/August 6th – East River 6-11
6-7a Incremental Shadows on June 21st – Whitey Ford Field 6-11
6-7b Incremental Shadows on June 21st – Whitey Ford Field 6-11
6-8a Incremental Shadows on June 21st – East River 6-11
6-8b Incremental Shadows on June 21st – East River 6-11
6-8c Incremental Shadows on June 21st – East River 6-11
6-9a Incremental Shadows on December 21st – Whitey Ford Field 6-11
6-9b Incremental Shadows on December 21st – Whitey Ford Field 6-11
6-10a Incremental Shadows on December 21st – East River 6-11
6-10b Incremental Shadows on December 21st – East River 6-11
6-10c Incremental Shadows on December 21st – East River 6-11
7-1 Urban Design Study Area 7-3
7-2 Study Area Built Density 7-4
7-3 Aerial Photo 7-4
7-4 Study Area Building Heights 7-4
7-5a Primary Study Area Key Map 7-4
7-5b Primary Study Area – Streetscape 7-4
7-6a Secondary Study Area Key Map 7-5
7-6b Secondary Study Area – Streetscape 7-5
7-6c Secondary Study Area – Streetscape 7-5
7-6d Secondary Study Area – Streetscape 7-5
7-6e Secondary Study Area – Streetscape 7-5
7-7a Secondary Study Area – Buildings 7-6
7-7b Secondary Study Area – Buildings 7-6
7-8 Projected Development Site 1 – Proposed Ground Floor Plan 7-9
7-9 Projected Development Site 1 – Proposed Massing 7-9
7-10 Projected Development Site 1 – Illustrative Rendering 7-9
7-11 Projected Development Site 1 – Elevations 7-11
7-12 Projected Development Site 1: No-Action Pedestrian View Looking North on 3rd Street 7-14
7-13 Projected Development Site 1: With-Action Pedestrian View Looking North on 3rd Street 7-14
7-14 Projected Development Site 1: No-Action Pedestrian View Looking West on 26th Avenue 7-14
7-15 Projected Development Site 1: With-Action Pedestrian View Looking West on 26th Avenue 7-14
7-16 Projected Development Site 1: No-Action Pedestrian View Looking East on 26th Avenue 7-14
7-17 Projected Development Site 1: With-Action Pedestrian View Looking East on 26th Avenue 7-14
7-18 Proposed Open Space 7-15
7-19 Illustrative View of 3rd Street 7-16
7-20 Illustrative Rendering of the Peninsula under With-Action Conditions 7-18
8-1 Water Resources and Wetlands 8-3
8-2 Flood Zones 8-7
8-3 Tidal Wetlands Wetland Boundary 8-11
10-1 Project Location and DEP Subcatchment Areas 10-3
10-2 Existing and Proposed Sanitary Sewer System 10-3
10-3 Existing and Proposed Storm Sewer System 10-3
10-4 DEP Water Mains 10-5
11-1 Project Location 11-1
14-1 Location of Proposed Astoria Cove Play Area 14-8
14-2 Noise Receptor Locations 14-10
14-3 Nearby Noise Sensitive Uses 14-16
14-4 Noise Attenuation Requirements 14-22

17-1 Anticipated Construction Schedule 17-7
17-2 Combined Operational and Construction Peak Hour Vehicle Trips During the 2027 Q3 Through 2027 Q4 Peak Construction Period 17-14
17-3 2021 Existing Traffic Volumes – Construction Peak Hours 17-14
17-4 2027 Peak Construction Period No-Action Traffic Volumes 17-14
17-5 2027 Peak Construction Period With-Action Traffic Volumes 17-14
18-1 Proposed Subway Mitigation Schematic 18-21
19-1 Lower Density Alternative 19-13