Pfizer Sites Rezoning

Draft Environmental Impact Statement (DEIS)

CEQR No. 15DCP117K
ULURP Nos.: N150277ZRK & 1502787ZMK

Lead Agency:
City Planning Commission, City of New York
Marisa Lago, Chair

May 19, 2017

Pfizer Sites Rezoning

Draft Environmental Impact Statement (DEIS)

May 19, 2017

Project Location:	Community District 1 Borough of Brooklyn
CEQR No.:	15DCP117K
Type of Action:	Unlisted
ULURP Nos.:	N150277ZRK & 1502787ZMK
Lead Agency:	City Planning Commission, City of New York Marisa Lago, Chair
Lead Agency Contact:	Robert Dobruskin, AICP Director, Environmental Assessment and Review Division 120 Broadway, 31st Floor Department of City Planning, City of New York New York, NY 10007 +1.212.720.3423
Applicant:	Harrison Realty LLC
Prepared by:	Philip Habib & Associates

The DEIS is available for review on the website of the New York City Department of City Planning: http://www1.nyc.gov/site/planning/applicants/eis-documents.page

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

TABLE OF CONTENTS

Executive Summary **ES-1**

Chapter 1: Project Description **1-1**
A. Introduction 1-1
B. Existing Conditions 1-4
Rezoning Area 1-3
Neighborhood Context 1-6
C. Proposed Action 1-7
Proposed Zoning Map Amendment 1-7
Proposed Zoning Text Amendment 1-8
Restrictive Declaration (RD) 1-9
(E) Designation 1-9
D. RWCDS/Proposed Project 1-9
RWCDS 1-10
RWCDS No-Action Conditions 1-11
RWCDS With-Action Conditions 1-12
Build Year 1-15
E. Purpose and Need 1-15
F. Public Review Process 1-16
Uniform Land Use Review Procedure (ULURP) 1-16
City Environmental Quality Review (CEQR) 1-17

Chapter 2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
B. Principal Conclusions 2-2
C. Methodology 2-2
Analysis Year 2-3
Study Area Definition 2-3
Data Sources 2-3
D. Existing Conditions 2-4
Land Use 2-4
Zoning 2-7
Public Policy 2-14
E. Future Without the Proposed Action 2-17
Land Use 2-17
Zoning 2-18
Public Policy 2-20
G. The Future without the Proposed Action (With-Action Condition) 2-20
Proposed Action 2-20
RWCDS With-Action Conditions 2-21
Land Use 2-22
Zoning 2-22
Public Policy 2-27

Chapter 3: Socioeconomic Conditions **3-1**
A. Introduction 3-1
B. Principal Conclusions 3-2
Direct Displacement 3-2
Indirect Residential Displacement 3-3

Indirect Business Displacement 3-3
Adverse Effects on Specific Industries 3-4
C. Methodology 3-4
Determining Whether a Socioeconomic Assessment is Appropriate 3-5
Analysis Format 3-7
Study Area Definition 3-7
Data Sources 3-8
D. Preliminary Assessment 3-8
Indirect Residential Displacement 3-8

Chapter 4: Community Facilities 4-1
A. Introduction 4-1
B. Principal Conclusions 4-1
C. Preliminary Screening 4-2
D. Public Elementary, Intermediate and High Schools 4-3
Methodology 4-3
Indirect Effects on Public Schools 4-4
Existing Conditions 4-4
Future Without the Proposed Action (No-Action) 4-6
Future With the Proposed Action (With-Action) 4-9
Impact Significance 4-11
E. Child Care 4-12
Methodology 4-12
Indirect Effects on Child Care Centers 4-13
Existing Conditions 4-13
Future Without the Proposed Action (No-Action) 4-13
Future With the Proposed Actions (With-Action) 4-15
Impact Significance 4-15
F. Libraries 4-16
Methodology 4-16
Indirect Effects on Libraries 4-17
Existing Conditions 4-17
Future Without the Proposed Action (No-Action) 4-19
Future With the Proposed Actions (With-Action) 4-19
Impact Significance 4-20

Chapter 5: Open Space 5-1
A. Introduction 5-1
B. Principal Conclusions 5-1
C. Open Space Study Area and Methodology 5-2
Open Space Study Area 5-2
Analysis Framework 5-3
D. Preliminary Assessment 5-5
E. Detailed Analysis 5-5
Existing Conditions 5-5
Quantitative Analysis of Open Space Adequacy 5-12
Qualitative Assessment of Open Space Adequacy 5-13
Future Without the Proposed Action (No-Action) 5-14
Open Space Resources 5-16
Quantitative Analysis of Open Space Adequacy 5-17
Qualitative Assessment of Open Space Adequacy 5-17
Future With the Proposed Action (With-Action) 5-17
Direct Effects Analysis 5-18

Indirect Effects Analysis 5-18
Assessment of Open Space Adequacy 5-19

Chapter 6: Shadows 6-1
A. Introduction 6-1
B. Principal Conclusions 6-1
C. Methodology 6-2
Future Without the Proposed Action (No-Action) 6-4
Future With the Proposed Action (With-Action) 6-4
D. Preliminary Screening 6-5
Tier 1 Screening Assessment 6-5
Tier 2 Screening Assessment 6-5
Tier 3 Screening Assessment 6-5
E. Detailed Analysis of Shadow Impacts 6-6
Resources Affected by Project-Generated Shadows 6-6
Detailed Shadows Analysis 6-6
Assessment 6-9

Chapter 7: Historic and Cultural Resources 7-1
A. Introduction 7-1

Chapter 8: Urban Design and Visual Resources 8-1
A. Introduction 8-1
B. Principal Conclusions 8-2
C. Methodology 8-2
Wind Screening 8-3
Definition of Study Area 8-4
D. Preliminary Assessment 8-4
E. Existing Conditions 8-4
Project Area 8-4
Study Area 8-6
F. Future Without the Proposed Action 8-13
Project Area 8-13
Study Area 8-13
G. Future With the Proposed Action 8-14
Project Area 8-14
Study Area 8-15
Summary 8-16

Chapter 9: Hazardous Materials 9-1
A. Introduction 9-1
B. Principal Conclusions 9-1
C. Existing Conditions 9-2
Previous Site Assessments and Remediation Activities 9-2
D. Future Without the Proposed Action (No-Action) 9-2
E. Future With the Proposed Action (With-Action) 9-3

Chapter 10: Water and Sewer Infrastructure 10-1
A. Introduction 10-1
B. Principal Conclusions 10-1
Water Supply 10-1
Sanitary (Dry Weather) Flows 10-1
Stormwater (Wet Water) Flows 10-2

C. Methodology 10-2
Water Supply 10-2
Wastewater and Stormwater Conveyance and Treatment 10-3
D. Existing Conditions 10-3
Sewer System 10-3
E. Future without the Proposed Action (No-Action) 10-5
Sewer System 10-5
F. Future with the Proposed Action (With-Action) 10-6
Sewer System 10-6

Chapter 11: Energy 11-1
A. Introduction 11-1
B. Principal Conclusions 11-1
C. Methodology 11-2
D. Existing Conditions 11-2
Energy Supply and Transmission 11-2
Recent Energy Conservation Directives 11-3
Existing Demand 11-4
E. Future without the Proposed Action (No-Action) 11-5
Energy Supply and Transmission 11-5
No-Action Demand 11-5
F. Future with the Proposed Action (With-Action) 11-5
Energy Supply and Transmission 11-5
With-Action Demand 11-5

Chapter 12: Transportation 12-1
A. Introduction 12-1
B. Principal Conclusions 12-2
Traffic 12-2
Parking 12-2
Transit 12-2
Pedestrians 12-3
C. Level 1 and Level 2 Screening Analysis 12-3
Level 1 Screening Analysis 12-4
Traffic 12-7
Parking 12-8
Transit 12-10
Pedestrians 12-12
D. Vehicular Traffic 12-14
Street Network 12-14
Analysis Methodology 12-15
Existing Conditions 12-16
Future Without the Proposed Action (No-Action Condition) 12-18
Future With the Proposed Action (With-Action Condition) 12-22
E. Rail Transit 12-26
Analysis Methodology 12-27
Existing Condition 12-28
Future Without the Proposed Action (No-Action Condition) 12-28
Future With the Proposed Action (With-Action Condition) 12-28
F. Pedestrians 12-31
Analysis Methodology 12-31
Existing Condition 12-33
Future Without the Proposed Action (No-Action Condition) 12-34

Future With the Proposed Action (With-Action Condition) 12-34
G. Vehicular and Pedestrian Safety Evaluation 12-46
H. Summary 12-47
Chapter 13: Air Quality 13-1
A. Introduction 13-1
B. Principal Conclusions 13-2
C. Mobile Source Screening 13-3
D. Stationary Source Analysis 13-3
HVAC Screening 13-3
CEQR Screening Analysis 13-7
Detailed Analysis 13-8
NO_2 Analysis 13-19
E. Industrial Source Analysis 13-23
Data Sources 13-24
Industrial Source Type 13-24
Methodology 13-26
Screening Analysis 13-26
PERC and Nickel Cancer Risk and Annual Concentration Ratios Estimate 13-27
Summary of Toxic Emissions Analysis 13-28
F. Garage Emissions Analysis 13-28
Background Concentrations 13-28
Parking Facilities Analysis 13-29
Results 13-30
G. (E) Designation 13-31

Chapter 14: Greenhouse Gas Emissions and Climate Change 14-1
A. Introduction 14-1
B. Principal Conclusions 14-2
C. Background 14-2
Recognized Greenhouse Gases 14-2
Carbon Dioxide (CO_2) 14-2
Methane (CH_4) 14-2
Nitrous Oxide (N_2O) 14-3
Fluorinated Gases 14-3
Climate Change 14-4
D. Methodology 14-4
Greenhouse Gas Emissions 14-4
Climate Change 14-6
E. GHG Emissions 14-7
Operational Emissions 14-7
Mobile Source Emissions 14-7
Summary 14-8
Consistency with GHG Reduction Goal 14-8
F. Climate Change 14-9

Chapter 15: Noise 15-1
A. Introduction 15-1
B. Principal Conclusions 15-1
C. Noise Fundamentals 15-2
"A"-Weighted Sound Level (dBA) 15-2
Community Response to Changes in Noise Levels 15-3
Noise Descriptors Used in Impact Assessment 15-3
Applicable Noise Codes and Impact Criteria 15-4

New York City Noise Code 15-4
D. Noise Prediction Methodology 15-6
Proportional Modeling 15-6
E. Existing Conditions 15-7
Selection of Noise Receptor Locations 15-7
Noise Monitoring 15-8
Equipment Used During Noise Monitoring 15-8
Existing Noise Levels at Noise Receptor Locations 15-8
Measured Noise Levels 15-8
F. Future without the Proposed Action (No-Action) 15-9
G. Future with the Proposed Action (With-Action) 15-10
H. Attenuation Requirements 15-11
(E) Designation 15-12
I. Other Noise Concerns 15-13
Mechanical Equipment 15-13
Aircraft Noise 15-13
Train Noise 15-13

Chapter 16: Public Health 16-1
A. Introduction 16-1
B. Principal Conclusions 16-1
C. Public Health Assessment 16-2

Chapter 17: Neighborhood Character 17-1
A. Introduction 17-1
B. Principal Conclusions 17-2
C. Methodology 17-2
Study Area 17-3
D. Preliminary Assessment 17-3
Defining Features 17-3
Assessment of the Potential to Affect the Defining Features of the Neighborhood 17-6

Chapter 18: Construction 18-1
A. Introduction 18-1
B. Principal Conclusions 18-2
C. Conceptual Construction Schedule and Activities 18-2
Construction Sequencing 18-2
Construction Activities 18-3
Estimate of Construction Workers and Construction Period Trucks 18-8
D. Preliminary Assessment 18-9
Transportation 18-9
Air Quality 18-12
Noise 18-16
Vibration 18-21
Historic and Cultural Resources 18-22
Hazardous Materials 18-22
Natural Resources 18-23
Summary 18-23

Chapter 19: Mitigation 19-1
A. Introduction 19-1
B. Principal Conclusions 19-1
Community Facilities and Services 19-1

Transportation 19-2
C. Community Facilities and Services 19-3
Intermediate Schools 19-3
D. Transportation 19-3
Traffic 19-3
Effects of Traffic and Sidewalk Mitigation on Corner Area and Crosswalk Conditions 19-4

Chapter 20: Alternatives 20-1
A. Introduction 20-1
B. Principal Conclusions 20-1
No-Action Alternative 20-1
Lesser Density Alternative 20-2
No Significant Adverse Schools Impact Alternative 20-3
C. No-Action Alternative 20-4
Land Use, Zoning, and Public Policy 20-4
Socioeconomic Conditions 20-5
Community Facilities and Services 20-5
Open Space 20-5
Shadows 20-5
Historic and Cultural Resources 20-6
Urban Design and Visual Resources 20-6
Hazardous Materials 20-6
Water and Sewer Infrastructure 20-6
Energy 20-7
Transportation 20-7
Air Quality 20-7
Greenhouse Gas Emissions and Climate Change 20-7
Noise 20-8
Public Health 20-8
Neighborhood Character 20-8
Construction 20-8
D. Lesser Density Alternative 20-8
Land Use, Zoning, and Public Policy 20-10
Socioeconomic Conditions 20-11
Community Facilities and Services 20-13
Open Space 20-13
Shadows 20-14
Historic and Cultural Resources 20-14
Urban Design and Visual Resources 20-15
Hazardous Materials 20-15
Water and Sewer Infrastructure 20-15
Energy 20-16
Transportation 20-16
Air Quality 20-19
Greenhouse Gas Emissions and Climate Change 20-20
Noise 20-20
Public Health 20-21
Neighborhood Character 20-21
Construction 20-21
E. No Significant Adverse Schools Impact Alternative 20-22

Chapter 21: Unavoidable Adverse Impacts 21-1

A. Introduction 21-1
B. Community Facilities and Services: Intermediate Schools 21-1
C. Transportation: Traffic 21-2

Chapter 22: Growth-Inducing Aspects of the Proposed Action 22-1

Chapter 23: Irreversible and Irretrievable Commitment of Resources 23-1

APPENDICES

Appendix I: Proposed Zoning Text Amendment
Appendix II: Agency Correspondence
Appendix III: WRP Consistency Assessment Form
Appendix IV: Transportation Planning Factors Memo

LIST OF TABLES

ES-1 Summary of Rezoning Area Existing Conditions ES-6
ES-2 Project Area RWCDS Conditions ES-14
ES-3 Maximum Amount of Floor Area That Can Be Developed: With-Action Conditions ES-15
ES-4 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts ES-29
1-1 Summary of Rezoning Area Existing Conditions 1-6
1-2 Project Area RWCDS Conditions 1-13
1-3 Maximum Amount of Floor Area That Can Be Developed: With-Action Conditions 1-14
2-1 Study Area Generalized Land Use 2-8
2-2 No-Build Developments 2-19
2-2a No-Build Developments: Broadway Triangle Rezoning City-owned Development Sites 2-19
2-3 Comparison of Existing and Proposed Zoning 2-25
3-1 Recent Study Area Residential Developments 3-10
3-2 Population Income Characteristics in the ½-Mile Study Area, Borough of Brooklyn and New York City- 2000 and 2010-14 3-10
3-3 Distribution of Household Income in the Study Area, Borough of Brooklyn, and New York City (1999, 2010-14) 3-12
3-4 2000 and 2010-14 Residential Population 3-13
3-5 Estimated Residential Population in the ½-Mile Study Area—No-Action and With-Action Conditions 3-13
3-6 Housing Characteristics and Trends, 2000 and 2010-14 3-14
3-7 A Comparison of Current Average Rental Rates in Williamsburg, Bedford Stuyvesant and the Borough of Brooklyn, 2010 and 2016 3-15
3-8 Comparison of Condominium Sales in Williamsburg, Bedford Stuyvesant and the Borough of Brooklyn, 2015-2016 3-17
3-9 A Comparison of One to Three Family Dwelling Sales in Williamsburg, Bedford Stuyvesant and the Borough of Brooklyn, 2015-2016 3-17
4-1a 2015-2016 CSD 14, Sub-district 1 Elementary & Intermediate School Existing Enrollment and Capacity 4-5
4-1b 2015-2016 Brooklyn High School Existing Enrollment and Capacity 4-6
4-2a 2019 No-Action: Projected Enrollment in CSD 14, Sub-district 1 Elementary and Intermediate Schools 4-8
4-2b 2019 No-Action: Projected Enrollment in Brooklyn High Schools 4-9
4-3 2019 Future With the Proposed Action: Estimated Number of Students Introduced 4-9
4-4a Total Projected With-Action Enrollment and Utilization change for Elementary and Intermediate Schools in CSD 14, Sub-district 1 4-10
4-4b 2019 - Total Projected With-Action Enrollment and Utilization change for High Schools in Brooklyn 4-10
4-5 Study Area Publicly-funded Child Care 4-14
4-6 Projected Publicly-Funded Child Care Enrollment and Capacity Changes in the 2019 No-Action 4-14
4-7 2019 RWCDS With-Action: Estimated Number of Child Care Eligible Children Under Age 6 4-15
4-8 Projected Publicly-Funded Child Care Enrollment and Capacity Changes in the 2019 With-Action 4-15
4-9 Public Libraries in the ¾-Mile Study Area 4-17
4-10 Libraries Study Area: Population, Holdings, and Holdings per Resident 4-20
5-1 2016 Existing Study Area Population 5-6
5-2a Study Area Age Groups (2010) 5-6
5-2b Brooklyn, Age Groups (2010) 5-6
5-3 Inventory of Existing Study Area Public Open Spaces 5-9
5-4 Analysis of Adequacy of Open Space Resources in the Study Area under 2016 Existing Conditions 5-13
5-5 Additional Open Space Resources Adjacent to the Study Area 5-15
5-6 2019 No-Action Study Area Population 5-16
5-7 Analysis of Adequacy of Open Space Resources in the Study Area under 2019 No-Action Conditions 5-17
5-8 2019 Future With the Proposed Action: Open Space Ratios Summary 5-19
6-1 Sunlight Sensitive Resources Warranting Further Analysis Based on Tier 1 and 2 Assessment 6-5

6-2 Duration of Shadows on Sunlight Sensitive Resources (Increment Compared to No-Action) 6-7
10-1 Existing Project Area Surface Areas and Runoff Coefficients 10-5
10-2 Existing Project Site Stormwater and Sanitary Sewage Flow Volumes 10-5
10-3 Project Area Water Demand and Sewage Generation: 2019 No-Action vs. 2019 With-Action Conditions 10-7
10-4 With-Action Project Area Surface Areas and Runoff Coefficients 10-7
10-5 Project Area Stormwater and Sanitary Sewage Flow Volumes – With-Action vs. Existing Conditions 10-8
11-1 With-Action/Increment Annual Energy Consumption for the Project Area 11-6
12-1 Transportation Planning Factors 12-5
12-2a Travel Demand Forecast (Person Trips) 12-6
12-2b Travel Demand Forecast (Vehicle Trips) 12-7
12-3 Projected Weekday Hourly Parking Demand 12-9
12-4 Projected Saturday Hourly Parking Demand 12-9
12-5 2019 Bus Route Assignments 12-12
12-6 Intersection LOS Criteria 12-16
12-7 2015 Existing Traffic Levels of Service 12-18
12-8 2019 No-Action Sites 12-19
12-9 No-Action Intersection Improvements from the Broadway Triangle FEIS Mitigation 12-20
12-10 2019 No-Action Traffic Levels of Service 12-21
12-11 2019 With-Action Traffic Levels of Service 12-24
12-12 Subway Station Element LOS Criteria 12-27
12-13 2015 Existing Fare Array Levels of Service 12-29
12-14 2015 Existing Stairway Levels of Service 12-29
12-15 2019 No-Action Fare Array Levels of Service 12-30
12-16 2019 No-Action Stairway Levels of Service 12-30
12-17 Subway Stairway Significant Impact Thresholds 12-31
12-18 2019 With-Action Fare Array Levels of Service 12-32
12-19 2019 With-Action Stairway Levels of Service 12-32
12-20 LOS Criteria for Pedestrian Elements 12-33
12-21 2015 Existing Sidewalk Levels of Service 12-35
12-22 2015 Existing Crosswalk Levels of Service 12-36
12-23 2015 Existing Corner Area Levels of Service 12-37
12-24 2019 No-Action Sidewalk Levels of Service 12-38
12-25 2019 No-Action Crosswalk Levels of Service 12-39
12-26 2019 No-Action Corner Area Levels of Service 12-40
12-27 Significant Impact Criteria for Sidewalks in a CBD Location 12-42
12-28 Significant Impact Criteria for Corners and Crosswalks in a CBD Location 12-43
12-29 2019 With-Action Sidewalk Levels of Service 12-44
12-30 2019 With-Action Crosswalk Levels of Service 12-45
12-31 2019 With-Action Corner Area Levels of Service 12-46
12-32 Three-Year Accident Data 12-47
13-1 Applicable National Ambient Air Quality Standards and CEQR Significant Threshold Criteria 13-4
13-2 Building Parameters 13-7
13-3 Results of the Screening Analysis for Buildings Located on Blocks 2249 and 2265 13-9
13-4 $PM_{2.5}$ and NO_2 Emission Rates and Stack Parameters 13-11
13-5 Modeling Parameters for HVAC Analysis 13-12
13-6 $PM_{2.5}$ Analysis Results for Individual Buildings 13-13
13-7 $PM_{2.5}$ Cumulative Analysis Results 13-14
13-8 Results of NO_2 Analysis for Project-on-Project 13-19
13-9 1-Hour NO_2 Cumulative Analysis Results 13-20
13-10 Summary of Results ($\mu g/m^3$) 13-20
13-11 Estimated Short-term (1-hour) Concentration Ratios 13-27
13-12 Estimated Annual Concentration Ratios and Incremental Cancer Risks 13-28

13-13 Maximum Background Pollutant Concentrations for Parking Garage Analysis 13-29
14-1 Global Warming Potential for Primary Greenhouse Gases 14-3
14-2 NPCC Baseline Climate and Mean Annual Changes 14-4
14-3 RWCDS/Future With-Action Condition Annual Vehicle Miles Traveled (VMT/year)....14-6
14-4 Annual Operational Emissions....14-7
14-5 Annual Mobile Source Emissions 14-8
14-6 Summary of Total Annual GHG Emissions....14-8
15-1 Common Noise Levels 15-3
15-2 Average Ability to Perceive Changes in Noise Levels 15-3
15-3 Noise Exposure Guidelines for Use In City Environmental Impact Review 15-5
15-4 Required Attenuation Values to Achieve Acceptable Interior Noise Levels....15-5
15-5 Noise Receptor Locations....15-7
15-6 Existing Noise Levels (in dBA) at the Monitoring Locations 15-9
15-7 Future No-Build Noise Levels and total PCE Values at Receptor Locations (in dBA)....15-10
15-8 Future Build Noise Levels and total PCE Values at Receptor Locations (in dBA)....15-10
15-9 Proposed Development Attenuation Requirements....15-11
18-1 Construction Oversight in New York City 18-6
18-2 Estimated Total Number of Construction Workers, Construction Worker Vehicles, and Construction Trucks On-site Per Day....18-9
18-3 Q3 2018 Peak Construction Vehicle Trip Projections....18-11
18-4 Typical Construction Equipment Noise Emission Levels (dBA)....18-20
19-1 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts 19-2
19-2 Proposed Traffic Mitigation Measures....19-5
19-3 Action-with-Mitigation Traffic Conditions at Impacted Intersections – Weekday AM Peak Hour....19-6
19-4 Action-with-Mitigation Traffic Conditions at Impacted Intersections – Weekday Midday Peak Hour 19-7
19-5 Action-with-Mitigation Traffic Conditions at Impacted Intersections – Weekday PM Peak Hour....19-8
19-6 Action-with-Mitigation Traffic Conditions at Impacted Intersections – Saturday Midday Peak Hour....19-9
19-7 Action-with-Mitigation Crosswalk Conditions....19-10
19-8 Action-with-Mitigation Corner Conditions....19-10
20-1 Comparison of the Lesser Density Alternative and the Proposed Action 20-9
20-2 Comparison of Existing, Proposed Action, and Lesser Density Alternative Zoning....20-12
20-3 Total Projected Lesser Density Alternative Enrollment and Utilization change for Elementary and Intermediate Schools in CSD 14, Sub-district 1 20-13
20-4 2019 Lesser Density Alternative: Open Space Ratios Summary....20-14
20-5 Comparison of Peak Hour Person Trips by Mode: Proposed Action vs. Lesser Density Alternative....20-17
20-6 Comparison of Peak Hour Vehicle Trips: Proposed Action vs. Lesser Density Alternative 20-17
20-7 Future Traffic Impact Comparison: Lesser Density Alternative vs. Proposed Action....20-18
20-8 2019 - Total Projected Enrollment and Utilization change for Elementary and Intermediate Schools in CSD 14, Sub-district 1: No Significant Adverse Schools Impacts Alternative....20-23

LIST OF FIGURES

		Following Page
1-1	Project Area Dimensions	1-1
1-2	Rezoning Area and Project Area	1-2
1-3a	Project Area Existing Conditions	1-5
1-3b	Project Area Existing Conditions	1-5
1-4	Site Photo Key	1-5
1-5	Proposed Zoning Map Amendment	1-7
1-6	Proposed Zoning Text Amendment	1-9
1-7	Applicant's Proposed Development Site Plan	1-10
1-8	Proposed Ground Floor Plan	1-10
1-9	Second Floor/Courtyard Plan	1-10
1-10	Applicant's Proposed Development Axonometric Diagram	1-10
1-11a	Illustrative View from Union Avenue	1-10
1-11b	Illustrative View from Gerry Street	1-10
1-11c	Illustrative Bird's-Eye View	1-10
1-12	Preliminary Design of Publicly-Accessible Open Space	1-10
1-13	RWCDS Site Plan	1-15
1-14	RWCDS Axonometric Diagram	1-15
1-15	Illustrated Site Plan	1-15
2-1	Land Use Study Area	2-1
2-2	Land Use Map	2-7
2-3	Study Area Zoning	2-9
2-4	Study Area Inclusionary Housing Designated Areas	2-10
2-5	Rezonings Approved Since 2007	2-12
2-6	Coastal Zone Boundary	2-16
2-7	1989 FEIS Map	2-17
2-8	No-Build Projects by 2019	2-18
2-9	2019 Floodplain Preliminary FIRM	2-30
2-10	NNPCC 2020s Floodplain Projections	2-30
2-11	NPCC 2050s Floodplain Projections	2-30
3-1	Socioeconomic Conditions Study Area	3-8
3-2	Recent Study Area Residential Developments	3-9
3-3	Protected Housing Units	3-11
4-1	Study Area Elementary and Intermediate Schools	4-4
4-2	Child Care Facilities in Study Area	4-13
4-3	Library Study Area	4-16
4-4	Census Tracts in Study Area	4-16
5-1	Open Space Study Area	5-3
5-2	Open Space Resources	5-8
5-3	Preliminary Design of Publicly-Accessible Open Space	5-18
5-4	Illustrated Site Plan	5-18
5-5	Second Floor/Courtyard Plan	5-20
6-1	Longest Shadow Study Area - Tier 1 and 2 Screening	6-5
6-2	Tier 3 Shadow Screening	6-6
6-3	Incremental Shadows on March 21/September 21	6-7
6-4	Incremental Shadows on May 6/August 6	6-7
6-5	Incremental Shadows on June 21	6-7

6-6 Incremental Shadows on December 21 6-7
8-1 Urban Design and Visual Resources Study Area 8-4
8-2 2014 Aerial Photo 8-5
8-3 Aerial Views 8-5
8-4 Urban Design and Visual Resources Sub-Areas 8-7
8-5 Urban Design and Visual Resources Study Area Photos 8-7
8-6a Urban Design and Visual Resources Sub-Area Photos 8-7
8-6b Urban Design and Visual Resources Sub-Area Photos 8-7
8-6c Urban Design and Visual Resources Sub-Area Photos 8-7
8-6d Urban Design and Visual Resources Sub-Area Photos 8-7
8-6e Urban Design and Visual Resources Sub-Area Photos 8-7
8-6f Urban Design and Visual Resources Sub-Area Photos 8-7
8-6g Urban Design and Visual Resources Sub-Area Photos 8-7
8-6h Urban Design and Visual Resources Sub-Area Photos 8-7
8-6i Urban Design and Visual Resources Sub-Area Photos 8-7
8-6j Urban Design and Visual Resources Sub-Area Photos 8-7
8-7 Building Heights 8-9
8-8 Building Density 8-8
8-9a Comparison of Existing and With-Action Conditions - View west from Gerry Street and Harrison Avenue 8-14
8-9b Comparison of Existing and With-Action Conditions - View north at Gerry Street, Flushing and Union avenues 8-14
8-9c Comparison of Existing and With-Action Conditions – View southwest from Walton Street and Harrison Avenue 8-14
8-9d Comparison of Existing and With-Action Conditions – View southwest from Wallabout Street and Harrison Avenue 8-14
8-9e Comparison of Existing and With-Action Conditions – View northeast from Wallabout Street and Union Avenue. 8-14
8-9f Comparison of Existing and With-Action Conditions – View southeast from Walton Street and Union Avenue 8-14
8-9g Comparison of Existing and With-Action Conditions – View northwest from the mid-block of Gerry Street 8-14
12-1 2019 Traffic Assignment 12-7
12-2 Traffic Analysis Intersections 12-8
12-3 2019 Transit Route Assignments 12-10
12-4 2019 Weekday AM/Midday Pedestrian Assignments 12-12
12-5 2019 Weekday PM/Saturday Midday Pedestrian Assignments 12-12
12-6 Pedestrian Analysis Locations 12-12
12-7a 2015 Existing AM/Midday Traffic Volumes 12-14
12-7b 2015 Existing PM/Saturday Traffic Volumes 12-14
12-8a 2019 No-Action AM/Midday Traffic Volumes 12-19
12-8b 2019 No-Action PM/Saturday Traffic Volumes 12-19
12-9a 2019 With-Action AM/Midday Traffic Volumes 12-22
12-9b 2019 With-Action PM/Saturday Traffic Volumes 12-22
13-1 Pfizer Site Proposed Developments on Blocks 2249 and 2265 13-6
13-2 Designated Area for the Stacks on Building B 13-15
13-3 Designated Area for the Stacks on Building C 13-15
13-4 Designated Area for Stacks on Building D 13-16
13-5 Designated Area for Stacks on Building F 13-17
13-6 Designated Area for Stacks on Building G 13-18
15-1 Noise Monitoring Locations 15-7
15-2 Building Attenuation Requirements 15-12
18-1a Construction Schedule 18-2

18-1b Construction Schedule 18-2
18-1c Construction Schedule 18-2
18-1d Construction Schedule 18-2
20-1 Lesser Density Alternative Illustrative Roof Plan 20-9
20-2a Comparison of Proposed Project and Lesser Density Alternative – View west from Gerry Street and Harrison Avenue 20-15
20-2b Comparison of Proposed Project and Lesser Density Alternative – View north at Gerry Street, Flushing and Union avenues 20-15
20-2c Comparison of Proposed Project and Lesser Density Alternative – View southeast from Walton Street and Union Avenue 20-15