Innovation QNS

Final Environmental Impact Statement (FEIS)

CEQR No.: 21DCP180Q

ULURP Nos.:

C 220370 ZSQ	C 220364 ZMQ
C 220371 ZSQ	C 220365 ZSQ
C 220372 ZSQ	C 220366 ZSQ
C 220373 ZSQ	N 220367 ZRQ
C 220374 ZSQ	C 220368 ZSQ
N 220375 LDQ	C 220369 ZSQ

Lead Agency:
City Planning Commission, City of New York
Daniel R. Garodnick, Chair

Lead Agency Contact:
Stephanie Shellooe, Director
Environmental Assessment and Review Division
NYC Department of City Planning
120 Broadway, 31st floor
New York, NY 10271

Prepared by:
AKRF, Inc.
Philip Habib & Associates

September 9, 2022

Innovation QNS
FINAL ENVIRONMENTAL IMPACT STATEMENT (FEIS)
September 9, 2022

CEQR No.:	21DCP180Q	
ULURP Nos.:	C 220370 ZSQ	C 220364 ZMQ
	C 220371 ZSQ	C 220365 ZSQ
	C 220372 ZSQ	C 220366 ZSQ
	C 220373 ZSQ	N 220367 ZRQ
	C 220374 ZSQ	C 220368 ZSQ
	N 220375 LDQ	C 220369ZSQ
Type of Action:	Type I	
Project Location:	Queens, New York Community District 1	
Lead Agency:	City Planning Commission, City of New York Daniel R. Garodnick, Chair	
Lead Agency Contact:	Stephanie Shellooe, Director Environmental Assessment and Review Division NYC Department of City Planning 120 Broadway, 31st floor New York, NY 10271	
Project Applicants:	Silverstein Astoria Member LLC Kaufman BedRock Astoria I LLC	
Prepared by:	AKRF, Inc. Philip Habib & Associates	

A public hearing on the Draft Environmental Impact Statement (DEIS) was held on August 10, 2022. Written comments on the DEIS were received and considered by the Lead Agency up until August 22, 2022.

The FEIS is available on the website of the New York City Department of City Planning, via the Innovation QNS Rezoning and LSGD project page on ZAP: https://zap.planning.nyc.gov/projects/2021Q0106.

To view the Innovation QNS FEIS and Appendix, navigate to the project page in ZAP and select Public Documents, then “FEIS_21DCP180Q”.

Table of Contents

Foreword **1**

Executive Summary **S-1**

Chapter 1: Project Description **1-1**
A. Introduction 1-1
B. Required Approvals and Review Procedures 1-2
C. Background to the Proposed Actions 1-3
Description of the Project Area 1-3
Description of the Surrounding Area 1-4
Description of the Proposed Development 1-6
D. Existing Zoning 1-9
E. Proposed Actions 1-10
Zoning Map Amendments 1-10
Zoning Text Amendments 1-10
Special Permits 1-10
F. Purpose and Need 1-11
G. Analysis Framework 1-16
Build Year 1-16
Reasonable Worst Case Development Scenario (RWCDS) 1-16
H. Public Review Process 1-22
Uniform Land Use Review Procedure (ULURP) 1-22
City Environmental Quality Review 1-22

Chapter 2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
Principal Conclusions 2-2
B. Methodology 2-4
Study Area 2-4
C. Existing Conditions 2-4
Land Use 2-4
Zoning 2-8
Public Policy 2-10
D. The Future without the Proposed Actions 2-13
Land Use 2-13
Zoning 2-14
Public Policy 2-14
E. The Future with the Proposed Actions 2-14
Land Use 2-14
Zoning 2-18

Public Policy 2-21

Chapter 3: Socioeconomic Conditions 3-1
A. Introduction 3-1
Principal Conclusions 3-1
B. Methodology 3-4
Determining Whether a Socioeconomic Assessment is Appropriate 3-5
Analysis Format 3-7
Study Area Definition 3-7
Data Sources 3-7
C. Preliminary Assessment 3-8
Direct Business Displacement 3-8
Indirect Residential Displacement 3-15
Indirect Business Displacement 3-20
Adverse Effects on Specific Industries 3-22
D. Detailed Indirect Residential Displacement Analysis 3-23
Existing Conditions and Trends 3-23
The Future without the Proposed Actions (No Action Condition) 3-29
The Future with the Proposed Actions (With Action Condition) 3-29

Chapter 4: Community Facilities and Services 4-1
A. Introduction 4-1
Principal Conclusions 4-2
B. Preliminary Screening 4-3
Direct Effects 4-3
Indirect Effects 4-3
C. Potential Indirect Effects on Public Elementary, Intermediate, and High Schools 4-5
Methodology 4-5
Existing Conditions 4-6
The Future without the Proposed Actions 4-7
The Future with the Proposed Actions 4-9
D. Potential Indirect Effects on Public Libraries 4-10
Methodology 4-10
Existing Conditions 4-11
The Future without the Proposed Actions 4-11
The Future with the Proposed Actions 4-12
E. Potential Indirect Effects on Publicly Financed Early Childhood Programs 4-13
Methodology 4-13
Existing Conditions 4-14
The Future without the Proposed Actions 4-15
The Future with the Proposed Actions 4-16

Chapter 5: Open Space 5-1
A. Introduction 5-1
Principal Conclusions 5-2
B. Methodology 5-4
Direct Effects 5-4
Indirect Effects 5-4

Detailed Analysis Framework 5-4
NYC Parks Walk to a Park Initiative 5-5
C. Existing Conditions 5-9
Study Area Population 5-9
Open Space Inventory 5-11
Assessment of Open Space Adequacy 5-15
D. The Future without the Proposed Actions 5-17
Indirect Effects 5-17
E. The Future with the Proposed Actions 5-20
Direct Effects 5-20
Indirect Effects 5-22

Chapter 6: Shadows 6-1
A. Introduction 6-1
Principal Conclusions 6-1
B. Definitions and Methodology 6-1
Definitions 6-1
Methodology 6-2
C. Preliminary Screening Assessment 6-3
Tier 1 Screening Assessment 6-4
Tier 2 Screening Assessment 6-4
Tier 3 Screening Assessment 6-5
D. Detailed Shadow Analysis 6-6
Determination of Impact Significance 6-7
Summary of Analysis Results 6-8
Assessment of Shadow Impacts on Playground Thirty Five XXXV 6-9
Project-Generated Open Spaces 6-11
E. Conclusion 6-13

Chapter 7: Historic and Cultural Resources 7-1
A. Introduction 7-1
Principal Conclusions 7-1
B. Methodology 7-2
C. Existing Conditions 7-3
Architectural Resources 7-3
D. The Future without the Proposed Actions 7-6
Project Area 7-6
Study Area 7-7
E. The Future with the Proposed Actions 7-8
Project Area 7-8
Study Area 7-8

Chapter 8: Urban Design and Visual Resources 8-1
A. Introduction 8-1
Principal Conclusions 8-1
B. Methodology 8-4
C. Existing Conditions 8-6
Urban Design 8-6

Visual Resources and View Corridors 8-14
D. The Future without the Proposed Actions 8-15
Project Area 8-15
Study Area 8-16
E. The Future with the Proposed Actions 8-16
Urban Design 8-16
View Corridors and Visual Resources 8-23
Conclusion 8-24

Chapter 9: Hazardous Materials 9-1
A. Introduction 9-1
Principal Conclusions 9-2
B. Methodology 9-2
Sanborn Fire Insurance Map Review 9-3
Previous Reports Review 9-3
Database Review 9-4
Site Reconnaissance 9-4
C. Existing Conditions 9-5
Topography and Hydrogeology 9-5
Regulatory Database Records 9-5
Overview of Historical Uses 9-5
D. The Future without the Proposed Actions 9-12
E. The Future with the Proposed Actions 9-12
F. Conclusion 9-14

Chapter 10: Water and Sewer Infrastructure 10-1
A. Introduction 10-1
Principal Conclusions 10-2
B. Methodology 10-3
C. Existing Conditions 10-4
Water Supply System 10-4
Sewer System and Wastewater Treatment 10-5
Water Consumption 10-6
Sanitary Flows 10-6
Stormwater Flows 10-7
D. The Future without the Proposed Actions (No Action Condition) 10-9
Water Supply 10-9
Sewer System and Wastewater Treatment 10-10
Stormwater Flows 10-10
E. The Future with the Proposed Actions (With Action Condition) 10-11
Water Supply 10-12
Sewer System and Wastewater Treatment 10-13
Stormwater Flows 10-14

Chapter 11: Solid Waste and Sanitation Services 11-1
A. Introduction 11-1
Principal Conclusions 11-2
B. Methodology 11-2

C. Existing Conditions 11-3
Description of Current Solid Waste Sanitation Services 11-3
Solid Waste Generation on Projected Development Sites 11-4
D. The Future without the Proposed Actions 11-5
E. The Future with the Proposed Actions 11-6

Chapter 12: Energy 12-1
A. Introduction 12-1
Principal Conclusions 12-2
B. Methodology 12-2
C. Existing Conditions 12-3
Energy Supply and Transmission 12-3
Recent Energy Conservation Directives 12-4
Existing Demand 12-4
D. The Future without the Proposed Actions 12-5
E. The Future with the Proposed Actions 12-5

Chapter 13: Transportation 13-1
A. Introduction 13-1
B. Principal Conclusions 13-3
Traffic 13-4
Transit 13-4
Citywide Ferry Service (CWFS) 13-6
Pedestrians 13-6
Vehicular and Pedestrian Safety 13-7
Parking 13-8
C. Preliminary Analysis Methodology 13-8
D. Level 1 Screening Assessment 13-9
Background 13-9
Transportation Planning Factors 13-9
Travel Demand Forecast 13-10
E. Level 2 Screening Assessment 13-19
Vehicular Traffic 13-19
Transit 13-20
Pedestrians 13-22
Citywide Ferry Service 13-23
Parking 13-24
F. Transportation Analyses Methodologies 13-24
Traffic 13-24
Transit 13-26
Pedestrians 13-28
Street User Safety Evaluation 13-32
Parking 13-33
G. Traffic 13-33
Existing Conditions 13-33
The Future without the Proposed Actions (No Action Condition) 13-37
The Future with the Proposed Actions (With Action Condition) 13-37
H. Transit 13-48

Existing Conditions 13-48
The Future without the Proposed Actions (No Action Condition) 13-55
The Future with the Proposed Actions (With Action Condition) 13-55
I. Pedestrians 13-58
Existing Conditions 13-58
The Future without the Proposed Actions (No Action Condition) 13-62
The Future with the Proposed Actions (With Action Condition) 13-62
J. Street User Safety Evaluation 13-70
Recent DOT Initiatives 13-70
Study Area High Crash Locations 13-71
Priority Corridors 13-72
K. Parking 13-74

Chapter 14: Air Quality 14-1
A. Introduction 14-1
Principal Conclusions 14-1
B. Pollutants for Analysis 14-2
Carbon Monoxide 14-3
Nitrogen Oxides, VOCs, and Ozone 14-3
Lead 14-3
Respirable Particulate Matter—PM_{10} and $PM_{2.5}$ 14-4
Sulfur Dioxide 14-4
C. Air Quality Regulations, Standards, and Benchmarks 14-5
National and State Air Quality Standards 14-5
NAAQS Attainment Status and State Implementation Plans 14-6
Determining the Significance of Air Quality Impacts 14-7
D. Methodology for Predicting Pollutant Concentrations 14-8
Mobile Sources 14-8
Stationary Sources 14-14
E. Existing Conditions 14-20
F. The Future without the Proposed Project 14-20
Mobile Sources 14-20
Stationary Sources 14-21
G. The Future with the Proposed Project 14-21
Mobile Sources 14-21
Stationary Sources 14-24

Chapter 15: Greenhouse Gas Emissions and Climate Change 15-1
A. Introduction 15-1
Principal Conclusions 15-1
B. Greenhouse Gas Emissions 15-2
Pollutants of Concern 15-2
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 15-3
Methodology 15-6
Projected GHG Emissions 15-10
Elements That Would Reduce GHG Emissions 15-13
C. Conclusion 15-16

Chapter 16: Noise 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Acoustical Fundamentals 16-2
"A"-Weighted Sound Level (dBA) 16-2
Noise Descriptors Used in Impact Assessment 16-3
C. Noise Standards and Criteria 16-4
New York CEQR Technical Manual Noise Standards 16-4
Impact Significance Criteria 16-5
Environmental Conditions for Buildings in MX Districts 16-5
D. Existing Noise Levels 16-6
Selection of Noise Receptor Locations 16-6
Noise Monitoring 16-6
Existing Noise Levels at Noise Receptor Locations 16-7
E. Noise Prediction Methodology 16-9
General Methodology 16-9
Playground Noise 16-10
F. The Future without the Proposed Actions 16-10
G. The Future with the Proposed Actions 16-12
Traffic Noise 16-12
Playground Noise 16-12
H. Noise Attenuation Measures 16-14
Newly Introduced Open Space 16-19
I. Mechanical Equipment 16-19

Chapter 17: Public Health 17-1
A. Introduction 17-1
Principal Conclusions 17-1
B. Methodology 17-2
Air Quality 17-2
Construction Noise 17-2
C. Public Health Assessment 17-3
Air Quality 17-3
Construction Noise 17-4

Chapter 18: Neighborhood Character 18-1
A. Introduction 18-1
Principal Conclusions 18-2
B. Methodology 18-3
Study Area 18-4
C. Preliminary Assessment 18-4
Existing Conditions 18-4
The Future without the Proposed Actions 18-8
Assessment of the Potential to Affect the Defining Features of the Neighborhood 18-8
Conclusion 18-17

Chapter 19: Construction 19-1
A. Introduction 19-1

Principal Conclusions 19-1
B. Governmental Coordination and Oversight 19-5
C. Conceptual Construction Phasing and Schedule 19-6
D. Construction Description 19-8
General Construction Practices 19-8
Description of Construction Activities 19-9
E. Number of Construction Workers and Material Deliveries 19-11
F. Environmental Effects of the Proposed Development's Construction Activities 19-13
Transportation 19-13
Air Quality 19-25
Noise 19-31
Vibration 19-57
Other Technical Areas 19-59

Chapter 20: Mitigation 20-1
A. Introduction 20-1
Principal Conclusions 20-1
B. Community Facilities—Publicly Financed Early Childhood Programs 20-8
C. Community Facilities—Libraries 20-9
D. Open Space 20-11
E. Shadows 20-2
F. Transportation 20-12
Traffic 20-12
Transit 20-20
Pedestrians 20-21
G. Air Quality 20-26
H. Construction 20-27
Traffic 20-27
Noise 20-31

Chapter 21: Alternatives 21-1
A. Introduction 21-1
Principal Conclusions 21-2
B. No Action Alternative 21-6
Land Use, Zoning, and Public Policy 21-6
Socioeconomic Conditions 21-7
Community Facilities and Services 21-7
Open Space 21-8
Shadows 21-8
Historic and Cultural Resources 21-8
Urban Design and Visual Resources 21-9
Hazardous Materials 21-9
Water and Sewer Infrastructure 21-10
Solid Waste and Sanitation Services 21-10
Energy 21-10
Transportation 21-11
Air Quality 21-12
Greenhouse Gas Emissions and Climate Change 21-13

Noise 21-13
Public Health 21-14
Neighborhood Character 21-14
Construction 21-14
C. No Unmitigated Significant Adverse Impact Alternative 21-15
Community Facilities and Services 21-15
Open Space 21-17
Shadows 21-17
Transportation 21-18
Air Quality 21-19
Construction 21-19
D. Proposed Modified Application Alternative 21-21
Land Use, Zoning, and Public Policy 21-23
Socioeconomic Conditions 21-23
Community Facilities and Services 21-23
Open Space 21-23
Shadows 21-25
Historic and Cultural Resources 21-26
Urban Design and Visual Resources 21-26
Hazardous Materials 21-27
Water and Sewer Infrastructure 21-27
Solid Waste and Sanitation Services 21-27
Energy 21-28
Transportation 21-28
Air Quality 21-28
Greenhouse Gas Emissions and Climate Change 21-29
Noise 21-29
Public Health 21-29
Neighborhood Character 21-30
Construction 21-30

Chapter 22: Unavoidable Adverse Impacts 22-1
A. Introduction 22-1
B. Community Facilities—Publicly Financed Early Childhood Programs 22-1
C. Community Facilities—Libraries 22-2
D. Open Space 22-3
E. Shadows 22-4
F. Transportation 22-4
Traffic 22-4
Transit 22-5
Pedestrians 22-5
G. Air Quality 22-6
H. Construction 22-6
Traffic 22-6
Noise 22-7

Chapter 23: Growth-Inducing Aspects of the Proposed Actions 23-1

Chapter 24: Irreversible and Irretrievable Commitments of Resources 24-1

Chapter 25: Response to Comments on the DEIS 25-1

APPENDICES

Appendix A Zoning Text and Sensitivity Memo
Appendix B Historic Resources
Appendix C Hazardous Materials
Appendix D Transportation
Appendix E Noise
Appendix F Construction
Appendix G Mitigation
Appendix H Written Comments Received on the DEIS

List of Tables

S-1 Project Area Lots....S-5
S-2 RWCDS Summary....S-20
S-3 Number of Impacted Intersections and Lane Groups by Peak Hour....S-38
S-4 Summary of Significantly Impacted Intersections....S-39
S-5 Summary of Significant Subway Line Haul Impacts....S-40
S-6 Summary of Significant Pedestrian Impacts....S-40
S-7 High Crash Locations....S-41
S-8 Number of Impacted Intersections and Lane Groups by Peak Hour Year 2 Construction (Fourth Quarter) Peak Construction Period....S-46
S-10 Summary of Lane Groups/Intersections With Significant Adverse Traffic Impacts ...S-52
S-11 Lane Groups With Unmitigated Significant Adverse Traffic Impacts....S-53
S-12 Summary of Lane Groups/Intersections With Significant Adverse Construction Traffic Impacts....S-56
S-13 Lane Groups With Unmitigated Significant Adverse Construction Traffic Impacts ...S-56
1-1 Project Area Lots....1-5
1-2 RWCDS Summary....1-19
2-1 Study Area No Build Projects....2-14
2-2 RWCDS Summary....2-16
2-3 Comparison of Zoning Districts....2-20
3-1 2019 Employment by Industry....3-10
3-2 Private Businesses and Employment Potentially Displaced by the Proposed Actions 3-11
3-3 Directly Displaced Employment....3-12
3-4 Household Income Characteristics (2006–2010, 2015–2019 ACS)....3-16
3-5 Average and Median Gross Rents....3-16
3-6 Average Rents in the Study Area....3-17
3-7 2021 New York City Area Median Income (AMI)....3-17
3-8 2021 New York City Affordable Monthly Rents by Area Median Income (AMI)....3-18
3-9 Market Rate Units by Number of Bedrooms....3-18

3-10 Weighted Average Income of With Action Market-Rate Renters 3-19
3-11 Weighted Average Income of Total With Action Population 3-19
3-12 No Action Condition Population 3-20
3-13 With Action Condition Population 3-20
3-14 Household Income Characteristics (2006–2010, 2014–2019 ACS) 3-23
3-15 Household Income Distribution 2019 3-24
3-16 Percentage Living in Poverty 2019 3-24
3-17 Housing Units, Vacancy, and Tenure 3-25
3-18 2019 Housing Units by Year Structure Built 3-25
3-19 Units in Structure—Socioeconomic Study Area 2019 3-25
3-20 Renter-Occupied Housing Units by Gross Rent as Percentage of Household Income 3-26
3-21 Average Market Rents for Units Built Since 2010 3-26
3-22 Certificates of Occupancy and Residential Demolitions 2010–2021 3-27
3-23 Low-Income Renter Households: Socioeconomic Study Area 3-28
3-24 Allocation of Low-Income Households 3-28
4-1 Preliminary Screening Analysis Criteria: Queens 4-4
4-2 Public Schools Serving the Study Area, Enrollment and Capacity Data, 2019–2020 School Year 4-7
4-3 No Action Scenario—Utilization in CSD 30/Subdistrict 2 4-8
4-4 With Action Scenario—Utilization in CSD 30/Subdistrict 2 4-9
4-5 Public Libraries Serving the Project Area 4-11
4-6 No Action Scenario: Catchment Area Population 4-12
4-7 With Action Scenario: Catchment Area Population 4-12
4-8 Publicly Financed Early Childhood Programs Serving the Study Area 4-15
4-9 Affordable Housing Projects in the Study Area 4-16
4-10 Estimated Child Care Facility Enrollment, Capacity, and Utilization 4-17
5-1 Existing Worker Population 5-10
5-2 Study Area Residential Populations 5-10
5-3 Residential Study Area Population Age Distribution 5-11
5-4 Study Area Open Space Inventory 5-13
5-5 Adequacy of Open Space Resources in the Study Area—Existing Conditions 5-15
5-6 Study Area No Build Projects 5-18

5-7 Adequacy of Open Space Resources—No Action Condition (Non-Residential Study Area) 5-19

5-8 Adequacy of Open Space Resources—No Action Condition (Residential Study Area) 5-20

5-9 Adequacy of Open Space Resources—With Action Condition (Non-Residential Study Area) 5-23

5-10 Passive Open Space Ratios Summary (Non-Residential Study Area) 5-23

5-11 Adequacy of Open Space Resources—With Action Condition (Residential Study Area) 5-24

5-12 Open Space Ratio Summary (Residential Study Area) 5-24

6-1 Tier 1: Longest Shadow 6-4

6-2 Tier 3 Assessment 6-6

6-3 Incremental Shadow Durations 6-9

7-1 Known and Potential Architectural Resources within 90 Feet of Proposed Construction 7-9

9-1 Hazardous Materials Assessment – Project Area Lots 9-8

10-1 Existing Water Consumption 10-7

10-2 Existing Wastewater Generation on the Projected Development Sites by Subcatchment Area 10-7

10-3 Existing Surface Coverage 10-8

10-4 No Action Condition Water Consumption 10-10

10-5 No Action Condition Wastewater Generation on the Projected Development Sites by Subcatchment Area 10-10

10-6 No Action Condition Surface Coverage 10-11

10-7 With Action Condition Water Consumption 10-12

10-8 With Action Condition Wastewater Generation on the Projected Development Sites by Subcatchment Area 10-13

10-9 With Action Condition Surface Coverage 10-15

10-10 DEP Volume Calculation Matrix: Existing and With Action Condition Volume Comparison 10-15

11-1 Existing Solid Waste Generation on Projected Development Sites 11-5

11-2 No Action Solid Waste Generation on Projected Development Sites 11-6

11-3 With Action Solid Waste Generation on Projected Development Sites 11-7

11-4 Comparison of Weekly Solid Waste Generation on Projected Development Sites (Existing, No Action, With Action Conditions) 11-7

12-1 Existing Annual Energy Consumption for the Projected Development Sites 12-4

12-2 No Action Annual Energy Consumption for the Projected Development Sites 12-5
12-3 With Action Annual Energy Consumption for the Projected Development Sites 12-6
13-1 2032 RWCDS No Action and With Action Land Uses 13-3
13-2 Number of Impacted Intersections and Lane Groups by Peak Hour 13-4
13-3 Summary of Significantly Impacted Intersections 13-5
13-4 Summary of Significant Subway Line Haul Impacts 13-6
13-5 Summary of Significant Pedestrian Impacts 13-7
13-6 High Crash Locations 13-7
13-7 Transportation Planning Factors 13-12
13-8 RWCDS Travel Demand Forecast 13-16
13-9 Summary of Net Incremental Peak Hour Trips Generated under the RWCDS 13-19
13-10 RWCDS Net Incremental Peak Hour Subway Trips by Station 13-21
13-11 Bus Routes Serving the Project Area 13-22
13-12 Net Incremental Bus Trips by Route 13-23
13-13 Intersection Level of Service Criteria 13-25
13-14 Level of Service Criteria for Subway Station Elements 13-27
13-15 Significant Impact Thresholds for Stairways and Passageways 13-28
13-16 Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions ... 13-29
13-17 Significant Impact Criteria for Sidewalks in a CBD Location 13-31
13-18 Significant Impact Criteria for Corners and Crosswalks in a CBD Location 13-32
13-19 Congested Lane Groups at Analyzed Intersections under Existing Conditions 13-36
13-20 Congested Lane Groups at Analyzed Intersections under No Action Conditions—Weekday AM Peak Hour 13-38
13-21 Congested Lane Groups at Analyzed Intersections under No Action Conditions—Weekday Midday Peak Hour 13-39
13-22 Congested Lane Groups at Analyzed Intersections under No Action Conditions—Weekday PM Peak Hour 13-40
13-23 Congested Lane Groups at Analyzed Intersections under No Action Conditions—Saturday Peak Hour 13-41
13-24 Congested Lane Groups at Analyzed Intersections under With Action Conditions—Weekday AM Peak Hour 13-44
13-25 Congested Lane Groups at Analyzed Intersections under With Action Conditions—Weekday Midday Peak Hour 13-45
13-26 Congested Lane Groups at Analyzed Intersections under With Action Conditions—Weekday PM Peak Hour 13-46

13-27 Congested Lane Groups at Analyzed Intersections under With Action Conditions—Saturday Peak Hour 13-47
13-28 Existing Conditions Subway Station Stair Analysis 13-50
13-29 Existing Conditions Subway Station Fare Array Analysis 13-50
13-30 Existing Conditions Subway Line Haul Analysis 13-51
13-31 Existing Conditions Local Bus Analysis 13-52
13-32 No Action Subway Station Stair Analysis 13-53
13-33 No Action Subway Station Fare Array Analysis 13-53
13-34 No Action Subway Line Haul Analysis 13-54
13-35 No Action Local Bus Analysis 13-55
13-36 With Action Subway Station Stair Analysis 13-56
13-37 With Action Subway Station Fare Array Analysis 13-56
13-38 With Action Subway Line Haul Analysis 13-57
13-39 With Action Conditions Local Bus Analysis 13-58
13-40 Existing Sidewalk Conditions 13-59
13-41 Existing Crosswalk Conditions 13-60
13-42 Existing Corner Conditions 13-61
13-43 No Action Sidewalk Conditions 13-63
13-44 No Action Crosswalk 13-64
13-45 No Action Corner Conditions 13-65
13-46 With Action Sidewalk Conditions 13-67
13-47 With Action Crosswalk Conditions 13-68
13-48 With Action Corner Conditions 13-69
13-49 Summary of Motor Vehicle Crash Data 2017–2019 13-73
13-50 Total Weekday Hourly Parking Accumulation for the Proposed Development (Sites A-E) 13-76
13-51 Total Saturday Hourly Parking Accumulation for the Proposed Development (Sites A-E) 13-77
13-52 Total Weekday Hourly Parking Accumulation for the Additional Affected Area (Sites F-K) 13-78
13-53 Total Saturday Hourly Parking Accumulation for the Additional Affected Area (Sites F-K) 13-79
13-54 Total Weekday Hourly Parking Accumulation for the Projected Development Site (Sites A-K) 13-80

13-55 Total Saturday Hourly Parking Accumulation for the Projected Development Site (Sites A-K) 13-81

13-56 Proposed Accessory Parking Spaces on the Projected Development Site 13-82

14-1 National Ambient Air Quality Standards (NAAQS) 14-5

14-2 Maximum Background Pollutant Concentrations for Mobile Source Analysis 14-11

14-3 Mobile Source Analysis Sites 14-12

14-4 Exhaust Stack Parameters and Emission Rates – Applicant-Controlled Lots 14-17

14-5 Exhaust Stack Parameters and Emission Rates – Additional Affected Sites 14-18

14-6 Maximum Background Pollutant Concentrations 14-19

14-7 Representative Monitored Ambient Air Quality Data 14-20

14-8 Maximum Predicted 8-Hour Average CO No Action Concentration 14-21

14-9 Maximum Predicted 24-Hour Average PM_{10} No Action Concentrations ($\mu g/m^3$) 14-21

14-10 Maximum Predicted 8-Hour CO With Action Concentrations (PPM) 14-22

14-11 Maximum Predicted 24-Hour Average PM_{10} With Action Concentration ($\mu g/m^3$)... 14-22

14-12 Maximum Predicted 24-Hour Average $PM_{2.5}$ With Action and Incremental Concentration ($\mu g/m^3$) 14-23

14-13 Maximum Predicted Annual Average $PM_{2.5}$ With Action Incremental Concentration ($\mu g/m^3$) 14-23

14-14 Maximum Predicted Annual Average $PM_{2.5}$ Grid Analysis Incremental Concentration ($\mu g/m^3$) 14-24

14-15 Maximum Modeled Pollutant Concentrations on the Proposed Development and the Additional Affected Area ($\mu g/m^3$) 14-24

14-16 Maximum Modeled Pollutant Concentrations on Existing Buildings ($\mu g/m^3$) 14-25

15-1 GWP for Major GHGs 15-3

15-2 Vehicle Miles Traveled Per Year—RWCDS 15-8

15-3 Annual Building Operational Emissions—RWCDS 15-11

15-4 Annual Mobile Source Emissions—RWCDS (Metric Tons CO2e, 2032) 15-11

15-5 Total Construction GHG Emissions (Metric Tons CO2e) 15-12

15-6 Summary of Annual GHG Emissions—RWCDS (Metric Tons CO2e) 15-12

16-1 Noise Levels of Common Sources 16-3

16-2 Noise Exposure Guidelines for Use in City Environmental Impact Review 16-4

16-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 16-5

16-4 Noise Receptor Locations 16-6

16-5 Measured Noise Levels (in dBA) 16-8

16-6 Playground Boundary Noise $L_{eq(1)}$ Noise Levels (in dBA) 16-10

16-7 2032 No Action Condition Noise Levels (in dBA) 16-11

16-8 2032 With Action Condition Noise Levels (in dBA) 16-13

16-9 Required Attenuation at Noise Measurement Locations (in dBA) 16-14

16-10 Minimum Required Attenuation at Development Sites (in dBA) 16-15

19-1 Number of Impacted Intersections and Lane Groups by Peak Hour Year 2 Construction (Fourth Quarter) Peak Construction Period 19-2

19-2 Summary of Significantly Impacted Intersections Year 2 Construction (Fourth Quarter) Peak Construction Period 19-3

19-3 Construction Oversight in New York City 19-6

19-4 Conceptual Construction Schedule 19-7

19-5 Average Number of Daily Workers and Trucks by Quarter Proposed Development 19-12

19-6 Average Number of Daily Workers and Trucks by Quarter Projected Development Sites in Additional Affected Area 19-12

19-7 Average Number of Daily Workers and Trucks by Quarter Proposed Actions (Proposed Development + Projected Development Sites in Additional Affected Area) 19-13

19-8 Year 2 Construction (Fourth Quarter) Peak Incremental Construction Vehicle Trip Projections (in PCEs) 19-14

19-9 Year 2 Construction (Fourth Quarter) Peak Incremental Construction and Operational Vehicle Trip Projections (in PCEs) 19-15

19-10 Congested Lane Groups at Analyzed Intersections under Existing and Year 2 Construction No Action Conditions—AM Peak Hour 19-18

19-11 Congested Lane Groups at Analyzed Intersections Under Existing and Year 2 Construction No Action Conditions—PM Peak Hour 19-19

19-12 Congested Lane Groups at Analyzed Intersections Under Year 2 Construction With Action (Construction) Conditions—AM Peak Hour 19-20

19-13 Congested Lane Groups at Analyzed Intersections Under Year 2 Construction With Action (Construction) Conditions—PM Peak Hour 19-21

19-14 Year 2 Construction Conditions Along the North Sidewalk On 36th Street Between 38th and Steinway Streets in the Am and Pm Construction Peak Hours 19-24

19-15 Year 2 Construction (Fourth Quarter) Construction Worker Parking Accumulation 19-25

19-16 Maximum Pollutant Concentrations – Proposed Development 19-30

19-17 Maximum Pollutant Concentrations – Projected Developments in the Additional Affected Area 19-30

19-18 Maximum Pollutant Concentrations – Cumulative Total (Proposed Development + Projected Developments in the Additional Affected Area) 19-30

19-19 Noise Receptors by Location and Land Use 19-34

19-20 Construction Noise Analysis Time Periods 19-39

19-21 Typical Construction Equipment Noise Emission Levels (dBA) 19-41

19-22 Construction Noise Analysis Results in dBA 19-42

19-23 Locations with Significant Adverse Impacts Related to Construction Noise 19-57

19-24 Vibration Source Levels for Construction Equipment..... 19-59

20-1 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts.... 20-4

20-2 Lane Groups with Unmitigated Significant Adverse Traffic Impacts 20-5

20-3 Summary of Lane Groups/Intersections with Significant Adverse Construction Traffic Impacts..... 20-7

20-4 Lane Groups with Unmitigated Significant Adverse Construction Traffic Impacts.... 20-7

20-5 Proposed Traffic Mitigation Measures 20-15

20-6 Action-With-Mitigation Conditions at Impacts Lane Groups Weekday AM Peak Hour.20-16

20-7 Action-With-Mitigation Conditions at Impacted Lane Groups Weekday Midday Peak Hour 20-17

20-8 Action-With-Mitigation Conditions at Impacted Lane Groups Weekday PM Peak Hour 20-18

20-9 Action-With-Mitigation Conditions at Impacted Lane Groups Saturday Peak Hour 20-19

20-10 Summary of Significant Subway Line Haul Impacts..... 20-21

20-11 Summary of Significant Pedestrian Impacts..... 20-22

20-12 Action-With-Mitigation Crosswalk Conditions..... 20-24

20-13 Action-With-Traffic Mitigation Crosswalk Conditions..... 20-25

20-14 Action-With-Traffic Mitigation Corner Conditions 20-25

20-15 Maximum Predicted Annual Average $PM_{2.5}$ With Action and Incremental Concentrations With Traffic Mitigation ($\mu g/m^3$) 20-26

20-16 Summary of Significantly Impacted Intersections in the Year 2 (Fourth Quarter) Peak Construction Period 20-27

20-17 Proposed Construction Traffic Mitigation Measures..... 20-29

20-18 Action-With-Mitigation Conditions at Impacted Lane Groups in the AM Construction Peak Hour 20-30

20-19 Action-With-Mitigation Conditions at Impacted Lane Groups in the PM Construction Peak Hour 20-30

20-20 Locations With Significant Adverse Impacts Related to Construction Noise 20-31

21-1 Adequacy of Open Space Resources— Proposed Modified Application Alternative (Residential Study Area)..... 21-25

21-2 Open Space Ratio Summary—Proposed Modified Application Alternative (Residential Study Area)..... 21-25

List of Figures

Following page:

S-1 Project Location S-1
S-2 Project Area S-1
S-3 Existing Zoning S-2
S-4 Proposed Zoning S-2
S-5 Proposed Development Ground Floor Plan S-10
S-6 Proposed Development Rooftop Plan S-10
S-7 Proposed Development Massing S-10
S-8 Projected Development Sites S-17
S-9 No Action Scenario Site Plan S-20
S-10 No Action Scenario Massing S-20
S-11a With Action Scenario Massing S-23
S-11b With Action Scenario Massing S-23
S-11c With Action Scenario Massing S-23
1-1 Project Location 1-1
1-2 Project Area 1-1
1-3 Existing Zoning 1-2
1-4 Proposed Zoning 1-2
1-5 Proposed Development Ground Floor Plan 1-9
1-6 Proposed Development Rooftop Plan 1-9
1-7 Proposed Development Massing 1-9
1-8 Projected Development Sites 1-16
1-9 No Action Scenario Site Plan 1-19
1-10 No Action Scenario Massing 1-19
1-11a With Action Scenario Massing 1-22
1-11b With Action Scenario Massing 1-22
1-11c With Action Scenario Massing 1-22
2-1 Existing Land Use 2-4

2-2 Existing Zoning 2-8
2-3 No Build Projects 2-13
2-4 Proposed Zoning 2-18
3-1 Socioeconomic Study Area 3-7
4-1 Public Schools in the Study Area 4-5
4-2 Public Libraries in the Study Area 4-11
4-3 Early Childhood Programs in the Study Area 4-14
5-1 Open Space Study Area and Resources 5-6
5-2 Walk to a Park Service Area 5-9
5-3 Proposed Development Open Space—Conceptual Design 5-21
6-1 Tier 1 and Tier 2 Assessments 6-3
6-2 Tier 3 Assessment: December 21 6-6
6-3 Tier 3 Assessment: March 21 / September 21 6-6
6-4 Tier 3 Assessment: May 6 / August 6 6-6
6-5 Tier 3 Assessment: June 21 6-6
6-6 Shadows – Detailed Analysis 6-8
6-7 Shadows – Detailed Analysis 6-8
6-8 Shadows – Detailed Analysis 6-8
6-9 Shadows – Detailed Analysis 6-8
6-10 Shadows – Detailed Analysis 6-8
6-11 Shadows – Detailed Analysis 6-8
6-12 Shadows – Detailed Analysis 6-8
6-13 Shadows – Detailed Analysis 6-8
6-14 Shadows – Detailed Analysis 6-8
6-15 Shadows – Detailed Analysis 6-8
6-16 Shadows – Detailed Analysis 6-8
6-17 Shadows – Detailed Analysis 6-8
6-18 Shadows – Detailed Analysis 6-8
6-19 Shadows – Detailed Analysis 6-8
6-20 Shadows – Detailed Analysis 6-8
6-21 Shadows – Detailed Analysis 6-8
6-22 Shadows – Detailed Analysis 6-8
6-23 Shadows – Detailed Analysis 6-8

6-24 Playground Thirty Five XXV Site Plan 6-9
7-1 Architectural Resources 7-1
7-2a Projected Development Site A 7-2
7-2b Projected Development Site B 7-2
7-2c Projected Development Site D 7-2
7-2d Projected Development Site E 7-2
7-2e Projected Development Site F 7-2
7-2f Projected Development Site K 7-2
7-3 Development Site 7-3
7-4 Development Site 7-3
7-5 Development Site 7-4
7-6 Development Site 7-4
7-7 Development Site 7-4
7-8 Development Site 7-4
7-9 Development Site 7-4
7-10 Development Site 7-4
7-11 Development Site 7-4
7-12 Development Site 7-4
7-13 Development Site 7-4
7-14 Development Site 7-4
7-15 Additional Affected Area 7-4
7-16 Additional Affected Area 7-5
7-17 Additional Affected Area 7-5
7-18 Additional Affected Area 7-5
7-19 Study Area 7-6
7-20 Study Area 7-6
8-1 Urban Design and Visual Resources Project Location Map 8-5
8-2 Urban Design and Visual Resources Aerial 8-5
8-3 Urban Design and Visual Resources Building Heights in the Project Area 8-6
8-4 Urban Design and Visual Resources Built FAR in the Project Area 8-6
8-5 Urban Design and Visual Resources Lot Coverage in the Project Area 8-6
8-6a Photographs of Projected Development Site A 8-6
8-6b Photographs of Projected Development Sites A and B 8-6

8-6c Photographs of Projected Development Sites C and D 8-7
8-6d Photographs of Projected Development Site D 8-7
8-6e Photographs of Blocks 668 and 670 8-8
8-6f Photographs of Blocks 668 and 669 8-9
8-6g Photograph of Projected Development Site C 8-10
8-7 Urban Design and Visual Resources Building Heights in the Study Area 8-10
8-8 Urban Design and Visual Resources Built FAR in the Study Area 8-10
8-9 Urban Design and Visual Resources Lot Coverage in the Study Area 8-10
8-10a Photographs of Study Area 8-12
8-10b Photographs of Study Area 8-12
8-10c Photographs of Study Area 8-12
8-10d Photographs of Study Area 8-12
8-10e Photographs of Study Area 8-13
8-10f Photographs of Study Area 8-13
8-10g Photographs of Study Area 8-13
8-10h Photographs of Study Area 8-13
8-10i Photographs of Study Area 8-14
8-11 No Action Scenario Site Plan 8-15
8-12 No Action Scenario Massing 8-15
8-13 Proposed Development Ground Floor Plan 8-16
8-14 Proposed Development Massing 8-16
8-15 With Action Scenario Massing 8-16
8-16a Illustrative Renderings of No Action and With Action Conditions: View East on 35th Avenue from 35th Street 8-16
8-16b Illustrative Renderings of No Action and With Action Conditions: View South on Steinway Street from 34th Avenue 8-16
8-16c Illustrative Renderings of No Action and With Action Conditions: View North on 41st Street from Northern Boulevard 8-16
8-16d Illustrative Renderings of No Action and With Action Conditions: View North on 37th Street from 37th Avenue 8-16
8-16e Illustrative Renderings of No Action and With Action Conditions: View West on 35th Avenue from Northern Boulevard 8-16
8-17 Elevations of Projected Development Site A 8-17
8-18 Illustrative Rendering of Projected Development Site A, View Southeast from 35th Avenue 8-17

8-19 Elevations of Projected Development Site B 8-17
8-20 Elevations of Projected Development Site B 8-17
8-21 Illustrative Rendering of Projected Development Sites B and C, View South on Steinway Street from 35th Avenue 8-17
8-22 Illustrative Rendering of Projected Development, View Southwest on 35th Avenue with Site B in Background 8-17
8-23 Projected Development Site C 8-18
8-24 Illustrative Rendering of Open Space on Projected Development Site C 8-18
8-25 Elevations of Projected Development Site C 8-18
8-26 Elevations of Projected Development Site C 8-18
8-27 Elevations of Projected Development Site D 8-18
8-28 Elevations of Projected Development Site D 8-18
8-29 Illustrative Rendering of Projected Development Site D, View from 42nd Street 8-18
8-30 Elevations of Projected Development Site E 8-19
8-31 Elevations of Projected Development Site E 8-19
8-32 Aerial Views of the Projected Development 8-21
8-33 Elevations of Projected Development in Context 8-21
8-34 Elevations of Projected Development in Context 8-21
8-35 Elevations of Projected Development in Context 8-21
8-36 Elevations of Projected Development in Context 8-21
8-37 Elevations of Projected Development in Context 8-21
8-38 Elevations of Projected Development in Context 8-21
8-39 Elevations of Projected Development in Context 8-21
8-40 Elevations of Projected Development in Context 8-21
8-41 Illustrative Rendering of the Projected Development Site D, View from 36th Street and 35th Avenue 8-21
13-1 Traffic Study Area 13-20
13-2 Project Area Transit Services 13-21
13-3 Analyzed Pedestrian Elements 13-24
13-4 Study Area Bicycle Routes 13-35
13-5 Existing AM Peak Hour Traffic Volumes 13-35
13-6 Existing Midday Peak Hour Traffic Volumes 13-35
13-7 Existing PM Peak Hour Traffic Volumes 13-35
13-8 Existing Saturday Peak Hour Traffic Volumes 13-35

13-9 No Action AM Peak Hour Traffic Volumes 13-37
13-10 No Action Midday Peak Hour Traffic Volumes 13-37
13-11 No Action PM Peak Hour Traffic Volumes 13-37
13-12 No Action Saturday Peak Hour Traffic Volumes 13-37
13-13 AM Peak Hour Project Increment Traffic Volumes 13-42
13-14 Midday Peak Hour Project Increment Traffic Volumes 13-42
13-15 PM Peak Hour Project Increment Traffic Volumes 13-42
13-16 Saturday Peak Hour Project Increment Traffic Volumes 13-42
13-17 With Action AM Peak Hour Traffic Volumes 13-42
13-18 With Action Midday Peak Hour Traffic Volumes 13-42
13-19 With Action PM Peak Hour Traffic Volumes 13-42
13-20 With Action Saturday Peak Hour Traffic Volumes 13-42
13-21 36th Street (M/R) Subway Station 13-48
13-22 Steinway Street (M/R) Subway Station 13-48
13-23 36th Street (N/W) Subway Station 13-49
14-1 Building Distribution Diagram 14-12
16-1 Noise Receptor Locations 16-6
16-2 Noise (E) Designation Attenuation Requirements 16-15
19-1 Conceptual Construction Schedule 19-6
19-2 Incremental AM Construction Peak Hour Traffic Volumes 19-15
19-3 Incremental PM Construction Peak Hour Traffic Volumes 19-15
19-4 Existing AM Construction Peak Hour Traffic Volumes 19-16
19-5 Existing PM Construction Peak Hour Traffic Volumes 19-16
19-6 No Action AM Construction Peak Hour Traffic Volumes 19-16
19-7 No Action PM Construction Peak Hour Traffic Volumes 19-16
19-8 With Action AM Construction Peak Hour Traffic Volumes 19-17
19-9 With Action PM Construction Peak Hour Traffic Volumes 19-17
19-10 Construction Noise Impacts (Existing Receptors) 19-41
19-11 Construction Noise Impacts (Project-Generated Receptors) 19-41
21-1 Massing of Proposed Modified Application Alternative 21-21
21-2 Massing of Proposed Modified Application Alternative, View from Northern Boulevard 21-21
21-3 Site Plan of Proposed Modified Application Alternative 21-21

21-4 Illustrative Rendering of No Action/Future with Proposed Modified Application Alternative: View East on 35th Avenue from 35th Street.....21-25

21-5 Illustrative Rendering of No Action/Future with Proposed Modified Application Alternative: View South on Steinway Street from 34th Avenue 21-25

21-6 Illustrative Rendering of No Action/Future with Proposed Modified Application Alternative: View West on 35th Avenue from Northern Boulevard.....21-25

✷