Crotona Park East/West Farms Rezoning and Related Actions

FINAL ENVIRONMENTAL IMPACT STATEMENT

CEQR # 10DCP017X



Lead Agency:
City Planning Commission, City of New York
Amanda M. Burden, FAICP, Chair

August 26, 2011

Crotona Park East/West Farms Rezoning and Related Actions

FINAL ENVIRONMENTAL IMPACT STATEMENT

CEQR # 10DCP017X

ULURP Nos.:100310ZMX
100312ZSX
100313ZSX
110297ZSX
N100311ZRX
110234HAX

Action Location: Bronx, NY

LEAD AGENCY:
City Planning Commission, City of New York
Amanda M. Burden, FAICP, Chair

LEAD AGENCY CONTACT:
Robert Dobruskin, AICP, Director
Environmental Assessment and Review Division
New York City Department of City Planning
22 Reade Street, Room 4E
New York, NY 10007
(212) 720-3423

PREPARED FOR THE LEAD AGENCY BY:
Stantec Consulting Services, Inc.
Sandstone Environmental Associates, Inc.

August 26, 2011

Crotona Park East/West Farms Rezoning and Related Actions FEIS

Table of Contents

EXECUTIVE SUMMARY ES-1
1. PROJECT DESCRIPTION ES-1
Project Identification ES-1
Description of the Proposed Action and the Proposed Project ES-3
Expected Sequencing of Construction ES-22
Required Public Approvals ES-22
Projected Development ES-32
Reasonable Worst Case Development Scenario (RWCDS) ES-33
Public Review Process ES-40
2. EXISTING AND FUTURE ENVIRONMENTAL CONDITIONS AND PROBABLE IMPACTS OF THE PROPOSED ACTION ES-42
A Land Use, Zoning, and Public Policy ES-42
B Socioeconomic Conditions ES-42
C Community Facilities and Services ES-44
D Open Space ES-46
E Shadows ES-46
F Historic and Cultural Resources ES-47
G Urban Design and Visual Resources ES-48
H Natural Resources ES-48
I Hazardous Materials ES-49
J Water and Sewer Infrastructure ES-49
K Solid Waste and Sanitation Services ES-51
L Energy ES-51
M Transportation ES-51
N Air Quality ES-53
O Greenhouse Gas Emissions ES-54
P Noise ES-55
Q Public Health ES-56
R Neighborhood Character ES-57
S Construction Impacts ES-57
3. MITIGATION ES-60
Elementary Schools ES-61
Traffic ES-65
Construction ES-67
4. UNAVOIDABLE ADVERSE IMPACTS ES-68
Open Space ES-69
Historic and Cultural Resources ES-69
Transportation ES-69
Construction ES-70
5. ALTERNATIVES ES-71
No-Action (As-of-Right) Alternative ES-71
No-Impact Alternative ES-72

Lesser Density Alternative ES-73
6. GROWTH INDUCING ASPECTS OF THE PROPOSED ACTION ES-74
7. IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES ES-74

1. PROJECT DESCRIPTION 1-1
INTRODUCTION 1-1
DESCRIPTION OF THE PROPOSED ACTION AND PROPOSED PROJECT 1-3
Description of the Proposed Action 1-4
Purpose and Need of the Proposed Action 1-13
Description of the Proposed Project 1-15
Expected Sequencing of Construction 1-32
REQUIRED PUBLIC APPROVALS 1-34
Restrictive Declaration 1-43
PROJECTED DEVELOPMENT 1-43
General Criteria for Development Sites 1-44
Reasonable Worst Case Development Scenario (RWCDS) 1-45
PUBLIC REVIEW PROCESS 1-51
Uniform Land Use Review Procedure (ULURP) 1-51
Environmental Review (CEQR) 1-51

2. EXISTING AND FUTURE ENVIRONMENTAL CONDITIONS AND PROBABLE IMPACTS OF THE PROPOSED ACTION

2.A LAND USE, ZONING, AND PUBLIC POLICY A-1
INTRODUCTION A-1
PRINCIPAL CONCLUSIONS A-1
METHODOLOGY A-1
Study Areas A-3
Waterfront Revitalization Program A-3
Preliminary Assessment A-3
EXISTING CONDITIONS A-10
Rezoning Area A-10
Primary Study Area A-12
Secondary Study Area A-14
FUTURE NO ACTION CONDITIONS A-15
Rezoning Area A-15
Primary and Secondary Study Areas A-16
FUTURE ACTION CONDITION A-19
Rezoning Area A-19
Primary and Secondary Study Areas A-23
Waterfront Revitalization Program A-23
Sustainability and PlaNYC A-31
Sustainability and PlaNYC A-32
CONCLUSION A-35

2.B SOCIOECONOMIC CONDITIONS B-1
INTRODUCTION B-1

PRINCIPAL CONCLUSIONS B-2
Direct Residential Displacement B-2
Direct Business Displacement B-2
Indirect Residential Displacement B-2
Indirect Business Displacement B-3
Adverse Effects on Specific Industries B-3
METHODOLOGY B-3
Data Sources B-3
Study Area Definitions B-4
Assessment Methodology B-9
PRELIMINARY ASSESSMENT B-9
Direct Residential Displacement B-9
Direct Business Displacement B-11
Indirect Residential Displacement B-21
Indirect Business Displacement B-26
Adverse Effect on a Specific Industry B-35
DETAILED ASSESMENT OF THE POTENTIAL FOR INDIRECT RESIDENTIAL DISPLACEMENT B-36
Introduction B-36
Existing Conditions B-37
Future Conditions without the Proposed Action B-64
Future Conditions with the Proposed Action and Its Potential Impact B-65

2.C COMMUNITY FACILITIES AND SERVICES C-1
INTRODUCTION C-1
PRINCIPAL CONCLUSIONS C-1
Libraries C-1
Public Schools C-2
Child Care Centers C-2
METHODOLOGY C-3
Libraries C-3
Public Schools C-3
Child Care Centers C-4
Health Care Facilities C-5
Police and Fire Protection Services C-5
PRELIMINARY SCREENING C-5
Libraries C-6
Public Schools C-6
Child Care Centers C-6
Health Care Facilities C-6
Police and Fire Protection Services C-7
EXISTING CONDITIONS C-7
Libraries C-7
Public Schools C-11
Child Care Facilities C-20
Police Services C-23
Fire Protection C-23
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION C-25

Libraries C-25
Public Schools C-25
Child Care Facilities C-29
FUTURE CONDITIONS WITH THE PROPOSED ACTION AND ITS POTENTIAL IMPACT C-30
Libraries C-30
Public Schools C-30
Publicly Subsidized Child Care Centers C-32
CONCLUSIONS C-32

2.D OPEN SPACE D-1
INTRODUCTION D-1
PRINCIPAL CONCLUSIONS D-1
METHODOLOGY D-2
Population D-3
Residential Study Area Definition D-4
Non-Residential Study Area Definition D-4
EXISTING CONDITIONS D-5
EXISTING CONDITIONS D-6
EXISTING CONDITIONS D-7
Residential Study Area Demographics D-7
Non-Residential Study Area Demographics D-11
Existing Open Space Inventory D-13
Quantitative Analysis of Adequacy D-20
Qualitative Analysis of Adequacy D-21
THE FUTURE WITHOUT THE PROPOSED ACTION D-24
Future No-Action User Population D-24
Open Space Inventory D-26
Quantitative Analysis of Adequacy D-27
Qualitative Analysis of Adequacy D-28
THE FUTURE WITH THE PROPOSED ACTION D-29
User Population D-29
Open Space Inventory D-30
Quantitative Analysis of Adequacy D-31
Qualitative Analysis of Adequacy D-32
Determining Impact Significance D-33
CONCLUSION D-34

2.E SHADOWS E-1
INTRODUCTION E-1
PRINCIPAL CONCLUSIONS E-1
METHODOLOGY E-2
PROPOSED ACTION CHARACTERISTICS E-3
Results of the Screening Analysis E-6
Description of the Detailed Analysis E-10
Results of the Detailed Shadow Analysis E-11
CONCLUSION E-26

2.F HISTORIC AND CULTURAL RESOURCES F-1
INTRODUCTION F-1
PRINCIPAL CONCLUSIONS F-1
Architectural Resources F-1
Archaeological Resources F-1
METHODOLOGY F-2
Architectural Resources F-2
Archaeological Resources F-4
HISTORY F-4
EXISTING CONDITIONS F-6
Architectural Resources F-6
Archaeological Resources F-6
FUTURE NO-ACTION CONDITIONS F-9
Architectural Resources F-9
Archaeological Resources F-9
FUTURE ACTION CONDITIONS F-9
Architectural Resources F-9
Archaeological Resources F-9
CONCLUSION F-12

2.G URBAN DESIGN AND VISUAL RESOURCES G-1
INTRODUCTION G-1
PRINCIPAL CONCLUSIONS G-1
METHODOLOGY G-1
Study Areas G-2
PRELIMINARY ASSESSMENT G-10
EXISTING CONDITIONS G-10
Urban Design G-10
Visual Resources G-29
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION G-30
FUTURE CONDITIONS WITH THE PROPOSED ACTION G-31
Proposed Zoning Map Changes G-31
Development Scenario G-37
CONCLUSION G-63
CONCLUSION G-64
CONCLUSION G-65
Urban Design G-65
Visual Resources G-67

2.H NATURAL RESOURCES H-1
INTRODUCTION H-1
IMPACT SCREENING ANALYSIS FOR POTENTIAL NATURAL RESOURCE IMPACTS H-4
Initial Impact Screening H-4
Secondary Impact Screening H-5
CONCLUSION H-7

2.I HAZARDOUS MATERIALS I-1
INTRODUCTION I-1
PRINCIPAL CONCLUSIONS I-1
METHODOLOGY I-2
EXISTING CONDITIONS I-2
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION I-3
FUTURE CONDITIONS WITH THE PROPOSED ACTION AND ITS POTENTIAL IMPACT I-3
Impact Potential I-3
E Designations I-4
Review and Approval Procedures for the Proposed Project I-7
CONCLUSION I-7

2.J WATER AND SEWER INFRASTRUCTURE J-1
INTRODUCTION J-1
PRINCIPAL CONCLUSIONS J-1
Water Supply J-1
Wastewater Treatment J-1
Sanitary and Storm water Drainage and Management J-2
METHODOLOGY J-2
Water Supply J-2
Wastewater Treatment J-3
Sanitary and Storm water Drainage Management J-3
EXISTING CONDITIONS J-6
Water Supply J-6
Wastewater Treatment J-7
Sanitary and Storm water Drainage Management J-8
FUTURE WITHOUT THE PROPOSED ACTION J-9
Water Supply and Wastewater Treatment J-9
Sanitary and Storm water Drainage Management J-10
FUTURE WITH THE PROPOSED ACTION J-12
Water Supply J-12
Wastewater Treatment J-14
Sanitary and Storm water Drainage Management J-14
Sanitary and Storm water Drainage Management J-15
STORMWATER BEST MANAGEMENT PRACTICES CONCEPT PLAN SUMMARY J-17
Contextual Districts J-17
Stormwater Source Controls J-17
Enterprise Green Communities J-18
CONCLUSION J-19
Water Supply J-19
Wastewater Treatment J-19
Sanitary and Storm water Drainage and Management J-19

2.K SOLID WASTE AND SANITATION SERVICES K-1
INTRODUCTION K-1
PRINCIPAL CONCLUSIONS K-1

METHODOLOGY K-1
EXISTING CONDITIONS K-2
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION K-3
FUTURE CONDITIONS WITH THE PROPOSED ACTION K-4
CONCLUSIONS K-5

2.L ENERGY L-1
INTRODUCTION L-1
PRINCIPAL CONCLUSIONS L-1
METHODOLOGY L-1
EXISTING CONDITIONS L-2
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION L-3
FUTURE CONDITIONS WITH THE PROPOSED ACTION L-3
CONCLUSIONS L-5

2.M TRANSPORTATION M-1
INTRODUCTION M-1
PRINCIPAL CONCLUSIONS M-1
METHODOLOGY M-3
Preliminary Trip Generation Analysis M-3
Detailed Transportation Analysis Parameters and Criteria for Impact Analyses M-7
EXISTING CONDITIONS M-15
Data Collection M-15
Traffic M-16
Transit Overview M-31
Pedestrian Overview M-32
Subway Station Analysis M-33
Subway Line Haul Analysis M-34
Pedestrian Elements M-36
Parking M-38
Safety M-41
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION M-44
No Action Development and Background Growth M-44
Changes in the Transportation Environment M-46
Traffic M-53
Summary of LOS Analysis M-63
Transit and Pedestrians M-68
Subway Station Analysis M-68
Subway Line Haul Analysis M-69
Pedestrian Analysis M-70
Parking M-73
FUTURE WITH THE PROPOSED ACTION CONDITION M-74
With Action Increment M-74
Traffic M-77
Transit and Pedestrians M-112
Parking M-117
SUMMARY OF CONCLUSIONS M-119

Traffic M-119
Transit and Pedestrian M-119
Parking M-119

2.N AIR QUALITY N-1
INTRODUCTION N-1
PRINCIPAL CONCLUSIONS N-1
Mobile Sources and Parking Facilities N-1
Stationary Sources N-1
Air Toxics N-2
Odors N-2
METHODOLOGY N-2
Standards and Evaluation Criteria N-2
Parking Facilities N-11
Stationary Sources N-13
EXISTING CONDITIONS N-17
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION N-17
Projected Development N-17
Mobile Sources N-17
Parking Facilities N-19
Stationary HVAC Sources N-19
FUTURE CONDITIONS WITH THE PROPOSED ACTION N-19
Mobile Sources N-21
Parking Facilities N-23
Stationary HVAC Sources N-27
Impacts to the Surrounding Community N-29
Project-on-Project Impacts N-36
Air Toxics and Odors N-47
E Designations and Restrictive Declarations, Proposed Action N-50

2.O GREENHOUSE GAS EMISSIONS O-1
INTRODUCTION O-1
PRINCIPAL CONCLUSIONS O-1
METHODOLOGY O-2
ESTIMATED ANNUAL GREENHOUSE GAS EMISSIONS O-3
Operations Emissions O-3
Mobile Source Emissions O-4
Construction Emissions O-6
CONSISTENCY WITH THE GHG REDUCTION GOAL O-8
CONCLUSIONS O-11
Applicant-Controlled Development Sites O-11
Non-Applicant Development Sites O-12
Proposed Action (All Development Sites) O-12

2.P NOISE P-1
INTRODUCTION P-1
PRINCIPAL CONCLUSIONS P-1

Mobile Sources P-1
Stationary Sources P-2
NOISE FUNDAMENTALS P-3
METHODOLOGY P-6
Noise Monitoring P-6
Modeling of Future Noise Levels P-6
Impact Determination and Noise Standards and Guidelines P-7
EXISTING CONDITIONS P-9
Traffic Intersections P-9
Highways P-12
Rail P-12
FUTURE CONDITIONS WITHOUT THE PROPOSED ACTION P-13
FUTURE CONDITIONS WITH THE PROPOSED ACTION P-15
Intersection and Highway Noise P-15
Rail Noise P-18
Playground Noise P-19
HVAC Noise P-20
Supplemental Noise Monitoring for Window/Wall Attenuation P-20
Required Noise Attenuation P-23

2.Q PUBLIC HEALTH Q-1
INTRODUCTION Q-1
PRINCIPAL CONCLUSIONS Q-1
METHODOLOGY Q-1
SUMMARY OF AIR & NOISE POLLUTION SOURCES FROM THE PROPOSED ACTION Q-2
Construction Q-2
Operation Q-3
AIR QUALITY POLLUTANTS OF CONCERN AND RELATED HEALTH EFFECTS Q-4
Particulate Matter Q-4
PM2.5-Related Health Effects Q-5
LOCAL HEALTH STATISTICS Q-7
REGULATIONS AND STANDARDS Q-9
Air Quality Q-9
Noise Q-10
AIR QUALITY AND NOISE IMPACT CRITERIA Q-10
Air Quality Q-10
Noise Q-11
IMPACT ASSESSMENT Q-13
Operational Air Quality Q-13
Operational Noise Q-14
Construction Air Quality Q-15
Construction Noise Q-16
Rodent Control Q-17
CONCLUSION Q-17

2.R NEIGHBORHOOD CHARACTER R-1
INTRODUCTION R-1

PRINCIPAL CONCLUSIONS R-1
METHODOLOGY R-1
EXISTING CONDITIONS R-4
Proposed Rezoning Area R-4
Crotona Park East R-7
West Farms R-8
Bronx River Valley R-9
Relationship between the Rezoning Area and the Rest of the Study Area R-9
THE FUTURE WITHOUT THE PROPOSED ACTION R-10
THE FUTURE WITH THE PROPOSED ACTION AND ITS POTENTIAL IMPACT R-10
Redevelopment under the RWCDS R-10
Technical Area Significant Adverse Impacts and Moderate Adverse Effects R-11
Potential to Affect a Defining Feature of the Neighborhood R-13

2.S CONSTRUCTION IMPACTS S-1
INTRODUCTION S-1
PRINCIPAL CONCLUSIONS S-2
Traffic – Construction Peak Period Analysis S-2
Parking S-3
Transit and Pedestrians Analysis S-3
Air Quality and Noise S-3
Other Technical Areas S-4
METHODOLOGY S-5
Regulatory Framework: S-5
Reasonable Worst Case Construction Sequencing S-6
Transportation-Related Analysis Assumptions S-9
Air Quality-Related Analysis Assumptions S-10
Noise-Related Analysis Assumptions S-10
ASSESSMENT OF THE NEED FOR A PRELIMINARY OR DETAILED ASSESSMENT S-11
Transportation S-11
Air Quality or Noise S-13
EVALUATION CRITERIA S-13
Transportation S-14
Air Quality S-14
Noise S-14
CONSTRUCTION IMPACTS ASSESSMENT S-15
Preliminary Traffic Assessment S-15
Detailed Traffic Analysis S-24
Preliminary Parking Assessment S-35
Preliminary Transit and Pedestrian Assessment S-35
Preliminary Assessment of Air Quality and Noise S-36
Detailed Construction Noise Analysis S-65
Preliminary Assessment of other Impact Areas S-71

3. MITIGATION 3-1
INTRODUCTION 3-1
ELEMENTARY SCHOOLS 3-1
Impact 3-1

Proposed Mitigation Measures....3-1
Potential Impacts of the New School Mitigation....3-4
OPEN SPACE....3-85
Impact....3-85
Proposed Mitigation Measures....3-85
ARCHAEOLOGICAL RESOURCES....3-87
Impact....3-87
Proposed Mitigation Measures....3-87
TRAFFIC....3-88
Impacts....3-88
Proposed Mitigation Measures....3-88
CONSTRUCTION....3-102
Impacts....3-102
Proposed Mitigation Measures....3-102

4. . UNAVOIDABLE SIGNIFICANT ADVERSE IMPACTS....4-1
INTRODUCTION....4-1
OPEN SPACE....4-1
HISTORIC AND CULTURAL RESOURCES....4-1
TRANSPORTATION....4-2
CONSTRUCTION....4-3
Traffic....4-3
Noise....4-3

5. ALTERNATIVES TO THE PROPOSED ACTION....5-1
INTRODUCTION....5-1
PRINCIPAL CONCLUSIONS....5-1
No-Action (As-of-Right) Alternative....5-1
No-Impact Alternative....5-3
Lesser Density Alternative....5-4
NO-ACTION ALTERNATIVE....5-5
Description....5-5
Comparison with the Proposed Action....5-5
Changes in the Transportation Environment....5-11
THE NO-IMPACT ALTERNATIVE....5-24
Description....5-24
Comparison with the Proposed Action....5-25
THE LESSER DENSITY ALTERNATIVE....5-28
Description....5-28
Comparison with the Proposed Action....5-37

8. RESPONSE TO COMMENTS ON THE DRAFT SCOPE OF WORK AND THE DRAFT ENVIRONMENTAL IMPACT STATEMENT....8-1
INTRODUCTION....8-1
LIST OF ELECTED OFFICIALS, GOVERNMENTAL AGENCIES, AND ORGANIZATIONS WHO COMMENTED ON THE DRAFT SCOPE....8-1
Elected Officials and Governmental Agencies....8-1

Organizations 8-1
RESPONSE TO DRAFT SCOPE OF WORK COMMENTS 8-2
General Comments 8-2
Review Process, Analytical Framework, Project Description 8-2
Socioeconomic Conditions 8-4
Community Facilities and Services 8-7
Open Space 8-7
Shadows 8-8
Historic and Cultural Resources 8-8
Urban Design and Visual Resources 8-8
Hazardous Materials 8-9
Water and Sewer Infrastructure 8-9
Transportation 8-11
Greenhouse Gas Emissions 8-12
Neighborhood Character 8-12
LIST OF ELECTED OFFICIALS, COMMUNITY BOARDS, ORGANIZATIONS AND THE INTERESTED PUBLIC WHO COMMENTED ON THE DEIS 8-12
Elected Officials and Community Boards 8-12
Organizations and Interested Public 8-12
RESPONSE TO DRAFT ENVIRONMENTAL IMPACT STATEMENT COMMENTS 8-13
General Comments 8-13
Comments on the Proposed Action and the Proposed Project 8-13
Comments on Socioeconomic Conditions 8-14
Comments on Open Space 8-16
Comments on Urban Design and Visual Resources 8-19
Comments on Construction Impacts 8-20

APPENDICES

1. ZONING TEXT AMENDMENT
2. AGENCY CORRESPONDENCE:
   a. LPC Final Sign-off
   b. SHPO Final Letter
   c. SCA Letter of Intent
   d. Library Letter
3. SHADOWS
4. WRP FORM AND ASSESSMENT
5. ARCHAEOLOGICAL PROTOCOL
6. CONSTRUCTION SCHEDULE AND CORDON MAPS
7. TRANSPORTATION
   7.1 Transportation Planning Assumptions
   7.2 Lesser Density Traffic Analysis
8. HAZARDOUS MATERIALS REPORT
9. WRITTEN COMMENTS ON THE DRAFT SCOPE
10. WRITTEN COMMENTS ON THE DEIS

List of Tables

EXECUTIVE SUMMARY
Table ES-1: List of Blocks and Lots Affected by Crotona Park East/West Farms Rezoning ES-6
Table ES-2: Proposed Project: Summary of Proposed Program ES-10
Table 3: Expected Sequencing of Development and Accessory Parking ES-22
Table ES-4: Summary of Existing Conditions, the Future without the Proposed Action and the Future with the Proposed Action ES-36
Table ES-5: Archaeologically Sensitive Lots for Sites not under Applicant Control ES-48
Table ES-6: Summary of Significantly Impacted Intersections ES-52
Table ES-7: 2022 Future with Action Elementary School Enrollment, Capacity, and Utilization - Comparison of No-School and With-School Scenarios ES-62

PROJECT DESCRIPTION
Table 1-1: List of Blocks and Lots Affected by Crotona Park East/West Farms Rezoning 1-7
Table 1-2: Proposed Project: Summary of Proposed Program 1-15
Table 1-3: Expected Sequencing of Development and Accessory Parking 1-32
Table 1-4: Summary of Existing Conditions, the Future without the Proposed Action and the Future with the Proposed Action 1-47

2.A LAND USE, ZONING, AND PUBLIC POLICY
Table A-1: Land Uses in the Proposed Rezoning Area A-6
Table A-2: Summary of Existing Allowed Density and Building Form within the Proposed Rezoning Area A-6
Table A-3: Project Increment on Projected Development Sites A-8
Table A-4: Summary of Proposed Allowed Density and Building Form within the Rezoning Area A-8
Table A-5: Summary of Proposed Zoning District Changes A-8
Table A-6: No Build Projects within the Secondary Study Area (1/4 mile) A-17

2.B SOCIOECONOMIC CONDITIONS
Table B-1: Residents and Households in 2010: Quarter-Mile Study Area B-10
Table B-2: Housing Units in 2010 Quarter-Mile Study Area B-11
Table B-3: Businesses and Vacant Commercial and Industrial Space in the Proposed Rezoning Area (Existing Conditions) B-13
Table B-4: Anticipated Direct Displacement of Currently Non-Residential Properties, by Type of Business B-16
Table B-5: Anticipated Direct Displacement on Currently Non-Residential Properties, by Development Parcel B-17
Table B-6: Auto Repair and Maintenance Establishments B-20
Table B-7: Income Levels and Poverty Rates in 1999 and 2000: Quarter-Mile Study Area B-23
Table B-8: Residents and Households in 2010: Half-Mile Study Area B-24
Table B-9: Housing Units in 2010: Half-Mile Study Area B-25
Table B-10: Employment in 2000: Quarter-Mile Study Area B-28
Table B-11: Workers in 2000 by Economic Sector: Quarter-Mile Study Area B-29
Table B-12: Business Establishments in 1998 and 2008 in Zip Codes 10459 and 10460 ..... B-30
Table B-13: Details for Certain Economic Categories B-32
Table B-14: Business Establishments in 1998 and 2008 in Zip Codes 10459 and 10460, the Bronx, and New York City B-33
Table B-15: Residents and Households in 2000 and 2010 ..... B-37

Table B-16: Age Distribution in 2010 ..... B-38
Table B-17: Income Levels, Poverty Rate, and Labor Force Data in 1999 and 2000 ..... B-39
Table B-18: 1999 Median Incomes and Poverty Rates by Census Tract B-41
Table B-19: Income Levels in 1989 and 1999 ..... B-44
Table B-20: Housing Units and Tenure in 2010 ..... B-45
Table B-21: Contract Rents in 2000 ..... B-46
Table B-22: Gross Rents in 2000 ..... B-48
Table B-23: Gross Rent as Percentage of Income in 2000 ..... B-49
Table B-24: Rents in 2000 by Census Tract B-53
Table B-25: Income Restricted Housing B-62
Table B-26: Unprotected Housing Units in 2000 ..... B-67
Table B-27: Renter Average Household Incomes by Building Size B-69
Table B-28: Income Comparisons Between Study Area Tracts and the Bronx B-70
Table B-29: Rental Units in Small Buildings Constructed Before 1990 ..... B-73
Table B-30: Households at Risk B-79
Table B-31: Indirect Residential Displacement Potential B-80

2.C COMMUNITY FACILITIES AND SERVICES

Table C-1: Preliminary Screening Analysis Criteria C-6
Table C-2: Library Study Area Population C-10
Table C-3: CSD 12 Elementary Schools within Sub-District 2 ..... C-13
Table C-4: CSD 12 Elementary Schools within a Half-Mile of the Proposed Rezoning Area 2009-2010 Enrollment, Capacity, and Utilization Data C-14
Table C-5: CSD 12 Intermediate Schools within Sub-District 2 ..... C-15
Table C-6: CSD 12 Intermediate Schools within a Mile of the Proposed Rezoning Area 2009-2010 Enrollment, Capacity, and Utilization Data C-16
Table C-7: 2009-2010 High School Enrollment, Capacity, and Utilization Data the Bronx C-16
Table C-8: Public High Schools within One Mile of the Proposed Rezoning Area C-19
Table C-9: Publicly Funded Child Care Programs in 1 1/2 Mile Study Area C-20
Table C-10: Fire Protection and EMS Services C-23
Table C-11: No-Action Developments and Student Generation C-26
Table C-12: 2022 Future No-Action Elementary School Enrollment, Capacity, and Utilization Data . C-28
Table C-13: 2022 Future No-Action Intermediate School Enrollment, Capacity, and Utilization Data C-29
Table C-14: 2022 Future No-Action High School Enrollment, Capacity, and Utilization Data in the Bronx C-29
Table C-15: 2022 Future With-Action Elementary School Enrollment, Capacity, and Utilization Data .. C-31
Table C-16: 2022 Future With-Action Intermediate School Enrollment, Capacity, and Utilization Data C-31
Table C-17: 2022 Future With-Action High School Enrollment, Capacity, and Utilization Data in The Bronx C-32

2.D OPEN SPACE

Table D-1: Residential Study Area 2010 Census Residential Population D-7
Table D-2: Residential Study Area Age Distribution D-8
Table D-3: Residential Study Area 2000 Worker Population D-9
Table D-4: Residential Study Area Commercial Development Since 2000 ..... D-10
Table D-5: Residential Study Area Population D-10
Table D-6: Non-Residential Study Area 2010 Census Residential Population D-11
Table D-7: Non-Residential Study Area Age Distribution D-11

Table D-8: Non-Residential Study Area 2000 Worker Population.....D-12
Table D-9: Non-Residential Study Area Commercial Development Since 2000.....D-12
Table D-10: Non-Residential Study Area Population.....D-13
Table D-11: Existing Open Space Resources, Residential Study Area D-15
Table D-12: Existing Open Space Resources, Residential Study Area D-18
Table D-13: Analysis of Adequacy – Existing Conditions, Residential Study Area.....D-21
Table D-14: Analysis of Adequacy – Existing Conditions, Non-Residential Study Area.....D-22
Table D-15: Anticipated Development in the Study Areas -- 2022 Future No-Action Condition D-25
Table D-16: Study Area Populations – 2022 Future No-Action Condition.....D-26
Table D-17: 2022 Open Space Inventory - New Open Spaces in the Future No-Action Condition.....D-27
Table D-18: Analysis of Adequacy – 2022 Future No-Action Condition, Residential Study Area D-28
Table D-19: Analysis of Adequacy – Future No-Action Condition, Non-Residential Study Area D-28
Table D-20: Projected Population -- 2022 Future Action Condition.....D-30
Table D-21: 2022 Open Space Inventory -- New Open Spaces under the Future Action Condition D-31
Table D-22: Analysis of Adequacy – 2022 Future Action Condition, Residential Study Area.....D-31
Table D-23: 2022 Future Action Condition Analysis of Adequacy – Non-Residential Study Area D-32
Table D-24: Comparison, 2022 Action and No Action Conditions, Residential Study Area.....D-34
Table D-25: Comparison of 2022 Action and No Action Conditions, Non-Residential Study Area D-34

2.E SHADOWS

Table E-1: Height of Proposed Buildings Analyzed..... E-5
Table E-2: Incremental Shadow Durations..... E-12
Table E-3: Estimated Annual Power Loss for the Bronx River House As a Result of Proposed Action Shadows..... E-26

2.F HISTORIC AND CULTURAL RESOURCES

Table F-1: Archaeologically Sensitive Lots for Sites NOT Under Control of the Project Applicant Crotona Park East / West Farms Rezoning APE F-2
Table F-2: Archaeologically Sensitive Lots within the Crotona Park East / West Farms Rezoning APE F-7
Table F-3: Archaeologically Sensitive Lots Recommended for Archaeological Field Testing, for Sites under Control of the Project Applicant..... F-11
Table F-4: Archaeologically Sensitive Lots for Sites NOT Under Control of the Project Applicant. Crotona Park East / West Farms Rezoning APE F-11

2.I HAZARDOUS MATERIALS

Table I-1: Finding Recommendations for Parcels within the Proposed Rezoning Area..... I-6

2.J WATER AND SEWER INFRASTRUCTURE

Table J-1 : Existing Water Consumption and Wastewater Generation.....J-7
Table J-2: Existing Surface Calculations.....J-8
Table J-3: Existing Storm water and Wastewater Generation J-8
Table J-4: Existing Storm water and Wastewater Generation J-9
Table J-5: 2022 No-Action Condition Water Consumption and Wastewater Generation.....J-10
Table J-6: No Action Surface Calculations.....J-11
Table J-7: 2022 No Action Storm water and Wastewater Generation For HP-003 Drainage Area.....J-11
Table J-8: 2022 No Action Storm water and Wastewater Generation For HP-004 Drainage Area.....J-12
Table J-9: 2022 Proposed Action Water Consumption and Wastewater Generation J-13
Table J-10: Summary of Water Consumption J-14
Table J-11: 2022 Proposed Action Surface Calculations.....J-15
Table J-12: Proposed Action Storm water and Wastewater Generation For HP-003 Drainage Area.....J-15

Table J-13: Proposed Action Storm water and Wastewater Generation For HP-004 Drainage Area..... J-16
Table J-14: Existing and Proposed Action Comparison For HP-003 Drainage Area..... J-16
Table J-15: Existing and Proposed Action Comparison For HP-004 Drainage Area..... J-17

2.K SOLID WASTE AND SANITATION SERVICES

Table K-1 : Existing Conditions: Estimated Weekly Solid Waste Generation on Projected Development Parcels..... K-3
Table K-2 : Future No-Action Conditions: Estimated Weekly Solid Waste Generation on Projected Development Parcels..... K-3
Table K-3 : Future Action Condition: Estimated Weekly Solid Waste Generation on Projected Development Parcels..... K-4
Table K-4 Future Action Condition Increment: Estimated Weekly Solid Waste Generation on Projected Development Parcels as Compared to Future No-Action Conditions..... K-5

2.L ENERGY

Table L-1: Floor Area: Existing Conditions..... L-2
Table L-2: Annual Energy Consumption: Existing Conditions..... L-2
Table L-3: Floor Area: Future Conditions without the Proposed Action..... L-3
Table L-4: Annual Energy Consumption: Future Conditions without the Proposed Action..... L-3
Table L-5: Floor Area: Future Action Conditions..... L-4
Table L-6: Annual Energy Consumption: Future Action Conditions..... L-4

2.M TRANSPORTATION

Table M-1: Summary of Significantly Impacted Intersections..... M-2
Table M-2: Transportation Assumption Factors..... M-5
Table M-3: Proposed Garage Entrance/Exit Locations..... M-6
Table M-4: Intersection Level of Service Criteria..... M-9
Table M-5: Level of Service Criteria for Subway Station Elements..... M-12
Table M-6: Level of Service Criteria for Pedestrian Elements..... M-14
Table M-7: Number of Approach Movements with Substandard Level of Service in Existing Conditions..... M-27
Table M-8: Existing LOS Table Signalized Intersections..... M-28
Table M-9: Existing LOS Table Unsignalized Intersections..... M-29
Table M-10: Summary of Bus Routes in Study Area..... M-32
Table M-11: 2009 Existing Subway Stairs Operations..... M-34
Table M-12: 2009 Existing Subway Turnstile Operations..... M-34
Table M-13: 2009 Existing Subway Line Haul Conditions..... M-35
Table M-14: 2009 Existing Corner and Crosswalk Level of Service Table..... M-36
Table M-15: 2009 Existing Sidewalk Level of Service Table..... M-37
Table M-16: Existing Parking Utilization..... M-38
Table M-17: Parking Regulations..... M-41
Table M-18: Reportable Accidents in Study Area Overview..... M-42
Table M-19: Pedestrian and Bicycle Related Accidents in Study Area..... M-43
Table M-20: Projects Expected to Be Completed in Study Area before 2022..... M-44
Table M-21: East 177th Street at the Sheridan Expressway Signal Timing Changes - AM..... M-47
Table M-22: East 177th Street at the Sheridan Expressway Signal Timing Changes - Midday..... M-47
Table M-23: East 177th Street at the Sheridan Expressway Signal Timing Changes - PM..... M-48
Table M-24: Westchester Avenue at Sheridan Expressway Service Road and Whitlock Avenue Signal Timing Changes..... M-50

Table M-25: Westchester Avenue at Sheridan Expressway Service Road and Sheridan Off-Ramp Signal Timing Changes M-51
Table M-26: West Farms Road at Longfellow Avenue and Home Street Signal Timing Changes M-51
Table M-27: West Farms Road at Freeman Street Signal Timing Changes M-52
Table M-28: Number of Approach Movements with Substandard Level of Service in No Action Condition M-63
Table M-29: No Action Level of Service Analysis M-64
Table M-30: No Action Unsignalized Level of Service Analysis Tables M-65
Table M-31: 2022 No-Action Subway Stairs Operations M-69
Table M-32: 2022 No-Action Subway Turnstile Operations M-69
Table M-33: 2022 No Action Subway Line Haul Conditions M-70
Table M-34: 2022 No-Action Corners and Crosswalk Level of Service Table M-71
Table M-35: 2022 No-Action Sidewalk Level of Service Table M-72
Table M-36: 2022 No-Action Parking Demand and Utilization M-73
Table M-37: Project Size Allocated to each Garage Entrance Location M-74
Table M-38: Project Generated Person Trip by Entrance Location M-75
Table M-39: Project Eliminated Person Trip by Entrance Location M-75
Table M-40: Net Project Person Trip by Entrance Location M-76
Table M-41: Vehicle Trip by Land Use M-77
Table M-42: Number of Approach Movements with Substandard Level of Service in Proposed Action Condition M-102
Table M-43: Number of Impacts Created by the Proposed Action M-102
Table M-44: No Action and Proposed Action LOS for Signalized Intersections - AM Peak Period . M-106
Table M-45: No Action and Proposed Action LOS for Signalized Intersections - Midday Peak Period . M-107
Table M-46: No Action and Proposed Action LOS for Signalized Intersections - PM Peak Period .. M-108
Table M-47: No Action and Proposed Action LOS for Unsignalized Intersections - AM Peak Period ... M-109
Table M-48: No Action and Proposed Action LOS for Unsignalized Intersections - Midday Peak Period M-110
Table M-49: No Action and Proposed Action LOS for Unsignalized Intersections - PM Peak Period ... M-111
Table M-50: Projected Transit and Pedestrian Trips By Parcel for the Proposed Action M-112
Table M-51: 2022 With Action Subway Stairs Operations M-113
Table M-52: 2022 With Action Subway Turnstile Operations M-114
Table M-53: 2022 With Action Subway Line Haul Conditions M-115
Table M-54: 2022 With Action Corner and Crosswalk Level of Service Tables M-115
Table M-55: 2022 With-Action Sidewalk Level of Service Tables M-116
Table M-56: Proposed Action Parking Accumulation by Land Use M-117
Table M-57: Proposed Action Parking Accumulation M-118
Table M-58: Proposed Action Parking Utilization M-119

2.N AIR QUALITY

Table N-1: National and New York State Ambient Air Quality Standards and Monitored Values N-4
Table N-2: Monitored CO Values (ppm) N-6
Table N-3: Traffic Volume Increments for CO Screening Analysis N-8
Table N-4: $PM_{2.5}$ Screening Analysis N-12
Table N-5: Generic Pollutant Concentrations for Industrial Source Screen N-17
Table N-6: Eight-Hour Mobile Source CO (ppm), No Action Conditions N-18
Table N-7: No-Action PM_{10} Concentrations at E. 174th St./Boone Avenue (ug/m^3) N-18

Table N-8: No Action Conditions, PM_{10} at Cross Bronx Expressway (ug/m^3) N-19
Table N-9: Eight-Hour Mobile Source CO Concentrations (ppm), Action Conditions N-21
Table N-10: Action Conditions, PM10 at E. 174th St./Boone Avenue (ug/m^3) N-21
Table N-11: Action Conditions, PM2.5 at E. 174th St./Boone Avenue (ug/m^3) N-22
Table N-12: Action Conditions, PM10 at Cross Bronx Expressway (ug/m^3) N-22
Table N-13: Action Conditions, PM2.5 at Cross Bronx Expressway (ug/m^3) N-23
Table N-14: Proposed Parking Facilities N-23
Table N-15: CO Concentrations from Largest Garage N-26
Table N-16: Screening Analysis for Project on Project Impacts, Proposed Action N-37
Table N-17: HVAC AERMOD Modeling for 24-Hour SO_2 (µg/m^3), Proposed Action N-40
Table N-18: HVAC AERMOD Modeling for Annual NO_x (µg/m^3), Proposed Action N-43
Table N-19: HVAC AERMOD Cluster Modeling for 24-Hour SO_2 (µg/m^3), Proposed Action N-46
Table N-20: HVAC AERMOD Cluster Modeling for Annual NO2 (µg/m^3), Proposed Action N-46
TableN-21: Industrial Sites with Air Quality Permits N-48
Table N-22: Non-Criteria Pollutant Concentrations (µg/m^3) at 1743 West Farms Road Compared with NYSDEC Standards N-50
Table N-23: Restrictive Declarations and (E) Designations for Proposed Action N-50

2.O GREENHOUSE GAS EMISSIONS

Table O-1: Annual Operational GHG Emissions and Carbon Intensity O-4
Table O-2: Estimated Annual VMTs for the Proposed Action O-5
Table O-3: Estimated Annual Mobile Source GHG Emissions (in metric tons) O-6
Table O-4: Construction Carbon Calculator Inputs and Results O-8

2.P NOISE

Table P-1: Sound Pressure Level and Loudness of Typical Noises in Indoor & Outdoor Environments P-5
Table P-2: Noise Exposure Guidelines for Use in City Environmental Impact Review P-7
Table P-3: Required Attenuation Values to Achieve Acceptable Interior Noise Levels P-8
Table P-4: HUD Acceptability Standards for Noise P-9
Table P-5: Monitored Noise Levels (dBA) P-11
Table P-6: Intersection, Rail, and Highway Noise (dBA), No Action Conditions P-14
Table P-7: Mobile Source Noise Screen, 2022 Traffic Volumes P-16
Table P-8: Noise Levels (dBA), Future Conditions with the Proposed Action P-17

2.Q PUBLIC HEALTH

Table Q-1: Noise Exposure Guidelines for Use in City Environmental Impact Review Q-12
Table Q-2: Required Attenuation Values to Achieve Acceptable Interior Noise Levels Q-13

2.S CONSTRUCTION IMPACTS

Table S-1: Regulatory Framework in New York City S-6
Table S-2: Detailed Phasing Study S-16
Table S-3: Construction Activities by Building Type S-17
Table S-4: Construction Activity Analysis, By Cordon Line S-19
Table S-5: Analysis of Construction-Related and Project-Related Off-Peak Vehicular Trips Compared to Peak Hour Volumes for Build Conditions S-21
Table S-6: East 177th Street at the Sheridan Expressway Signal Timing Changes - AM S-26
Table S-7: East 177th Street at the Sheridan Expressway Signal Timing Changes - PM S-26
Table S-8: Westchester Avenue at Sheridan Expressway Service Road and Whitlock Avenue Signal Timing Changes S-28

Table S-9: Westchester Avenue at Sheridan Expressway Service Road and Sheridan Off-Ramp Signal Timing Changes S-29
Table S-10: West Farms Road at Longfellow Avenue and Home Street Signal Timing Changes S-29
Table S-11: West Farms Road at Freeman Street Signal Timing Changes S-30
Table S-12: Baseline Construction Traffic and Level-of-Service Analysis S-33
Table S-13: Parking Supply And Demand at the Peak Construction Cordon S-35
Table S-14: Comparison of Peak Construction Bus, Subway and Walk Trips With the Proposed Action Peak Periods S-36
Table S-15: Distribution of Employees' Vehicles for Air and Noise Cordons 8.1 and 8.2 ..... S-38
Table S-16: Average Hourly Truck Trips for Air and Noise Cordons 5 through 8.1 ..... S-39
Table S-17: On-Site Truck Trips and Diesel Equipment by Air and Noise Cordon S-42
Table S-18: Hourly Truck Trips and PCEs for Air and Noise Cordons 5 through 7 ..... S-46
Table S-19: Equipment Noise (Leq) by Construction Stage S-50
Table S-20: Duration of Leq Equipment Noise Levels > 62.0 dBA S-51
Table S-21: On-Site Diesel Equipment by Air and Noise Cordon S-52
Table S-22: Cumulative Construction Noise at Boone Avenue & E. 172nd Street, Air and Noise Cordons 4 – 12.1 ..... S-55
Table S-23: Cumulative Construction Noise at Southern Longfellow Ave., E. 172nd to E. 173rd Streets, S-56
Table S-24: Cumulative Construction Noise at, Northern Longfellow Ave., E. 172nd to E. 173rd Streets, ... S-57
Table S-25: Cumulative Construction Noise at Southern Longfellow Ave., E. 173rd to E. 174th Streets, Air and Noise Cordons 4 – 12.1 ..... S-58
Table S-26: Cumulative Construction Noise at E. 173rd Street, Boone Ave – West Farms Road, Air and Noise Cordons 4 – 12.1 ..... S-59
Table S-27: Cumulative Construction Noise at Parcel 2S, Air and Noise Cordons 4 – 12.1 ..... S-60
Table S-28: Cumulative Construction Noise at Longfellow Avenue, E. 173 – E. 174 Streets, Air and Noise Cordons 14 – 21 ..... S-61
Table S-29: Cumulative Construction Noise at Parcel 3A, Air and Noise Cordons 14 - 21 ..... S-62
Table S-30: Cumulative Construction Noise at Parcel 5E, Air and Noise Cordons 14 - 21 ..... S-63
Table S-31: Cumulative Construction Noise at Parcel 4A, Air and Noise Cordons 14 - 21 ..... S-64
Table S-32: Modeled Sources and Receivers S-66
Table S-33: RCNM Construction Noise Results S-70

3. MITIGATION OF PROJECT IMPACTS

Table 3-1: 2022 Future Elementary School Enrollment, Capacity, and Utilization with and without the New School 3-4
Table 3-3: 2022 Action Condition per the RWCDS: Water Demand and Effluent Flow 3-20
Table 3-4: Future Action Condition with School: Estimated Weekly Solid Waste Generation on Projected Development Parcels 3-21
Table 3-5: Future Action Condition per RWCDS: Estimated Weekly Solid Waste Generation on Projected Development Parcels 3-21
Table 3-6: Floor Area: Future Action Condition with School 3-22
Table 3-7: Floor Area: Future Action Condition per the RWCDS 3-22
Table 3-8: Annual Energy Consumption: Future Action Condition with School 3-22
Table 3-9: Annual Energy Consumption: Future Action Condition per the RWCDS 3-23
Table 3-10: 7:30-8:30 AM Student Trip Generation and Modal Split 3-24
Table 3-11: 7:30-8:30 AM Staff Trip Generation and Mode Split 3-24
Table 3-12: Comparison of Person Trips Generated by Mode for the Proposed Action with and without the New School 3-25

Table 3-13: Comparison of Vehicle Trips Generated by the Proposed Action with and without the School 3-25
Table 3-14: Level of Service Table Comparing No-Action, Proposed Action, and New School Mitigation, Signalized Intersections, AM Peak Period....3-51
Table 3-15: Level of Service Table Comparing No-Action, Proposed Action, and New School Mitigation, Signalized Intersections, Midday Peak Period....3-52
Table 3-16: Level of Service Table Comparing No-Action, Proposed Action, and New School Mitigation, Signalized Intersections, PM Peak Period....3-53
Table 3-17: Level of Service Table Comparing No-Action, Proposed Action, and New School Mitigation, Unsignalized Intersections, AM Peak Period....3-54
Table 3-20: LOS Table for Proposed Traffic Mitigation Measures for the New School Mitigation Scenario, Signalized Intersections, AM Peak Period....3-57
Table 3-21: LOS Table for Proposed Traffic Mitigation Measures for the New School Mitigation Scenario, Signalized Intersections, Midday Peak Period....3-58
Table 3-22: LOS Table for Proposed Traffic Mitigation Measures for the New School Mitigation Scenario, Signalized Intersections, PM Peak Period....3-59
Table 3-26: Proposed Traffic Mitigation Measures for the New School Mitigation Scenario, AM Peak Period....3-63
Table 3-27: Proposed Traffic Mitigation Measures for the New School Mitigation Scenario, Midday Peak Period....3-63
Table 3-28: Proposed Traffic Mitigation Measures for the New School Mitigation Scenario, PM Peak Period....3-64
Table 3-30: 2022 Proposed Action with School Sidewalk LOS Tables....3-67
Table 3-31: Reportable Accidents Occurring at Intersections near Proposed School....3-68
Table 3-32: Pedestrian and Bicycle Accidents Occurring at Intersections near Proposed School....3-68
Table 3-33: Traffic Volume Increments for CO Screen, New School Mitigation....3-70
Table 3-34: Eight-Hour Mobile Source CO Concentrations (ppm), New School Mitigation....3-71
Table 3-35: New School Mitigation, PM10 Concentrations (ug/m3)....3-71
Table 3-36: New School Mitigation, PM2.5 Concentrations (ug/m3)....3-72
Table 3-37: Future Action Conditions per School Mitigation Scenario: GHG Emission Summary....3-75
Table 3-38: School Mitigation: Annual Operational GHG Emissions and Carbon Intensity....3-76
Table 3-39: School Mitigation: Estimated Annual VMT....3-77
Table 3-40: School Mitigation: Estimated Annual Mobile Source GHG Emissions....3-78
Table 3-41: New School Mitigation: Construction Carbon Calculator Input and Results....3-79
Table 3-43: Total GHG Emissions: New School Mitigation Compared with RWCDS....3-80
Table 3-44: Comparison of Vehicular Volumes, No-Action and New School Mitigation Conditions....3-82
Table 3-45: Comparison of Noise Levels, No-Action and New School Mitigation Conditions....3-83
Table 3-46: Proposed Traffic Mitigation Measures – AM Peak Period....3-94
Table 3-47: Proposed Traffic Mitigation Measures – Midday Peak Period....3-94
Table 3-48: Proposed Traffic Mitigation Measures – PM Peak Period....3-95
Table 3-49: Level of Service Table for Proposed Traffic Mitigation Measures Signalized Intersections – AM Peak Period....3-96
Table 3-50: Level of Service Table for Proposed Traffic Mitigation Measures Signalized Intersections – MD Peak Period....3-97
Table 3-51: Level of Service Table for Proposed Traffic Mitigation Measures Signalized Intersections – PM Peak Period....3-98
Table 3-52: Level of Service Table for Proposed Traffic Mitigation Measures Unsignalized Intersections – AM Peak Period....3-99
Table 3-53: Level of Service Table for Proposed Traffic Mitigation Measures Unsignalized Intersections – Midday Peak Period....3-100

Table 3-54: Level of Service Table for Proposed Traffic Mitigation Measures Unsignalized Intersections – PM Peak Period.....3-101

5. ALTERNATIVES TO THE PROPOSED ACTION

Table 5-1: 2022 Sub-district 2 Elementary School Enrollment, Capacity, and Utilization Data.....5-7
Table 5-2: East 177th Street at the Sheridan Expressway Signal Timing Changes - AM.....5-12
Table 5-3: East 177th Street at the Sheridan Expressway Signal Timing Changes - Midday.....5-13
Table 5-4: East 177th Street at the Sheridan Expressway Signal Timing Changes - PM.....5-13
Table 5-5: Westchester Avenue at Sheridan Expressway Service Road and Whitlock Avenue Signal Timing Changes.....5-15
Table 5-6: Westchester Avenue at Sheridan Expressway Service Road and Sheridan Off-Ramp Signal Timing Changes.....5-16
Table 5-7: West Farms Road at Longfellow Avenue and Home Street Signal Timing Changes.....5-17
Table 5-8: West Farms Road at Freeman Street Signal Timing Changes.....5-17
Table 5-9: Number of Approach Movements with Substandard Level of Service in No-Action Conditions.....5-19
Table 5-10: Number of Approach Movements with Substandard Level of Service in No-Action Conditions.....5-20
Table 5-11: Comparison of Noise Levels (dBA) under the No-Action Alternative and the Proposed Action.....5-22
Table 5-12: Reasonable Worst Case Development Scenarios, Proposed Action vs. Lesser Density Alternative.....5-30
Table 5-13: 2022 Sub-district 2 Elementary School Enrollment, Capacity, and Utilization Data.....5-39
Table 5-14: Comparison of Person Trips Generated by the Proposed Project and the Lesser Density Alternative.....5-43
Table 5-15: Comparison of Vehicular Trips Generated by the Proposed Project and the Lesser Density Alternative.....5-44
Table 5-16: Summary of Impacted Intersections under the Proposed Action.....5-44
Table 5-17: Restrictive Declarations and (E) Designations for the Lesser Density Alternative.....5-46

List of Figures

EXECUTIVE SUMMARY
Figure ES-1: Development Parcels and Proposed Rezoning ES-2
Figure ES-2: Existing and Proposed Zoning ES-7
Figure ES-4: LSGD Buildings and Building 4 - Boone Avenue Massing Diagram ES-12
Figure ES-5: Buildings 3A, 3B and 3C -- Boone Avenue Rendering (without School) ES-14
Figure ES-6: Buildings 5 and 6 - Illustrative Site Plan ES-19
Figure ES-7: Buildings 5 and 6 - Conceptual Massing Diagram ES-20
Figure ES-8: Building 6 - Rendering ES-21
Figure ES-9: LSGD Buildings - Proposed Lot Coverage Waivers ES-24
Figure ES-10: Delineation of Projected and Potential Development Sites ES-39

1. PROJECT DESCRIPTION
Figure 1-1: Development Parcels and Proposed Rezoning 1-2
Figure 1-2: Existing and Proposed Zoning 1-8
Figure 1-3: LSGD Buildings - Site Plan 1-16
Figure 1-4: LSGD Buildings -- Boone Avenue Elevation 1-17
Figure 1-5: LSGD Buildings and Building 4 - Boone Avenue Massing Diagram 1-19
Figure 1-6: Buildings 3A, 3B and 3C -- Boone Avenue Rendering (without School) 1-21
Figure 1-7: Buildings 5 and 6 - Illustrative Site Plan 1-28
Figure 1-8: Buildings 5 and 6 - West Farms Road Elevation 1-29
Figure 1-9: Buildings 5 and 6 - Conceptual Massing Diagram 1-30
Figure 1-10: Building 6 - Rendering 1-31
Figure 1-11: Anticipated Construction Sequencing for the Proposed Project 1-33
Figure 1-12: LSGD Buildings - Proposed Lot Coverage Waivers 1-35
Figure 1-13: Delineation of Projected and Potential Development Sites 1-50

2.A LAND USE, ZONING, AND PUBLIC POLICY
Figure A-1: Land Use, Zoning, and Public Policy Study Areas A-2
Figure A-2: Existing Land Use A-4
Figure A-3: Existing Zoning A-5
Figure A-4: Existing and Proposed Zoning A-7
Figure A-5: No Build Projects A-18
Figure A-6: Delineation of Projected and Potential Development Sites A-21
Figure A-7: Coastal Boundary of New York A-31

2.B SOCIOECONOMIC CONDITIONS
Figure B-1: Proposed Rezoning Area B-5
Figure B-2: Socioeconomic Study Area B-6
Figure B-3: Zip Codes 10459 and 1046 ..... B-8
Figure B-4: Median Household Income in 1999 ..... B-42
Figure B-5: Poverty Rates in 1999 ..... B-43
Figure B-6: Median Contract Rents in 2000 ..... B-50
Figure B-7: Median Gross Rents in 2000 ..... B-51
Figure B-8: Median Gross Rent as a Percentage of Income B-52
Figure B-9: NYCHA Public Housing B-54
Figure B-10: Section 202 Housing B-56
Figure B-11: Mitchell-Lama Housing B-58

Figure B-12: Recent Income Limited and Supportive Housing B-59
Figure B-13: Phipps, MBD, HELP, and Unique People Services Housing B-61
Figure B-14: Census Tracts where the Percentage of Unprotected Rental Units is Very Low B-68
Figure B-15: Census Tracts where the Average Incomes of Renters in Small Buildings are Higher Than Those of Bronx Rental Households B-71
Figure B-16: Census Tracts with At-Risk Population B-74

2.C COMMUNITY FACILITIES AND SERVICES

Figure C-1: Libraries C-9
Figure C-2: Existing Public Elementary and Intermediate Schools C-12
Figure C-3 : Public High Schools C-18
Figure C-4: Publicly Funded Child Care Program Locations C-22
Figure C-5: Police, Fire, and Emergency Medical Services C-24

2.D OPEN SPACE

Figure D-1: Open Space Study Areas D-5
Figure D-2: Open Space Resources D-14

2.E SHADOWS

Figure E-1: Preliminary Screening Analysis E-27
Figure E-2: Shadow Study, March 21/September 21 (Spring/Fall Equinox) - 8:30 AM E-28
Figure E-3: Shadow Study, March 21/September 21 (Spring/Fall Equinox) - 10:30 AM E-28
Figure E-4: Shadow Study, March 21/September 21 (Spring/Fall Equinox) – 12 PM E-29
Figure E-5: Shadow Study, March 21/September 21 (Spring/Fall Equinox) – 3:15 PM E-29
Figure E-6: Shadow Study, March 21/September 21 (Spring/Fall Equinox) – 3:59 PM E-30
Figure E-7: Shadow Study, March 21/September 21 (Spring/Fall Equinox) – 4:25 PM E-30
Figure E-8: Shadow Study, March 21/September 21 (Spring/Fall Equinox) – 4:39 PM E-31
Figure E-9: Shadow Study, March 21/September 21 (Spring/Fall Equinox) – 5:39 PM E-31
Figure E-10: Shadow Study, May 6/August 6- 7:19 AM E-32
Figure E-11: Shadow Study, May 6/August 6- 11:45 AM E-32
Figure E-12: Shadow Study, May 6/August 6- 12:00 PM E-33
Figure E-13: Shadow Study, May 6/August 6- 3:00 PM E-33
Figure E-14: Shadow Study, May 6/August 6- 3:40 PM E-34
Figure E-15: Shadow Study, May 6/August 6- 4:55 PM E-34
Figure E-16: Shadow Study, May 6/August 6- 5:00 PM E-35
Figure E-17: Shadow Study, May 6/August 6- 6:26 PM E-35
Figure E-18: Shadow Study, June 21 (Summer Solstice)- 7:00 AM E-36
Figure E-19: Shadow Study, June 21 (Summer Solstice)- 7:45 AM E-36
Figure E-20: Shadow Study, June 21 (Summer Solstice)- 12:00 PM E-37
Figure E-21: Shadow Study, June 21 (Summer Solstice)- 12:45 PM E-37
Figure E-22: Shadow Study, June 21 (Summer Solstice)- 3:00 PM E-38
Figure E-23: Shadow Study, June 21 (Summer Solstice)- 3:45 PM E-38
Figure E-24: Shadow Study, June 21 (Summer Solstice)- 5:15 PM E-39
Figure E-25: Shadow Study, June 21 (Summer Solstice)- 5:30 PM E-39
Figure E-26: Shadow Study, June 21 (Summer Solstice)- 7:00 PM E-40
Figure E-27: Shadow Study, December 21 (Winter Solstice)- 8:45 AM E-41
Figure E-28: Shadow Study, December 21 (Winter Solstice)- 9:30 AM E-41
Figure E-29: Shadow Study, December 21 (Winter Solstice)- 12:00 PM E-42
Figure E-30: Shadow Study, December 21 (Winter Solstice)- 2:10 PM E-42
Figure E-31: Shadow Study, December 21 (Winter Solstice)- 3:00 PM E-43

Figure E-32: Shadow Study, March 21/September 21 (Spring/Fall Equinox)- 5:35 PM E-44
Figure E-33: Shadow Study, March 21/September 21 (Spring/Fall Equinox)- 5:39 PM E-44
Figure E-34: Shadow Study, June 21 (Summer Solstice)- 6:55 PM E-45
Figure E-35: Shadow Study, June 21 (Summer Solstice)- 7:00 PM E-45
Figure E-36: Shadow Study for Existing NYCHA Buildings east Bronx River - March 21/September 21 - 8:30 AM E-46
Figure E-37: Shadow Study for Existing NYCHA Buildings east Bronx River - May 6/August 6 – 7:19 AM E-47
Figure E-38: Shadow Study for Existing NYCHA Buildings east Bronx River – June 21 – 7:00 AM. E-48
Figure E-39: Shadow Study for Existing NYCHA Buildings east Bronx River – December 21 – 8:45 AM E-49
Figure E-40: Shadow Study for Existing NYCHA Buildings east Bronx River – December 21 – 10:15 AM E-50

2.F HISTORIC AND CULTURAL RESOURCES

Figure F-1: 400 Foot Study Area F-3
Figure F-2: Approximate Locations of Potential Archaeological Sensitivity F-10

2.G URBAN DESIGN AND VISUAL RESOURCES

Figure G-1: Aerial Photograph of Proposed Rezoning & Study Area G-3
Figure G-2: Existing and Proposed Zoning G-32
Figure G-3: Illustrative Bulk Diagrams G-33
Figure G-4: Proposed and Projected Development Sites G-44
Figure G-5: Massing Diagram for Southern Applicant Development Sites (GLSD) G-45
Figure G-6: Southern Applicant Development Sites (LSGD) Elevations and Perspectives G-48
Figure G-7: LSGD Site Plan - Jennings St. to East 173rd St. G-52
Figure G-8: Massing Diagrams for Northern Development Sites G-55
Figure G-9: Elevation for Northern Applicant Sites G-57
Figure G-10: Site Plan - North of Cross Bronx Expressway G-60
Figure G-11: Streetscape Representations G-61

2.H NATURAL RESOURCES

Figure H-1: Natural Resource Study Area H-3

2.I HAZARDOUS MATERIALS

Figure I-1: Block and Lot Numbers I-5

2.J WATER AND SEWER INFRASTRUCTURE

Figure J-1: Subcatchment Areas J-5

2.M TRANSPORTATION

Figure M-1: Crotona Park Traffic Study Area and Study Intersections M-8
Figure M-2: Existing AM Traffic Volume Network M-18
Figure M-3: Existing Midday Traffic Volume Network M-22
Figure M-4: Existing PM Traffic Volume Networks M-24
Figure M-5: Pedestrian Element Analysis Locations M-33
Figure M-6: Existing Parking Regulation Map M-39
Figure M-7: Projects to be Completed by 2022 ..... M-45
Figure M-8: No Action AM Traffic Volume Network M-54
Figure M-9: No Action MD Traffic Volume Network M-57

Figure M-10: No Action PM Traffic Volume Network M-59
Figue M-11: AM Project Generated M-78
Figure M-12: Midday Project Generated Vehicle Trips M-82
Figure M-13: PM Project Generated Vehicle Trips M-86
Figure M-14: Proposed Action AM Traffic Network M-90
Figure M-15: Proposed Action Midday Traffic Volume Network M-94
Figure M-16: Proposed Action PM Traffic Volume Network M-98

2.N AIR QUALITY

Figure N-1: Intersections Modeled for CO N-9
Figure N-2: Delineation of Projected and Potential Development Sites N-20
Figure N-3: Parking Facility Layout, Building 1 ..... N-25
Figure N-4: 400- and 1,000- foot Radii from Rezoning Boundaries N-27
Figure N-5: Locations of Boiler Permits with $\geq$ 20 million BTU N-28
Figure N-6: Blocks 3013, 3014, & 3009 ..... N-30
Figure N-7: Blocks 3013, 3014, & 3009 ..... N-31
Figure N-8: Blocks 3015, 3010 & 2998 ..... N-32
Figure N-9: Blocks 3015, 3010 & 2998 ..... N-33
Figure N-10: Block 3016 ..... N-34
Figure N-11: Block 3016 ..... N-35
Figure N-12: Sites with Operating Permits for Processes N-48

2.P NOISE

Figure P-1: Traffic Noise Monitoring Locations P-10
Figure P-2: Rail and Elevated Highway Noise Monitoring Locations (Northern End of the Proposed Rezoning Area) P-12
Figure P-3: Rail Noise Monitoring Locations (Southern End of Rezoning Area) P-13
Figure P-4: Elevated Rail Noise at West Farms Sq. and E. Tremont Ave. subway platform P-13
Figure P-5: Playground Location at Parcel 2 South P-20
Figure P-6: Blocks 3013, 3014, & 3009 ..... P-29
Figure P-7: Blocks 3013, 3014, & 3009 ..... P-30
Figure P-8: Blocks 3015, 3010 & 2998 ..... P-31
Figure P-9: Blocks 3015, 3010 & 2998 ..... P-32
Figure P-10: Block 3016 ..... P-33
Figure P-11: Block 3016 ..... P-34

2.R NEIGHBORHOOD CHARACTER

Figure R-1: Neighborhood Character Study Area R-3

2.S CONSTRUCTION IMPACTS

Figure S-1: Projected Development by Building Type S-8

3. MITIGATION OF PROJECT IMPACTS

Figure 3-1: New School Location 3-3
Figure 3-4: AM Project with School Mitigation Generated Vehicle Trips 3-26
Figure 3-5: Midday Project with School Mitigation Generated Vehicle Trips 3-30
Figure 3-6: PM Project with School Mitigation Generated Vehicle Trips 3-34
Figure 3-7: Proposed Action with School Mitigation AM Traffic Volume Network 3-38
Figure 3-8: Proposed Action with School Mitigation Midday Traffic Volume Network 3-42
Figure 3-9: Proposed Action with School Mitigation PM Traffic Volume Network 3-46

Figure 3-10: Buildings 3A, 3B and 3C with and without the School 3-73

5. ALTERNATIVES TO THE PROPOSED ACTION
Figure 5-1: Proposed Action and Lower Density Alternative Zoning.....5-28
Figure 5-2: Massing of the Lesser Density Alternative Applicant Properties 5-33
Figure 5-3: Massing of the Lesser Density Alternative North of the Cross Bronx Expressway 5-36