625 WEST 57TH STREET



DRAFT SUPPLEMENTAL ENVIRONMENTAL IMPACT STATEMENT

CEQR No: 12DCP020M

Lead Agency:
City Planning Commission, City of New York
Amanda M. Burden, FAICP, Chair

Preparers:
AKRF, Inc.
Philip Habib & Associates

July 11, 2012

625 WEST 57TH STREET
DRAFT SUPPLEMENTAL ENVIRONMENTAL IMPACT STATEMENT (DSEIS)

Project Location:	Community District 4 Borough of Manhattan
CEQR No.	12DCP020M
Type of Action:	Unlisted
ULURP Nos.	120396 ZMM, 120397 ZSM, 120398 ZSM, 010151(B) ZSM, 010148(A) ZMM
Lead Agency:	New York City Planning Commission
Lead Agency Contact:	Robert Dobruskin, Director, Department of City Planning—Environmental Assessment and Review Division
Project Applicant:	Durst Development LLC
Preparers:	AKRF, Inc. 440 Park Avenue South New York, NY 10016 Philip Habib & Associates 102 Madison Avenue, 11th Floor New York, NY 10016
Acceptance Date:	July 11, 2012

The DSEIS is available for review on the website of the Department of City Planning.
http://www.nyc.gov/dcp

A public hearing on the Draft Supplemental Environmental Impact Statement (DSEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

Table of Contents

Executive Summary **S-1**

1: Project Description **1-1**
A. Project Identification 1-1
B. Project Description 1-2
History of the Project Block 1-2
Proposed Project 1-4
Proposed Actions 1-6
C. Project Purpose and Need 1-7
Goals and Objectives of the Proposed Project 1-7
D. Analysis Framework for Environmental Review 1-8
The Future Without the Proposed Project 1-9
E. Environmental Review 1-10
Uniform Land Use Review Procedure 1-10
Environmental Review 1-10

2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
Principal Conclusions 2-1
B. Summary of 2001 FEIS Findings 2-2
C. Methodology 2-3
D. Development History 2-3
Study Area 2-3
Project Block 2-4
E. Existing Conditions 2-5
Land Use 2-5
Zoning 2-7
Public Policy 2-10
F. The Future Without the Proposed Project 2-12
Land Use 2-12
Zoning 2-15
Public Policy 2-15
G. Probable Impacts of the Proposed Project 2-15
Land Use 2-16
Zoning 2-17
Public Policy 2-18

3: Socioeconomic Conditions **3-1**
A. Introduction 3-1
Principal Conclusions 3-1

B. Summary of 2001 FEIS Findings 3-2
C. Analytical Framework 3-3
D. Methodology 3-4
Determining Whether A Socioeconomic Assessment Is Appropriate 3-4
Analysis Format 3-5
Study Area Delineation 3-5
Data Sources 3-6
E. Preliminary Assessment 3-6
Direct Residential Displacement 3-6
Direct Business Displacement 3-6
Indirect Residential Displacement 3-6
Indirect Business Displacement 3-9
Adverse Effects On Specific Industries 3-10

4: Community Facilities and Services 4-1
A. Introduction 4-1
Principal Conclusions 4-1
B. Summary of 2001 FEIS Findings 4-2
C. Analytical Framework 4-2
D. Preliminary Screening 4-3
Direct Effects 4-3
Indirect Effects 4-3
E. Public Elementary and Intermediate Schools 4-5
Methodology 4-5
Existing Conditions 4-6
The Future Without the Proposed Project 4-7
Probable Impacts of the Proposed Project 4-8

5: Open Space 5-1
A. Introduction 5-1
Principal Conclusions 5-1
B. Summary of 2001 FEIS Findings 5-2
C. Methodology 5-2
Analytical Framework 5-2
Direct Effects Analysis 5-2
Indirect Effects Analysis 5-3
D. Preliminary Assessment 5-6
Existing Conditions 5-6
Study Area Open Spaces 5-6
Adequacy of Open Space Resources 5-11
E. The Future Without the Proposed Project 5-11
Study Area Population 5-11
Study Area Open Spaces 5-12
Adequacy of Open Space Resources 5-13
F. Probable Impacts of the Proposed Project 5-13
Direct Effects 5-13
Study Area Population 5-13
Study Area Open Spaces 5-13

Adequacy of Open Space Resources 5-14
G. Conclusion 5-15

6: Shadows 6-1
A. Introduction 6-1
Principal Conclusions 6-2
B. Summary of 2001 FEIS Findings 6-2
C. Definitions and Methodology 6-2
Analytical Framework 6-2
Definitions 6-3
Methodology 6-4
D. Preliminary Assessment 6-4
Tier 1 Screening Assessment 6-4
Tier 2 Screening Assessment 6-5
Tier 3 Screening Assessment 6-5
E. Detailed Analysis 6-6
Open Space Resources of Concern 6-7
Natural Resources of Concern 6-7
March 21/September 21 (Figures 6-4 and 6-5) 6-8
May 6/August 6 (Figures 6-6 and 6-7) 6-9
June 21 (Figures 6-8 and 6-9) 6-9
December 21 (Figures 6-10 to 6-17) 6-9
F. Conclusion 6-9

7: Historic and Cultural Resources 7-1
A. Introduction 7-1
Principal Conclusions 7-1
B. Summary of 2001 FEIS Findings 7-1
C. Methodology 7-2
Analytical Framework 7-2
Architectural Resources 7-2
D. Development History 7-3
E. Existing Conditions 7-4
Architectural Resources 7-4
F. The Future Without the Proposed Project 7-5
Project Site 7-5
Study Area 7-5
G. Probable Impacts of the Proposed Project 7-6
Architectural Resources 7-6

8: Urban Design and Visual Resources 8-1
A. Introduction 8-1
Principal Conclusions 8-1
B. Summary of 2001 FEIS Findings 8-1
C. Preliminary Assessment 8-2
D. Analytical Framework 8-3
E. Methodology 8-3
F. Existing Conditions 8-4

Urban Design 8-4
Visual Resources 8-8
G. The Future Without the Proposed Project 8-10
Projected Development Sites 8-10
Study Area 8-10
H. Probable Impacts of the Proposed Project 8-10
Urban Design 8-10
Visual Resources 8-13

9: Hazardous Materials 9-1
A. Introduction 9-1
Principal Conclusions 9-1
B. Summary of 2001 FEIS Findings 9-1
Topography, Geology and Groundwater 9-2
Potential for Site Contamination 9-2
Subsurface Investigation 9-2
Probable Impacts 9-3
C. Changes to Existing Conditions Since 2001 FEIS 9-3
Projected Development Site 1 9-3
Projected Development Site 2 9-5
D. The Future Without the Proposed Project 9-5
E. Probable Impacts of the Proposed Project 9-6

10: Transportation 10-1
A. Introduction 10-1
Principal Conclusions 10-2
B. Summary of 2001 FEIS Findings 10-2
Vehicular Traffic 10-2
Parking 10-3
Pedestrians 10-3
C. Analytical Framework 10-3
D. Methodology 10-3
E. Existing Conditions 10-4
Vehicular Traffic 10-4
Capacity Analysis 10-5
Pedestrians 10-6
F. The Future Without the Proposed Project 10-8
Vehicular Traffic 10-8
Parking 10-9
Pedestrians 10-9
G. Probable Impacts of the Proposed Project 10-9
Access and Circulation 10-10
Transportation Planning Assumption and Demand Forecasts 10-10
Vehicle Trip Assignment and Capacity Analysis 10-11
Traffic Safety 10-12
Parking 10-12
H. Conclusion 10-14

11: Air Quality 11-1
A. Introduction 11-1
Principal Conclusions 11-1
B. Summary of 2001 FEIS Findings 11-4
C. Pollutants for Analysis 11-4
Carbon Monoxide 11-4
Nitrogen Oxides, VOCs, and Ozone 11-5
Lead 11-5
Respirable Particulate Matter—PM_{10} and $PM_{2.5}$ 11-6
Sulfur Dioxide 11-6
Air Toxics 11-7
D. Air Quality Standards, Regulations and Benchmarks 11-7
National and State Air Quality Standards 11-7
NAAQS Attainment Status and State Implementation Plans 11-9
Determining the Significance of Air Quality Impacts 11-10
E. Methodology for Predicting Pollutant Concentrations 11-12
Introduction 11-12
Mobile Sources 11-12
Stationary Sources 11-13
F. Existing Conditions 11-23
G. The Future Without the Proposed Project 11-24
H. Probable Impacts of the Proposed Project 11-24
Mobile Sources 11-24
Stationary Sources 11-25

12: Greenhouse Gas Emissions and Climate Change 12-1
A. Introduction 12-1
Principal Conclusions 12-1
B. Summary of 2001 FEIS Findings 12-2
C. Pollutants of Concern 12-2
D. Policy, Regulations, Standards, and Benchmarks 12-3
E. Methodology 12-5
Building Operational Emissions 12-5
Mobile Source Emissions 12-6
Construction Emissions 12-7
Emissions from Solid Waste Management 12-7
F. Probable Impacts of the Proposed Project 12-8
Greenhouse Gas Emissions 12-8
Assessment of Consistency With the GHG Reduction Goal 12-10
G. Probable Impacts of Climate Change On the Proposed Project 12-12

13: Noise 13-1
A. Introduction 13-1
Principal Conclusions 13-1
B. Summary of 2001 FEIS Findings 13-1
C. New York CEQR Noise Standards 13-1
D. Existing Noise Levels 13-2
E. The Future Without the Proposed Project 13-2

F. Probable Impacts of the Proposed Project 13-2
Noise Attenuation Measures 13-2

14: Public Health 14-1
A. Introduction and Screening Analysis 14-1
B. Summary of 2001 FEIS Findings 14-1

15: Neighborhood Character 15-1
A. Introduction 15-1
Principal Conclusions 15-1
B. Summary of 2001 FEIS Findings 15-2
C. Analytical Framework 15-3
D. Methodology 15-3
Neighborhood Character Components 15-3
Study Area 15-4
E. Existing Conditions 15-4
Project Block 15-5
Study Area 15-5
F. The Future Without the Proposed Project 15-7
Project Block 15-7
Study Area 15-7
G. Probable Impacts of the Proposed Project 15-7
Project Block 15-7
Study Area 15-8
H. Conclusion 15-10

16: Construction 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Summary of 2001 FEIS Findings 16-5
C. Construction Phasing and Activities 16-5
Introduction 16-5
Construction Phasing and Schedule 16-5
Construction Methods and Activities 16-6
General Construction Practices 16-9
Construction Workers and Deliveries 16-12
D. The Future Without the Proposed Project 16-14
E. Probable Impacts of the Proposed Project 16-14
Transportation 16-14
Air Quality 16-18
Noise and Vibration 16-21
Other Technical Areas 16-29
F. Conclusion 16-30

17: Alternatives 17-1
A. Introduction 17-1
B. Summary of 2001 FEIS Findings 17-1
C. No Action Alternative 17-1

Land Use, Zoning and Public Policy 17-2
Socioeconomic Conditions 17-2
Community Facilities and Services 17-3
Open Space 17-4
Shadows 17-4
Historic and Cultural Resources 17-4
Urban Design and Visual Resources 17-4
Hazardous Materials 17-5
Transportation 17-5
Air Quality 17-6
Greenhouse Gas Emissions 17-6
Noise 17-6
Public Health 17-7
Neighborhood Character 17-7
Construction Impacts 17-7
D. No Impact Alternative 17-8
Open or Louvered Design At the Top of the Building Options 17-8
Reduced Height Building 17-9

18: Growth-Inducing Aspects of the Proposed Actions 18-1

19: Irreversible and Irretrievable Commitment of Resources 19-1

20: Mitigation 20-1
A. Introduction 20-1
Principal Conclusions 20-1
B. Air Quality 20-1
Overview 20-1
Refined Analysis 20-2
Proposed Mitigation Measures 20-2

Appendices (CD-only)

Appendix A, "Agency Correspondence"

Appendix B, "Noise"

List of Tables

S-1 Proposed Project Development Program S-5

S-2 Permitted Building Program..... S-9

S-3 Building Attenuation Requirements..... S-19

1-1 Proposed Project Development Program 1-5

1-2 Permitted Building Program.....1-9

2-1 Zoning Districts in the Study Area.....2-8

2-2 Permitted Building Program.....2-13

2-3 Projects Under Construction or Proposed Within and Adjacent to the 1/4-Mile Study Area 2-14

3-1 Median Household Income (1999, 2004-2009) 3-7

3-2 2000 and 2010 Population.....3-9

4-1 Indirect Effects Analysis - Preliminary Screening Analysis Criteria 4-4

4-2 Public Schools Serving the Proposed Project, Enrollment and Capacity Data, 2010-2011 School Year.....4-6

4-3 Projected New Housing Units and Estimated Number of Students Introduced By Development in the Future Without the Proposed Project.....4-7

4-4 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization: 2015 Future Without the Proposed Project 4-8

4-5 Estimated Number of Students Introduced in the Study Areas: 2015 Future With the Proposed Project.....4-8

4-6 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization: 2015 Future With the Proposed Project 4-9

5-1 Existing Residential Population 5-6

5-2 Open Space Resources Within Residential Study Area 5-7

5-3 Open Space Resources Nearby Residential Study Area.....5-10

5-4 Existing Conditions: Adequacy of Open Space Resources.....5-11

5-5 Future Without the Proposed Project: Changes to Open Space Resources.....5-12

5-6 Future Without the Proposed Project: Adequacy of Open Space Resources 5-13

5-7 Future With the Proposed Project: Adequacy of Open Space Resources 5-14

5-8 Future With the Proposed Project: Open Space Ratios Summary 5-14

10-1 Intersection Level of Service Criteria 10-5

10-2 2011 Existing Traffic Levels of Service ..... *following* 10-6

10-3 Sidewalk Level of Service Criteria 10-7

10-4 Corner and Crosswalk Level of Service Criteria 10-7

10-5 2011 Existing Sidewalk Conditions ..... *following* 10-8

10-6 2011 Existing Corner and Crosswalk Conditions ..... *following* 10-8

10-7 2015 Future Without the Proposed Project Traffic Levels of Service ..... *following* 10-10

10-8 Weekday Future Without the Proposed Project Parking Accumulation ..... *following* 10-10

10-9 Saturday Future Without the Proposed Project Parking Accumulation ..... *following* 10-10

10-10 2015 Future Without the Proposed Project Sidewalk Conditions ..... *following* 10-10

10-11 2015 Future Without the Proposed Project Corner and Crosswalk Conditions *following* 10-10

10-12 Transportation Planning Assumptions Future With the Proposed Project Scenario ..... *following* 10-10

10-13 Transportation Demand Forecast Future With the Proposed Project Scenario ..... *following* 10-10

10-14 2015 Future With the Proposed Project Traffic Levels of Service ..... *following* 10-12

10-15 Weekday Future With the Proposed Project Parking Accumulation ..... *following* 10-12

10-16 Saturday Future With the Proposed Project Parking Accumulation ..... *following* 10-12

10-17 Significant Pedestrian Impact Criteria in CBD District ..... *following* 10-14

10-18 2015 Future With the Proposed Project Sidewalk Conditions ..... *following* 10-14

10-19 2015 Future With the Proposed Project Corner and Crosswalk Conditions ..... *following* 10-14

11-1 National Ambient Air Quality Standards (NAAQS) 11-8

11-2 Estimated HVAC Emissions from the Proposed Project 11-14

11-3 Maximum Background Pollutant Concentrations for Stationary Source Analysis 11-17

11-4 Con Edison Plant Stack Parameters and Emission Rates (g/Sec) 11-22

11-5 Representative Monitored Ambient Air Quality Data 11-23

11-6 Future Maximum NO_2 and PM_{10} Concentrations from the Proposed Project's HVAC Sources (in $\mu g/m^3$) 11-25

11-7 Maximum Predicted $PM_{2.5}$ Annual Average Concentrations from the Proposed Project's HVAC Sources (in $\mu g/m^3$) 11-25

11-8 Magnitude, Frequency and Location of 24-Hour $PM_{2.5}$ Impacts > 2 $\mu g/m^3$ from the Proposed Project 11-26

11-9 Maximum Predicted Impacts from Industrial Sources 11-28

11-10 Future Maximum Predicted Concentrations on the Proposed Project from the Consolidated Edison Power House (in μg/m^3) 11-29

11-11 Future Maximum Predicted $PM_{2.5}$ Annual Average Increments on the Proposed Project from the Consolidated Edison Power House (in μg/m^3) 11-29

11-12 Magnitude, Frequency and Location of 24-Hour $PM_{2.5}$ Impacts > 2 μg/m^3 on the Proposed Project from the Consolidated Edison Power House 11-30

11-13 Future Maximum Predicted Concentrations from the Consolidated Edison Power House on Developments Within 400 Feet of the Proposed Project (in μg/m^3) 11-32

11-14 Future Maximum Predicted $PM_{2.5}$ Increments from the Consolidated Edison Power House On Developments Within 400 Feet of the Proposed Project (in μg/m^3) 11-32

11-15 Potential Impacts from the Consolidated Edison Power House on Developments Within 400 feet of the Proposed Project (in μg/m^3) 11-32

12-1 Global Warming Potential (GWP) for Major GHGs 12-3

12-2 Annual Trips (Vehicle-Trip/Year) 12-7

12-3 Total Distances Traveled (VMT/Year) 12-7

12-4 GHG Emissions—Mixed-Use Building (On Projected Development Site 1) 12-8

12-5 GHG Emissions—Midblock Community Facility and Mini-Storage Conversion Buildings 12-8

12-6 Mobile Source Emissions (Metric Tons CO_2e) 12-9

12-7 Summary of Annual GHG Emissions 2015 (Metric Tons CO_2e) 12-9

13-1 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 13-1

13-2 Existing Noise Levels (in dBA) 13-2

13-3 Building Attenuation Requirements 13-3

16-1 Construction Oversight in New York City 16-10

16-2 Average Daily Construction Workers and Delivery Trucks 16-13

16-3 Average Peak Hour Construction Vehicle Trips in PCEs (Quarterly) 16-16

16-4 Incremental Peak Hour Construction Vehicle Trips in PCEs 16-16

16-5 Peak Hour Construction Person Trip Projections 16-17

16-6 Typical Construction Equipment Noise Emission Levels (dBA) 16-24

16-7 Construction Equipment Noise Screening Results (in dBA) 16-26

16-8 Vibration Source Levels for Construction Equipment 16-28

17-1 Future Maximum Predicted Concentrations from the Consolidated Edison Power House on Developments Within 400 feet of the Proposed Project Reduced Height Building (μg/m^3) 17-9

17-2 Future Maximum Predicted $PM_{2.5}$ Increments from the Consolidated Edison Power House on Developments Within 400 feet of the Proposed Project Reduced Building Height 17-10

20-1 Future Maximum Predicted Concentrations from the Consolidated Edison Power House On Developments Within 400 Feet of the Proposed Project Reduced Building Height ($\mu g/m^3$) 20-3

20-2 Future Maximum Predicted $PM_{2.5}$ Increments from the Consolidated Edison Power House On Developments Within 400 Feet of the Proposed Project Reduced Building Height ($\mu g/m^3$) 20-4

List of Figures

following page

S-1 Project Location S-2
S-2 Proposed Zoning S-2
S-3 Previously Approved Project-Site Plan S-2
S-4 Existing Zoning S-4
S-5 Project Block Aerial Photo S-4
S-6a Projected Development Site 1 Ground-Floor Plan S-6
S-6b Projected Development Site 1 Mezzanine Plan S-6
S-7a Projected Development Site 1 North Elevation S-6
S-7b Projected Development Site 1 South Elevation S-6
S-8 Projected Development Site 1 - Section S-6
S-9 Projected Development Site 2 Building Section S-6
S-10 Projected Development Site 2 Illustrative Ground-Floor Plan S-6
S-11 Minimum Distance Between Buildings Diagram S-8
S-12 Tower Regulations Isometric Diagram S-8
S-13 Permitted Building Ground Floor Plan S-10
S-14 Permitted Building Elevation S-10
1-1 Project Location 1-2
1-2 Proposed Zoning 1-2
1-3 Previously Approved Project-Site Plan 1-2
1-4 Existing Zoning 1-4
1-5 Project Block Aerial Photo 1-4
1-6a Projected Development Site 1 Ground-Floor Plan 1-6
1-6b Projected Development Site 1 Mezzanine Plan 1-6
1-7a Projected Development Site 1 North Elevation 1-6
1-7b Projected Development Site 1 South Elevation 1-6
1-8 Projected Development Site 1 - Section 1-6
1-9 Projected Development Site 2 Building Section 1-6

1-10 Projected Development Site 2 Ground-Floor Plan 1-6
1-11 Minimum Distance Between Buildings Diagram 1-8
1-12 Tower Regulations Isometric Diagram 1-8
1-13 Permitted Building Ground Floor Plan 1-10
1-14 Permitted Building Elevation 1-10
2-1 Land Use Study Area 2-4
2-2 Land Use 2-6
2-3 Zoning 2-8
2-4 Development Projects in the Future without the Proposed Project 2-14
3-1 Socioeconomic Conditions Study Area 3-6
4-1 Elementary and Intermediate Public Schools 4-6
5-1 Open Space Study Area 5-4
5-2 Open Space Resources 5-6
5-3 Future without the Proposed Project: Changes to the Open Space Resources 5-12
6-1 Tier 1 & Tier 2 Screening Assessment 6-10
6-2 Tier 3 Screening Assessment 6-10
6-3 Three-Dimensional Computer Model 6-10
6-4 March 21/September 21 - 8:00 AM EST 6-10
6-5 March 21/September 21 - 8:45 AM EST 6-10
6-6 May 6/August 6 - 6:45 AM EST 6-10
6-7 May 6/August 6 - 7:30 AM EST 6-10
6-8 June 21 - 6:30 AM EST 6-10
6-9 June 21 - 7:15 AM EST 6-10
6-10 December 21 - 9:15 AM EST 6-10
6-11 December 21 - 10:00 AM EST 6-10
6-12 December 21 - 10:45 AM EST 6-10
6-13 December 21 - 11:30 AM EST 6-10
6-14 December 21 - 2:15 PM EST 6-10
6-15 December 21 - 2:45 PM EST 6-10
6-16 Parcel “O” Plaza 6-10
6-17 December 21 – Shadows on Parcel “O” Plaza 6-10
7-1 Historic Resources Study Area 7-2
7-2 Known Historic Resources in Study Area 7-4

8-1 Urban Design and Visual Resources Study Area 8-4
8-2 Project Block Aerial Photo 8-4
8-3 Photographs of Projected Development Sites 8-4
8-4 Photographs of Project Block and Study Area 8-4
8-5 Photographs of Study Area 8-6
8-6 Photographs of Study Area 8-6
8-7 Photographs of Project Site 8-6
8-8 Photographs of Study Area 8-8
8-9 Photographs of Study Area 8-8
8-10 Photographs of Study Area 8-8
8-11 Photographs of Study Area 8-10
8-12 Permitted Building Scenario Elevation 8-10
8-13 Proposed Site Plan 8-10
8-14 Proposed Open Space Plan 8-10
8-15 Projected Development Site 1 – South Elevation 8-10
8-16 Projected Development Site 1 – North Elevation 8-10
8-17 Projected Development Site 1 – Ground Floor Plan 8-10
8-18 Projected Development Site 1 – Building Section 8-12
8-19 Projected Development Site 2 Illustrative Ground Floor Plan 8-12
8-20 Proposed Site 1 Mid-Block Access Drive East-West Section 8-12
8-21 Isometrics of Proposed Project 8-12
8-22 Illustrative Streetscape Elevations 8-12
8-23 Illustrative Renderings of Proposed Project in Context, with Existing Conditions Comparison 8-14
8-24 Illustrative Renderings of Proposed Project in Context, with Existing Conditions Comparison 8-14
8-25 Illustrative Renderings of Proposed Project in Context 8-14
8-26 Illustrative Renderings of Proposed Project in Context 8-14
9-1 NYSDEC BCP Site Boundaries 9-4
10-1 Project Site Location and Street Network 10-4
10-2 2011 Existing Traffic Volumes 10-4
10-3 2015 Future Without Proposed Project Traffic Volumes 10-8
10-4 2015 Future With Proposed Project Traffic Volume Increments 10-12

10-5 2015 Future With Proposed Project Traffic Volumes 10-12
11-1 Analysis of Con Edison Power House 11-20
16-1 Conceptual Construction Schedule 16-6
16-2 Concrete Operation and Crane Location Plan.....16-10
16-3 Construction Incremental Passenger Car Equivalent Trips 16-16
17-1 Option A 17-8
17-2 Option B.....17-8
17-3 Reduced Height.....17-9
20-1 Option A 20-2
20-2 Option B.....20-2
20-3 Reduced Height.....20-4

✷