Queens Future

Draft Environmental Impact Statement

PREPARED FOR

Office of Deputy Mayor for Housing,
Economic Development, and Workforce

PREPARED BY

vhb
One Penn Plaza
Suite 715
New York, NY 10119
212.857.7350

ULURP #: 250046ZMQ, 250047MMQ
CEQR #: 23DME006Q

September 20, 2024

Queens Future
Draft Environmental Impact Statement (DEIS)

September 20, 2024

CEQR No.: 23DME006Q

ULURP No.: 250046ZMQ, 250047MMQ

Lead Agency: Office of the Deputy Mayor for Housing, Economic Development and Workforce

Lead Agency Contact:
Hilary Semel
Director and General Counsel
Mayor's Office of Environmental Coordination
100 Gold Street, 2nd Floor
New York, New York, 10038

Prepared By:
VHB Engineering, Surveying and Landscape Architecture, P.C.
One Penn Plaza
Suite 715
New York, NY 10119

Prepared For: Queens Future, LLC

Table of Contents

Section Page

Executive Summary ES-1

Introduction ES-1
Project Area and Context ES-3
Development Site ES-3
Project Area ES-6
History of Project Area and Surrounding Context ES-8
Required Approvals ES-10
City Approvals ES-10
State Approvals ES-11
Proposed Project ES-13
Mixed-Use Development - Areas of Development A and B ES-16
Parking ES-19
Public Realm Improvements ES-20
Roadway Improvements ES-27
Project Purpose and Need ES-30
Analysis Framework ES-31
Future No-Action Condition ES-31
Future With-Action Condition ES-31
Analysis (Build Year) ES-34
Principal Conclusions of Environmental Analysis ES-34
Land Use, Zoning, and Public Policy ES-34
Socioeconomic Conditions ES-35
Community Facilities and Services ES-37
Open Space ES-37
Shadows ES-38
Historic and Cultural Resources ES-40
Urban Design and Visual Resources ES-41
Natural Resources ES-42
Hazardous Materials ES-43
Water and Sewer Infrastructure ES-43
Solid Waste and Sanitation Services ES-44
Energy ES-45
Transportation ES-45
Air Quality ES-48
Greenhouse Gas Emissions and Climate Change ES-49
Noise ES-50
Public Health ES-52
Neighborhood Character ES-52
Construction ES-53

Mitigation *ES-57*
Alternatives *ES-60*
Unavoidable Significant Adverse Impacts *ES-62*
Growth-Inducing Aspects of the Proposed Project *ES-62*
Irreversible and Irretrievable Commitments of Resources *ES-63*

Project Description 1-1

Introduction 1-1
Project Area and Context 1-3
Development Site *1-3*
Project Area *1-6*
History of Project Area and Surrounding Context *1-8*
Required Approvals 1-10
City Approvals *1-10*
State Approvals *1-11*
Proposed Project 1-13
Mixed-Use Development - Areas of Development A and B *1-16*
Parking *1-19*
Public Realm Improvements *1-20*
Roadway Improvements *1-27*
Project Purpose and Need 1-30
Analysis Framework 1-31
Future No-Action Condition *1-31*
Future With-Action Condition *1-31*
Analysis (Build Year) *1-34*
Environmental Review Process 1-34
City Environmental Quality Review (CEQR) *1-34*

Land Use, Zoning, and Public Policy 2-1

Introduction 2-1
Principal Conclusions 2-2
Methodology 2-3
Assessment 2-6
Existing Conditions *2-6*
No-Action Condition *2-15*
With-Action Condition *2-17*

Socioeconomic Conditions 3-1

Introduction 3-1
Principal Conclusions 3-2
Indirect Business Displacement in Subareas 1 and 2 ..... *3-2*
Indirect Business Displacement in Subarea 3 ..... *3-3*
Indirect Residential Displacement *3-3*

Initial Screening Assessment 3-4
Preliminary Assessment for Indirect Business Displacement 3-5
Indirect Business Displacement Methodology *3-5*
Existing Conditions *3-7*
No-Action Condition *3-11*
With-Action Condition *3-12*
Preliminary Assessment for Indirect Residential Displacement 3-15
Indirect Residential Displacement Methodology *3-15*
Existing Conditions *3-18*
No-Action Condition *3-19*
With-Action Condition *3-20*

Community Facilities and Services 4-1

Introduction 4-1
Principal Conclusions 4-1
Initial Screening Assessment 4-2
Direct Effects *4-2*
Public Schools *4-2*
Libraries *4-2*
Early Childhood Programs *4-2*
Health Care Facilities *4-3*
Police and Fire Services *4-3*
Preliminary Assessment for Police and Fire Services 4-3
Police Protection Services *4-3*
Fire Protection Services *4-5*

Open Space 5-1

Introduction 5-1
Principal Conclusions 5-1
Methodology 5-2
Open Space Study Area *5-3*
Direct Effects Analysis *5-6*
Indirect Effects Analysis *5-6*
Impact Assessment *5-7*
Detailed Assessment 5-8
Existing Conditions: Direct Effects *5-8*
Existing Conditions: Indirect Effects *5-11*
No-Action Condition: Direct Effects *5-16*
No-Action Condition: Indirect Effects *5-16*
With-Action Condition: Direct Effects *5-18*
With-Action Condition: Indirect Effects *5-23*

Shadows 6-1

Introduction 6-1
Principal Conclusions 6-4
Methodology 6-5
Sunlight-Sensitive Resources 6-6
Preliminary Assessment 6-6
Detailed Assessment 6-7
Determination of Significance 6-7
Preliminary Assessment 6-8
Tier 1 and 2 Screening 6-8
Tier 3 Screening Assessment 6-12
Detailed Assessment 6-18
No-Action Condition 6-18
With-Action Condition 6-18
Modeling Results 6-18
With-Action Open Space 6-24

Historic and Cultural Resources 7-1

Introduction 7-1
Principal Conclusions 7-2
Archaeological Resources 7-2
Architectural Resources 7-2
Methodology 7-3
Preliminary Assessment 7-8
Existing Conditions 7-8
No-Action Condition 7-23
With-Action Condition 7-25

Urban Design and Visual Resources 8-1

Introduction 8-1
Principal Conclusions 8-3
Urban Design 8-3
Visual Resources 8-3
Methodology 8-3
Detailed Analysis 8-5
Existing Conditions 8-5
No-Action Condition 8-19
With-Action Condition 8-19

Natural Resources 9-1

Introduction 9-1
Principal Conclusions 9-2
Methodology 9-2
Existing Conditions 9-3
Habitats and Vegetation 9-3

Wildlife *9-4*
Rare/Protected Species *9-5*
Wetlands and Surface Waters *9-7*
No-Action Condition 9-7
With-Action Condition 9-7
Habitats and Vegetation *9-10*
Wildlife *9-13*
Rare/Protected Species *9-16*
Wetlands and Surface Waters *9-16*

Hazardous Materials 10-1

Introduction 10-1
Principal Conclusions 10-1
Methodology 10-2
Assessment 10-3
Existing Conditions *10-3*
No-Action Condition *10-9*
With-Action Condition *10-9*

Water and Sewer Infrastructure 11-1

Introduction 11-1
Principal Conclusions 11-2
Methodology 11-3
Existing Conditions 11-3
Water Supply *11-3*
Sanitary Sewage *11-4*
Stormwater *11-5*
Water Consumption and Sanitary Flows *11-8*
Stormwater Flows *11-8*
No-Action Condition 11-10
With-Action Condition 11-11
Water Demand *11-13*
Sanitary Sewage *11-14*
Stormwater *11-15*
Stormwater Calculations *11-15*

Solid Waste and Sanitation Services 12-1

Introduction 12-1
Principal Conclusions 12-2
Methodology 12-2
Assessment 12-3
Existing Conditions *12-3*
No-Action Condition *12-5*
With-Action Condition *12-5*

Energy **13-1**

Introduction 13-1
Principal Conclusions 13-2
Methodology 13-2
Assessment 13-3
Existing Conditions *13-3*
No-Action Condition *13-4*
With-Action Condition *13-4*

Transportation **14-1**

Introduction 14-1
Principal Conclusions 14-8
Traffic *14-8*
Parking *14-12*
Subways *14-12*
Buses *14-13*
Pedestrians *14-13*
Vehicular and Pedestrian Safety *14-13*
Methodology 14-14
Level 1 Screening Assessment *14-14*
Level 1 Screening Results *14-23*
Level 2 Screening Assessment (Trip Assignment) *14-34*
Level 2 Screening Results *14-39*
Detailed Analysis Methodology 14-49
Traffic *14-49*
Parking *14-52*
Transit *14-53*
Pedestrians *14-55*
Vehicle and Pedestrian Safety *14-59*
Existing Conditions 14-59
Traffic *14-59*
Parking *14-81*
Subways *14-84*
Buses *14-94*
Pedestrians *14-95*
No-Action Conditions 14-107
Traffic *14-107*
Parking *14-126*
Subways *14-126*
Buses *14-132*
Pedestrians *14-133*
With-Action Conditions 14-145
Traffic *14-145*
Parking *14-195*
Subways *14-198*
Pedestrians *14-218*

Vehicular and Pedestrian Safety *14-232*

Air Quality **15-1**

Introduction 15-1
Principal Conclusions 15-3
Mobile Sources *15-3*
Parking Facilities *15-4*
Stationary Sources *15-4*
Industrial Sources *15-4*
National Ambient Air Quality Standards 15-4
Pollutants of Concern 15-6
Regulatory Context 15-6
Impact Criteria 15-7
CO De Minimis Criteria *15-7*
$PM_{2.5}$ De Minimis Criteria *15-7*
Non-Criteria Pollutant Thresholds *15-8*
Background Concentrations 15-8
Methodology 15-8
Mobile Sources *15-8*
Stationary Sources *15-14*
Existing Conditions 15-15
Assessment 15-15
Mobile Sources *15-15*
Parking Analysis *15-23*
Industrial Source Analysis *15-28*

Greenhouse Gas Emissions and Climate Change **16-1**

Introduction 16-1
Principal Conclusions 16-4
Pollutants of Concern 16-4
Applicable Policies, Regulations and Benchmarks for Reducing GHG Emissions 16-6
New York State Climate Leadership and Community Protection Act *16-6*
New York City Local Law 66 ..... *16-7*
New York City Local Law 97 ..... *16-7*
New York City Energy Conservation Code *16-7*
New York City Local Law 154 ..... *16-7*
Other Benchmarks *16-8*
Climate Change Initiatives 16-8
Methodology 16-9
GHG Emissions Assessment *16-9*
Climate Change Assessment *16-11*
GHG Assessment 16-11
Direct GHG Emissions *16-11*
Indirect GHG Emissions *16-11*
Mobile Source Emissions *16-12*
Construction Emissions *16-12*

Consistency with GHG Reduction Goals *16-13*
Resilience to Climate Change *16-15*

Noise **17-1**

Introduction 17-1
Principal Conclusions 17-2
Existing Noise Receptors *17-2*
New Noise Receptors *17-3*
Noise Background 17-4
Noise Standards and Impact Criteria 17-6
Noise Exposure Guidelines *17-6*
Impact Criteria *17-6*
Assessment Methodology 17-8
General Methodology *17-8*
Mobile Sources *17-11*
Stationary Sources *17-12*
Existing Condition 17-13
No-Action Condition 17-17
Existing Noise Receptors *17-17*
New Noise Receptors *17-18*
With-Action Condition 17-18
Existing Noise Receptors *17-18*
New Noise Receptors *17-20*
Noise Attenuation Measures 17-22
Acceptability Assessment *17-22*
Required Noise Attenuation *17-23*

Public Health **18-1**

Introduction 18-1
Principal Conclusions 18-2
Methodology 18-2
Assessment 18-2
Hazardous Materials *18-2*
Water Quality *18-3*
Air Quality *18-3*
Noise *18-4*
Problem Gambling *18-5*
Construction *18-7*

Neighborhood Character **19-1**

Introduction 19-1
Principal Conclusions 19-2
Methodology 19-3
Preliminary Assessment 19-5
Existing Conditions *19-5*

No-Action Condition *19-9*
With-Action Condition *19-10*

Construction 20-1

Introduction 20-1
Principal Conclusions 20-1
Transportation *20-2*
Air Quality *20-4*
Noise *20-4*
Other Technical Areas *20-5*
Methodology 20-6
Construction Regulations and General Practices 20-6
Construction Oversight *20-6*
Construction Hours *20-7*
Construction Practices *20-7*
Construction Description 20-9
Construction Schedule *20-9*
Construction Activities *20-13*
Number of Construction Workers and Material Deliveries *20-17*
Assessment of Project Construction 20-18
Transportation *20-18*
Air Quality *20-31*
Noise *20-39*
Vibration *20-54*
Land Use and Neighborhood Character *20-54*
Socioeconomic Conditions *20-54*
Community Facilities *20-54*
Open Space *20-54*
Historic and Cultural Resources *20-55*
Natural Resources *20-55*
Hazardous Materials *20-56*

Mitigation 21-1

Introduction 21-1
Principal Conclusions 21-1
Water and Sewer Infrastructure *21-2*
Transportation *21-2*
Water and Sewer Infrastructure 21-5
Transportation 21-5
Traffic *21-5*
Transit *21-15*
Pedestrians *21-22*
Traffic Monitoring Plan *21-28*
Transportation Demand Management (TDM) *21-29*
Construction Mitigation *21-31*

Alternatives..... 22-1

Introduction.....22-1
Principal Conclusions.....22-2
No-Action Alternative.....*22-2*
Phoenix Meadows Alternative.....*22-2*
Proposed Project with Passerelle Bridge Replacement Alternative.....*22-2*
No Unmitigated Significant Adverse Impacts Alternative.....*22-3*
No-Action Alternative.....22-4
Description of the No-Action Alternative.....*22-4*
Land Use, Zoning, and Public Policy.....*22-4*
Socioeconomic Conditions.....*22-5*
Community Facilities and Services.....*22-5*
Open Space.....*22-6*
Shadows.....*22-6*
Historic and Cultural Resources.....*22-6*
Urban Design and Visual Resources.....*22-7*
Natural Resources.....*22-7*
Hazardous Materials.....*22-8*
Water and Sewer Infrastructure.....*22-8*
Solid Waste and Sanitation Services.....*22-8*
Energy.....*22-9*
Transportation.....*22-9*
Air Quality.....*22-10*
Greenhouse Gas Emissions and Climate Change.....*22-10*
Noise.....*22-10*
Public Health.....*22-11*
Neighborhood Character.....*22-11*
Construction.....*22-11*
Phoenix Meadows Alternative.....22-11
Description of the Phoenix Meadows Alternative.....*22-11*
Ability to Meet Purpose and Need of the Proposed Actions.....*22-12*
Phoenix Meadows Alternative Compared with the Proposed Actions.....*22-13*
Proposed Project with Passerelle Bridge Reconstruction Alternative.....22-14
Description of the Proposed Project with Passerelle Bridge Replacement Alternative.....*22-14*
History of Passerelle Bridge Reconstruction Proposals.....*22-15*
Passerelle Bridge Replacement Alternative Compared to the Proposed Project.....*22-16*
No Unmitigated Significant Adverse Impacts Alternative.....22-16

Unavoidable Significant Adverse Impacts..... 23-1

Introduction.....23-1
Water and Sewer Infrastructure.....23-1
Transportation.....23-2
Traffic.....*23-2*
Buses.....*23-2*
Pedestrians.....*23-3*

Growth-Inducing Aspects of the Proposed Project 24-1

Introduction.....24-1
Principal Conclusions.....24-2

Irreversible and Irretrievable Commitments of Resources 25-1

List of Appendices

Appendix A .....No-Build Projects

Appendix B ..... Waterfront Revitalization Consistency Assessment

Appendix C .....Natural Resources

Appendix D..... Transportation

Appendix E.....Mitigation

Appendix F.....Construction

Appendix G.....Agency Correspondence

List of Tables

Table No.	Title	Page
Table 1	Existing Conditions Map Key	ES-8
Table 2	With-Action Condition	ES-14
Table 3	Proposed Project Parking Supply	ES-19
Table 1-1	Existing Conditions Map Key	1-8
Table 1-2	With-Action Condition	1-14
Table 1-3	Proposed Project Parking Supply	1-19
Table 2-1	Existing Land Use in the Study Area	2-8
Table 2-2	No-Action Projects Within Quarter-Mile Study Area	2-15
Table 3-1	Employment by Industry Sector	3-9
Table 3-2	General Types of Business in Subarea 3 – Corona along the Roosevelt Avenue Corridor	3-11
Table 3-3	Area Population	3-18
Table 3-4	Household and Housing Data	3-18
Table 3-5	Housing Tenure	3-18
Table 3-6	Median Gross Rent	3-19
Table 3-7	Average and Median Household Income	3-19
Table 3-8	Estimated Income for Market-Rate Units	3-21
Table 4-1	FDNY Facilities Serving the Development Site	4-6
Table 5-1	Future No-Action and With-Action Population/Employment Summary	5-3
Table 5-2	Existing Conditions Map Key	5-11
Table 5-3	Existing Population in Non-Residential Quarter-Mile Study Area	5-11
Table 5-4	Existing Non-residential Study Area Open Spaces	5-14
Table 5-5	Existing Conditions – Adequacy of Open Space Resources	5-16
Table 5-6	Planned Development Projects Non-residential Study Area	5-17
Table 5-7	No-Action Population in Non-Residential Quarter-Mile Study Area	5-17
Table 5-8	No-Action Condition – Adequacy of Open Space Resources	5-18
Table 5-9	With-Action Condition – Proposed Open Spaces	5-24
Table 5-10	With-Action Condition – Adequacy of Open Space Resources	5-31

Table 5-11 Comparison of Open Space Ratios 5-32

Table 6-1 Sunlight-Sensitive Resources in the Study Area 6-9

Table 6-2 Resources Not Affected by Incremental Shadow (Screened at Tier 3) 6-12

Table 6-3 Resources Advanced to Detailed Assessment Based on Tier 3 Results 6-13

Table 6-4 Detailed Analysis Summary of Incremental Shadow Entry/Exit Times 6-19

Table 7-1 S/NR-Eligible Previously Identified Architectural Resources within the Study Area 7-13

Table 7-2 No-Action Projects Within Quarter-Mile Study Area 7-25

Table 8-1 Study Area Visual Resources 8-17

Table 9-1 Summary of USFWS IPaC Resources List 9-6

Table 11-1 Existing Surface Coverage 11-8

Table 11-2 NYCDEP Flow Volume Matrix – Existing Conditions – Outfall #1 11-9

Table 11-3 NYCDEP Flow Volume Matrix – Existing Conditions – Outfall #2 11-9

Table 11-4 NYCDEP Flow Volume Matrix – Existing Conditions – Outfall #3 11-9

Table 11-5 NYCDEP Flow Volume Matrix – Existing Conditions – Outfall #4 11-10

Table 11-6 With-Action Water Demand and Sewage Generation Rates 11-13

Table 11-7 With-Action Water Demand for Area of Development B 11-13

Table 11-8 With-Action Surface Coverage 11-15

Table 11-9 NYCDEP Flow Volume Matrix – Existing and With-Action Conditions – Outfall #1 11-16

Table 11-10 NYCDEP Flow Volume Matrix – Existing and With-Action Conditions – Outfall #2 11-16

Table 11-11 NYCDEP Flow Volume Matrix – Existing and With-Action Conditions – Outfall #3 11-17

Table 11-12 NYCDEP Flow Volume Matrix – Existing and With-Action Conditions – Outfall #4 11-17

Table 12-1 With-Action Condition: Solid Waste Generation (*CEQR Technical Manual Rates*) 12-6

Table 12-2 With-Action Condition: Solid Waste Generation Rates (*Applicant Rates*) 12-7

Table 12-3 With-Action Condition: Estimated Recycling, Organics, and Trash Breakdown (*Applicant Rates*) 12-8

Table 13-1 With-Action Condition: Estimated Annual Consumption (*CEQR Technical Manual Rates*) 13-5

Table 13-2 With-Action Condition: Estimated Annual Consumption (*Applicant Estimates*) 13-6

Table 14-1 Development Increment for Analysis 14-4

Table 14-2 2030 With-Action Condition Significant Impacts Summary 14-9
Table 14-3 Summary of Highway Segment Impacts 14-12
Table 14-4 Weekday Travel Demand Characteristics 14-15
Table 14-5 Weekend Travel Demand Characteristics 14-17
Table 14-6 Trip Generation Summary by Land Use – Primary and Internal Capture Trips 14-24
Table 14-7 With-Action Condition Trip Generation Summary – Person Trips 14-28
Table 14-8 Non-Gameday Trip Generation Summary by Land Use – Vehicle Trips 14-30
Table 14-9 Gameday Trip Generation Summary by Land Use – Vehicle Trips 14-32
Table 14-10 Study Area Highway Segments Selected for Detailed Traffic Analysis 14-42
Table 14-11 Project-Generated Bus Trips By Route 14-47
Table 14-12 Level of Service Criteria for Highway Network Segments 14-52
Table 14-13 Level of Service Criteria for Subway Station Elements 14-53
Table 14-14 Significant Impact Guidance for Stairs and Passageways 14-54
Table 14-15 Level-of-Service Criteria for Pedestrian Elements 14-56
Table 14-16 Significant Impact Criteria for Sidewalks – Non-CBD Areas 14-57
Table 14-17 Significant Impact Criteria for Sidewalks – CBD Areas 14-58
Table 14-18 Significant Impact Criteria for Corners and Crosswalks - Non-CBD Areas 14-58
Table 14-19 Significant Impact Criteria for Corners and Crosswalks - CBD Areas 14-59
Table 14-20 2022 Existing Non-Gameday Traffic Level of Service Summary – Overall Intersections 14-68
Table 14-21 2022 Existing Gameday Traffic Level of Service Summary – Overall Intersections . 14-69
Table 14-22 2022 Existing Non-Gameday Traffic Level of Service Summary – Traffic Lane Groups 14-69
Table 14-23 2022 Existing Gameday Traffic Level of Service Summary – Traffic Lane Groups.... 14-69
Table 14-24 2022 Existing Condition: Non-Gameday Highway Segments Level of Service Summary 14-76
Table 14-25 2022 Existing Condition: Gameday Highway Segments Level of Service Summary 14-77
Table 14-26 Existing Non-Gameday Off-Street Parking Inventory 14-82
Table 14-27 Existing Gameday Off-Street Parking Inventory 14-83
Table 14-28 2022 Existing Subway Station Vertical Circulation Level of Service 14-88
Table 14-29 2022 Existing Subway Station Passageway Level of Service 14-90
Table 14-30 2022 Existing Subway Station Fare Control Level of Service 14-93

Table 14-31 Existing Subway Line-Haul Analysis 14-94
Table 14-32 Existing Local Bus Analysis 14-95
Table 14-33 2022 Existing Non-Gameday Pedestrian Levels of Service Summary 14-96
Table 14-34 2022 Existing Gameday Pedestrian Levels of Service Summary 14-97
Table 14-35 2022 Existing Non-Gameday Pedestrian Levels of Service – Sidewalks 14-98
Table 14-36 2022 Existing Gameday Pedestrian Levels of Service – Sidewalks 14-100
Table 14-37 2022 Existing Non-Gameday Pedestrian Levels of Service – Crosswalks 14-103
Table 14-38 2022 Existing Gameday Pedestrian Levels of Service – Crosswalks 14-104
Table 14-39 2022 Existing Non-Gameday Pedestrian Levels of Service – Corners 14-105
Table 14-40 2022 Existing Gameday Pedestrian Levels of Service – Corners 14-106
Table 14-41 Background Development Projects 14-107
Table 14-42 2030 No-Action Non-Gameday Traffic Level of Service Summary – Overall Intersections 14-111
Table 14-43 2030 No-Action Gameday Traffic Level of Service Summary – Overall Intersections 14-112
Table 14-44 2030 No-Action Non-Gameday Traffic Level of Service Summary – Traffic Lane Groups 14-112
Table 14-45 2030 No-Action Gameday Traffic Level of Service Summary – Traffic Lane Groups 14-113
Table 14-46 2030 No-Action Condition: Non-Gameday Highway Segments Level of Service Summary 14-120
Table 14-47 2030 No-Action Condition: Gameday Highway Segments Level of Service Summary 14-121
Table 14-48 2030 No-Action Subway Station Vertical Circulation Level of Service 14-126
Table 14-49 2030 No-Action Subway Station Passageway Level of Service 14-128
Table 14-50 2030 No-Action Subway Station Fare Control Level of Service 14-131
Table 14-51 No-Action Subway Line-Haul Analysis 14-132
Table 14-52 No-Action Local Bus Analysis 14-133
Table 14-53 2030 No-Action Non-Gameday Pedestrian Levels of Service Summary 14-134
Table 14-54 2030 No-Action Gameday Pedestrian Levels of Service Summary 14-135
Table 14-55 2030 No-Action Non-Gameday Pedestrian Levels of Service – Sidewalks 14-136
Table 14-56 2030 No-Action Gameday Pedestrian Levels of Service – Sidewalks 14-138
Table 14-57 2030 No-Action Non-Gameday Pedestrian Levels of Service – Crosswalks 14-141
Table 14-58 2030 No-Action Gameday Pedestrian Levels of Service – Crosswalks 14-142

Table 14-59 2030 No-Action Non-Gameday Pedestrian Levels of Service – Corners 14-143
Table 14-60 2030 No-Action Gameday Pedestrian Levels of Service – Corners 14-144
Table 14-61 2030 With-Action Non-Gameday Traffic Level of Service Summary – Overall Intersections 14-157
Table 14-62 2030 With-Action Gameday Traffic Level of Service Summary – Overall Intersections 14-158
Table 14-63 2030 With-Action Non-Gameday Traffic Level of Service Summary – Traffic Lane Groups 14-159
Table 14-64 2030 With-Action Gameday Traffic Level of Service Summary – Traffic Lane Groups 14-160
Table 14-65 2030 With-Action Condition: Non-Gameday Highway Segments Level of Service Summary 14-172
Table 14-66 2030 With-Action Condition: Gameday Highway Segments Level of Service Summary 14-173
Table 14-67 Proposed Project Parking Supply 14-196
Table 14-68 Projected Non-Gameday Parking Demand 14-197
Table 14-69 Projected Gameday Parking Demand 14-198
Table 14-70 2030 With-Action Baseline Scenario Subway Station Vertical Circulation Level of Service 14-199
Table 14-71 2030 With-Action Baseline Scenario Subway Station Passageway Level of Service 14-201
Table 14-72 2030 With-Action Baseline Scenario Subway Station Fare Control Level of Service 14-204
Table 14-73 2030 With-Action with Improvements Scenario Subway Station Vertical Circulation Level of Service 14-209
Table 14-74 2030 With-Action with Improvements Scenario Subway Station Passageway Level of Service 14-211
Table 14-75 2030 With-Action With Improvements Scenario Subway Station Fare Control Level of Service 14-214
Table 14-76 With-Action Subway Line-Haul Analysis 14-216
Table 14-77 With-Action Local Bus Analysis 14-218
Table 14-78 2030 With Action Non-Gameday Pedestrian Levels of Service Summary 14-221
Table 14-79 2030 With-Action Gameday Pedestrian Levels of Service Summary 14-222
Table 14-80 2030 With Action Non-Gameday Pedestrian Levels of Service – Sidewalks 14-222
Table 14-81 2030 With-Action Gameday Pedestrian Levels of Service – Sidewalks 14-225
Table 14-82 2030 With-Action Non-Gameday Pedestrian Levels of Service – Crosswalks 14-228

Table 14-83 2030 With-Action Gameday Pedestrian Levels of Service – Crosswalks 14-229
Table 14-84 2030 With-Action Non-Gameday Pedestrian Levels of Service – Corners 14-230
Table 14-85 2030 With-Action Gameday Pedestrian Levels of Service – Corners 14-231
Table 14-86 Vehicle and Pedestrian Crash Summary 14-233
Table 15-1 National and New York Ambient Air Quality Standards 15-5
Table 15-2 Background Concentrations 15-8
Table 15-3 Existing Monitored Concentrations 15-15
Table 15-4 NGD Weekday Signalized Intersections Trips Screening 15-18
Table 15-5 NGD Weekend Signalized Intersections Trips Screening 15-18
Table 15-6 GD Weekday Signalized Intersections Trips Screening 15-18
Table 15-7 GD Weekend Signalized Intersections Trips Screening 15-19
Table 15-8 Highest 1-Hour and 8-Hour CO Concentrations (ppm) Saturday 7 PM Start 15-20
Table 15-9 Highest 1-Hour and 8-Hour CO Concentrations (ppm) Saturday 4 PM Start 15-20
Table 15-10 Highest 24-Hour $PM_{2.5}$ Concentrations ($\mu g/m^3$) 15-21
Table 15-11 Highest Annual $PM_{2.5}$ Concentrations ($\mu g/m^3$) 15-21
Table 15-12 Highest Annual $PM_{2.5}$ Concentrations ($\mu g/m^3$) 15-22
Table 15-13 Hourly In and Out Volumes for Area of Development D Garage, Game Day 15-24
Table 15-14 Highest Concentrations from Area of Development D Garage 15-25
Table 15-15 Hourly In and Out Volumes in Podium Garage within Area of Development A for the Game Day 15-26
Table 15-16 Hourly In and Out Volumes in Podium Garage within Area of Development A for the No Game Day 15-27
Table 15-17 Highest Concentrations from Area of Development A Garage 15-28
Table 15-18 Existing Industrial Sources 15-28
Table 16-1 With-Action Condition 16-2
Table 16-2 Global Warming Potential for Primary Greenhouse Gases 16-5
Table 16-3 GHG Emissions from Area of Development A and Area of Development B Natural Gas-Fired Cooking 16-11
Table 16-4 GHG Emissions from Electricity Generation 16-12
Table 16-5 GHG Emissions from Mobile Sources 16-12
Table 16-6 LL97 GHG Limits for the Proposed Development 16-14
Table 17-1 Common Indoor and Outdoor Sound Levels 17-5
Table 17-2 Noise Exposure Guidelines for Use in City Environmental Impact Review 17-7

Table 17-3 With-Action Condition – Proposed Open Spaces 17-9
Table 17-4 Noise Level Measured During Game 17-13
Table 17-5 Measured Sound Levels Where Vehicular Noise is Predominant 17-16
Table 17-6 Measured Sound Levels Where Train Noise Is Predominant 17-16
Table 17-7 Predicted No-Action Mobile Source Noise Screening at Existing Receptor Site 7 17-17
Table 17-8 Predicted No-Action Sound Levels Compared to Existing Sound Levels 17-18
Table 17-9 Mobile Source Noise Screening at Existing Receptors 17-19
Table 17-10 Predicted With-Action Sound Levels Compared to No Action Sound Levels at Existing Receptors 17-20
Table 17-11 Predicted With-Action Sound Levels at New Receptors During Nongame-Day Midday 17-21
Table 17-12 With-Action Sound Levels from Active Open Space Recreational Area 17-21
Table 17-13 Sound Level Acceptability, dBA 17-22
Table 17-14 Required Attenuation Values 17-23
Table 17-15 Required Attenuation for Each Façade of the Hotel Towers 17-25
Table 20-1 Construction Traffic Impact Mitigation Summary 20-3
Table 20-2 Construction Parking Availability 20-15
Table 20-3 Average Number of Daily Construction Workers and Trucks by Quarter 20-18
Table 20-4 Average Number of Daily Number of Construction PCE Trips by Quarter 20-19
Table 20-5 Non-Gameday Construction Vehicle Trips by Hour (Q1 2029) 20-21
Table 20-6 Gameday Construction Vehicle Trips by Hour (Q1 2029) 20-22
Table 20-7 Comparison of Vehicle Trips – Construction vs. Operational Conditions 20-22
Table 20-8 Existing Off-Street Parking Inventory 20-28
Table 20-9 Existing vs No-Action vs With-Action Pedestrian Levels of Service - Sidewalks 20-30
Table 20-10 Existing vs No-Action vs With-Action Pedestrian Levels of Service - Crosswalks 20-31
Table 20-11 Highest Peak Emissions for Areas of Development (lb/day) 20-36
Table 20-12 Highest Rolling Average Annual Emissions for Areas of Development (lb/day) 20-36
Table 20-13 Highest Predicted Concentrations from Construction Activities at the Area of Development A 20-38
Table 20-14 Highest Predicted Concentrations from Construction Activities at the Area of Development B 20-39
Table 20-15 Construction Noise Receptor Locations and Land Use Descriptions 20-44

Table 20-16 Construction Mobile Source Analysis on a Non-game Day 20-45
Table 20-17 Construction Mobile Source Analysis on a Game Day 20-46
Table 20-18 Construction Equipment by Peak Month 20-48
Table 20-19 Existing Sound Level Measurements 20-50
Table 20-20 Construction Noise Assessment Results Summary 20-52
Table 21-1 Non-Gameday Traffic Impact Mitigation Summary 21-3
Table 21-2 Gameday Traffic Impact Mitigation Summary 21-3
Table 21-3 Traffic Mitigation Summary 21-6
Table 21-4 2030 Mitigation Baseline Scenario Subway Station Vertical Circulation Level of Service 21-17
Table 21-5 2030 Mitigation Baseline Scenario Subway Station Passageway Level of Service 21-18
Table 21-6 2030 Mitigation Baseline Scenario Subway Station Fare Control Level of Service 21-19
Table 21-7 With-Action and Mitigation Local Bus Analysis 21-21
Table 21-8 Non-Gameday Summary of Elements with Significant Adverse Pedestrian Impacts 21-22
Table 21-9 Gameday Summary of Elements with Significant Adverse Pedestrian Impacts 21-23
Table 21-10 Sidewalk Impact Mitigation Summary 21-24
Table 21-11 Crosswalk Impact Mitigation Summary 21-25
Table 21-12 Corner Impact Mitigation Summary 21-27

List of Figures

Figure No.	Title	Page

Figure 1 Site Location Map ES-2
Figure 2 Tax Map ES-4
Figure 3 Project Area Existing Conditions ES-7
Figure 4 Existing Zoning Map ES-9
Figure 5 Proposed Zoning Map ES-12
Figure 6 Proposed Project Site Plan ES-15
Figure 7 Proposed Parkland Demapping ES-17
Figure 8 Illustrative Massing of Proposed Development ES-18
Figure 9 Proposed Open Space Plan ES-22

Figure 10 Illustrative Image of Open Space (OS-1) Looking Northwest ES-23
Figure 11 Illustrative Image of Open Space (OS-1) ES-23
Figure 12 Illustrative Image of Open Space (OS-1) Looking East ES-24
Figure 13 Illustrative Image of Open Space (OS-2) North of Shea Road ES-24
Figure 14 Illustrative Image of Open Space (OS-3) near Area of Development B ES-25
Figure 15 Illustrative Image of Open Space (OS-4) North of Roosevelt Avenue ES-26
Figure 16 Illustrative View of MTA Station Improvements ES-27
Figure 17 Proposed Network Changes ES-29
Figure 18 RWCDS Building Envelopes ES-33
Figure 1-1 Site Location Map 1-2
Figure 1-2 Tax Map 1-4
Figure 1-3 Project Area Existing Conditions 1-7
Figure 1-4 Existing Zoning Map 1-9
Figure 1-5 Proposed Zoning Map 1-12
Figure 1-6 Proposed Project Site Plan 1-15
Figure 1-7 Proposed Parkland Demapping 1-17
Figure 1-8 Illustrative Massing of Proposed Development 1-18
Figure 1-9 Proposed Open Space Plan 1-22
Figure 1-10 Illustrative Image of Open Space (OS-1) Looking Northwest 1-23
Figure 1-11 Illustrative Image of Open Space (OS-1) 1-23
Figure 1-12 Illustrative Image of Open Space (OS-1) Looking East 1-24
Figure 1-13 Illustrative Image of Open Space (OS-2) North of Shea Road 1-24
Figure 1-14 Illustrative Image of Open Space (OS-3) near Area of Development B 1-25
Figure 1-15 Illustrative Image of Open Space (OS-4) North of Roosevelt Avenue 1-26
Figure 1-16 Illustrative View of MTA Station Improvements 1-27
Figure 1-17 Proposed Network Changes 1-29
Figure 1-18 RWCDS Building Envelopes 1-33
Figure 2-1 Land Use 2-5
Figure 2-2 Existing Zoning Map 2-9
Figure 2-3 No-Action Projects 2-16
Figure 2-4 Illustrative Massing of Proposed Project and Uses 2-20
Figure 2-5 Proposed Zoning Map 2-24

Figure 3-1 Socioeconomic Indirect Business Displacement Assessment Study Area 3-6
Figure 3-2 Socioeconomic Study Area Commercial Uses 3-8
Figure 3-3 Socioeconomic Indirect Residential Displacement Assessment Study Area 3-17
Figure 4-1 Police Precincts and Stations Serving the Development Site 4-4
Figure 4-2 Fire and EMS Services Serving the Development Site 4-7
Figure 5-1 Non-Residential Open Space Study Area Map 5-5
Figure 5-2 Project Area Existing Conditions 5-10
Figure 5-3 Non-Residential Open Space Inventory Map 5-12
Figure 5-4 Proposed Parkland Demapping 5-20
Figure 5-5 Proposed Open Space Improvements 5-22
Figure 5-6 With Action Condition - Proposed Open Space Map 5-25
Figure 5-7 Illustrative Image of Open Space (OS-1) Looking Northwest from Mets Plaza 5-26
Figure 5-8 Illustrative Image of Open Space (OS-1) adjacent to the Western Perimeter of Citi Field Stadium, View North 5-26
Figure 5-9 Illustrative Image of Open Space (OS-1) Looking Southeast 5-27
Figure 5-10 Illustrative Image of Open Space (OS-6) South of Roosevelt Avenue, West of Stadium Place South, View North 5-28
Figure 5-11 Illustrative Image of Open Space (OS-3) near Area of Development B, View East 5-29
Figure 5-12 Illustrative Image of Open Space (OS-4) North of Roosevelt Avenue, West of the Mets-Willets Point NYCT No. 7 Train Subway Station, View East 5-30
Figure 6-1 Maximum Building Envelope Plan 6-3
Figure 6-2 Tier 1 and Tier 2 Screening 6-11
Figure 6-3 Tier 3 Screening December 21 Analysis Day 6-14
Figure 6-4 Tier 3 Screening March 21 Analysis Day 6-15
Figure 6-5 Tier 3 Screening May 6 Analysis Day 6-16
Figure 6-6 Tier 3 Screening June 21 Analysis Day 6-17
Figure 6-7 O1/N1 December 21- 9:00AM 6-28
Figure 6-8 O1/N1 December 21- 10:00AM 6-28
Figure 6-9 O4 March 21/September 21 – 7:45AM 6-29
Figure 6-10 O4 March 21/September 21 – 8:45AM 6-29
Figure 6-11 O4 May 6/August 6 – 6:30AM 6-30
Figure 6-12 O4 May 6/August 6 – 7:30AM 6-30

Figure 6-13 O4 May 6/August 6 – 8:30AM 6-31
Figure 6-14 O4 June 21 – 6:00AM 6-31
Figure 6-15 O4 June 21 – 7:00AM 6-32
Figure 6-16 O4 June 21 – 8:00AM 6-32
Figure 6-17 O4 June 21 – 9:00AM 6-33
Figure 6-18 O5 December 21- 11:30AM 6-33
Figure 6-19 O5 December 21- 12:30PM 6-34
Figure 6-20 O5 December 21- 1:30PM 6-34
Figure 6-21 O5 December 21- 2:30PM 6-35
Figure 6-22 O5 March 21/September 21- 12:30PM 6-35
Figure 6-23 O5 March 21/September 21- 1:30PM 6-36
Figure 6-24 O5 March 21/September 21 – 2:30PM 6-36
Figure 6-25 O5 March 21/September 21 – 3:30PM 6-37
Figure 6-26 O5 March 21/September 21 – 4:29PM 6-37
Figure 6-27 O5 May 6/August 6 – 1:00PM 6-38
Figure 6-28 O5 May 6/August 6 – 2:00PM 6-38
Figure 6-29 O5 May 6/August 6 – 3:00PM 6-39
Figure 6-30 O5 May 6/August 6 – 4:00PM 6-39
Figure 6-31 O5 May 6/August 6 – 5:00PM 6-40
Figure 6-32 O5 June 21 – 1:30PM 6-40
Figure 6-33 O5 June 21 – 2:30PM 6-41
Figure 6-34 O5 June 21 – 3:30PM 6-41
Figure 6-35 O5 June 21- 4:30PM 6-42
Figure 6-36 O5 June 21- 5:30PM 6-42
Figure 7-1 Historic and Cultural Resources Study Area 7-7
Figure 7-2 Historic Resources Map and Photo Locations 7-14
Figure 8-1 Illustrative Site Plan 8-2
Figure 8-2 Urban Design and Visual Resources Study Area and Photograph Locations 8-6
Figure 8-3 Study Area Visual Resources and Comparative Viewpoints Map Key 8-18
Figure 8-4 Maximum Building Envelope Plan 8-21
Figure 8-5 Illustrative Image of Open Space North of Roosevelt Avenue, West of the Mets-Willets Point NYCT No. 7 Train Subway Station, View East 8-23

Figure 8-6 Illustrative View of Applicant's Vision for MTA Station Improvements (Under Review by MTA), View South 8-23
Figure 8-7 Illustrative Massing of Proposed Development 8-26
Figure 8-8 Seaver Way Elevation View of Proposed Buildings Maximum Envelopes 8-27
Figure 8-9 Illustrative Image of Open Space Looking Northwest from Mets Plaza 8-29
Figure 8-10 Illustrative Image of Open Space adjacent to the Western Perimeter of Citi Field Stadium, View North 8-30
Figure 8-11 Illustrative Image of Open Space Looking Southeast 8-30
Figure 8-12 Illustrative Image of Open Space South of Roosevelt Avenue, West of Stadium Place South, View North 8-31
Figure 8-13 Illustrative Image of Open Space near Area of Development B, View East 8-31
Figure 8-14 No-Action — View North from Citi Field Plaza 8-33
Figure 8-15 With-Action (Maximum Envelopes) — View North from Citi Field Plaza 8-33
Figure 8-16 No-Action — View South from Flushing Bay Marina 8-34
Figure 8-17 With-Action (Maximum Envelopes) — View South from Flushing Bay Marina 8-34
Figure 8-18 No-Action — View North from Mets-Willets Point NYCT No. 7 Train Subway Station Platform Towards Flushing Bay 8-35
Figure 8-19 With-Action (Maximum Envelopes) — View North from Mets-Willets Point NYCT No. 7 Train Subway Station Platform Towards Flushing Bay 8-35
Figure 8-20 No-Action — View North from Passerelle Bridge 8-37
Figure 8-21 With-Action (Maximum Envelopes) — View North from Passerelle Bridge 8-37
Figure 8-22 No-Action — View Southwest from Seaver Way towards Passerelle Bridge 8-38
Figure 8-23 With-Action (Maximum Envelopes) — View Southwest from Seaver Way towards Passerelle Bridge 8-38
Figure 9-1 USFWS National Wetlands Inventory 9-9
Figure 10-1 Phase II Environmental Site Investigation and Site Investigation Findings Sample Location Map 10-7
Figure 11-1 Existing Drainage Areas 11-6
Figure 11-2 Development Site Outfall Locations 11-7
Figure 11-3 Proposed Project Site Plan 11-12
Figure 14-1 Project Location 14-3
Figure 14-2 Project Features 14-7
Figure 14-3 Proposed Shea Road On-Ramp Diversion 14-38
Figure 14-4 Study Area Intersections Selected for Detailed Traffic Analysis 14-41

Figure 14-5 Study Area Highway Segments Selected for Detailed Traffic Analysis 14-46
Figure 14-6 Pedestrian Analysis Locations 14-49
Figure 14-7 Existing Mets – Willets Point Subway Station Elements – Street Level 14-85
Figure 14-8 Existing Mets – Willets Point Subway Station Elements – Mezzanine Level 14-86
Figure 14-9 Existing Mets – Willets Point Subway Station Elements – Platform Level 14-87
Figure 14-10 With-Action Roadway Improvements 14-146
Figure 14-11 With-Action Gameday Traffic Agent Locations 14-151
Figure 14-12 Mets – Willets Point With Improvements Scenario: Subway Station Elements – Street Level 14-206
Figure 14-13 Mets – Willets Point With Improvements Scenario: Subway Station Elements – Mezzanine Level 14-207
Figure 14-14 Mets – Willets Point With Improvements Scenario: Subway Station Elements – Platform Level 14-208
Figure 15-1 Proposed Project Site Plan 15-2
Figure 15-2 $PM_{2.5}$ Annual Grid Analysis 15-13
Figure 15-3 Intersections Selected for the Mobile Source Analysis 15-17
Figure 15-4 Willets Point Project Phase 2 Development 15-29
Figure 16-1 Proposed Project Site Plan 16-3
Figure 16-2 Three Scopes of GHG Emissions 16-10
Figure 16-3 Embodied Carbon of a Building 16-13
Figure 17-1 With Action Condition - Proposed Open Space Map 17-10
Figure 17-2 Noise Monitoring Locations 17-15
Figure 17-3 Required Noise Attenuation 17-26
Figure 20-1 Anticipated Construction Schedule 20-10
Figure 20-2 Noise Receptor Locations 20-43

List of Photos

Photo No.	Title	Page

Photo 1 View Northwest from Mets-Willets Point NYCT No. 7 Train Subway Station ES-5
Photo 2 View West from Passerelle Pedestrian Bridge ES-5
Photo 1-1 View Northwest from Mets -Willets Point NYCT No. 7 Train Subway Station 1-5

Photo 1-2 View West from Passerelle Pedestrian Bridge 1-5

Photo 7-1 World's Fair Site - World's Fair Marina Pavilions 7-18

Photo 7-2 Pavilion on the Passerelle Bridge 7-19

Photo 7-3 Paint Shed 7-19

Photo 7-4 Porpoise Bridge (tidal gate bridge) - BIN 2270690 7-20

Photo 7-5 Passerelle Bridge 7-20

Photo 7-6 Concrete Arches - 1964 Ruin 7-21

Photo 7-7 Main Gate Entrance 7-21

Photo 7-8 Passerelle Buildings at Main Entrance 7-22

Photo 7-9 Willets Point Subway Station 7-22

Photo 7-10 IRT Interlocking Tower 7-23

Photo 8-1 View Looking North Towards the Development Site from Mets-Willets Point NYCT No. 7 Train Subway Station 8-9

Photo 8-2 View Looking South Towards the Elevated Tracks of the MTA No. 7 Line 8-9

Photo 8-3 View Looking West Towards the Surface Parking Lot from Mets Plaza 8-9

Photo 8-4 View Looking Northwest from Passerelle Bridge 8-9

Photo 8-5 View Looking South from Passerelle Bridge 8-10

Photo 8-6 View Looking Southwest from Roosevelt Avenue 8-10

Photo 8-7 View Looking West from the Mets-Willets Point NYCT No. 7 Train Subway Station 8-10

Photo 8-8 View Looking Southeast Towards the Mets-Willets Point NYCT No. 7 Train Subway Station from Roosevelt Avenue 8-10

Photo 8-9 View Looking Southwest Towards Shea Road from Boat Basin Place 8-11

Photo 8-10 View Looking North Towards the Whitestone Expressway from Boat Basin Place 8-11

Photo 8-11 View Looking Southeast from Seaver Way In Between 35 Avenue and 36 Avenue 8-15

Photo 8-12 View Looking North Towards Citi Field from Mets Plaza 8-15

Photo 8-13 View Looking East Towards 38th Avenue from 112th 8-15

Photo 8-14 View Looking Northwest Towards 38th Avenue from 114 Street 8-15

Photo 8-15 View Looking East from the Malcolm X Promenade 8-16

Photo 8-16 View Looking Southeast Towards the Candela from the Malcolm X Promenade 8-16

Photo 8-17 View Looking Southeast from Flushing Meadows Corona Park 8-16

Photo 8-18 View Looking Northeast Towards Hinton Park from 37th Avenue 8-16