MSK Pavilion

Draft Environmental Impact Statement (DEIS)

CEQR No.: 23DCP118M

ULURP Nos.: 240235 ZSM
240236 GFM
240237 ZMM
240238 ZRM
240239 ZAM
240240 LDM
240241 ZSM
240242 ZCM

Lead Agency:
City Planning Commission, City of New York
Daniel R. Garodnick, Chair

Lead Agency Contact:
Stephanie Shellooe, Director
Environmental Assessment and Review Division
NYC Department of City Planning
120 Broadway, 31st floor
New York, NY 10271

Prepared by:
AKRF, Inc.

April 26, 2024

MSK Pavilion

Draft Environmental Impact Statement (DEIS)

April 26, 2024

CEQR No.:	23DCP118M	
ULURP Nos.:	240235 ZSM	240239 ZAM
	240236 GFM	240240 LDM
	240237 ZMM	240241 ZSM
	240238 ZRM	240242 ZCM
Type of Action:	Type I	
Project Location:	1233 York Avenue New York, NY 10065 Manhattan Community District 8	
Lead Agency:	City Planning Commission, City of New York Daniel R. Garodnick, Chair	
Lead Agency Contact:	Stephanie Shellooe, Director Environmental Assessment and Review Division 120 Broadway, 31st floor New York, NY 10271	
Project Applicant:	Memorial Sloan Kettering Cancer Center	
Prepared by:	AKRF, Inc. 440 Park Avenue South, 7th floor New York, NY 10016	

A public hearing on this Draft Environmental Impact Statement (DEIS) will be held at a date to be announced. Advance notice will be advertised stating the time and place of the hearing. Written comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing.

The DEIS is available on the website of the New York City Department of City Planning, via the MSK Pavilion project page on ZAP: http:// https://zap.planning.nyc.gov/projects/2022M0359.

To view the MSK Pavilion DEIS and Appendices, navigate to the project page in ZAP and select Public Documents, then "DEIS_23DCP118M."

Table of Contents

Executive Summary **ES-1**

Chapter 1: Project Description **1-1**
A. Introduction 1-1
B. Project Description 1-2
Description of the Development Site, Rezoning Area, and Project Area 1-2
Description of Surrounding Area 1-3
Description of the Proposed Project 1-3
Proposed Actions Necessary to Facilitate the Proposed Project 1-4
C. Purpose and Need 1-5
Existing Needs 1-5
Benefits of the Proposed Project 1-6
D. Analysis Framework 1-7
Build Year 1-7
Reasonable Worst Case Development Scenario 1-7
Identification of Development Sites 1-7
The Future without the Proposed Project (No Action Condition) 1-8
The Future with the Proposed Project (With Action Condition) 1-8
E. Public Review Process 1-9
Uniform Land Use Review Procedure 1-9
City Environmental Quality Review 1-10

Chapter 2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
Principal Conclusions 2-1
B. Methodology 2-2
C. Development History 2-2
D. Existing Conditions 2-3
Land Use 2-3
Zoning and Public Policy 2-5
E. The Future without the Proposed Project (the No Action Condition) 2-6
Land Use 2-6
Zoning and Public Policy 2-7
F. The Future with the Proposed Project (the With Action Condition) 2-7
Land Use 2-7
Zoning and Public Policy 2-8

Chapter 3: Community Facilities and Services **3-1**
A. Introduction 3-1
B. Principal Conclusions 3-1

C. Preliminary Screening 3-2
D. Existing Conditions 3-2
Health Care Facilities 3-2
E. The Future without the Proposed Project (No Action Condition) 3-3
F. The Future with the Proposed Project (With Action Condition) 3-3

Chapter 4: Open Space 4-1
A. Introduction 4-1
B. Principal Conclusions 4-2
C. Methodology 4-2
Direct Effects 4-2
Indirect Effects 4-2
D. Existing Conditions 4-4
Study Area Population 4-4
Open Space Inventory 4-5
Assessment of Open Space Adequacy 4-7
E. The Future without the Proposed Project (No Action Condition) 4-8
Indirect Effects 4-8
Assessment of Open Space Adequacy 4-9
F. The Future with the Proposed Project (With Action Condition) 4-9
Direct Effects 4-9
Indirect Effects 4-10
Assessment of Open Space Adequacy 4-10

Chapter 5: Shadows 5-1
A. Introduction 5-1
Principal Conclusions 5-1
B. Definitions and Methodology 5-2
Definitions 5-2
Methodology 5-3
C. Preliminary Screening Assessment 5-3
Tier 1 Screening Assessment 5-4
Tier 2 Screening Assessment 5-4
Tier 3 Screening Assessment 5-5
D. Detailed Shadow Analysis 5-8
Determination of Impact Significance 5-8
Summary of Analysis Results 5-9
Assessment of Shadow Impacts by Resource 5-10
E. Conclusions 5-17

Chapter 6: Historic and Cultural Resources 6-1
A. Introduction 6-1
Principal Conclusions 6-2
B. Methodology 6-2
C. Existing Conditions 6-3
Architectural Resources 6-3
D. The Future without the Proposed Project (No Action Condition) 6-9
Development Site, Rezoning Area, and 2001 LSCFD 6-9

Study Area 6-9
E. The Future with the Proposed Project (With Action Condition) 6-10
Development Site, Rezoning Area, and 2001 LSCFD 6-10
Study Area 6-10
References 6-14

Chapter 7: Urban Design and Visual Resources 7-1
A. Introduction 7-1
Principal Conclusions 7-2
B. Methodology 7-3
C. Existing Conditions 7-3
Urban Design 7-3
Visual Resources and View Corridors 7-9
D. The Future without the Proposed Project (No Action Condition) 7-12
Development Site, Rezoning Area, and Project Area 7-12
Study Area 7-12
E. The Future with the Proposed Project (With Action Condition) 7-12
Urban Design 7-12
Visual Resources and View Corridors 7-14

Chapter 8: Hazardous Materials 8-1
A. Introduction 8-1
Principal Conclusions 8-2
B. Potential Contaminants of Concern 8-2
C. Existing Conditions 8-4
Subsurface Conditions 8-4
Phase I Environmental Site Assessment 8-4
Subsurface (Phase II) Investigation 8-5
D. The Future without the Proposed Project (No Action Condition) 8-7
E. The Future with the Proposed Project (With Action Condition) 8-7

Chapter 9: Water and Sewer Infrastructure 9-1
A. Introduction 9-1
Principal Conclusions 9-1
B. Methodology 9-2
C. Existing Conditions 9-3
Sewer System and Wastewater Treatment 9-3
Sanitary Flows 9-4
Stormwater Flows 9-4
D. The Future without the Proposed Project (No Action Condition) 9-6
E. The Future with the Proposed Project (With Action Condition) 9-6
Sanitary Flows 9-6
Stormwater Flows 9-7

Chapter 10: Transportation 10-1
A. Introduction 10-1
Background 10-1
B. Principal Conclusions 10-3

C. Preliminary Analysis Methodology and Screening Assessment 10-4
Level 1 Screening Assessment 10-5
Level 1 Screening 10-10
Level 2 Screening Assessment 10-11
D. Transportation Analysis Methodologies 10-14
Traffic Operations 10-14
Vehicular and Pedestrian Safety Evaluation 10-15
E. Detailed Traffic Analysis 10-15
Existing Conditions 10-15
The Future Without the Proposed Project 10-17
Probable Impacts of the Proposed Project 10-18
Optional Use of East 66th Street for Clean Bay 10-19
F. Street User Safety Evaluation 10-20
Second Avenue and East 63rd Street 10-27
Second Avenue and East 64th Street 10-27
Second Avenue and East 65th Street 10-27
Second Avenue and East 66th Street 10-27
Second Avenue and East 71st Street 10-28
Second Avenue and East 72nd Street 10-28
First Avenue and East 62nd Street 10-28
First Avenue and East 68th Street 10-28
First Avenue and East 69th Street 10-28
First Avenue and East 70th Street 10-29
First Avenue and East 72nd Street 10-29
York Avenue and East 61st Street 10-29
York Avenue and East 62nd Street 10-29
York Avenue and East 66th Street 10-30
York Avenue and East 68th Street 10-30
York Avenue and East 70th Street 10-30
York Avenue and East 71st Street 10-30
York Avenue and East 72nd Street 10-31
York Avenue and East 73rd Street 10-31
G. Parking Assessment 10-31
Existing Conditions 10-31
The Future without the Proposed Project (No Action Condition) 10-35
The Future with the Proposed Project (With Action Condition) 10-35

Chapter 11: Air Quality 11-1
A. Introduction 11-1
Principal Conclusions 11-2
B. Pollutants for Analysis 11-2
Carbon Monoxide 11-3
Nitrogen Oxides, VOCs, and Ozone 11-3
Lead 11-3
Respirable Particulate Matter—PM_{10} and $PM_{2.5}$ 11-4
Sulfur Dioxide 11-4
C. Air Quality Regulations, Standards, and Benchmarks 11-5
National and State Air Quality Standards 11-5

NAAQS Attainment Status and State Implementation Plans 11-6
Determining the Significance of Air Quality Impacts 11-7
D. Methodology for Predicting Pollutant Concentrations 11-8
Mobile Sources 11-8
Stationary Sources 11-9
E. Existing Conditions 11-17
F. The Future without the Proposed Project (No Action Condition) 11-18
G. Probable Impacts of the Proposed Project (With Action Condition) 11-18
Mobile Sources 11-18
Stationary Sources 11-19
H. Proposed Air Quality (E) Designations 11-20

Chapter 12: Greenhouse Gas Emissions and Climate Change 12-1
A. Introduction 12-1
Principal Conclusions 12-2
B. Greenhouse Gas Emissions 12-3
Pollutants of Concern 12-3
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 12-4
Methodology 12-7
Projected GHG Emissions 12-11
Elements that would Reduce GHG Emissions 12-12

Chapter 13: Noise 13-1
A. Introduction 13-1
Principal Conclusions 13-1
B. Acoustical Fundamentals 13-2
"A"-Weighted Sound Level (dBA) 13-2
Noise Descriptors Used in Impact Assessment 13-3
C. Noise Standards and Criteria 13-3
New York CEQR Technical Manual Noise Standards 13-3
D. Existing Noise Levels 13-5
Selection of Noise Receptor Locations 13-5
Noise Monitoring 13-5
Existing Noise Levels at Noise Receptor Locations 13-6
E. Noise Prediction Methodology 13-6
General Methodology 13-6
F. The Future without the Proposed Project (No Action Condition) 13-7
G. The Future with the Proposed Project (With Action Condition) 13-8
H. Noise Attenuation Measures 13-9
I. Mechanical Equipment 13-10

Chapter 14: Public Health 14-1
A. Introduction 14-1
Principal Conclusions 14-1
B. Methodology 14-1
C. Public Health Assessment 14-2
Chronic Exposure to High Levels of Noise 14-2
Prolonged Exposure to Noise Levels Above 85 dBA 14-3

Unpredictable Exposure to Short-Term High Noise Levels 14-3

Chapter 15: Neighborhood Character 15-1
A. Introduction 15-1
Principal Conclusions 15-2
B. Methodology 15-2
Study Area 15-3
Impact Assessment 15-3
C. Preliminary Assessment 15-3
Defining Features 15-3
Assessment of the Potential to Affect the Defining Features of the Neighborhood 15-5

Chapter 16: Construction 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Governmental Coordination and Oversight 16-4
C. Construction Phasing and Schedule 16-5
D. Construction Description 16-6
General Construction Practices 16-6
Description of Construction Activities 16-7
E. Number of Construction Workers and Material Deliveries 16-8
F. Environmental Effects of the Proposed Development's Construction Activities 16-9
Transportation 16-9
Air Quality 16-26
Noise 16-31
Vibration 16-45
Other Technical Areas 16-47

Chapter 17: Alternatives 17-1
A. Introduction 17-1
Principal Conclusions 17-1
B. No Action Alternative 17-2
Land Use, Zoning, and Public Policy 17-3
Community Facilities 17-3
Shadows 17-3
Open Space 17-4
Historic Resources 17-4
Urban Design and Visual Resources 17-4
Hazardous Materials 17-5
Water and Sewer Infrastructure 17-5
Transportation 17-5
Air Quality 17-6
Greenhouse Gases and Climate Change 17-7
Noise 17-7
Neighborhood Character 17-7
Public Health 17-8
Construction 17-8
C. Reduced Height Alternative 17-9

Reduced Height Alternative Shadows 17-9

Chapter 18: Mitigation 18-1
A. Introduction 18-1
B. Principal Conclusions 18-1
Shadows 18-1
Construction 18-2
Shadows 18-3
C. Construction 18-4
Traffic 18-4
Noise 18-9

Chapter 19: Unavoidable Adverse Impacts 19-1
A. Introduction 19-1
B. Shadows 19-1
C. Construction 19-2
Traffic 19-2
Noise 19-2

Chapter 20: Growth-Inducing Aspects of the Proposed Project 20-1
A. Introduction 20-1
B. Assessment 20-1

Chapter 21: Irreversible and Irretrievable Commitments of Resources 21-1
A. Introduction 21-1
B. Assessment 21-1

Appendices

Appendix A Proposed Zoning Text
Appendix B Historic and Cultural Resources
Appendix C Hazardous Materials
Appendix D Construction

List of Tables

ES-1 Anticipated Construction Schedule—Proposed Project ES-7
ES-2 Development Program Summary ES-9
ES-3 Development Site Population ES-9
1-1 Anticipated Construction Schedule—Proposed Project 1-7
1-2 Development Program Summary 1-9
1-3 Development Site Population 1-9
4-1 Existing Worker Population 4-5
4-2 Study Area Open Space Inventory 4-6
4-3 Existing Conditions: Adequacy of Open Space Resources 4-8
4-4 No Action Condition: Publicly Accessible Open Space Changes 4-9
4-5 No Action Condition: Adequacy of Open Space Resources 4-9
4-6 With Action Condition: Adequacy of Open Space Resources 4-10
4-7 Passive Open Space Ratios Summary 4-10
5-1 Tier 3 Assessment 5-7
5-2 Incremental Shadow Durations 5-10
6-1 Known and Potential Architectural Resources 6-5
9-1 Existing Water Consumption and Wastewater Generation 9-4
9-2 Existing Surface Coverage 9-5
9-3 With Action Water Consumption and Wastewater Generation 9-7
9-4 DEP Volume Calculation Matrix: Existing and With Action Condition Volume Comparison 9-8
10-1 Program Summary 10-3
10-2 Travel Demand Factors 10-5
10-3 Trip Generation Summary – No Action Condition 10-8
10-4 Trip Generation Summary – With Action Condition 10-9
10-5 Trip Generation Summary – Net Incremental Trips 10-9
10-6 Traffic Level 2 Screening Analysis Results – Recommended Analysis Locations 10-13
10-7 Level of Service Criteria for Signalized Intersections 10-14

10-8 Existing Conditions Traffic Analysis Results 10-16
10-9 Existing Conditions Level of Service Analysis 10-16
10-10 2030 No Action Traffic Analysis Results 10-17
10-11 Existing and 2030 No Action Conditions Level of Service Analysis 10-17
10-12 2030 With Action Traffic Analysis Results 10-18
10-13 2030 No Action and With Action Conditions Level of Service Analysis 10-19
10-14 Crash Summary 10-21
10-15 Vehicle and Pedestrian Crash Details 10-22
10-16 On-Street Parking Regulations 10-32
10-17 Existing Off-Street Parking Utilization – 1/4 Mile Study Area 10-34
10-18 Existing and 2030 No Action Parking Supply and Utilization 10-35
10-19 Incremental Parking Demand – Weekday 10-36
10-20 2030 No Action and 2030 With Action Parking Supply and Utilization – ¼-Mile 10-36
11-1 National Ambient Air Quality Standards (NAAQS) 11-6
11-2a Stack Parameters and Emission Rates for MSKCC Central Plant 11-11
11-2b Stack Parameters and Emission Rates for Weil Cornell 11-11
11-2c Stack Parameters and Emission Rates for Rockefeller University 11-12
11-3 Background Pollutant Concentrations for Stationary Source Analysis 11-13
11-4 Stack Parameters for RRL Laboratory Exhausts 11-14
11-5 Selected Hazardous Materials in the Existing RRL Laboratories 11-15
11-6 Chemicals Selected for Worst-Case Spill Analysis 11-16
11-7 Representative Monitored Ambient Air Quality Data 11-18
11-8 Maximum Modeled Pollutant Concentrations on the Proposed Project ($\mu g/m^3$)—Existing Major and Large Sources 11-19
11-9 Maximum Predicted Concentrations (ppm) 11-20
12-1 GWP for Major GHGs 12-4
12-2 Vehicle Miles Traveled Per Year 12-9
12-3 Annual Building Operational Emissions 12-11
12-4 Annual Mobile Source Emissions (Metric Tons CO_2e) 12-11
12-5 Total Construction GHG Emissions (Metric Tons CO_2e) 12-12
12-6 Summary of Annual GHG Emissions (Metric Tons CO_2e) 12-12
13-1 Noise Levels of Common Sources 13-3
13-2 Noise Exposure Guidelines for Use in City Environmental Impact Review 13-4

13-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 13-5
13-4 Noise Receptor Locations 13-5
13-5 Measured Noise Levels (in dBA) 13-6
13-7 2030 No Action Condition Noise Levels (in dBA) 13-8
13-8 2030 With Action Condition Noise Levels (in dBA) 13-8
13-9 CEQR-Required Attenuation at Noise Measurement Locations (in dBA) 13-9
13-10 Minimum Required Attenuation at Development Sites (in dBA) 13-9
16-1 Construction Oversight in New York City 16-5
16-2 Anticipated Construction Schedule – Proposed Project 16-5
16-3 Average Number of Daily Workers and Trucks by Quarter Proposed Project 16-9
16-4 Peak Construction Vehicle Trip Projections – Proposed Project 16-11
16-5 Construction Traffic Level 2 Screening Analysis Results—Selected Analysis Locations 16-12
16-6 2028 Construction With Action Condition Summary of Significant Adverse Traffic Impacts 16-14
16-7 Construction Existing, No Action, and With Action Conditions Los Analysis Weekday 6–7 AM Peak Hour 16-14
16-8 Construction Existing, No Action, and With Action Conditions Los Analysis Weekday 3–4 PM Peak Hour 16-16
16-9 Construction Pedestrian Level 2 Screening Results – Selected Analysis Locations 16-20
16-10 Level of Service Criteria for Pedestrian Elements 16-22
16-11 Significant Impact Guidance for Sidewalks 16-23
16-12 Significant Impact Guidance for Corners and Crosswalks 16-24
16-13 Existing and 2028 No Action and With Action Conditions Construction and Operational Peak Hour Pedestrian Level of Service Analysis 16-25
16-14 Representative Monitored Ambient Air Quality Data 16-30
16-15 Maximum Pollutant Concentrations – Proposed Project 16-31
16-16 Noise Receptors by Location and Land Use 16-34
16-17 Measured Existing Noise Levels (in dBA) 16-37
16-18 Construction Noise Analysis Time Periods 16-38
16-19 Construction Equipment Noise Emissions in dBA 16-40
16-20 Construction Noise Analysis Results in dBA 16-41
16-21 Vibration Source Levels for Construction Equipment (dBA) 16-46
18-1 2028 Construction With Action Condition Summary of Significant Adverse Traffic Impacts 18-4

18-2 Recommended Mitigation Measures Weekday Am Construction Peak Hour..... 18-5

18-3 Recommended Mitigation Measures Weekday Pm Construction Peak Hour 18-5

18-4 Construction No Action, With Action, and Mitigation Conditions LOS Analysis Weekday 6–7 AM Peak Hour 18-6

18-5 Construction No Action, With Action, and Mitigation Conditions LOS Analysis Weekday 3–4 PM Peak Hour..... 18-7

List of Figures

ES-1 Project Location
ES-2 Existing and Proposed Zoning
ES-3 Existing LSCFD/MSKCC Campus Site Plan
ES-4 Proposed Roof Plan
ES-5 Proposed Program Stack (North-South Section Looking West from York Avenue)
ES-6 Building Section – North-South Section
ES-7 Building Section – East-West Section
ES-8 Proposed Ground Floor Plan
ES-9 Proposed Corner of York Avenue and East 67th Street – Ground Floor Entrance
ES-10 Proposed Maximum Zoning Envelope
1-1 Project Location
1-2 Existing and Proposed Zoning
1-3 Existing LSCFD/MSKCC Campus Site Plan
1-4 Proposed Roof Plan
1-5 Proposed Program Stack (North-South Section Looking West from York Avenue)
1-6 Building Section – North-South Section
1-7 Building Section – East-West Section
1-8 Proposed Ground Floor Plan
1-9 Proposed Corner of York Avenue and East 67th Street – Ground Floor Entrance
1-10 Proposed Maximum Zoning Envelope
2-1 Existing Land Use
2-2 Existing Zoning
2-3 Proposed Zoning
3-1 Upper East Side MSKCC Facilities
4-1 Walk-to-a-Park Service Area
4-2 Open Space Study Area
5-1 Tier 1 and Tier 2 Assessments
5-2 Tier 3 Assessment: December 21

5-3 Tier 3 Assessment: March 21 / September 21
5-4 Tier 3 Assessment: May 6 / August 6
5-5 Tier 3 Assessment: June 21
5-6 Detailed Analysis, St Catherine's Park: December 21
5-7 Detailed Analysis, St Catherine's Park: March 21 / September 21
5-8 Detailed Analysis, St Catherine's Park: March 21 / September 21
5-9 Detailed Analysis, St Catherine's Park: March 21 / September 21
5-10 St. John of Nepomucene Church – Interior Photographs
5-11 Detailed Analysis, St. John of Nepomucene Church: March 21 / September 21
5-12 Detailed Analysis, St. John of Nepomucene Church: March 21 / September 21
5-13 Detailed Analysis, St. John of Nepomucene Church: May 6 / August 6
5-14 Detailed Analysis, St. John of Nepomucene Church: May 6 / August 6
5-15 Detailed Analysis, St. John of Nepomucene Church: May 6 / August 6
5-16 Detailed Analysis, St. John of Nepomucene Church: May 6 / August 6
5-17 Detailed Analysis, St. John of Nepomucene Church: June 21
5-18 Detailed Analysis, St. John of Nepomucene Church: June 21
5-19 Detailed Analysis, St. John of Nepomucene Church: June 21
5-20 Detailed Analysis, Manhattan House Apartments: March 21 / September 21
5-21 Detailed Analysis, Manhattan House Apartments: December 21
5-22 Rockefeller University landscape plan
5-23 Detailed Analysis, Rockefeller University Historic District: March 21 / September 21
5-24 Detailed Analysis, Rockefeller University Historic District: March 21 / September 21
5-25 Detailed Analysis, Rockefeller University Historic District: March 21 / September 21
5-26 Detailed Analysis, Rockefeller University Historic District: May 6 / August 6
5-27 Detailed Analysis, Rockefeller University Historic District: May 6 / August 6
5-28 Detailed Analysis, Rockefeller University Historic District: May 6 / August 6
5-29 Detailed Analysis, Rockefeller University Historic District: May 6 / August 6
5-30 Detailed Analysis, Rockefeller University Historic District: May 6 / August 6
5-31 Detailed Analysis, Rockefeller University Historic District: June 21
5-32 Detailed Analysis, Rockefeller University Historic District: June 21
5-33 Detailed Analysis, Rockefeller University Historic District: June 21
5-34 Detailed Analysis, Rockefeller University Historic District: June 21
5-35 Detailed Analysis, Rockefeller University Historic District: June 21

6-1 Historic and Cultural Resources
6-2 Existing LSCFD/MSKCC Campus Site Plan
6-3 Development Site
6-4 Development Site and Rezoning Area
6-5 LSCFD—Known Architectural Resource
6-6 LSCFD
6-7 LSCFD
6-8 Study Area—Known Architectural Resources
6-9 Study Area—Known Architectural Resources
6-10 Study Area—Known Architectural Resources
6-11 Study Area—Known Architectural Resources
6-12 Study Area—Known Architectural Resources
6-13 Study Area—Known Architectural Resources
6-14 Study Area—Potential Architectural Resources
7-1 Urban Design and Visual Resources
7-2 Urban Design and Visual Resources Aerial Map
7-3 Development Site
7-4 Development Site and Proposed Rezoning Area
7-5 Project Area
7-6 Project Area
7-7 Project Area
7-8 Study Area
7-9 Study Area
7-10 Study Area
7-11 Study Area
7-12 Study Area
7-13 Study Area
7-14 Study Area
7-15 Study Area
7-16 Study Area
7-17 Study Area
7-18 Study Area
7-19 Proposed Project, Roof Plan

7-20 Proposed Project, North-South Section

7-21 Proposed Project, East-West Section

7-22 Proposed Ground Floor Plan

7-23 Proposed Project – Contextual southwest view from York Avenue and East 67th Street, including the double-height lobby and bridge over East 67th Street

7-24 Proposed Project – Southwest view from the corner of York Avenue and East 67th Street, including landscaping, seating areas, and the double-height lobby

7-25 Proposed Project – Contextual northwest view from York Avenue and East 66th Street, including landscaping, seating areas, and the double-height lobby

7-26 Proposed Project – Contextual view north from East 66th Street, including landscaping, seating areas, the double-height lobby, and the southern building entrance

7-27 Proposed Project, Maximum Zoning Envelope

7-28 No Action/With Action Comparison, View southwest on York Avenue from East 69th Street

7-29 No Action/With Action Comparison, View southwest on York Avenue from East 68th Street

7-30 No Action/With Action Comparison, View northwest on York Avenue from East 65th Street

7-31 No Action/With Action Comparison, View southeast on East 67th Street

7-32 No Action/With Action Comparison, View northwest on East 66th Street

10-1 Proposed Ground Floor Plan

10-2 No Action Project Generated Vehicle Trips, Weekday PM Peak Hour

10-3 With Action Project Generated Vehicle Trips, Weekday PM Peak Hour

10-4 With Action Incremental Vehicle Trips, Weekday PM Peak Hour

10-5 2022 Existing Traffic Volumes, Weekday PM Peak Hour

10-6 2030 No Action Traffic Volumes, Weekday PM Peak Hour

10-7 2030 With Action Traffic Volumes, Weekday PM Peak Hour

10-8 On-Street Parking Regulations

10-9 Off-Street Parking Facilities

13-1 Noise Receptor Locations

13-2 Noise Attenuation Requirements

16-1 Construction Plan—Maintenance and Protection of Traffic

16-2 Proposed Project Construction PCE Trips, Weekday 6-7 AM Peak Hour

16-3 Proposed Project Construction PCE Trips, Weekday 3-4 PM Peak Hour

16-4 Proposed Project Construction Pedestrian Trips, Weekday 6-7 AM Peak Hour

16-5 Proposed Project Construction Pedestrian Trips, Weekday 3-4 PM Peak Hour
16-6 Construction Existing Traffic Volumes, Weekday 6-7 AM Peak Hour
16-7 Construction Existing Traffic Volumes, Weekday 3-4 PM Peak Hour
16-8 2028 Construction No Action Traffic Volumes, Weekday 6-7 AM Peak Hour
16-9 2028 Construction No Action Traffic Volumes, Weekday 3-4 PM Peak Hour
16-10 2028 Construction With Action Traffic Volumes, Weekday 6-7 AM Peak Hour
16-11 2028 Construction With Action Traffic Volumes, Weekday 3-4 PM Peak Hour
16-12 Construction Existing Pedestrian Volumes, Weekday 6-7 AM Peak Hour
16-13 Construction Existing Pedestrian Volumes, Weekday 8:15-9:15 AM Peak Hour
16-14 Construction Existing Pedestrian Volumes, Weekday 12:45-1:45 PM Peak Hour
16-15 Construction Existing Pedestrian Volumes, Weekday 3-4 PM Peak Hour
16-16 Construction Existing Pedestrian Volumes, Weekday 4:45-5:45 PM Peak Hour
16-17 2028 Construction No Action Pedestrian Volumes, Weekday 6-7 AM Peak Hour
16-18 2028 Construction No Action Pedestrian Volumes, Weekday 8:15-9:15 AM Peak Hour
16-19 2028 Construction No Action Pedestrian Volumes, Weekday 12:45-1:45 PM Peak Hour
16-20 2028 Construction No Action Pedestrian Volumes, Weekday 3-4 PM Peak Hour
16-21 2028 Construction No Action Pedestrian Volumes, Weekday 4:45-5:45 PM Peak Hour
16-22 2028 Construction With Action Pedestrian Volumes, Weekday 6-7 AM Peak Hour
16-23 2028 Construction With Action Pedestrian Volumes, Weekday 8:15-9:15 AM Peak Hour
16-24 2028 Construction With Action Pedestrian Volumes, Weekday 12:45-1:45 PM Peak Hour
16-25 2028 Construction With Action Pedestrian Volumes, Weekday 3-4 PM Peak Hour
16-26 2028 Construction With Action Pedestrian Volumes, Weekday 4:45-5:45 PM Peak Hour
16-27 Construction Noise Receptor Locations
16-28 Construction Noise Impacts