BLOCK 675 EAST

Final Environmental Impact Statement (FEIS)

CEQR No.:
17DCP159M

ULURP Nos.:

Block 675, Lot 12 (formerly Lots 12, 29, 36)	C180127 ZMM N180128 ZRM N180128(A) ZRM C180129 ZSM 180129(A) ZSM
Block 675, Lots 38, 39	C180150 ZMM N180151 ZRM N180151(A) ZRM C180152 ZSM 180152(A) ZSM

Lead Agency:
City Planning Commission, City of New York
Marisa Lago, Chair

Lead Agency Contact:
Robert Dobruskin, AICP

Applicants:
DD West 29th LLC
West 30th Street LLC

Prepared by:
AKRF, Inc.

APRIL 2018

Block 675 East
FINAL ENVIRONMENTAL IMPACT STATEMENT (FEIS)

Project Location:	Community District 4, Borough of Manhattan	
CEQR No.	17DCP159M	
Type of Action:	Type I	
ULURP Nos.	Block 675, Lot 12 (formerly Lots 12, 29, 36) C180127 ZMM N 180128 ZRM N 180128(A) ZRM C180129 ZSM 180129(A) ZSM	Block 675, Lots 38, 39 C180150 ZMM N 180151 ZRM N 180151(A) ZRM C180152 ZSM 180152(A) ZSM

Lead Agency: City Planning Commission, City of New York
Marisa Lago, Chair

Lead Agency Contact: Robert Dobruskin, AICP
Director, Environmental Assessment and Review Division
New York City Department of City Planning
120 Broadway, 31st Floor
New York, NY 10007
212-720-3423
rdobrus@planning.nyc.gov

Project Applicants: DD West 29th LLC
West 30th Street LLC

Prepared by: AKRF, Inc.
440 Park Avenue South
New York, NY 10016

Acceptance Date: April 27, 2018

Table of Contents

Executive Summary **S-1**

1: Project Description **1-1**
A. Introduction 1-1
B. Area Affected by the Proposed Actions 1-2
Project Area 1-2
Granting Site 1-3
Hudson River Park Improvements 1-4
C. Background 1-4
Project Area 1-4
Hudson River Park Act and Special Hudson River Park District 1-4
Surrounding Area 1-5
D. Purpose and Need 1-6
Hudson River Park Improvements 1-6
Project Area 1-8
E. Proposed Actions 1-8
Actions Required for Project Site A 1-9
Actions Required for Project Site B 1-11
F. Proposed Developments 1-13
Project Site A 1-14
Project Site B 1-15

2: Analytical Framework **2-1**
A. Introduction 2-1
B. Public Review Process 2-1
Uniform Land Use Review Procedure 2-2
New York City Environmental Quality Review 2-2
C. Framework for Analysis 2-3
D. Study Areas 2-4
E. Analysis Year 2-4
Project Site A 2-4
Project Site B 2-5
F. Defining Analysis Conditions/Reasonable Worst Case Development Scenario 2-5
Existing Conditions 2-5
The Future without the Proposed Actions 2-6
The Future with the Proposed Actions 2-9
Increment for Analysis 2-12
G. Determining Impact Significance 2-13
H. Mitigation 2-13
I. Analysis of Project Permutations 2-13
J. Alternatives 2-13

3: Land Use, Zoning, and Public Policy 3-1
A. Introduction 3-1
Principal Conclusions 3-1
B. Methodology 3-2
C. Background and Development History 3-2
D. Existing Conditions 3-3
Land Use 3-3
Zoning 3-5
Public Policy 3-7
E. The Future without the Proposed Actions 3-9
Land Use 3-9
Zoning 3-10
Public Policy 3-10
F. The Future with the Proposed Actions 3-11
Land Use 3-11
Zoning 3-12
Public Policy 3-17

4: Socioeconomic Conditions 4-1
A. Introduction 4-1
Principal Conclusions 4-1
B. Methodology 4-3
Background 4-3
Analysis Format 4-4
Project Area 4-4
Study Area 4-4
Data Sources 4-4
C. Screening Assessment 4-5
Determining whether a Socioeconomic Assessment is Appropriate 4-5
D. Preliminary Assessment 4-6
Direct Business Displacement 4-6
Indirect Residential Displacement 4-11
Indirect Business Displacement 4-15
Adverse Effects on Specific Industries 4-17

5: Community Facilities and Services 5-1
A. Introduction 5-1
Principal Conclusions 5-1
B. Preliminary Screening 5-2
Direct Effects 5-2
Indirect Effects 5-3
C. Potential Indirect Effects on Public Elementary and Intermediate Schools 5-4
Methodology 5-4
Existing Conditions 5-5
The Future without the Proposed Actions 5-6
The Future with the Proposed Actions 5-7
D. Potential Indirect Effects on Public Libraries 5-8
Methodology 5-8

Existing Conditions 5-8
The Future without the Proposed Actions 5-9
The Future with the Proposed Actions 5-9
E. Publicly Funded Child Care Centers 5-10
Methodology 5-10
Existing Conditions 5-12
The Future without the Proposed Actions 5-12
The Future with the Proposed Actions 5-12

6: Open Space 6-1
A. Introduction 6-1
Principal Conclusions 6-1
B. Methodology 6-2
Direct Effects 6-2
Indirect Effects 6-2
C. Existing Conditions 6-5
Study Area Population 6-5
Inventory of Publicly Accessible Open Space 6-6
Assessment of Open Space Adequacy 6-10
D. The Future without the Proposed Actions (No Action Condition) 6-11
Study Area Population 6-11
Open Space Resources 6-11
Assessment of Open Space Adequacy 6-11
E. The Future with the Proposed Actions (With Action Condition) 6-12
Direct Effects 6-12
Indirect Effects 6-13

7: Shadows 7-1
A. Introduction 7-1
Principal Conclusions 7-1
B. Definitions and Methodology 7-2
Definitions 7-2
Methodology 7-2
C. Preliminary Screening Assessment 7-3
Tier 1 Screening Assessment 7-3
Tier 2 Screening Assessment 7-3
Tier 3 Screening Assessment 7-4
D. Detailed Analysis 7-5
Detailed Analysis Results 7-5
Shadows and the Four Seasons 7-6
Assessment by Resource 7-7
E. Conclusions 7-10

8: Historic and Cultural Resources 8-1
A. Introduction 8-1
Archaeological Resources 8-2
Architectural Resources 8-2
Principal Conclusions 8-2

B. Methodology 8-3
Archaeological Resources 8-3
Architectural Resources 8-3
C. Existing Conditions 8-5
Archaeological Resources 8-5
Architectural Resources 8-5
D. The Future without the Proposed Actions 8-10
Project Area 8-10
Granting Site 8-10
Study Area 8-10
E. The Future with the Proposed Actions 8-11
Archaeological Resources 8-11
Architectural Resources 8-11

9: Urban Design and Visual Resources 9-1
A. Introduction 9-1
Principal Conclusions 9-2
B. Methodology 9-2
C. Existing Conditions 9-4
Urban Design 9-4
View Corridors and Visual Resources 9-9
D. The Future without the Proposed Actions 9-10
Urban Design 9-10
View Corridors and Visual Resources 9-11
E. The Future with the Proposed Actions 9-12
Urban Design 9-12
View Corridors and Visual Resources 9-14

10: Hazardous Materials 10-1
A. Introduction 10-1
B. Principal Conclusions 10-1
C. Methodology 10-2
D. Existing Conditions 10-3
Subsurface Conditions 10-3
Hazardous Materials Assessment 10-3
E. The Future without the Proposed Actions 10-5
F. The Future with the Proposed Actions 10-5

11: Water and Sewer Infrastructure 11-1
A. Introduction 11-1
Principal Conclusions 11-1
B. Methodology 11-2
Water Supply 11-2
Wastewater and Stormwater Conveyance and Treatment 11-2
C. Existing Conditions 11-3
Conveyance System 11-3
Sanitary Flows 11-4
Stormwater Flows 11-4

D. The Future without the Proposed Actions 11-5
Conveyance System 11-5
Sanitary Flows 11-5
Stormwater Flows 11-5
E. The Future with the Proposed Actions 11-6
Conveyance System 11-6
Sanitary Flows 11-6
Stormwater Flows 11-7

12: Solid Waste and Sanitation Services 12-1
A. Introduction 12-1
B. Principal Conclusions 12-1
C. Methodology 12-2
D. Existing Conditions 12-2
Description of Current Solid Waste Sanitation Services 12-2
Solid Waste Generation on Project Area 12-4
E. Future without the Proposed Actions 12-4
F. Future with the Proposed Actions 12-5

13: Energy 13-1
A. Introduction 13-1
Principal Conclusions 13-1
B. Methodology 13-1
C. Existing Conditions 13-2
Energy Generation 13-2
Project Area Energy Consumption/Existing Demand 13-2
D. The Future without the Proposed Actions 13-3
E. The Future with the Proposed Actions 13-3

14: Transportation 14-1
A. Introduction 14-1
Project Site A 14-1
Project Site B 14-2
Lot 38 14-3
Principal Conclusions 14-3
B. Preliminary Analysis Methodology and Screening Assessment 14-5
Level 1 Screening Assessment 14-5
Level 2 Screening Assessment 14-10
C. Transportation Analysis Methodologies 14-15
Traffic Operations 14-15
Transit Operations 14-16
Pedestrian Operations 14-18
Vehicular and Pedestrian Safety Evaluation 14-21
Parking Conditions Assessment 14-21
D. Detailed Traffic Analysis 14-22
Existing Conditions 14-22
The Future without the Proposed Actions 14-24
The Future with the Proposed Actions 14-27

E. Detailed Transit Analysis 14-30
Existing Conditions 14-30
The Future without the Proposed Actions 14-31
The Future with the Proposed Actions 14-33
F. Detailed Pedestrian Analysis 14-35
Existing Conditions 14-35
The Future without the Proposed Actions 14-38
The Future with the Proposed Actions 14-41
G. Vehicular and Pedestrian Safety Evaluation 14-45
H. Parking Assessment 14-45
Existing Conditions 14-45
The Future without the Proposed Actions 14-47
The Future with the Proposed Actions 14-48

15: Air Quality 15-1
A. Introduction 15-1
Principal Conclusions 15-2
B. Pollutants for Analysis 15-2
Carbon Monoxide 15-3
Nitrogen Oxides, VOCs, and Ozone 15-3
Lead 15-4
Respirable Particulate Matter – PM_{10} and $PM_{2.5}$ 15-4
Sulfur Dioxide 15-5
Air Toxics 15-5
C. Air Quality Standards, Regulations and Benchmarks 15-5
National and State Air Quality Standards 15-5
NAAQS Attainment Status and State Implementation Plans 15-7
Determining the Significance of Air Quality Impacts 15-8
D. Methodology for Predicting Pollutant Concentrations 15-9
Mobile Sources 15-9
Stationary Sources 15-11
Industrial Sources 15-15
Additional Sources 15-16
E. Existing Conditions 15-18
F. The Future without the Proposed Actions 15-19
G. The Future with the Proposed Actions 15-19
Mobile Sources 15-19
Stationary Sources 15-20
Additional Sources 15-22

16: Greenhouse Gas Emissions and Climate Change 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Greenhouse Gas Emissions 16-4
Pollutants of Concern 16-4
Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 16-5
Methodology 16-7
Projected GHG Emissions 16-11

Elements that would Reduce GHG Emissions 16-14
C. Resilience to Climate Change 16-16
Development of Policy to Improve Climate Change Resilience 16-16
Resilience of the Proposed Projects to Climate Change 16-18

17: Noise 17-1
A. Introduction 17-1
Principal Conclusions 17-1
B. Acoustics Fundamentals 17-2
"A"-Weighted Sound Level (dBA) 17-2
Sound Level Descriptors 17-3
C. Noise Standards and Criteria 17-4
New York CEQR Noise Criteria 17-4
D. Existing Noise Levels 17-4
Equipment Used During Noise Monitoring 17-4
E. Noise Prediction Methodology 17-5
General Methodology 17-5
F. The Future without the Proposed Actions 17-6
G. The Future with the Proposed Actions 17-7
H. Noise Attenuation Measures 17-8
I. Consideration of the Hudson Tunnel Project 17-10
J. Mechanical Equipment 17-10

18: Public Health 18-1
A. Introduction 18-1
Principal Conclusions 18-1
B. Methodology 18-2
C. Public Health Assessment 18-2
Noise 18-2
Construction Noise 18-3

19: Neighborhood Character 19-1
A. Introduction 19-1
Principal Conclusions 19-2
B. Methodology 19-2
C. Preliminary Assessment 19-3
Defining Features 19-3
Assessment of the Potential to Affect the Defining Features of the Neighborhood 19-4

20: Construction 20-1
A. Introduction 20-1
Principal Conclusions 20-2
B. Governmental Coordination and Oversight 20-7
C. Construction Phasing and Schedule 20-8
D. Construction Description 20-9
Overview 20-9
General Construction Practices 20-9
General Construction Tasks 20-11

Number of Construction Workers and Material Deliveries 20-13
E. The Future without the Proposed Actions 20-14
F. Probable Impacts of the Proposed Actions 20-14
Transportation 20-15
Air Quality 20-23
Noise 20-31
Vibration 20-46
Other Technical Areas 20-48

21: Mitigation 21-1
A. Introduction 21-1
B. Principal Conclusions 21-2
Community Facilities – Publicly Funded Child Care Facilities 21-2
Open Space 21-3
Shadows 21-3
Transportation 21-4
Noise 21-5
Construction 21-5
C. Community Facilities – Publicly Funded Child Care Facilities 21-6
D. Open Space 21-8
E. Shadows 21-9
F. Transportation 21-9
Traffic 21-9
Pedestrians 21-12
G. Noise 21-13
H. Construction 21-13
Transportation 21-14
Noise 21-14

22: Project Permutations 22-1
A. Introduction 22-1
Principal Conclusions 22-2
B. Potential for Changes to Identified Impacts if a Project is not Pursued 22-3
Publicly Funded Child Care Centers 22-3
Open Space 22-4
Shadows 22-5
Transportation 22-6
Noise 22-8
Construction 22-8

23: Alternatives to the Proposed Actions 23-1
A. Introduction 23-1
B. No Action Alternative 23-1
Land Use, Zoning, and Public Policy 23-1
Socioeconomic Conditions 23-3
Community Facilities and Services 23-3
Open Space 23-3
Shadows 23-4

Historic and Cultural Resources....23-4
Urban Design and Visual Resources....23-4
Hazardous Materials....23-5
Water and Sewer Infrastructure....23-5
Solid Waste....23-5
Energy....23-5
Transportation....23-5
Air Quality....23-7
Greenhouse Gas Emissions and Climate Change....23-7
Noise....23-7
Public Health....23-8
Neighborhood Character....23-8
Construction Impacts....23-8
C. Reduced Impacts Alternative....23-8
Option 1....23-8
Option 2....23-10

24: Unavoidable Adverse Impacts....24-1
A. Introduction....24-1
B. Publicly Funded Child Care Facilities....24-1
C. Open Space....24-2
D. Shadows....24-3
E. Noise....24-3
F. Construction....24-4
Noise....24-4

25: Growth-Inducing Aspects of the Proposed Actions....25-1
A. Introduction....25-1

26: Irreversible and Irretrievable Commitments of Resources....26-1

27: Response to Comments on the DEIS....27-1
A. Introduction....27-1
B. List of Organizations and Individuals who Commented on the DEIS....27-1
Elected Officials....27-1
Community Board....27-1
Organizations....27-1
General Public....27-2
C. Comments and Responses....27-2
Project Description....27-2
Transportation....27-7
Construction....27-8
Mitigation....27-8
Miscellaneous....27-10

APPENDICES

Appendix A Proposed Text Amendments

Appendix B Waterfront Revitalization Program Consistency Assessment Forms

Appendix C Agency Correspondence

Appendix D High Line Plant Species

Appendix E Construction

Appendix F Comments Received on the Draft Environmental Impact Statement

List of Tables

1-1 Development Program for Proposed Projects (Approximate GSF) 1-14

2-1 Project Area – No Action Conditions (GSF) 2-6

2-2 2022 Background Development Projects 2-7

2-3 Project Area – Comparison of No Action and With Action Conditions (GSF) 2-12

3-1 Zoning Districts Located in the Study Area 3-6

4-1 2016 Private Employment in Socioeconomic Study Area, Manhattan, and New York City 4-8

4-2 2016 Private Businesses in Socioeconomic Study Area, Manhattan, and New York City 4-9

4-3 Annual Average Household Income (2000, 2011–2015 ACS) 4-12

4-4 Distribution of Household Incomes (2011–2015 ACS) 4-12

4-5 Average and Median Gross Rent (2000, 2011–2015 ACS) 4-13

4-6 Estimated Income for the Proposed Market-Rate Units 4-15

5-1 Preliminary Screening Analysis Criteria: Manhattan 5-3

5-2 Public Schools Serving the Study Area, Enrollment and Capacity Data, 2016–2017 School Year 5-5

5-3 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization: No Action Condition 5-6

5-4 Estimated Public Elementary and Intermediate School Enrollment, Capacity, and Utilization: With Action Condition 5-7

5-5 Public Libraries Serving the Project Area 5-9

5-6 Future without the Proposed Actions: Catchment Area Population 5-9

5-7 Future with the Proposed Actions: Catchment Area Population 5-10

5-8 Publicly Funded Child Care Facilities Serving the Study Area 5-12

5-9 Estimated Child Care Facility Enrollment, Capacity, and Utilization 5-13

6-1 Study Area Residential Population 6-5

6-2 Study Area Residential Population Age Breakdown 6-5

6-3 Existing Residential Study Area Open Spaces 6-8

6-4 Existing Conditions: Adequacy of Open Space Resources 6-10

6-5 No Action Condition: Adequacy of Open Space Resources 6-12
6-6 With Action Condition: Adequacy of Open Space Resources 6-14
6-7 Open Space Ratios Summary 6-14
7-1 Incremental Shadow Durations 7-6
8-1 Known Architectural Resources in the Study Area 8-7
11-1 Existing Water Consumption and Sewage Generation 11-4
11-2 Existing Surface Coverage 11-5
11-3 Water Consumption and Sewage Generation for the Proposed Projects 11-7
11-4 Proposed Surface Coverage 11-7
11-5 DEP Flow Volume Matrix: Existing and Build Volume Comparison 11-8
12-1 Existing Solid Waste Generation – Project Area 12-4
12-2 With Action Solid Waste Generation – Project Area 12-5
12-3 Comparison of Weekly Solid Waste Generation on Project Area (Existing, No Action, With Action Conditions) 12-6
13-1 Project Area – Existing Energy Consumption 13-3
13-2 Project Area – Projected Energy Consumption With Action Condition 13-3
14-1 Development Program for Analysis (Approximate GSF) Project Area 14-2
14-2 Summary of Significant Adverse Traffic Impacts 14-3
14-3 Summary of Significant Adverse Pedestrian Impacts 14-4
14-4 Travel Demand Assumptions 14-6
14-5 EMS Facility Staff Peak Hour Trips 14-7
14-6 Trip Generation Summary: Incremental Trips 14-9
14-7 Traffic Level 2 Screening Analysis Results With Action Incremental Vehicle Trips 14-12
14-8 Pedestrian Level 2 Screening Analysis Results With Action Incremental Pedestrian Trips 14-13
14-9 Level of Service Criteria for Signalized Intersections 14-15
14-10 Level of Service Criteria for Subway Station Elements 14-16
14-11 Significant Impact Guidance for Stairs and Passageways 14-17
14-12 Level of Service Criteria for Pedestrian Elements 14-19
14-13 Significant Impact Guidance for Sidewalks 14-20
14-14 Significant Impact Guidance for Corners and Crosswalks 14-21
14-15 Summary of Existing Traffic Analysis Results 14-23
14-16 Existing Conditions Level of Service Analysis Signalized Intersections 14-23

14-17 No Action Projects Anticipated to be Complete By 2022 14-25

14-18 Summary of No Action Traffic Analysis Results 14-27

14-19 Existing and 2022 No Action Conditions Level of Service Analysis Signalized Intersections 14-27

14-20 Summary of With Action Traffic Analysis Results 14-28

14-21 2022 No Action and With Action Conditions Level of Service Analysis Signalized Intersections 14-29

14-22 Existing Conditions Subway Line-Haul Analysis No. 7 Line 14-31

14-23 2022 No Action Condition Subway Vertical Circulation Element Analysis: Stairs 34th Street-Hudson Yards Station.....14-32

14-24 2022 No Action Condition Subway Vertical Circulation Element Analysis: Escalators 34th Street-Hudson Yards Station.....14-32

14-25 2022 No Action Condition Fare Array Analysis 34th Street-Hudson Yards Station..14-33

14-26 2022 No Action Condition Subway Line-Haul Analysis No. 7 Line 14-33

14-27 2022 With Action Condition Subway Vertical Circulation Element Analysis: Stairs 34th Street-Hudson Yards Station.....14-34

14-28 2022 With Action Condition Subway Vertical Circulation Element Analysis: Escalators 34th Street-Hudson Yards Station.....14-34

14-29 2022 With Action Condition Fare Array Analysis 34th Street-Hudson Yards Station14-35

14-30 2022 With Action Condition Subway Line-Haul Analysis No. 7 Line 14-35

14-31 Summary of Existing Pedestrian Analysis Results 14-36

14-32 Existing Conditions: Sidewalk Analysis.....14-37

14-33 Existing Conditions: Corner Analysis 14-37

14-34 Existing Conditions: Crosswalk Analysis.....14-38

14-35 Summary of 2022 No Action Pedestrian Analysis Results.....14-39

14-36 2022 No Action Condition: Sidewalk Analysis.....14-40

14-37 2022 No Action Condition: Corner Analysis.....14-40

14-38 2022 No Action Condition: Crosswalk Analysis.....14-41

14-39 Summary of 2022 With Action Pedestrian Analysis Results 14-42

14-40 2022 With Action Condition: Sidewalk Analysis.....14-43

14-41 2022 With Action Condition: Corner Analysis.....14-43

14-42 2022 With Action Condition: Crosswalk Analysis.....14-44

14-43 Accident Summary 14-45

14-44 On-Street Parking Regulations 14-46

14-45 Existing Weekday Off-Street Parking Supply and Utilization Approximately ¼-Mile Study Area 14-47

14-46 Existing and 2022 No Action Parking Supply and Utilization (¼-Mile) 14-47

14-47 Parking Demand from Proposed Projects – Weekday 14-48

14-48 2022 No Action and With Action Parking Supply and Utilization (¼-Mile) – Temporary Loss of Parking at Project Site A 14-49

15-1 National Ambient Air Quality Standards (NAAQS) 15-6

15-2 Maximum Background Pollutant Concentrations for Mobile Source Sites 15-11

15-3 Heating and Hot Water Systems Stack Parameters and Emission Rates 15-12

15-4 Project Site A Cogeneration System Stack Parameters and Emission Rates 15-13

15-5 Maximum Background Pollutant Concentrations 15-15

16-1 Global Warming Potential (GWP) for Major GHGs 16-5

16-2 Vehicle Miles Traveled per Year 16-10

16-3 Annual Building Energy Emissions, Project Site A 16-12

16-4 Annual Building Energy Emissions, Project Site B 16-12

16-5 Annual Mobile Source Emissions (Metric Tons CO_2E, 2022) 16-13

16-6 Total Construction GHG Emissions (Metric Tons CO_2E) 16-13

16-7 Summary of Annual GHG Emissions, 2021 (Metric Tons CO_2E, Excluding Construction) 16-13

17-1 Common Noise Levels 17-3

17-2 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 17-4

17-3 Existing Noise Levels in dBA 17-5

17-4 2022 No Action Condition Noise Levels (in dBA) 17-7

17-5 2022 With Action Condition Noise Levels (in dBA) 17-8

17-6 Required Attenuation at Noise Measurement Locations (in dBA) 17-8

17-7 Required Attenuation at Project Sites (in dBA) 17-9

20-1 Summary of Primary Agency Construction Oversight 20-8

20-2 Conceptual Construction Schedules 20-9

20-3 Average Number of Daily Construction Workers and Trucks by Year and Quarter Proposed Actions – Project Site A 20-14

20-4 Average Number of Daily Construction Workers and Trucks by Year and Quarter Proposed Actions – Project Site B 20-14

20-5 Peak Construction Vehicle Trip Projections Proposed Actions 20-16

20-6 Traffic Level 2 Screening Analysis Results With Action Incremental Vehicle Trips in PCEs 20-17

20-7 Summary of Existing Construction Traffic Analysis Results 20-17

20-8 Existing Conditions Level of Service Analysis Weekday Construction AM Peak Hour 20-18

20-9 Summary of No Action Construction Traffic Analysis Results 20-19

20-10 Existing and No Action Conditions Level of Service Analysis Weekday Construction AM Peak Hour 20-19

20-11 Summary of With Action Construction Traffic Analysis Results 20-20

20-12 No Action and With Action Conditions Level of Service Analysis Weekday Construction AM Peak Hour 20-20

20-13 Recommended Mitigation Measures Weekday Construction AM Peak Hour 20-21

20-14 No Action, With Action, and Mitigation Conditions Level of Service Analysis Weekday Construction AM Peak Hour 20-21

20-15 Background Pollutant Concentrations 20-28

20-16 Maximum Pollutant Concentrations from the Proposed Actions 20-29

20-17 Typical Construction Equipment Noise Emission Levels (dBA) 20-36

20-18 Noise Receptor Locations by Location and Associated Land Use 20-37

20-19 Noise Survey Results in dBA 20-38

20-20 Construction Noise Analysis Results in dBA 20-39

20-21 Vibration Source Levels for Construction Equipment 20-47

21-1 Summary of Significant Adverse Traffic Impacts 21-4

21-2 Summary of Significant Adverse Pedestrian Impacts 21-4

21-3 Child Care Slots to Be Funded 21-8

21-4 Recommended Mitigation Measures Weekday AM Peak Hour 21-10

21-5 Recommended Mitigation Measures Weekday Midday Peak Hour 21-10

21-6 Recommended Mitigation Measures Weekday PM Peak Hour 21-10

21-7 No Action, With Action, and Mitigation Conditions Level of Service Analysis Weekday AM Peak Hour 21-11

21-8 No Action, With Action, and Mitigation Conditions Level of Service Analysis Weekday Midday Peak Hour 21-11

21-9 2022 No Action and With Action Conditions Level of Service Analysis Weekday PM Peak Hour 21-11

21-10 No Action, With Action, and Mitigation Conditions Pedestrian Level of Service Analysis 21-12

21-11 Recommended Mitigation Measures Weekday Construction Am Peak Hour 21-14

22-1 Summary of Anticipated Impacts 22-2

22-2 Estimated Child Care Facility Enrollment, Capacity, and Utilization with Project Permutations 22-4

22-3 Open Space Ratios Summary with Project Permutations 22-5

22-4 Comparison of Trip Generation with Project Permutations 22-6

22-5 Summary of Significant Adverse Traffic Impacts and Mitigation Findings for Project Sites A and B 22-7

22-6 Summary of Significant Adverse Pedestrian Impacts for Project Sites A and B 22-7

22-7 Comparison of Construction Worker and Truck Projections with Project Permutations 22-9

23-1 Summary of Significant Adverse Traffic Impacts Avoided with the No Action Alternative 23-6

23-2 Summary of Significant Adverse Pedestrian Impacts Avoided with the No Action Alternative 23-7

List of Figures

Following page:

S-1 Project Location S-2
S-2 Project Sites S-2
S-3 Existing Zoning S-2
S-4 Proposed Zoning S-2
S-5 Project/Receiving Sites Tax Map S-2
S-6 Granting Site Tax Map S-4
S-7 Ground-Floor Plan S-14
S-8 Project Sites A and B: South Elevation S-14
S-9 Project Site A: East Elevation S-14
S-10 Project Sites A and B: North Elevation S-14
S-11 Project Site A: Proposed Roof Plan S-14
S-12 Project Site A: East-West Section of Proposed Tower S-14
S-13 Project Site A: North-South Section of Proposed Midrise Wing S-14
S-14 Project Site B: Proposed Roof Plan S-16
S-15 Project Site B: East-West Section of Proposed Building S-16
S-16 Project Site B: North-South Section of Proposed Building S-16
S-17 Comparison of Zoning Site Plans S-18
S-18 Comparison of Building Sections S-18
1-1 Project Location 1-2
1-2 Project Sites 1-2
1-3 Existing Zoning 1-2
1-4 Proposed Zoning 1-2
1-5 Project/Receiving Sites Tax Map 1-2
1-6 Granting Site Tax Map 1-4
1-7 Ground-Floor Plan 1-14
1-8 Project Sites A and B: South Elevation 1-14
1-9 Project Site A: East Elevation 1-14

1-10 Project Sites A and B: North Elevation 1-14
1-11 Project Site A: Proposed Roof Plan 1-14
1-12 Project Site A: East-West Section of Proposed Tower 1-14
1-13 Project Site A: North-South Section of Proposed Midrise Wing 1-14
1-14 Project Site B: Proposed Roof Plan 1-16
1-15 Project Site B: East-West Section of Proposed Building 1-16
1-16 Project Site B: North-South Section of Proposed Building 1-16
1-17 Comparison of Zoning Site Plans 1-17
1-18 Comparison of Building Sections 1-17
2-1 No Build Sites 2-8
3-1 Existing Land Use 3-2
3-2 Existing Zoning 3-6
3-3 New York City Coastal Zone Boundary 3-8
3-4 Proposed Zoning 3-12
4-1 Socioeconomic Study Area 4-4
5-1 Elementary and Intermediate Schools Serving the Study Area 5-4
5-2 Public Libraries Serving Study Area 5-10
5-3 Publicly Funded Child Care Services 5-12
6-1 Open Space Study Area 6-4
6-2 Open Space Resources 6-6
7-1 Tier 1 and 2 Assessments 7-4
7-2 Tier 3 Assessment 7-4
7-3 Tier 3 Assessment 7-4
7-4 December 21 7-6
7-5 December 21 7-6
7-6 December 21 7-6
7-7 March 21 / Sept. 21 7-6
7-8 March 21 / Sept. 21 7-6
7-9 March 21 / Sept. 21 7-6
7-10 March 21 / Sept. 21 7-6
7-11 May 6 / August 6 7-6
7-12 May 6 / August 6 7-6
7-13 May 6 / August 6 7-6

7-14 June 21 7-6
7-15 June 21 7-6
7-16 June 21 7-6
7-17 The High Line – Detail 7-6
8-1 Historic and Cultural Resources Project Location 8-4
8-2 Historic and Cultural Resources Project Site Photos 8-6
8-3 Historic and Cultural Resources Project Site Photos 8-6
8-4 Historic and Cultural Resources Known Architectural Resources 8-8
8-5 Photographs 8-8
8-6 Photographs 8-8
8-7 Photographs 8-10
9-1 Urban Design and Visual Resources Reference Map 9-2
9-2 Urban Design and Visual Resources Aerial Photograph 9-4
9-3 Existing Conditions 9-4
9-4 Existing Conditions 9-6
9-5 Existing Conditions 9-6
9-6 Existing Conditions 9-6
9-7 Existing Conditions 9-6
9-8 Existing Conditions 9-6
9-9 Existing Conditions 9-6
9-10 Proposed Massing of Project Site A and B with Existing and No Build Buildings 9-12
9-11 Illustrative Rendering of Project Site A 9-12
9-12 Illustrative Rendering of Project Site B 9-12
9-13 Comparison View from the High Line Looking Southeast 9-12
9-14 Comparison View from High Line Entrance Looking West 9-12
9-15 Comparison View from Eleventh Avenue and West 29th Street Looking Northwest 9-12
9-16 Comparison View from Eleventh Avenue and West 30th Street Looking Southwest 9-12
14-1 Project Sites 14-2
14-2 With Action Incremental Vehicle Trips Weekday AM Peak Hour 14-12
14-3 With Action Incremental Vehicle Trips Weekday Midday Peak Hour 14-12
14-4 With Action Incremental Vehicle Trips Weekday PM Peak Hour 14-12
14-5 Traffic Analysis Locations 14-12
14-6 With Action Incremental Pedestrian Trips Weekday AM Peak Hour 14-12

14-7 With Action Incremental Pedestrian Trips Weekday Midday Peak Hour 14-12
14-8 With Action Incremental Pedestrian Trips Weekday PM Peak Hour 14-12
14-9 Pedestrian Analysis Locations 14-14
14-10 Existing Traffic Volumes Weekday AM Peak Hour 14-24
14-11 Existing Traffic Volumes Weekday Midday Peak Hour 14-24
14-12 Existing Traffic Volumes Weekday PM Peak Hour 14-24
14-13 No Build Sites 14-24
14-14 2022 No Action Traffic Volumes Weekday AM Peak Hour 14-26
14-15 2022 No Action Traffic Volumes Weekday Midday Peak Hour 14-26
14-16 2022 No Action Traffic Volumes Weekday PM Peak Hour 14-26
14-17 2022 No Action Traffic Volumes Weekday AM Peak Hour 14-28
14-18 2022 No Action Traffic Volumes Weekday Midday Peak Hour 14-28
14-19 2022 No Action Traffic Volumes Weekday PM Peak Hour 14-28
14-20 Existing Pedestrian Volumes Weekday AM Peak Hour 14-36
14-21 Existing Pedestrian Volumes Weekday Midday Peak Hour 14-36
14-22 Existing Pedestrian Volumes Weekday PM Peak Hour 14-36
14-23 2022 No Action Pedestrian Volumes Weekday AM Peak Hour 14-38
14-24 2022 No Action Pedestrian Volumes Weekday Midday Peak Hour 14-38
14-25 2022 No Action Pedestrian Volumes Weekday PM Peak Hour 14-38
14-26 2022 With Action Pedestrian Volumes Weekday AM Peak Hour 14-42
14-27 2022 With Action Pedestrian Volumes Weekday Midday Peak Hour 14-42
14-28 2022 With Action Pedestrian Volumes Weekday PM Peak Hour 14-42
14-29 On-Street Parking Regulations 14-46
14-30 Off-Street Parking Facilities 14-46
17-1 Noise Receptor Locations 17-4
17-2 Window/Wall Attenuation Requirements 17-10
20-1 Conceptual Construction Schedules 20-8
20-2 Short-Term (24-Hour Average) $PM_{2.5}$ Construction Emissions Profile 20-26
20-3 Annual (Moving 12-Month Average) $PM_{2.5}$ Construction Emissions Profile 20-26
20-4 Construction Noise Receptor Locations 20-34
20-5 Construction Noise Impact Locations 20-44
22-1 The High Line – Detail Proposed Site A Building Alone 22-6
23-1 Reduction of Impacts Alternative - Option 1 23-10

23-2 Reduction of Impacts Alternative - Option 2.....23-10
23-3 The High Line - Detail Reduction of Impacts Alternative - Option 2 23-10
23-4 Elimination of Impacts Alternative.....23-12
23-5 The High Line - Detail Elimination of Impacts Alternative 23-12

✷