DeWitt Clinton Park North (801 Eleventh Avenue & 629 West 54th Street)

Draft Environmental Impact Statement

PREPARED FOR

760 12th, LLC and 801 11th Ave., LLC
770 Lexington Avenue
New York, NY, 10065
212.888.7400 ext. 7315

PREPARED BY

VHB Engineering, Surveying and Landscape Architecture, P.C.
One Penn Plaza
Suite 715
New York, NY 10119
212.722.9247

CEQR #25DCP049M

December 12, 2025

Table of Contents

Chapter Page

Executive Summary ES-1

Introduction ES-1
Project Area and Development Sites ES-1
Neighborhood Context ES-8
Proposed Actions ES-9
Proposed Projects ES-10
Project Purpose and Need ES-14
Analysis Framework ES-15
Identification of Development Sites ES-15
Analysis (Build) Year ES-15
Reasonable Worst-Case Development Scenario ES-15
Principal Conclusions of Environmental Analysis ES-20
Land Use, Zoning, and Public Policy ES-20
Socioeconomic Conditions ES-21
Community Facilities and Services ES-22
Open Space ES-23
Shadows ES-25
Urban Design and Visual Resources ES-25
Hazardous Materials ES-26
Water and Sewer Infrastructure ES-27
Transportation ES-27
Air Quality ES-29
Greenhouse Gas Emissions ES-29
Noise ES-30
Public Health ES-31
Neighborhood Character ES-31
Construction ES-31
Effects on Disadvantaged Communities ES-36
Mitigation ES-36
Project Permutations ES-38
Alternatives ES-38
Unavoidable Significant Adverse Impacts ES-40
Growth-Inducing Aspects of the Proposed Project ES-41
Irreversible and Irretrievable Commitments of Resources ES-42

Project Description 1-1

Introduction 1-1
Project Area and Development Sites 1-2
Neighborhood Context 1-8

Proposed Actions 1-9
Proposed Projects 1-10
Project Purpose and Need 1-14
Analysis Framework 1-15
Identification of Development Sites *1-15*
Analysis (Build) Year *1-15*
Reasonable Worst-Case Development Scenario *1-15*
Public Review Process 1-20
Environmental Review Process 1-21
CEQR and SEQRA *1-21*

Land Use, Zoning, and Public Policy 2-1

Introduction 2-1
Principal Conclusions 2-6
Land Use and Zoning *2-6*
Public Policy *2-6*
Methodology 2-6
Study Area Definition *2-7*
Assessment 2-7
Existing Conditions *2-7*
No-Action Condition *2-20*
With-Action Condition *2-21*

Socioeconomic Conditions 3-1

Introduction 3-1
Principal Conclusions 3-2
Methodology 3-3
Analysis Format *3-3*
Indirect Residential Displacement Methodology *3-4*
Preliminary Assessment 3-6
Existing Conditions *3-6*
No-Action Condition *3-8*
With Action Condition *3-9*

Community Facilities and Services 4-1

Introduction 4-1
Principal Conclusions 4-2
Indirect Effects on Public Schools *4-2*
Indirect Effects on Early Childhood Programs *4-3*
Indirect Effects on Libraries *4-3*
Methodology 4-3
Public Schools *4-4*
Early Childhood Programs *4-5*
Libraries *4-5*
Detailed Assessment: Public Schools 4-7

Existing Conditions *4-7*
No-Action Condition *4-10*
With-Action Condition *4-11*
Detailed Analysis: Early Childhood Programs 4-11
Existing Conditions *4-11*
No-Action Condition *4-13*
Future With-Action Condition *4-14*
Detailed Analysis: Libraries 4-14
Existing Conditions *4-14*
No-Action Condition *4-16*
With-Action Condition *4-16*

Open Space 5-1

Introduction 5-1
Principal Conclusions 5-2
Direct Effects *5-2*
Indirect Effects *5-2*
Methodology 5-3
Direct Effects Analysis *5-4*
Indirect Analysis *5-4*
Detailed Assessment 5-9
Existing Conditions *5-9*
No-Action Condition *5-18*
With-Action Condition *5-21*

Shadows 6-1

Introduction 6-1
Principal Conclusions 6-2
Methodology 6-2
Sunlight-Sensitive Resources *6-3*
Preliminary Assessment *6-3*
Determination of Significance *6-4*
Preliminary Assessment 6-5
Tiers 1 and 2 Screening *6-5*
Tier 3 Screening Assessment *6-8*
Detailed Assessment 6-13
No-Action Condition *6-13*
With-Action Condition *6-13*

Urban Design and Visual Resources 7-1

Introduction 7-1
Principal Conclusions 7-2
Urban Design *7-2*
Visual Resources *7-2*
Methodology 7-2

Assessment Criteria *7-3*
Study Area *7-4*
Detailed Analysis 7-4
Existing Conditions *7-4*
No-Action Condition *7-17*
With-Action Condition *7-26*

Hazardous Materials 8-1

Introduction 8-1
Principal Conclusions 8-2
Methodology 8-2
Assessment 8-4
Existing Conditions *8-4*
Future No-Action Condition *8-6*
Future With-Action Condition *8-6*

Water and Sewer Infrastructure 9-1

Introduction 9-1
Principal Conclusions 9-2
Methodology 9-3
Existing Conditions 9-3
Water Supply *9-4*
Conveyance System *9-5*
Sanitary Flows *9-6*
Stormwater Flows *9-7*
The Future Without the Proposed Actions 9-8
The Future with the Proposed Actions 9-8
Water Demand *9-8*
Sanitary Flows *9-9*
Stormwater Flows *9-9*

Transportation 10-1

Introduction 10-1
Principal Conclusions 10-4
Traffic *10-4*
Parking *10-5*
Subways *10-5*
Buses *10-5*
Pedestrians *10-5*
Vehicular and Pedestrian Safety *10-5*
Methodology 10-5
Level 1 Screening Assessment *10-6*
Level 1 Screening Results *10-11*
Level 2 Screening Assessment *10-14*
Level 2 Screening Results *10-25*

Detailed Analysis Methodology 10-34
Traffic *10-34*
Parking *10-35*
Transit *10-35*
Pedestrians *10-37*
Vehicle and Pedestrian Safety *10-40*
Existing Conditions 10-41
Traffic *10-41*
Parking *10-48*
Subways *10-51*
Buses *10-53*
Pedestrians *10-55*
No-Action Conditions 10-58
Traffic *10-58*
Parking *10-65*
Subways *10-65*
Buses *10-68*
Pedestrians *10-69*
With-Action Conditions 10-73
Traffic *10-73*
Parking *10-83*
Subways *10-84*
Buses *10-88*
Pedestrians *10-89*
Vehicular and Pedestrian Safety *10-93*

Air Quality 11-1

Introduction 11-1
Principal Conclusions 11-2
Mobile Source Analyses *11-2*
HVAC and Hot Water Analysis *11-2*
Industrial Source Analysis *11-3*
Large or Major Source Analysis *11-3*
National Ambient Air Quality Standards 11-3
Pollutants of Concern 11-5
Regulatory Context 11-5
Impact Criteria 11-6
CO de Minimis Criteria *11-6*
$PM_{2.5}$ de Minimis Criteria *11-6*
Non-Criteria Pollutant Thresholds *11-7*
Background Concentrations 11-7
Methodology 11-8
Mobile Sources *11-8*
Stationary Sources *11-10*
Assessment 11-14
Mobile Sources *11-14*

Stationary Sources *11-14*
Conclusion *11-22*

Greenhouse Gas Emissions and Climate Change 12-1

Introduction 12-1
Principal Conclusions 12-2
Pollutants of Concern 12-3
Climate Change Initiatives 12-8
Methodology 12-9
GHG Emissions Assessment *12-9*
Climate Change Assessment *12-10*
Assessment 12-11
Direct GHG Emissions *12-11*
Indirect GHG Emissions *12-12*
Mobile Source Emissions *12-13*
Construction Emissions *12-13*
Consistency with the GHG Reduction Goals *12-14*
Resilience to Climate Change *12-16*

Noise 13-1

Introduction 13-1
Principal Conclusions 13-2
Noise Background 13-3
Noise Standards and Impact Criteria 13-5
Noise Exposure Guidelines *13-5*
Impact Criteria *13-5*
Assessment Methodology 13-7
General Methodology *13-7*
Mobile Sources *13-8*
Stationary Sources *13-10*
Existing Condition 13-10
No-Action Condition 13-14
With-Action Condition 13-15
Acceptability Assessment *13-18*

Public Health 14-1

Introduction 14-1
Principal Conclusions 14-2
Methodology 14-2
Assessment 14-2
Operational Period *14-2*
Construction Period *14-5*

Neighborhood Character 15-1

Introduction 15-1

Principal Conclusions 15-2
Methodology 15-2
Preliminary Assessment 15-4
Defining Features of the Neighborhood 15-4
Potential to Affect the Defining Features of the Neighborhood 15-5
Potential to Affect the Contributing Elements of Neighborhood Character 15-5

Construction 16-1

Introduction 16-1
Principal Conclusions 16-2
Transportation 16-2
Air Quality 16-3
Noise 16-3
Vibration 16-4
Other Technical Areas 16-5
Methodology 16-6
Construction Regulations and General Practices 16-6
Construction Oversight 16-6
Construction Hours 16-7
Construction Practices 16-7
Construction Description 16-8
Construction Schedule 16-8
Number of Construction Workers and Material Deliveries 16-12
Assessment of Project Construction 16-13
Land Use and Neighborhood Character 16-13
Socioeconomic Conditions 16-13
Community Facilities 16-13
Open Space 16-13
Historic and Cultural Resources 16-13
Natural Resources 16-14
Hazardous Materials 16-14
Water and Sewer Infrastructure 16-14
Transportation 16-14
Air Quality 16-40
Noise 16-44
Vibration 16-67

Effects on Disadvantaged Communities 17-1

Introduction 17-1
Principal Conclusions 17-2
Methodology 17-2
Study Area 17-3
Disadvantaged Communities Assessment 17-5
Impact Summary 17-5
Determination 17-7

Mitigation 18-1

Introduction 18-1
Principal Conclusions 18-1
Transportation 18-2
Construction 18-2
Transportation 18-3
Traffic 18-3
Buses 18-7
Construction 18-7
Traffic 18-7
Noise 18-18

Project Permutations 19-1

Introduction 19-1
Principal Conclusions 19-2
Potential for Changes to Identified Impacts if a Project is Not Pursued 19-3
Transportation 19-3
Construction 19-6

Alternatives 20-1

Introduction 20-1
Principal Conclusions 20-2
No-Action Alternative 20-2
No Unmitigated Significant Adverse Impacts Alternative 20-3
No Special Permit Alternative 20-3
No-Action Alternative 20-3
Description of the No-Action Alternative 20-3
Land Use, Zoning, and Public Policy 20-4
Socioeconomic Conditions 20-5
Community Facilities and Services 20-5
Open Space 20-5
Shadows 20-5
Urban Design and Visual Resources 20-6
Hazardous Materials 20-6
Water and Sewer Infrastructure 20-6
Transportation 20-6
Air Quality 20-6
Greenhouse Gas Emissions and Climate Change 20-7
Noise 20-7
Public Health 20-7
Neighborhood Character 20-7
Construction 20-7
Disadvantaged Communities 20-8
No Unmitigated Significant Adverse Impacts Alternative 20-8
Description of the No Unmitigated Significant Adverse Impacts Alternative 20-8

Construction *20-9*
No Special Permit Alternative 20-10
Description of the No Special Permit Alternative *20-10*
Land Use, Zoning, and Public Policy *20-11*
Socioeconomic Conditions *20-12*
Community Facilities and Services *20-12*
Open Space *20-12*
Shadows *20-13*
Urban Design and Visual Resources *20-13*
Hazardous Materials *20-13*
Water and Sewer Infrastructure *20-13*
Transportation *20-13*
Air Quality *20-15*
Greenhouse Gas Emissions and Climate Change *20-17*
Noise *20-17*
Neighborhood Character *20-18*
Public Health *20-18*
Construction *20-18*
Disadvantaged Communities *20-19*

Unavoidable Significant Adverse Impacts 21-1

Introduction 21-1
Construction 21-1
Traffic *21-1*
Noise *21-2*

Growth-Inducing Aspects of the Proposed Project 22-1

Introduction 22-1
Assessment 22-2

Irreversible and Irretrievable Commitments of Resources 23-1

Appendices

Appendix A ..... Waterfront Revitalization Program Consistancy Assessment

Appendix B ..... Phase I ESAs

Appendix C ..... Agency Correspondence

List of Tables

Table No.	Title	Page
Table ES-1	Future No-Action and With-Action Comparison	ES-20
Table ES-2	Summary of Anticipated Significant Impacts	ES-38
Table 1-1	Future No-Action and With-Action Comparison	1-20
Table 2-1	Study Area Generalized Land Use	2-10
Table 3-1	Area Population	3-6
Table 3-2	Household and Housing Data	3-6
Table 3-3	Housing Tenure	3-7
Table 3-4	Median Gross Rent	3-7
Table 3-5	Average and Median Household Income	3-8
Table 3-6	Household Income Distribution	3-8
Table 3-7	No-Build Developments and Estimated No-Action Population	3-9
Table 3-8	2024 New York City AMI	3-10
Table 3-9	Estimated Income for Market Rate Units	3-11
Table 4-1	Public School Enrollment, Capacity, and Utilization for Existing Conditions, School District 2, Subdistrict 3	4-8
Table 4-2	Projected Public School Enrollment, Capacity, and Utilization for No-Action Condition, School District 2, Subdistrict 3	4-10
Table 4-3	Projected Public School Enrollment, Capacity, and Utilization for With-Action Condition, School District 2, Subdistrict 3	4-11
Table 4-4	Publicly Funded Early Childhood Programs Serving the Study Area	4-12
Table 4-5	Childcare Eligible Children Anticipated in No-Action Development Projects	4-13
Table 4-6	No-Action Condition Estimated Publicly Funded Childcare Center Enrollment, Capacity, and Utilization	4-14
Table 4-7	With Action Condition Estimated Publicly Funded Child Care Center Enrollment, Capacity and Utilization	4-14
Table 4-8	No-Action Developments Within Library Catchment Area	4-16
Table 4-9	No-Action Condition Public Library Catchment Area Population and Holdings	4-16
Table 4-10	With-Action Condition Public Library Catchment Area Population and Holdings	4-16
Table 5-1	Percent Change Guidance to Determine Possible Open Space Impact	5-8

Table 5-2 Existing Population in the Residential Study Area 5-9
Table 5-3 Approximate Population from Developments Completed Since April 2020 5-10
Table 5-4 Existing Population within the Study Area 5-11
Table 5-5 Existing Worker Population in the Non-Residential Study Area 5-12
Table 5-6 Existing Open Space Resources 5-15
Table 5-7 Existing Conditions – Adequacy of Open Space Resources 5-18
Table 5-8 No-Action Condition: No-Build Developments Estimated Population 5-19
Table 5-9 No-Action Conditions – Adequacy of Open Space Resources 5-20
Table 5-10 With-Action Condition Study Area Populations 5-21
Table 5-11 With-Action Conditions – Adequacy of Open Space Resources 5-22
Table 6-1 Sunlight-Sensitive Resources in the Study Area 6-7
Table 6-2 Tier 1 through 3 Shadows Screening Results 6-13
Table 6-3 Detailed Analysis Summary of Incremental Shadow Entry/Exit Times 6-14
Table 9-1 Water Consumption and Wastewater Generation Rates 9-5
Table 9-2 Existing Water Consumption and Sewage Generation 9-5
Table 9-3 North River Average Monthly Flows 9-6
Table 9-4 Existing Surface Coverage 9-7
Table 9-5 NYC DEP Flow Volume Matrix – Existing Conditions 9-8
Table 9-6 With-Action Water Consumption and Sewage Generation 9-9
Table 9-7 With-Action Surface Coverage 9-9
Table 9-8 NYC DEP Flow Volume Matrix – With-Action Conditions 9-10
Table 9-9 Existing and With-Action Comparison Total Volume to North River WRRF 9-11
Table 10-1 Development Increment for Analysis 10-4
Table 10-2 Travel Demand Characteristics (Weekday) 10-7
Table 10-3 Travel Demand Characteristics (Saturday) 10-8
Table 10-4 Maximum Commercial Development Trip Generation Summary – Person Trips 10-12
Table 10-5 Maximum Residential Development Trip Generation Summary – Person Trips 10-12
Table 10-6 Maximum Commercial Development Trip Generation Summary – Vehicle Trips 10-13
Table 10-7 Maximum Residential Development Trip Generation Summary – Vehicle Trips 10-13
Table 10-8 Level 2 Screening Assessment Results – Vehicle Trips 10-26
Table 10-9 Level 2 Screening Assessment Results – Bus Trips 10-27
Table 10-10 Level 2 Screening Assessment Results – Subway Trips 10-28

Table 10-11 Level 2 Screening Assessment Results – Pedestrian Trips 10-29
Table 10-12 Level of Service Criteria for Subway Station Elements 10-36
Table 10-13 Significant Impact Guidance for Stairs and Passageways 10-36
Table 10-14 Level of Service Criteria for Pedestrian Elements 10-38
Table 10-15 Significant Impact Criteria for Sidewalks – CBD Areas 10-39
Table 10-16 Significant Impact Criteria for Corners and Crosswalks 10-40
Table 10-17 Year 2024 Existing Traffic Level of Service Summary – Overall Intersections 10-46
Table 10-18 Year 2024 Existing Traffic Level of Service Summary – Traffic Movements 10-46
Table 10-19 Existing Traffic Level of Service 10-46
Table 10-20 Off-Street Parking Inventory 10-50
Table 10-21 Existing Subway Station Level of Service – Fare Control Areas 10-52
Table 10-22 Existing Subway Station Level of Service – Stairways – AM Peak Hour 10-52
Table 10-23 Existing Subway Station Level of Service – Stairways – PM Peak Hour 10-53
Table 10-24 Existing Local Bus Analysis 10-54
Table 10-25 Year 2024 Existing Pedestrian Levels of Service Summary 10-55
Table 10-26 Year 2024 Existing Pedestrian Levels of Service – Sidewalks 10-56
Table 10-27 Year 2024 Existing Pedestrian Levels of Service – Crosswalks 10-57
Table 10-28 Year 2024 Existing Pedestrian Levels of Service – Corners 10-58
Table 10-29 Background Development Projects 10-59
Table 10-30 Year 2029 No-Action Traffic Level of Service Summary – Overall Intersections 10-63
Table 10-31 Year 2029 No-Action Traffic Level of Service Summary – Traffic Movements 10-63
Table 10-32 Year 2029 No-Action Traffic Level of Service 10-64
Table 10-33 No-Action Subway Station Level of Service – Fare Control Areas 10-66
Table 10-34 No-Action Subway Station Level of Service – Stairways – AM Peak Hour 10-66
Table 10-35 No-Action Subway Station Level of Service – Stairways – PM Peak Hour 10-67
Table 10-36 No-Action Subway Station Level of Service – Escalators 10-68
Table 10-37 No-Action Local Bus Analysis 10-69
Table 10-38 Year 2029 No-Action Pedestrian Levels of Service Summary 10-70
Table 10-39 Year 2029 No-Action Pedestrian Levels of Service – Sidewalks 10-71
Table 10-40 Year 2029 No-Action Pedestrian Levels of Service – Crosswalks 10-72
Table 10-41 Year 2029 No-Action Pedestrian Levels of Service – Corners 10-73
Table 10-42 Year 2029 With-Action Traffic Level of Service Summary – Overall Intersections 10-77

Table 10-43 Year 2029 With-Action Traffic Level of Service Summary – Traffic Movements 10-77
Table 10-44 No-Action vs. With-Action Traffic Level of Service – Weekday AM Peak Hour 10-78
Table 10-45 No-Action vs. With-Action Traffic Level of Service – Weekday PM Peak Hour 10-79
Table 10-46 No-Action vs. With-Action Traffic Level of Service – Saturday Peak Hour 10-80
Table 10-47 Projected Weekday Parking Demand 10-83
Table 10-48 Projected Saturday Parking Demand 10-84
Table 10-49 No-Action vs. With-Action Subway Station Level of Service – Fare Control Areas 10-85
Table 10-50 No-Action vs. With-Action Subway Station Level of Service – Stairways – AM Peak Hour 10-86
Table 10-51 No-Action vs. With-Action Subway Station Level of Service – Stairways – PM Peak Hour 10-87
Table 10-52 No-Action vs With-Action Subway Station Level of Service – Escalators 10-88
Table 10-53 With-Action Bus Analysis 10-89
Table 10-54 Year 2029 With-Action Pedestrian Levels of Service Summary 10-90
Table 10-55 Year 2029 With-Action Pedestrian Levels of Service – Sidewalks 10-91
Table 10-56 Year 2029 With-Action Pedestrian Levels of Service – Crosswalks 10-92
Table 10-57 Year 2029 With-Action Pedestrian Levels of Service – Corners 10-93
Table 10-58 Vehicle and Pedestrian Crash Summary 10-94
Table 11-1 National and New York Ambient Air Quality Standards 11-4
Table 11-2 Background Concentrations 11-8
Table 11-3 Highest Predicted CO Concentration from the Atypical Source (ppm) 11-14
Table 11-4 Highest Predicted PM_{10} Concentration from the Atypical Source ($\mu g/m^3$) 11-14
Table 11-5 Highest Predicted $PM_{2.5}$ Concentration from the Atypical Source ($\mu g/m^3$) 11-14
Table 11-6 NYCDEP Permits: Emergency or Portable Generators 11-18
Table 11-7 Results of Industrial Source Analysis 11-19
Table 11-8 Hazard Index Assessment 11-20
Table 11-9 Major Source Stack Parameters 11-20
Table 11-10 Major Source Emission Rates (g/sec) 11-21
Table 11-11 Highest Concentrations from the Major Source 11-21
Table 12-1 Global Warming Potential for Primary Greenhouse Gases (GHGs) 12-4
Table 12-2 Development Site 1 - GHG Emissions from Natural Gas Consumption 12-11
Table 12-3 Development Site 2 - GHG Emissions from Natural Gas Consumption 12-12

Table 12-4 Development Site 1 - GHG Emissions from Electricity Generation 12-12
Table 12-5 Development Site 2 - GHG Emissions from Electricity Generation 12-13
Table 12-6 GHG Emissions from Mobile Sources 12-13
Table 12-7 Local Law 97 GHG Limits of the Proposed Projects 12-15
Table 13-1 Common Indoor and Outdoor Sound Levels 13-4
Table 13-2 Noise Exposure Guidelines for Use in City Environmental Impact Review[1] 13-6
Table 13-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 13-7
Table 13-4 Ambient Sound Level Measurements 13-11
Table 13-5 Existing Condition and Measurement Noise PCEs 13-12
Table 13-6 Predicted Existing Condition Noise Levels Compared to Measurement Noise Levels 13-13
Table 13-7 No-Action and Existing Condition Noise PCEs 13-14
Table 13-8 Predicted No-Action Noise Levels Compared to Existing Condition Noise Levels 13-15
Table 13-9 With-Action and No-Action Condition Noise PCEs 13-17
Table 13-10 Predicted With-Action Noise Levels Compared to No-Action Noise Levels 13-18
Table 13-11 Predicted With-Action Noise Level and Required Building Attenuation Value 13-19
Table 16-1 Average Number of Daily Construction Workers and Trucks by Quarter 16-12
Table 16-2 Average Number of Daily Construction PCE Trips by Quarter 16-15
Table 16-3 Construction Vehicle Trips by Hour (Q3 2028) 16-16
Table 16-4 Vehicle Trips Comparison – Construction vs. Operational Conditions 16-16
Table 16-5 Year 2024 Existing Traffic Level of Service 16-20
Table 16-6 Year 2028 No-Action Traffic Level of Service 16-25
Table 16-7 Year 2028 No-Action vs. With-Action Traffic Levels of Service – AM Construction Peak Hour 16-33
Table 16-8 Year 2028 No-Action vs. With-Action Traffic Levels of Service – PM Construction Peak Hour 16-36
Table 16-9 Pollutants for Analysis and Averaging Periods 16-40
Table 16-10 Highest Predicted Total Concentrations for Construction Activities 16-44
Table 16-11 Receptors and Land Uses 16-49
Table 16-12 Construction Mobile Source Analysis 16-51
Table 16-13 Sound Levels and Maximum Numbers of the Construction Equipment 16-54
Table 16-14 Background Noise Level (dBA, Leq) 16-55

Table 16-15 Worst-Case Construction Noise Levels by Phase (dBA, Leq) 16-58
Table 16-16 Worst-Case Construction Noise Levels, Increase by Phase (dBA, Leq) 16-59
Table 16-17 Worst-Case Construction Interior Noise Levels by Phase (dBA, L10) 16-61
Table 18-1 Traffic Impact Mitigation Summary 18-3
Table 18-2 Summary of Significantly Impacted Traffic Movements 18-4
Table 18-3 Year 2029 No-Action vs. With-Action vs Mitigation Traffic Levels of Service – Saturday Peak Hour 18-5
Table 18-4 With-Action with Mitigation Bus Analysis 18-7
Table 18-5 Year 2028 No-Action vs. With-Action vs. Mitigation Traffic Levels of Service – AM Construction Peak Hour 18-9
Table 18-6 Year 2028 No-Action vs. With-Action vs. Mitigation Traffic Levels of Service – PM Construction Peak Hour 18-13
Table 19-1 Summary of Anticipated Significant Impacts 19-2
Table 19-2 Trip Generation Summary – Person Trips 19-4
Table 19-3 Trip Generation Summary – Vehicle Trips 19-5
Table 19-4 Comparison of Significant Bus Impacts 19-6
Table 19-5 Average Number of Daily Construction Workers and Trucks by Quarter 19-7
Table 20-1 Future No-Action and With-Action Comparison 20-11
Table 20-2 Comparison of Bus Shortfall 20-15

List of Figures

Figure No.	Title	Page

Figure ES-1 Site Location Map ES-3
Figure ES-2 Granting Sites ES-4
Figure ES-3 Development/Receiving Sites ES-5
Figure ES-4 Proposed Project Site Plan: Development Site 1 ..... ES-12
Figure ES-5 Proposed Project Site Plan: Development Site 2 ..... ES-13
Figure ES-6 Maximum Residential Scenario: Development Site 1 ..... ES-18
Figure ES-7 Maximum Residential Scenario: Development Site 2 ..... ES-19
Figure 1-1 Site Location Map 1-3

Figure 1-2 Granting Sites 1-4
Figure 1-3 Development/Receiving Sites 1-5
Figure 1-4 Proposed Project Site Plan: Development Site 1 1-12
Figure 1-5 Proposed Project Site Plan: Development Site 2 1-13
Figure 1-6 Maximum Residential Scenario: Development Site 1 1-18
Figure 1-7 Maximum Residential Scenario: Development Site 2 1-19
Figure 2-1 Site Location Map 2-3
Figure 2-2 Receiving Sites 2-4
Figure 2-3 Granting Sites 2-5
Figure 2-4 Tax Map 2-9
Figure 2-5 Land Use Map 2-12
Figure 2-6 Existing Zoning Map 2-16
Figure 2-7 Zoning District Comparison 2-25
Figure 2-8 Zoning District of the Granting Sites 2-26
Figure 3-1 Socioeconomic Study Area 3-5
Figure 4-1 Public Schools District 2, Subdistrict 3 4-9
Figure 4-2 Libraries Study Area 4-15
Figure 5-1 Open Space Study Area Map 5-5
Figure 5-2 Walk-to-a-Park Service Area 5-6
Figure 5-3 Proposed No-Build Open Space 5-20
Figure 6-1 Tiers 1 and Tier 2 Screening 6-6
Figure 6-2 Tier 3 Screening December 21 Analysis Day 6-9
Figure 6-3 Tier 3 Screening March 21 Analysis Day 6-10
Figure 6-4 Tier 3 Screening May 6 Analysis Day 6-11
Figure 6-5 Tier 3 Screening June 21 Analysis Day 6-12
Figure 6-6 June 21 – 8:00 AM 6-22
Figure 6-7 December 21 – 10:00 AM 6-24
Figure 6-8 December 21 – 11:00 AM 6-25
Figure 6-9 December 21 – 12:00 PM 6-26
Figure 6-10 March 21/September 21 – 8:00 AM 6-27
Figure 6-11 March 21/September 21 – 9:00 AM 6-28
Figure 6-12 March 21/September 21 – 10:00 AM 6-29

Figure 6-13 March 21/September 21 – 11:00 AM 6-30
Figure 6-14 March 21/September 21 – 12:00 PM 6-31
Figure 6-15 May 6/August 6 – 7:00 AM 6-32
Figure 6-16 May 6/August 6 – 8:00 AM 6-33
Figure 6-17 May 6/August 6 – 9:00 AM 6-34
Figure 6-18 May 6/August 6 – 10:00 AM 6-35
Figure 6-19 May 6/August 6 – 11:00 AM 6-36
Figure 6-20 June 21 – 6:15 AM 6-37
Figure 6-21 June 21 – 7:15 AM 6-38
Figure 6-22 June 21 – 8:15 AM 6-39
Figure 6-23 June 21 – 9:15 AM 6-40
Figure 6-24 June 21 – 10:15 AM 6-41
Figure 6-25 December 21 – 9:00 AM 6-43
Figure 6-26 December 21 – 10:00 AM 6-44
Figure 6-27 December 21 – 11:00 AM 6-45
Figure 6-28 March 21/September 21 – 8:15 AM 6-46
Figure 6-29 March 21/September 21 – 9:15 AM 6-47
Figure 6-30 March 21/September 21 – 10:15 AM 6-48
Figure 6-31 May 6/August 6 – 8:00 AM 6-49
Figure 6-32 May 6/August 6 – 9:00 AM 6-50
Figure 6-33 May 6/August 6 – 10:00 AM 6-51
Figure 6-34 December 21 – 9:15 AM 6-53
Figure 6-35 December 21 – 10:15 AM 6-54
Figure 6-36 December 21 – 11:15 AM 6-55
Figure 6-37 December 21 – 9:00 AM 6-57
Figure 6-38 December 21 – 10:00 AM 6-58
Figure 6-39 December 21 – 11:00 AM 6-59
Figure 6-40 December 21 – 12:00 PM 6-60
Figure 6-41 March 21/September 21 – 8:00 AM 6-61
Figure 6-42 March 21/September 21 – 9:00 AM 6-62
Figure 6-43 March 21/September 21 – 10:00 AM 6-63
Figure 6-44 May 6/August 6 – 7:00 AM 6-64

Figure 6-45 May 6/August 6 – 8:00 AM 6-65
Figure 6-46 June 21 – 6:30 AM 6-66
Figure 6-47 June 21 – 7:30 AM 6-67
Figure 7-1 Development Site and Study Area Photograph Locations 7-9
Figure 7-2 Comparative View Facing West on Eleventh Avenue at West 56th Street 7-19
Figure 7-3 Comparative View Facing North on Eleventh Avenue at West 54th Street 7-20
Figure 7-4 Comparative View Facing North from DeWitt Clinton Park 7-21
Figure 7-5 Comparative View Facing South on Twelfth Avenue between West 55th Street and West 56th Street 7-22
Figure 7-6 Comparative View Facing West on Eleventh Avenue at West 54th Street 7-23
Figure 7-7 Comparative View Facing North on the Hudson River Greenway at West 52nd Street 7-24
Figure 7-8 Comparative View Facing East from Hudson River Park at West 55th Street 7-25
Figure 7-9 Illustrative Rendering of Development Site 1 7-26
Figure 7-10 Illustrative Rendering of Development Site 2 7-27
Figure 7-11 Development Sites Illustrative Aerial Rendering 7-27
Figure 7-12 Development Site 1 Illustrative Sections – Maximum Commercial Scenario 7-29
Figure 7-13 Development Site 2 Illustrative Sections – Maximum Commercial Scenario 7-30
Figure 7-14 Development Site 1 Illustrative Sections – Maximum Residential Scenario 7-31
Figure 7-15 Development Site 2 Illustrative Sections – Maximum Residential Scenario 7-32
Figure 7-16 Development Site 1 Illustrative Axonometric Diagrams 7-33
Figure 7-17 Development Site 2 Illustrative Axonometric Diagrams 7-34
Figure 9-1 Project Site, North River WRRF, Outfall NR-035 9-7
Figure 10-1 Project Location 10-3
Figure 10-2 Project-Generated Vehicle Trips – Weekday AM Peak Hour 10-16
Figure 10-3 Project-Generated Vehicle Trips – Weekday Midday Peak Hour 10-17
Figure 10-4 Project-Generated Vehicle Trips – Weekday PM Peak Hour 10-18
Figure 10-5 Project-Generated Vehicle Trips – Saturday Peak Hour 10-19
Figure 10-6 Project-Generated Pedestrian Trips – Weekday AM Peak Hour 10-21
Figure 10-7 Project-Generated Pedestrian Trips – Weekday Midday Peak Hour 10-22
Figure 10-8 Project-Generated Pedestrian Trips – Weekday PM Peak Hour 10-23
Figure 10-9 Project-Generated Pedestrian Trips – Saturday Peak Hour 10-24

Figure 10-10 Traffic Study Area 10-25
Figure 10-11 Transit Study Area 10-32
Figure 10-12 Pedestrian Study Area 10-33
Figure 10-13 Year 2024 Existing Traffic Volumes – Weekday AM Peak Hour 10-43
Figure 10-14 Year 2024 Existing Traffic Volumes – Weekday PM Peak Hour 10-44
Figure 10-15 Year 2024 Existing Traffic Volumes – Saturday Peak Hour 10-45
Figure 10-16 Off-Street Parking Inventory 10-49
Figure 10-17 Year 2029 No-Action Traffic Volumes – Weekday AM Peak Hour 10-60
Figure 10-18 Year 2029 No-Action Traffic Volumes – Weekday PM Peak Hour 10-61
Figure 10-19 Year 2029 No-Action Traffic Volumes – Saturday Peak Hour 10-62
Figure 10-20 Year 2029 With-Action Traffic Volumes – Weekday AM Peak Hour 10-74
Figure 10-21 Year 2029 With-Action Traffic Volumes – Weekday PM Peak Hour 10-75
Figure 10-22 Year 2029 With-Action Traffic Volumes – Saturday Peak Hour 10-76
Figure 11-1 Development Site 1 Building Screening 11-16
Figure 11-2 Development Site 2 Building Screening 11-17
Figure 12-1 Three Scopes of GHG Emissions 12-10
Figure 12-2 Embodied Carbon of a Building 12-14
Figure 13-1 Noise Monitoring Locations 13-9
Figure 13-2 Composite Window/Wall Sound Attenuation Requirements 13-20
Figure 16-1 Conceptual Construction Schedule 16-9
Figure 16-2 Year 2024 Existing Traffic Volumes – AM Construction Peak Hour 16-18
Figure 16-3 Year 2024 Existing Traffic Volumes – PM Construction Peak Hour 16-19
Figure 16-4 Year 2028 No-Action Traffic Volumes – AM Construction Peak Hour 16-23
Figure 16-5 Year 2028 No-Action Traffic Volumes – PM Construction Peak Hour 16-24
Figure 16-6 Year 2028 Construction Trip Increment– AM Peak Hour 16-29
Figure 16-7 Year 2028 Construction Trip Increment– PM Peak Hour 16-30
Figure 16-8 Year 2028 Construction With-Action Traffic Volumes – AM Peak Hour 16-31
Figure 16-9 Year 2028 Construction With-Action Traffic Volumes – PM Peak Hour 16-32
Figure 16-10 Construction Noise Receptor Locations 16-48
Figure 16-11 Cumulative Sound Emissions from Stationary Equipment during Each Month 16-52
Figure 16-12 Construction Noise Impact 16-66

List of Photos

Figure No.	Title	Page
Photo ES-1	View of Development Site 1 looking East across Twelfth Avenue	ES-6
Photo ES-2	View of Development Site 1 looking North across West 54th Street	ES-6
Photo ES-3	Looking West along West 54th Street, Development Site 1 at Right	ES-6
Photo ES-4	Looking West along West 55th Street, Development Site 1 at Left	ES-6
Photo ES-5	View of Development Site 2, looking West across Eleventh Avenue	ES-7
Photo ES-6	Looking South along Eleventh Avenue, Development Site 2 at Right	ES-7
Photo ES-7	View of Development Site 2 looking North along Eleventh Avenue	ES-7
Photo ES-8	Looking Northeast along Eleventh Avenue, Development Site 2 at Left	ES-7
Photo 1-1	View of Development Site 1 looking East across Twelfth Avenue	1-6
Photo 1-2	View of Development Site 1 looking North across West 54th Street	1-6
Photo 1-3	Looking West along West 54th Street, Development Site 1 at Right	1-6
Photo 1-4	Looking West along West 55th Street, Development Site 1 at Left	1-6
Photo 1-5	View of Development Site 2, looking West across Eleventh Avenue	1-7
Photo 1-6	Looking South along Eleventh Avenue, Development Site 2 at Right	1-7
Photo 1-7	View of Development Site 2 looking North along Eleventh Avenue	1-7
Photo 1-8	Looking Northeast along Eleventh Avenue, Development Site 2 at Left	1-7
Photo 2-1	Development Site 1	2-13
Photo 2-2	Development Site 2	2-13
Photo 7-1	Development Site 1 (Block 1102, Lot 11)	7-10
Photo 7-2	Development Site 2 (Block 1103, Lot 36)	7-10
Photo 7-3	Route 9A Looking North	7-10
Photo 7-4	Route 9A Looking Northwest	7-10
Photo 7-5	Hudson River Greenway Looking East	7-11
Photo 7-6	West 55th Street Looking East	7-11
Photo 7-7	De Witt Clinton Park	7-11
Photo 7-8	West 54th Street Looking West	7-11
Photo 7-9	11th Avenue Looking North	7-12
Photo 7-10	West 56th Street Looking West	7-12

Photo 7-11 West 54th Street Looking East 7-12
Photo 7-12 827 Eleventh Avenue 7-13
Photo 7-13 Helena 57 West Apartments, 601 West 57th Street 7-13
Photo 7-14 625 West 57th Street 7-13
Photo 7-15 Department of Sanitation 7-13
Photo 7-16 Mercedes Dealership 7-14
Photo 7-17 CBS Studios 7-14
Photo 7-18 Terminal 5 & DSNY Skybridge 7-14
Photo 7-19 DSNY Salt Shed 7-15
Photo 7-20 DeWitt Clinton Park 7-15
Photo 7-21 View From Clinton Cove 7-15
Photo 7-22 Route 9A 7-15
Photo 7-23 West 54th Street Looking East 7-16
Photo 7-24 Hudson River Greenway 7-16
Photo 7-25 De Witt Clinton Park 7-16
Photo 7-26 Manhattan Community Boathouse 7-16
Photo 7-27 De Witt Clinton Park 7-17
Photo 7-28 De Witt Clinton Park 7-17