# Bay Street Corridor Rezoning and Related Actions

## Final Environmental Impact Statement (FEIS)




**CEQR No. 16DCP156R**
ULURP Nos. C190113 ZMR, N190114 ZRR, N190114(A) ZRR,
C190115 PPR, C190179 HAR, and C190179(A) HAR

**Lead Agency:**
City Planning Commission, City of New York
Marisa Lago, Chair

April 11, 2019

# Bay Street Corridor Rezoning and Related Actions

# FINAL ENVIRONMENTAL IMPACT STATEMENT (FEIS)

## April 11, 2019

**CEQR No.:** 16DCP156R

**ULURP Nos.:** C190113 ZMR
N190114 ZRR
N190114(A) ZRR
C190115 PPR
C190179 HAR
C190179(A) HAR

**Project Location:** Staten Island, New York
Community District 1

**Lead Agency:** City Planning Commission, City of New York
Marisa Lago, Chair

**Lead Agency Contact:** Olga Abinader, Acting Director
Environmental Assessment and Review Division
NYC Department of City Planning
120 Broadway, 31st floor
New York, NY 10271-3100
(212) 720-3493

**Prepared for:** New York City Department of City Planning
Christopher Hadwin, Director
Staten Island Office

Glen A. Price III, Director
Studies Implementation

**Prepared by:** New York City Department of City Planning

*With Assistance from:*

Langan Engineering, Environmental, Surveying and Landscape Architecture, D.P.C.
Philip Habib & Associates
AKRF, Inc.

The FEIS is available on the website of the New York City Department of City Planning: https://www1.nyc.gov/site/planning/applicants/eis-documents.page.

**EXECUTIVE SUMMARY** ..... **ES-1**

**CHAPTER 1: PROJECT DESCRIPTION** ..... **1-1**

**A. Introduction** **1-1**
**B. Required Approvals and Review Procedures** **1-8**
Zoning Map Amendments 1-8
Zoning Text Amendments 1-10
Disposition of City-Owned Properties & Urban Development Action Area (UDAA) Designation & Project Approval 1-13
City Map Amendment (Street Demapping) 1-13
**C. Background** **1-13**
Community Engagement and Interagency Participation 1-13
Context Area 1-14
Project Area 1-15
**D. Existing Zoning and Land Use** **1-16**
Bay Street Corridor Project Area Zoning 1-16
Bay Street Corridor Project Area Land Use 1-18
Canal Street Corridor Project Area Zoning 1-18
Canal Street Corridor Project Area Land Use 1-20
City Disposition Sites Zoning and Land Use 1-20
Stapleton Waterfront Phase III Sites A and B1 Zoning 1-25
Stapleton Waterfront Phase III Sites A and B1 Land Use 1-25
Special Purpose Districts 1-25
**E. Purpose and Need** **1-26**
**F. Description of the Proposed Actions** **1-28**
Proposed Zoning Map Amendments 1-29
Proposed Zoning Text Amendments 1-33
Proposed Disposition of City-Owned Properties & UDAAP Designation 1-35
Proposed City Map Amendment 1-36
(E) Designations (E-429) 1-36
**G. Analysis Framework** **1-37**
Reasonable Worst Case Development Scenario (RWCDS) 1-38
**H. The Future Without the Proposed Actions (No-Action Condition)** **1-45**
**I. The Future With the Proposed Actions (With-Action Condition)** **1-47**
Bay Street Corridor Project Area–

Projected Development Sites 1-47
Bay Street Corridor Project Area– Potential Development Sites 1-49
Canal Street Corridor Project Area – Projected Development Sites 1-49
Canal Street Corridor Project Area – Potential Development Sites 1-49
Projected City-Owned Development Sites 1-50

**J. Incremental Difference: No Action and With-Action Conditions 1-50**

**K. Public Review Process 1-50**

Uniform Land Use Review Procedure (ULURP 1-51
City Environmental Quality Review (CEQR) 1-51

**CHAPTER 2: LAND USE, ZONING, AND PUBLIC POLICY..... 2-1**

**A. Introduction 2-1**

**B. Principal Conclusions 2-2**

**C. Analysis Methodology 2-3**

Reasonable Worst Case Development Scenario (RWCDS) **2**-3
Study Areas 2-5

**D. Detailed Assessment 2-6**

Existing Conditions 2-6
The Future without the Proposed Actions (No-Action Condition) 2-31
The Future with the Proposed Actions (With-Action Condition) 2-43

**CHAPTER 3: SOCIOECONOMIC CONDITIONS..... 3-1**

**A. Introduction 3-1**

**B. Principal Conclusions 3-1**

Direct Residential Displacement 3-1
Direct Business and Institutional Displacement 3-2
Indirect Residential Displacement 3-3
Indirect Business and Institutional Displacement 3-4
Adverse Effects on Specific Industries 3-5

**C. Methodology 3-6**

Determining Whether a Socioeconomic Assessment is Appropriate 3-7

Study Area Definition 3-9
Data Sources 3-9
**D. Preliminary Assessment 3-12**
Direct Residential Displacement 3-12
Direct Business and Institutional Displacement 3-15
Indirect Residential Displacement 3-28
Indirect Business Displacement 3-29
Adverse Effects on Specific Industries 3-31
**E. Detailed Assessment of Indirect Residential Displacement 3-32**
Existing Conditions 3-33
The Future Without the Proposed Actions (No-Action Condition) 3-44
The Future With the Proposed Actions (With-Action Condition) 3-46
Indirect Residential Displacement Analysis 3-47

**CHAPTER 4: COMMUNITY FACILITIES AND SERVICES 4-1**
**A. Introduction 4-1**
**B. Principal Conclusions 4-1**
Public Schools 4-1
Child Care Centers 4-2
Libraries 4-3
Police, Fire, and Health Care Facilities 4-3
**C. Preliminary Screening 4-3**
Direct Effects 4-3
Indirect Effects 4-4
**D. Indirect Effects on Public Schools 4-7**
Methodology 4-7
Existing Conditions 4-8
The Future Without the Proposed Actions (No-Action Condition) 4-16
The Future With the Proposed Actions (With-Action Condition) 4-18
**E. Indirect Effects on Publicly Funded Child Care Centers 4-21**
Methodology 4-21
Existing Conditions 4-22

The Future Without the Proposed Actions
(No-Action Condition) 4-22
The Future With the Proposed Actions
(With-Action Condition) 4-23

**F. Indirect Effects on Public Libraries 4-25**
Methodology 4-25
Existing Conditions 4-26
The Future Without the Proposed Actions
(No-Action Condition) 4-30
The Future With the Proposed Actions
(With-Action Condition) 4-30

**CHAPTER 5: OPEN SPACE..... 5-1**

**A. Introduction 5-1**
**B. Principal Conclusions 5-1**
**C. Methodology 5-2**
Direct Effects 5-2
Indirect Effects 5-3
Study Areas 5-3
Analysis Framework 5-4
Impact Assessment 5-7
**D. Existing Conditions 5-7**
Study Area Population 5-7
Inventory of Publicly-Accessible Open Space 5-11
Assessment of Open Space Adequacy 5-16
**E. The Future Without the Proposed Actions (No-Action Condition) 5-19**
Study Area Population 5-19
Open Space Resources 5-20
Assessment of Open Space Adequacy 5-21
**F. The Future With the Proposed Actions 5-22**
Direct Effects 5-22
Indirect Effects 5-22
Assessment of Open Space Adequacy 5-23
Determining Impact Significance 5-24

**CHAPTER 6: SHADOWS..... 6-1**

**A. Introduction 6-1**
**B. Principal Conclusions 6-1**
**C. Methodology 6-2**
**D. Preliminary Screening Assessment 6-4**
Tier 1 Screening Assessment 6-5
Tier 2 Screening Assessment 6-6
Tier 3 Screening Assessment 6-8
**E. Detailed Analysis of Shadow Impacts 6-10**
Resource No. 1A & 1B: Lyons Pool-Entire Property & Lyons Pool-Main Pool 6-10
Resource No. 2: Tompkinsville Park 6-13
Resource No. 3: Tappen Park 6-22
Resource No. 4: Canal Street Greenstreets 6-32
Resource No. 10: Upper New York Bay 6-33
Project-Generated Open Space: Stapleton Phase III Open Space 6-46

**CHAPTER 7: HISTORIC AND CULTURAL RESOURCES..... 7-1**

**A. Introduction 7-1**
**B. Principal Conclusions 7-1**
Archaeological Resources 7-2
Architectural Resources 7-2
**C. Methodology 7-4**
Archaeological Resources 7-4
Architectural Resources 7-4
**D. Development Background 7-6**
**E. Existing Conditions 7-10**
Archaeological Resources 7-10
Architectural Resources 7-11
Designated Historic Resources 7-16
Potential/Eligible Historic Resources 7-25
**F. The Future Without the Proposed Actions (No-Action Condition) 7-26**
Archaeological Resources 7-26
Architectural Resources 7-26
**G. The Future With the Proposed Actions (With-Action Condition) 7-28**

Archaeological Resources 7-28
Architectural Resources 7-28

**CHAPTER 8: URBAN DESIGN AND VISUAL RESOURCES..... 8-1**
**A. Introduction 8-1**
**B. Principal Conclusions 8-1**
**C. Methodology 8-3**
Study Area 8-4
**D. Preliminary Assessment 8-6**
**E. Detailed Assessment 8-6**
Existing Conditions 8-6
The Future Without the Proposed Actions
(No-Action Condition) 8-35
The Future With the Proposed Actions
(With-Action Condition) 8-38

**CHAPTER 9: NATURAL RESOURCES..... 9-1**
**A. Introduction 9-1**
**B. Principal Conclusions 9-1**
**C. Summary of Previous Findings 9-2**
2006 New Stapleton Waterfront Development Plan FEIS 9-2
**D. Methodology 9-2**
Study Area 9-2
Field Visits 9-2
Existing Conditions 9-2
Future Without the Proposed Actions (No-Action Condition) 9-3
Future With the Proposed Actions (With-Action Condition) 9-3
**E. Regulatory Context 9-3**
Federal 9-3
State 9-4
**F. Existing Conditions 9-5**
Groundwater 9-5
Surface Water 9-5
Water Quality 9-7
Sediment Quality 9-7
Aquatic Biota 9-9

Essential Fish Habitat (EFH) 9-12
Coastal Resources 9-12
Wetlands 9-12
Floodplains 9-13
Geology 9-13
Ecological Communities 9-20
Wildlife 9-23
Rare, Threatened and Endangered Species 9-26
**G. The Future Without the Proposed Actions (No-Action Condition) 9-28**
**H. The Future With the Proposed Actions (With-Action Condition) 9-28**
Groundwater 9-28
Coastal Resources 9-28
Wetlands 9-29
Floodplains 9-29
Geology 9-30
Ecological Communities 9-30
Wildlife 9-30
Rare, Threatened, and Endangered Species 9-30

**CHAPTER 10: HAZARDOUS MATERIALS..... 10-1**
**A. Introduction 10-1**
**B. Principal Conclusions 10-5**
**C. Methodology 10-5**
Historic Sanborn Fire Insurance Maps 10-6
Regulatory Databases 10-6
Site Inspections 10-7
Limitations 10-7
**D. Existing Conditions 10-8**
Projected Development Sites 10-8
Potential Development Sites 10-15
**E. The Future Without the Proposed Actions (No-Action Condition) 10-19**
**F. The Future With the Proposed Actions (With-Action Condition) 10-20**
Assessment 10-20

**CHAPTER 11: WATER AND SEWER INFRASTRUCTURE..... 11-1**
**A. Introduction 11-1**

**B. Principal Conclusions 11-1**
Water Supply 11-1
Wastewater Treatment 11-2
Stormwater and Drainage Management 11-2
**C. Methodology 11-3**
**D. Existing Conditions 11-4**
Water Supply 11-4
Wastewater Treatment 11-4
Stormwater and Drainage Management 11-9
**E. The Future Without the Proposed Actions (No-Action Condition) 11-11**
Water Supply 11-11
Wastewater Treatment 11-12
Stormwater and Drainage Management 11-13
**F. The Future With the Proposed Actions (With-Action Condition) 11-13**
Water Supply 11-13
Wastewater Treatment 11-13
Stormwater and Drainage Management 11-15
Stormwater Best Management Practices 11-17

**CHAPTER 12: SOLID WASTE AND SANITATION SERVICES..... 12-1**
**A. Introduction 12-1**
**B. Principal Conclusions 12-1**
**C. Methodology 12-2**
**D. Existing Conditions 12-2**
Description of Current Solid Waste Sanitation Services 12-2
Solid Waste Generation on Projected Development Sites 12-4
**E. The Future Without the Proposed Actions (No-Action Condition) 12-5**
**F. Future With the Proposed Actions (With-Action Condition) 12-6**

**CHAPTER 13: ENERGY..... 13-1**
**A. Introduction 13-1**
**B. Principal Conclusions 13-1**
**C. Methodology 13-2**
**D. Existing Conditions 13-2**
Energy Supply and Transmission 13-2
Recent Energy Conservation Directives 13-3

Existing Demand 13-4
**E. The Future Without the Proposed Actions (No-Action Condition) 13-5**
Energy Supply and Transmission 13-5
No-Action Demand 13-5
**F. The Future With the Proposed Actions (With-Action Condition) 13-6**
Energy Supply and Transmission 13-6
With-Action Demand 13-6
Conclusion 13-7

**CHAPTER 14: TRANSPORTATION..... 14-1**
**A. Introduction 14-1**
**B. Principal Conclusions 14-4**
Traffic 14-4
Transit 14-4
Pedestrians 14-7
Vehicular and Pedestrian Safety 14-8
Parking 14-9
**C. Preliminary Analysis Methodology 14-9**
**D. Level 1 Screening Assessment 14-10**
Background 14-10
Transportation Planning Factors 14-11
Travel Demand Projection Summary 14-15
**E. Level 2 Screening Assessment 14-24**
Vehicular Traffic 14-24
Transit 14-36
Pedestrians 14-39
Parking Conditions 14-40
Vehicular and Pedestrian Safety Assessment 14-43
**F. Operational Analysis Methodology 14-43**
Traffic Operations 14-43
Transit Operations 14-45
Pedestrian Operations 14-47
Parking Conditions Assessment 14-50
Vehicular and Pedestrian Safety Assessment 14-51
**G. Traffic 14-51**
Existing Conditions 14-51

The Future without the Proposed Action 14-68
The Future with the Proposed Action 14-113
**H. Transit 14-153**
Existing Conditions 14-153
The Future without the Proposed Action 14-158
The Future with the Proposed Action 14-161
**I. Pedestrian 14-164**
Existing Conditions 14-164
The Future without the Proposed Actions 14-167
The Future with the Proposed Actions 14-173
**J. Vehicular and Pedestrian Safety Assessment 14-179**
Safety at Intersections 14-179
**K. Parking 14-182**
Existing Conditions 14-182
Parking Supply and Inventory 14-182
Existing Parking Conditions 14-185
Future Conditions Without the Proposed Action 14-185
Future Conditions With the Proposed Action 14-188

**CHAPTER 15: AIR QUALITY..... 15-1**
**A. Introduction 15-1**
**B. Principal Conclusions 15-1**
**C. Pollutants for Analysis 15-2**
Carbon Monoxide 15-3
Nitrogen Oxides, VOCs, and Ozone 15-3
Lead 15-3
Respirable Particulate Matter—$PM_{10}$ and $PM_{2.5}$ 15-4
Sulfur Dioxide 15-4
Noncriteria Pollutants 15-5
**D. Air Quality Regulations, Standards, and Benchmarks 15-5**
National and State Air Quality Standards 15-5
NAAQS Attainment Status and State Implementation Plans 15-7
Determining the Significance of Air Quality Impacts 15-8
**E. Methodology for Predicting Pollutant Concentrations 15-10**
Mobile Sources 15-10
Stationary Sources 15-17

**F. Existing Conditions 15-27**
**G. The Future Without the Proposed Actions (No-Action Condition) 15-28**
Mobile Sources 15-28
Stationary Sources 15-28
**H. The Future with the Proposed Actions (With-Action Condition) 15-29**
Mobile Sources 15-29
Stationary Sources 15-31

**CHAPTER 16: GREENHOUSE GAS EMISSIONS AND CLIMATE CHANGE..... 16-1**
**A. Introduction 16-1**
**B. Principal Conclusions 16-1**
**C. Recognized Greenhouse Gases 16-2**
Carbon Dioxide ($CO_2$) 16-2
Methane ($CH_4$) 16-3
Nitrous Oxide ($N_2O$) 16-3
Fluorinated Gases 16-3
**D. Methodology 16-4**
Greenhouse Gas Emissions 16-4
Climate Change 16-7
**E. Projected Greenhouse Gas (GHG) Emissions from the Proposed Actions 16-7**
Operational Emissions 16-7
Mobile Source Emissions 16-7
Summary 16-8
Consistency with the GHG Reduction Goal 16-8
**F. Adaptation to Climate Change 16-10**
**G. Development of Policy to Improve Climate Change Resilience 16-10**
**H. Resilience of the Proposed Project to Climate Change 16-13**

**CHAPTER 17: NOISE..... 17-1**
**A. Introduction 17-1**
**B. Principal Conclusions 17-1**
**C. Noise Standards and Criteria 17-1**
**D. Selection of Noise Receptor Locations 17-2**
**E. Existing Noise Levels 17-2**

**F. Noise Prediction Methodology 17-10**
General Methodology 17-10
Proportional Modeling 17-10
**G. The Future Without the Proposed Actions (No-Action Condition) 17-11**
**H. The Future with the Proposed Actions (With-Action Condition) 17-13**
**I. Assessment 17-16**
Attenuation Requirements 17-16
Mechanical Systems 17-18

**CHAPTER 18: PUBLIC HEALTH..... 18-1**
**A. Introduction 18-1**
**B. Principal Conclusions 18-1**
**C. Methodology 18-1**
**D. Public Health Assessment 18-2**
Chronic Exposure to High Levels of Noise 18-2
Prolonged Exposure to Noise Levels Above 85dBA 18-2
Unpredictable Exposure to Short-term High Noise Levels 18-3

**CHAPTER 19: NEIGHBORHOOD CHARACTER..... 19-1**
**A. Introduction 19-1**
**B. Principal Conclusions 19-2**
**C. Methodology 19-2**
Study Area 19-3
**D. Preliminary Assessment 19-5**
Defining Features 19-5
Assessment of the Potential to Affect the Defining Features of the Neighborhood 19-7

**CHAPTER 20: CONSTRUCTION..... 20-1**
**A. Introduction 20-1**
**B. Principal Conclusions 20-1**
Transportation 20-1
Air Quality 20-3
Noise 20-3
Vibration 20-4
Other Technical Areas 20-4
**C. Regulatory Framework 20-6**

Governmental Coordination and Oversight 20-6
**D. Conceptual Construction Schedule and Activities 20-7**
Construction Sequencing 20-7
Typical Construction Activities 20-8
Estimate of Construction Workers and
Construction Period Trucks 20-9
Construction Work Hours 20-11
Construction Staging Areas, Sidewalk and Lane Closures 20-12
**E. Preliminary Assessment 20-12**
Transportation 20-12
Air Quality 20-17
Noise 20-17
Other Technical Areas 20-18
**F. Detailed Analyses 20-23**
Air Quality 20-23
Noise 20-31
Vibration 20-76

**CHAPTER 21: MITIGATION..... 21-1**
**A. Introduction 21-1**
**B. Principal Conclusions 21-1**
Community Facilities 21-1
Open Space 21-2
Historic and Cultural Resources 21-3
Transportation 21-4
Construction 21-7
**C. Community Facilities 21-8**
Child Care Services 21-8
Public Schools 21-9
**D. Open Space 21-11**
**E. Historic and Cultural Resources 21-12**
**F. Transportation 21-12**
Proposed Schedule for Traffic and Pedestrian Mitigation
Measures 21-13
Traffic 21-14
Transit (bus) 21-51

Pedestrian 21-52
Parking 21-57
**G. Construction 21-58**
Historic and Cultural Resources 21-58
Noise 21-59

**CHAPTER 22: ALTERNATIVES..... 22-1**
**A. Introduction 22-1**
**B. Principal Conclusions 22-2**
No-Action Alternative Compared to the Proposed Actions 22-2
No Unmitigated Significant Adverse Impacts Alternative Compared to the Proposed Actions 22-2
Reduced Rezoning Area Alternative Compared to the Proposed Actions 22-4
A-Text Alternative Compared to the Proposed Actions 22-6
**C. No-Action Alternative Compared with the Proposed Actions 22-7**
Land Use, Zoning, and Public Policy 22-7
Socioeconomic Conditions 22-8
Community Facilities 22-8
Open Space 22-9
Shadows 22-10
Historic and Cultural Resources 22-10
Urban Design and Visual Resources 22-10
Natural Resources 22-11
Hazardous Materials 22-11
Water and Sewer Infrastructure 22-12
Solid Waste and Sanitation Services 22-12
Energy 22-12
Transportation 22-12
Air Quality 22-14
Greenhouse Gas Emissions and Climate Change 22-15
Noise 22-15
Public Health 22-15
Neighborhood Character 22-15
Construction 22-16

**D. No Unmitigated Significant Adverse Impacts Alternative Compared to the Proposed Actions 22-16**
Community Facilities 22-17
Open Space 22-18
Historic and Cultural Resources 22-18
Transportation 22-19
Construction 22-20
**E. Reduced Rezoning Area Alternative as Compared to the Proposed Actions 22-21**
Land Use, Zoning, and Public Policy 22-25
Socioeconomic Conditions 22-26
Community Facilities 22-26
Open Space 22-28
Shadows 22-32
Historic and Cultural Resources 22-33
Urban Design and Visual Resources 22-35
Natural Resources 22-35
Hazardous Materials 22-35
Water and Sewer Infrastructure 22-36
Solid Waste and Sanitation Services 22-37
Energy 22-38
Transportation 22-39
Air Quality 22-83
Greenhouse Gas Emissions and Climate Change 22-84
Noise 22-84
Public Health 22-84
Neighborhood Character 22-84
Construction 22-85
**F. A-Text Alternative as Compared to the Proposed Action 22-86**
Land Use, Zoning, and Public Policy 22-91
Socioeconomic Conditions 22-93
Community Facilities 22-95
Open Space 22-101
Shadows 22-103
Historic and Cultural Resources 22-104
Urban Design and Visual Resources 22-108

Natural Resources 22-109
Hazardous Materials 22-110
Water and Sewer Infrastructure 22-110
Solid Waste and Sanitation Services 22-112
Energy 22-113
Transportation 22-114
Air Quality 22-155
Greenhouse Gas Emissions and Climate Change 22-157
Noise 22-158
Public Health 22-160
Neighborhood Character 22-161
Construction 22-161

**CHAPTER 23: UNAVOIDABLE SIGNIFICANT ADVERSE IMPACTS..... 23-1**

**A. Introduction 23-1**
**B. Community Facilities 23-1**
Public Schools 23-1
Child Care Facilities 23-2
**C. Open Space 23-3**
**D. Historic and Cultural Resources 23-4**
**E. Transportation 23-4**
Traffic 23-4
Pedestrians 23-5
**F. Construction 23-6**
Historic and Cultural Resources 23-6
Noise 23-7

**CHAPTER 24: GROWTH-INDUCING ASPECTS OF THE PROPOSED ACTIONS..... 24-1**

**CHAPTER 25: IRREVERSIBLE AND IRRETRIEVABLE COMMITMENTS OF RESOURCES.... 25-1**

## APPENDICES

**APPENDIX A: PROPOSED ZONING TEXT AMENDMENTS..... A-1**

**APPENDIX B: DETAILED RWCDS TABLES.....B-1**

**APPENDIX C: LIST OF BLOCKS AND LOTS INCLUDED IN THE PROJECT AREA..... C-1**

**APPENDIX D: WATERFRONT REVITILIZATION PROGRAM (WRP) CAF .....D-1**

**APPENDIX E: PHASE 1A ARCHAEOLOGICAL STUDY ..... E-1**

**APPENDIX F: HAZARDOUS MATERIALS ..... F-1**

**APPENDIX G: TRANSPORTATION DEMAND FACTORS (TDF) MEMORANDUM..... G-1**

**APPENDIX H: PROPOSED AIR QUALITY (E) DESIGNATIONS.....H-1**

**APPENDIX I: NOISE ATTENUATION REQUIREMENTS.....I-1**

**APPENDIX J: CONSTRUCTION..... J-1**

**APPENDIX K: CORRESPONDENCE WITH CITY AGENCIES.....K-1**

**APPENDIX L: TECHNICAL MEMORANDUM 001……L-1**

**APPENDIX M: A-TEXT ALTERNATIVE……M-1**

**APPENDIX N: WRITTEN COMMENTS ON DRAFT ENVIRONMENTAL IMPACT STATEMENT……N-1**

**List of Tables**

On Page

1-1 2030 RWCDS No-Action and With-Action Conditions for Projected Development Sites....1-47
2-1 Reasonable Worst Case Development Scenario (RWCDS) Summary Table.....2-5
2-2 Existing Land Uses within the Primary Study Area Subareas.....2-7
2-3 Existing Land Uses within the City Disposition Sites' Primary Study Areas.....2-9
2-4 Existing Land Uses within the Secondary Study Area (Bay Street Corridor, Stapleton Waterfront Phase III Sites, and Canal Street Corridor) .....2-15
2-5 Primary Study Area Zoning Classifications.....2-16
2-6 Secondary Study Area Zoning Classifications.....2-25
2-7 Existing and No-Action Land Uses on Projected Development Sites.....2-31
2-8 Development Projects in the No-Action Condition.....2-34
2-9 With-Action Land Uses on Projected Development Sites.....2-44
2-10 RWCDS No-Action and With-Action Land Uses on Projected Development Sites.....2-45
2-11 Proposed Zoning Districts.....2-48
2-12 Summary of R6 and R6B Zoning Districts Regulations.....2-53
3-1 Housing Units Subject to Potential Direct Displacement as a Result of the Proposed Actions.....3-13
3-2 2016Private Employment in the Study Area, Staten Island, and New York City .....3-16
3-3 2016Private Businesses and Institutions in the Study Area.....3-17
3-4 Private Businesses and Institutions on Projected Development Sites .....3-18
3-5 Owner-Occupied Projected Development Sites .....3-18
3-5a Existing Private Business Establishments to Remain in With-Action Condition .....3-19
3-6 Private Businesses and Institutions Subject to Potential Direct Business Displacement as a Result of the Proposed Actions.....3-20
3-7 Projected Development Site Employment Figures for 2030 No-Action and With-Action Conditions.....3-21
3-8 Automotive-Related Uses Subject to Potential Direct Displacement by Type in the With-Action Condition.....3-21
3-9 Residential Population, 2000 and 2012-2016 .....3-33
3-10 Household Characteristics, 2000 and 2012-2016 .....3-33
3-11 Household Income Characteristics, 2000 and 2012-2016.....3-34
3-12 Household Income Distribution, 2012-2016.....3-35
3-13 Percent of Population Below the Poverty Line, 2000 and 2012-2016 .....3-35
3-14 Housing Units and Vacancy, 2000 and 2012-2016 .....3-36
3-15 Owner-Occupied and Renter-Occupied Units, 2000 and 2012-2016 .....3-36
3-16 Housing Units by Year Structure Build, 2012-2016 .....3-37
3-17 Median Home Value and Median Monthly Gross Rent, 2000 and 2012-2016 .....3-37
3-18 Gross Rent as a Percentage of Household Income, 2012-2016 .....3-37
3-19 Average Rental Rates for Staten Island Regions.....3-38
3-20 Study Area Building Permits by Year .....3-39
3-21 New Residential Development ..... 3-39
3-22 Staten Island Home Sale Prices by Neighborhood, 2016-2018 .....3-39
3-23 Pre-Foreclosure Properties and Foreclosure Filing Rates for the Study Area and Staten Island, 2018 .....3-40
3-24 2016 Housing Units in Rent-Regulated Buildings .....3-41
3-25 Renter-Occupied Housing Units in the Study Area, 2012-2016 .....3-41
3-26 Low-Income Renters, PUMA 3903, 2012-2016 .....3-43

3-27 2016 Protected and Unprotected Renter-Occupied Housing Units in the Study Area……3-44
3-28 Estimated Low-Income Population Subject to Potential Indirect Residential Displacement within the Study Area, 2016……3-44
3-29 Projects Under Construction or in Pre-Development in the Study Area……3-45
3-30 With-Action 2030 Population and Housing Growth in the Study Area……3-46
3-31 2030 No-Action and With-Action Residential Development on the Projected Development Sites……3-47
4-1 Preliminary Screening Analysis Criteria……4-4
4-2 Projected Development Sites and Associated Number of Projected Incremental Students by Respective CSD Sub-District……4-8
4-3 CSD 31, Sub-district 4 Elementary School Enrollment, Capacity, and Utilization for the 2017-2018 Academic Year……4-11
4-4 CSD 31, Sub-district 4 Intermediate School Enrollment, Capacity, and Utilization for the 2017-2018 Academic Year……4-12
4-5 Staten Island Public High School Enrollment, Capacity, and Utilization for the 2017-2018 Academic Year……4-14
4-6 2030 No-Action Staten Island High School Capacity Changes……4-17
4-7 2030 Estimated No-Action Elementary and Intermediate School Enrollment, Capacity, and Utilization……4-18
4-8 2030 Estimated No-Action High School Enrollment, Capacity, and Utilization……4-18
4-9 Estimated Number of Elementary and Intermediate Students Introduced in the Study Area in the 2030 Future with the Proposed Actions……4-19
4-10 2030 Estimated With-Action Elementary and Intermediate School Enrollment, Capacity, and Utilization……4-19
4-11 2030 Estimated With-Action High School Enrollment, Capacity, and Utilization……4-21
4-12 Publicly Funded Child Care Centers Serving the Project Area……4-22
4-13 Comparison of Budget Capacity, Enrollment, Available Slots, and Percent Utilized for the 2018 Existing Conditions and the 2030 No-Action Condition……4-23
4-14 Projected Number of Publicly Funded Child Care Children Generated by the Proposed Actions……4-23
4-15 Comparison of Budget Capacity, Enrollment, Available Slots, and Percent Utilized for the 2030 Future No-Action and With-Action Conditions……4-25
4-16 Public Libraries Serving the Project Area……4-26
4-17 Anticipated No-Action Residential Development within Each Library Catchment Area……4-30
4-18 No-Action Holdings-per-Resident Ratios……4-30
4-19 Anticipated With-Action Library Catchment Area Population Increases……4-31
4-20 With-Action Holdings-per-Resident Ratios……4-32
5-1 Open Space Ratio Summary……5-2
5-2 0.25-mile Non-Residential Study Area – Existing Residential and Non-Residential Populations……5-7
5-3 0.5-mile Residential Study Area – Existing Residential and Non-Residential Populations…5-8
5-4 Residential Study Area (0.5-mile) Residential Population Age Breakdown……5-10
5-5 Open Space Resources within the Non-Residential and Residential Open Space Study Areas……5-13
5-6 Adequacy of Open Space Resources: Existing Conditions……5-17
5-7 Open Space Resources for Qualitative Assessment……5-19
5-8 No-Action – Open Space Study Area Population……5-20
5-9 New Open Space Resources in No-Action Condition……5-20
5-10 Adequacy of Open Space Resources: No-Action Condition……5-21
5-11 With-Action – Open Space Study Area Population……5-22

5-12 Adequacy of Open Space Resources: With-Action Condition……5-23
5-13 Open Space Ratio Summary……5-25
6-1 Development Sites Warranting Preliminary Shadow Analyses……6-5
6-2 Sunlight-Sensitive Resources – Tier 2 Shadow Screening Assessment……6-8
6-3 Tier 3 Shadow Screening Assessment Results……6-10
6-4 Incremental Shadow Duration on Sunlight-Sensitive Resources (With-Action Condition) ……6-11
7-1 Designated and Eligible Historic Resources……7-16
7-2 Projected/Potential Development Sites Containing or Located in Proximity to Designated/ Eligible Historic Resources……7-33
7-3 Assessment of Proposed Actions' Potential Impacts on Designated and Eligible Historic Resources……7-35
9-1 Finfish Species with the Potential to occur in the Vicinity of Study Area……9-10
9-2 Essential Fish Habitat (EFH) Designated Species in the Vicinity of Study Area……9-12
9-3 Soil Types within the Project Area……9-20
9-4 Identified Plant Species in the Study Area……9-22
9-5 Bird Species within the Study Area……9-24
10-1 Regulatory Agency Databases Reviewed……10-7
10-2 E Designation Sites – Projected Development Sites……10-22
10-3 E Designation Sites – Potential Development Sites……10-23
10-4 Environmental Assessment and E Designation Details – Projected and Potential Development Sites……10-25
11-1 Existing Water Consumption & Waste Generation……11-5
11-2 2015-2016 Monthly Average Dry Weather Flows to Port Richmond WWTP……11-8
11-3 Existing Wastewater Generation on the Projected Development Sites……11-9
11-4 Existing Projected Development Sites Runoff Coefficients……11-10
11-5 Existing Combined Stormwater Runoff and Wastewater Generation from the Projected Development Sites……11-11
11-6 No-Action Water Consumption……11-12
11-7 No-Action Wastewater Generation on the Projected Development Sites……11-12
11-8 With-Action Water Consumption……11-14
11-9 With-Action Wastewater Generation on the Projected Development Sites……,11-14
11-10 With-Action Projected Development Sites Runoff Coefficients……11-15
11-11 With-Action Combined Stormwater Runoff and Wastewater Generation from the Projected Development Sites……11-16
12-1 Existing Solid Waste Generation on Projected Development Sites……12-4
12-2 No-Action Solid Waste Generation on Projected Development Sites……12-6
12-3 With-Action Solid Waste Generation on Projected Development Sites……12-7
12-4 Comparison of Weekly Solid Waste Generation on Projected Development Sites (Existing, No-Action, and With-Action Conditions)……12-8
13-1 Existing Annual Energy Consumption for the Projected Development Sites……13-4
13-2 No-Action Annual Energy Consumption for the Projected Development Sites……13-5
13-3 With-Action Annual Energy Consumption for the Projected Development Sites……13-7
14-1 2030 RWCDS No-Action and With-Action Land Uses……14-3
14-2 Number of Impacted Intersection and Lane Groups by Peak Hour……14-4
14-3a Summary of Significantly Impacted Signalized Intersections……14-5
14-3b Summary of Significantly Impacted Unsignalized Intersections……14-6
14-4 Summary of Significant Bus Impacts……14-7
14-5 Summary of Significant Pedestrian Impacts……14-7

14-6 Travel Demand Factors – Bay Street/Canal Street Corridor and Stapleton Waterfront Phase III Sites……14-12
14-7 Travel Demand Factors – City Disposition Site – Jersey Street……14-13
14-8 Travel Demand Factors – City Disposition Sites – 54 Central Avenue/55 Stuyvesant Place Sites……14-14
14-9 No-Action Project Increment – Weekday AM Peak Hour Trip Generation Estimates……14-16
14-10 No-Action Project Increment – Weekday MD Peak Hour Trip Generation Estimates……14-17
14-11 No-Action Project Increment – Weekday PM Peak Hour Trip Generation Estimates……14-18
14-12 No-Action Project Increment – Saturday MD Peak Hour Trip Generation Estimates……14-19
14-13 With-Action Project Increment – Weekday AM Peak Hour Trip Generation Estimates…14-20
14-14 With-Action Project Increment – Weekday MD Peak Hour Trip Generation Estimates…14-21
14-15 With-Action Project Increment – Weekday PM Peak Hour Trip Generation Estimates…14-22
14-16 With-Action Project Increment – Saturday MD Peak Hour Trip Generation Estimates….14-23
14-17 Summary of Net Incremental Trips Generated Under the RWCDS……14-23
14-18 RWCDS Net Incremental Peak Hour SIR Trips by Station……14-38
14-19 RWCDS Net Incremental Peak Hour Bus Trips by Route……14-39
14-20 Pedestrian Study Elements……14-42
14-21 LOS Criteria for Signalized Intersections……14-43
14-22 LOS Criteria for Unsignalized Intersections……14-44
14-23 LOS Criteria for Subway Station Stairways and Control Areas……14-45
14-24 LOS Criteria for Crosswalks and Corners (Signalized Intersections)……14-48
14-25 LOS Criteria for Crosswalks (Unsignalized Intersections)……14-48
14-26 LOS Criteria for Sidewalks……14-49
14-27 Existing Conditions Level of Service Analysis – Signalized Intersections……14-64
14-28 Existing Conditions Level of Service Analysis – Unsignalized Intersections……14-68
14-29 Signalized Level of Service Analysis – Weekday AM Peak Hour Existing vs. No-Action Conditions……14-90
14-30 Unsignalized Level of Service Analysis – Weekday AM Peak Hour Existing vs. No-Action Conditions……14-109
14-31 Signalized Level of Service Analysis – Weekday AM Peak Hour No-Action vs. With-Action Conditions……14-133
14-32 Unsignalized Level of Service Analysis – Weekday AM Peak Hour No-Action vs. With-Action Conditions……14-149
14-33 Existing Bus Transit Service……14-155
14-34 Existing Conditions – Vertical Circulation Analysis St. George, Tompkinsville, and Stapleton SIR Station Stairways……14-156
14-35 Existing Conditions – Turnstile Analysis St. George and Tompkinsville SIR Station Turnstiles……14-157
14-36 Existing Conditions – SIR Line Haul Analysis……14-157
14-37 Existing Conditions – Local Bus Line Haul Analysis……14-158
14-38 No-Action Condition – Vertical Circulation Analysis St. George, Tompkinsville, and Stapleton SIR Station Stairways……14-159
14-39 No-Action Condition – Turnstile Analysis St. George and Tompkinsville SIR Station Turnstiles……14-159
14-40 No-Action Condition – SIR Line Haul Analysis……14-160
14-41 No-Action Condition – Local Bus Line Haul Analysis……14-161
14-42 With-Action Condition – Vertical Circulation Analysis St. George, Tompkinsville, and Stapleton SIR Station Stairways……14-162
14-43 With-Action Condition – Turnstile Analysis St. George and Tompkinsville SIR Stations Turnstiles……14-162

14-44 With-Action Condition – SIR Line Haul Analysis……14-163
14-45 With-Action Condition – Local Bus Line Haul Analysis……14-163
14-46 Existing Conditions Level of Service Analysis – Corners……14-165
14-47 Existing Conditions Level of Service Analysis – Sidewalks……14-166
14-48 Existing Conditions Level of Service Analysis – Crosswalks at Signalized Intersections……14-166
14-49 Existing Conditions Level of Service Analysis – Crosswalks at Unsignalized Intersections……14-166
14-50 No-Action Conditions Level of Service Analysis – Corners……14-169
14-51 No-Action Conditions Level of Service Analysis – Sidewalks……14-171
14-52 No-Action Conditions Level of Service Analysis – Crosswalks at Signalized Intersections……14-172
14-53 No-Action Conditions Level of Service Analysis – Crosswalks at Unsignalized Intersections……14-172
14-54 With-Action Conditions Level of Service Analysis – Corners……14-173
14-55 With Actions Conditions Level of Service Analysis – Sidewalks……14-177
14-56 With-Action Conditions Level of Service Analysis – Crosswalks at Signalized Intersections……14-178
14-57 With-Action Conditions Level of Service Analysis – Crosswalks at Unsignalized Intersections……14-179
14-58 Crash Data……14-181
14-59 On-Street Parking Regulation Legend……14-184
14-60 Existing On-Street Parking Utilization Summary (Subareas and Total)……14-185
14-61 No-Action Weekday Hourly Parking Accumulation by Land Use……14-187
14-62 No-Action Saturday Hourly Parking Accumulation by Land Use……14-187
14-63 No-Action ¼-Mile On-Street Parking Utilization Summary (Subareas and Total)……14-188
14-64 With-Action Incremental Weekday Hourly Parking Accumulation by Land Use……14-189
14-65 With-Action Net Incremental Saturday Hourly Parking Accumulation by Land Use……14-189
14-66 With-Action ¼-Mile On-Street Parking Utilization Summary (Subareas and Total)……14-190
15-1 National Ambient Air Quality Standards (NAAQS)……15-6
15-2 Industrial Source Analysis: Relevant New York State Department of Environmental Conservation (NYSDEC) Air Guideline Concentrations……15-10
15-3 Maximum Background Pollutant Concentrations for Mobile Source Analysis……15-13
15-4 Mobile Source Analysis Sites……15-15
15-5 Background Pollutant Concentrations……15-20
15-6 Cluster Analysis Sites……15-21
15-7 Representative Monitored Ambient Air Quality Data……15-27
15-8 Maximum Predicted Eight-Hour Average CO No-Action Concentrations ……15-28
15-9 Maximum Predicted 24-Hour Average $PM_{10}$ No-Action Concentrations ……15-28
15-10 Maximum Predicted Eight-Hour Average CO With-Action Concentrations (ppm)……15-29
15-11 Maximum Predicted 24-Hour Average $PM_{10}$ With-Action Concentrations ($\mu g/M^3$)……15-29
15-12 Maximum Predicted 24-Hour Average $PM_{2.5}$ With-Action Concentrations ……15-30
15-13 Maximum Predicted Annual Average $PM_{2.5}$ Incremental Concentrations ……15-30
15-14 Heating and Hot Water System Analysis Summary……15-33
15-15 Heating and Hot Water System Analysis- Results for Projected Development Sites……15-34
15-16 Heating and Hot Water System Analysis- Results for Potential Development Sites……15-36
15-17 Maximum Pollutant Concentration……15-37
15-18 Maximum Predicted Impacts on Projected and Potential Development Sites from Existing Industrial Sources……15-39
15-19 Estimated Maximum Hazard Index from Existing Industrial Sources……15-40

15-20 Maximum Predicted Impacts on Projected and Potential Development Sites from Proposed Brewery Industrial Source, Building 7 ……15-41
15-21 Estimated Maximum Hazard Index from Proposed Brewery Industrial Source, Building 7 ……15-41
16-1 Global Warming Potential for Primary Greenhouse Gases……16-4
16-2 Proposed Actions' (RWCDS) Annual Vehicle Miles Traveled (miles per year)……16-6
16-3 Annual Operation Emissions – RWCDS Projected Development Sites……16-7
16-4 Annual Mobile Source Emissions for 2030 – RWCDS……16-8
16-5 Summary of Total Annual GHG Emissions from Projected Development Sites Under the Proposed Actions……16-8
17-1 Required Attenuation Values to Achieve Acceptable Interior Noise Levels……17-2
17-2 Receptor Locations……17-3
17-3 Existing Noise Levels (in dBA)……17-7
17-4 2030 No-Action Condition Noise Levels (in dBA)……17-11
17-5 2030 With-Action Condition Noise Levels (in dBA)……17-14
17-6 CEQR Building Attenuation Analysis Summary ……17-17
20-1 Construction Oversight in New York City……20-6
20-2 Estimated Total Number of Construction Workers and Construction Trucks On-Site Per Day……20-11
20-3 2029 (Q1) Peak Incremental Construction Vehicle Trip Projections (in PCEs)……20-14
20-4 2029 (Q1) vs. 2030 Peak Hour Construction & Operational Traffic Volumes (in PCEs)….20-14
20-5 2029 (Q1) vs. 2030 Peak Hour Construction and Operational Transit Trips……20-16
20-6 2029 (Q1) vs. 2030 Peak Hour Construction and Operational Pedestrian Trips……20-16
20-7 Eligible Historic Resources Located within 90 feet of a Projected/Potential Development Site(s) ……20-21
20-8 Pollutants for Analysis and Averaging Periods……20-24
20-9 Construction Equipment List……20-26
20-10 Maximum Predicted Pollutant Concentrations from Construction Site Sources- January 2020 Peak Analysis Period……20-30
20-11 Maximum Predicted Pollutant Concentrations from Construction Site Sources- January 2027 Peak Analysis Period……20-30
20-12 Typical Construction Equipment Noise Emission Levels (dBA)……20-36
20-13 Construction Noise Receptor Locations……20-38
20-14 Projected Development Site 4 Construction Noise Results in dBA……20-46
20-15 Projected Development Site 4 Demolition, Excavation, and Foundation Noise Levels……20-47
20-16 Projected Development Site 4 Superstructure Noise Levels……20-47
20-17 Projected Development Site 4 Interiors Noise Levels……20-47
20-18 Projected Development Site 22 Construction Noise Analysis Results in dBA……20-49
20-19 Projected Development Site 22 Demolition, Excavation, and Foundation Noise Levels….20-57
20-20 Projected Development Site 22 Superstructure Noise Levels……20-57
20-21 Projected Development Site 22 Interior Noise Levels……20-58
20-22 Maximum Predicted Noise Levels……20-59
20-23 Construction Noise Exposure at Project Buildings in dBA……20-69
20-24 Vibration Source Levels for Construction Equipment……20-77
21-1 Summary of Lane Groups/Intersections with Partially Mitigated and/or Unmitigated Significant Adverse Traffic Impacts ……21-4
21-2 Signalized Intersections with Partially Mitigated and/or Unmitigated Significant Adverse Traffic Impacts ……21-5
21-3 Unsignalized Intersections with Partially Mitigated and/or Unmitigated Significant Adverse Traffic Impacts ……21-6

21-4 Additional DOE-Operated and Contracted Child Care Facilities in Study Area.....21-9
21-5 Proposed Traffic Mitigation Table .....21-16
21-6 Signalized Level of Service Analysis- Weekday AM Peak Hour No. Action vs. With-Action vs. Mitigated Conditions .....21-32
21-7 Signalized Level of Service Analysis- Weekday MD Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-36
21-8 Signalized Level of Service Analysis- Weekday PM Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-40
21-9 Signalized Level of Service Analysis- Saturday MD Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-44
21-10 Unsignalized Level of Service Analysis- Weekday AM Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-48
21-11 Unsignalized Level of Service Analysis- Weekday MD Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-49
21-12 Unsignalized Level of Service Analysis- Weekday PM Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-50
21-13 Unsignalized Level of Service Analysis- Saturday MD Peak Hour No-Action vs. With-Action vs. Mitigated Conditions .....21-51
21-14 With-Action With-Mitigation Conditions Local Bus Analysis.....21-52
21-15 Summary of Significant Pedestrian Sidewalk Impacts.....21-52
21-16 Summary of Significant Pedestrian Crosswalk Impacts Signalized Intersections.....21-53
21-17 Summary of Significant Pedestrian Crosswalk Impacts Unsignalized Intersections .....21-53
21-18 Summary of Significant Pedestrian Crosswalk Impacts with Vehicle Mitigation Signalized Intersections .....21-54
21-19 With-Action With-Mitigation Sidewalk Conditions .....21-55
21-20 With-Action With-Mitigation Crosswalk Conditions Signalized Intersections.....21-56
21-21 With-Action With-Mitigation Crosswalk Conditions Unsignalized Intersections.....21-56
21-22 With-Action With-Mitigation ¼-Mile On-Street Parking Utilization Summary (Subareas and Total).....21-58
22-1 Comparison of RWCDS for Projected Development Sites in the Proposed Actions and Reduced Rezoning Area Alternative.....22-24
22-2 2030 Reduced Rezoning Area Alternative (RRAA) With-Action School Enrollment, Capacity, and Utilization.....22-27
22-3 Comparison of Budge Capacity, Enrollment, Available Slots, Utilization for the 2030 No-Action, Proposed Actions, and Reduced Rezoning Area Alternative (RRAA) Conditions .....22-28
22-4 Existing Open Space Resources- Proposed Actions and Reduced Rezoning Area Alternative.....22-29
22-5 Population- Existing, No-Action, and With-Action for the 2030 Proposed Actions and Reduced Rezoning Area Alternative.....22-31
22-6 Open Space Ratios Summary- No-Action, Reduced Rezoning Area Alternative, and Proposed Actions Conditions.....22-32
22-7 Reduced Rezoning Area Alternative Water Consumption.....22-36
22-8 Weekly Solid Waste Generation- No-Action, Reduced Rezoning Area Alternative (RRAA), and the Proposed Actions.....22-38
22-9 Reduced Rezoning Area Alternative (RRAA) Annual Energy Consumption for the Projected Development Sites, compared to Proposed Actions.....22-39
22-10 Total Development Area by Land Use: Proposed Actions compared to Reduced Rezoning Area Alternative.....22-40

22-11 Incremental Peak Hour Person Trips by Mode: Proposed Actions compared to Reduced Rezoning Area Alternative……22-41
22-12 Incremental Peak Hour Vehicle Trips: Proposed Actions compared to Reduced Rezoning Area Alternative……22-42
22-13 Impacted Lane Groups and Intersections with Significant Adverse Impacts Proposed Actions compared to Reduced Rezoning Area Alternative……22-43
22-14 Signalized Level of Service Analysis- Weekday AM Peak Hour, Proposed Actions compared to Reduced Rezoning Area Alternative……22-44
22-15 Proposed Traffic Mitigation Table: Reduced Rezoning Area Alternative……22-47
22-16 Signalized Level of Service Analysis- Weekday AM Peak Hour No-Action, With-Action, and Mitigated Conditions: Reduced Rezoning Area Alternative……22-58
22-17 Unsignalized Level of Service Analysis- Weekday AM Peak Hour No-Action, With-Action, and Mitigated Conditions: Reduced Rezoning Area Alternative……22-74
22-18 Reduced Rezoning Area Alternative: Local Bus Line Haul Analysis……22-76
22-19 Corner Conditions: With-Action Reduced Rezoning Area Alternative……22-77
22-20 Sidewalk Conditions: With-Action Reduced Rezoning Are Alternative……22-78
22-21 Sidewalk Conditions: With-Action With-Mitigation Reduced Rezoning Area Alternative.22-78
22-22 Crosswalk Conditions at Signalized Intersections: With-Action Reduced Rezoning Area Alternative……22-79
22-23 Crosswalk Conditions at Unsignalized Intersections: With-Action Reduced Rezoning Area Alternative……22-79
22-24 Crosswalk Conditions at Signalized Intersections with Vehicle Mitigation: With-Action With Mitigation Reduced Rezoning Area Alternative……22-80
22-25 Crosswalk Conditions at Signalized Intersections: With-Action With-Mitigation Reduced Rezoning Area Alternative……22-80
22-26 Crosswalk Conditions at Unsignalized Intersections: With-Acton With-Mitigation Reduced Rezoning Area Alternative……22-81
22-27 Reduced Rezoning Area Alternative Net Incremental Weekday Hourly Parking Accumulation by Land Use……22-81
22-28 Reduced Rezoning Area Alternative Net Incremental Saturday Hourly Parking Accumulation by Land Use……22-82
22-29 With-Action ¼-Mile On-Street Parking Utilization Summary (Subareas & Total)……22-82
22-30 City Disposition Sites 2 and 3 under the Proposed Actions and A-Text Alternative……22-88
22-31 RWCDS Projected Development Sites Affected by A-Text Alternative……22-90
22-32 Comparison of RWCDS for the 30 Projected Development Sites under the Proposed Actions and A-Text Alternative……22-91
22-33 Estimated Student Generation in the Future with the A-Text Alternative……22-96
22-34 2030 Estimated With-Action Elementary, Intermediate, and High School Enrollment, Capacity, and Utilization under the A-Text Alternative……22-96
22-35 Estimated Publicly-Funded Child Care Facility Enrollment, Capacity, and Utilization……22-99
22-36 A-Text Alternative With-Action Condition: Library Catchment Area Population……22-100
22-37 A-Text Alternative Water and Wastewater Generation……22-111
22-38 A-Text Alternative Wastewater Generation by Subcatchment Area……22-111
22-38a Comparison of Combined Stormwater Runoff and Wastewater Generation from the Stapleton Waterfront Phase III Sites in the Direct Drainage Area – Proposed Actions vs. A-Text Alternative……22-112
22-39 Weekly Solid Waste Generation – No Action, A-Text Alternative, and the Proposed Actions……22-113
22-40 A-Text Alternative Annual Energy Consumption for the Projected Development Sites, compared to Proposed Actions……22-114

22-41 Comparison of Incremental Peak Hour Trips by Mode – Proposed Actions vs. A-Text Alternative……22-115
22-42 Impacted Lane Groups and Intersections with Significant Adverse Impacts – Proposed Actions vs. A-Text Alternative……22-116
22-43 Signalized Level of Service Analysis – Weekday AM Peak Hour Proposed Actions compared to A-Text Alternative……22-117
22-44 Proposed Traffic Mitigation Table: A-Text Alternative……22-119
22-45 Signalized Level of Service Analysis – Weekday AM Peak Hour No-Action, With-Action, and Mitigated Conditions: A-Text Alternative……22-130
22-46 Unsignalized Level of Service Analysis – Weekday AM Peak Hour No-Action, With-Action, and Mitigated Conditions: A-Text Alternative……22-146
22-47 A-Text Alternative: Local Bus Line Haul Analysis……22-150
22-48 Corner Conditions: With-Action A-Text Alternative……22-151
22-49 Sidewalk Conditions: With-Action A-Text Alternative……22-152
22-50 Crosswalk Conditions: With-Action A-Text Alternative……22-152
22-51 A-Text Alternative Net Incremental Weekday Hourly Parking Accumulation by Land Use……22-153
22-52 A-Text Alternative Net Incremental Saturday Hourly Parking Accumulation by Land Use……22-153
22-53 A-Text Alternative With-Action ¼-Mile On-Street Parking Utilization Summary (Subareas & Total)……22-154
22-54 2030 A-Text Alternative Condition Noise Levels- Receptor Sites 2 and 7 (in dBA)……22-159
22-55 Noise Levels due to the School Playground (in dBA)……22-160
23-1 Summary of Unavoidable Adverse Traffic Impacts……23-5
23-2 Summary of Unavoidable Adverse Pedestrian Impacts……23-6

**List of Figures**

On Page

1-1 Regional Location Map....1-2
1-2 Project Area Location Map....1-3
1-3A Bay Street Corridor Project Area Tax Map....1-5
1-3B Canal Street Corridor Project Area Tax Map....1-6
1-3C City Disposition Sites Tax Map....1-7
1-4A Proposed Zoning Map Amendment Bay Street Corridor Project Area....1-9
1-4B Proposed Zoning Map Amendment Canal Street Corridor Project Area....1-11
1-5A Special Stapleton Waterfront District (SSWD) Subareas and Public Spaces....1-12
1-5 Existing Zoning Map....1-17
1-6A Land Use Map....1-19
1-6B City Disposition Site 1 Land Use Map....1-21
1-6C City Disposition Site 2 Land Use Map....1-23
1-6D City Disposition Site 3 Land Use Map....1-24
1-7 Overview of Projected and Potential Development Sites....1-39
1-8 Bay Street Corridor Projected and Potential Development Sites....1-40
1-9 Canal Street Corridor Projected and Potential Development Sites....1-41
2-1 Land Use Map....2-4
2-2 City Disposition Site 1 Land Use Map....2-10
2-3 City Disposition Site 2 Land Use Map....2-13
2-4 City Disposition Site 3 Land Use Map....2-14
2-5 Existing Zoning Map....2-17
2-6 Coastal Zone Boundary Map....2-29
2-7 Priority Marine Activity Zone....2-30
2-8 No Build Projects....2-35
2-9 Proposed Zoning Map Amendment Bay Street Corridor Project Area....2-46
2-10 Proposed Zoning Map Amendment Canal Street Corridor Project Area....2-47
2-11 Proposed Mandatory Inclusionary Housing (MIH) Area....2-51
2-12 FEMA FIRM....2-67
2-13 Tidal Wetland Location Map....2-70
2-14 Effects of Sea Level Rise on the 1% Annual Chance Floodplain....2-72
2-15 Areas Affected by Future High Tides....2-74
2-16 Proposed Visual Corridors....2-76
3-1 Study Area Census Tracts....3-11
3-2 Housing Units Subject to Potential Direct Displacement as a Result of the Proposed Actions....3-14
3-3 Buildings with Rent Protected Housing in the Study Area....3-42
4-1 Project Area Community School District Sub-District Map....4-10
4-2 Public Elementary and Intermediate School Location Map....4-13
4-3 Public High Schools within 1-Mile of the Project Area....4-15
4-4 Public Child Care Centers Study Area....4-24
4-5 Libraries Study Area....4-28
4-6 Library Catchment Areas....4-29
5-1 Open Space Study Areas Map....5-5
5-2 Open Space Resources Analyzed....5-12
6-1 Longest Shadow Study Area – Tier 1 Screening....6-7

6-2 Tier 2 Shadow Screening Assessment……6-9
6-3 Lyons Pool – Entire Property and Main Pool Incremental Shadow – March 21/ September 21……6-14
6-4 Lyons Pool – Entire Property and Main Pool Incremental Shadow – May 6/August 6……6-16
6-5 Lyons Pool – Entire Property and Main Pool Incremental Shadow – June 21……6-18
6-6 Lyons Pool – Entire Property and Main Pool Incremental Shadow – December 21……6-20
6-7 Tompkinsville Park Incremental Shadow – March 21/ September 21……6-23
6-8 Tompkinsville Park Incremental Shadow – May 6/ August 6……6-25
6-9 Tompkinsville Park Incremental Shadow – June 21……6-27
6-10 Tompkinsville Park Incremental Shadow – December 21……6-29
6-11 Tappen Park Incremental Shadow – December 21……6-31
6-12 Canal Street Green Streets Incremental Shadow – March 21/ September 21……6-34
6-13 Canal Street Green Streets Incremental Shadow – May 6/ August 6……6-36
6-14 Canal Street Green Streets Incremental Shadow – June 21……6-38
6-15 Canal Street Green Streets Incremental Shadow – December 21……6-40
6-16 Upper New York Bay Incremental Shadow – March 21/ September 21……6-42
6-17 Upper New York Bay Incremental Shadow – May 6/ August 6……6-43
6-18 Upper New York Bay Incremental Shadow – June 21……6-44
6-19 Upper New York Bay Incremental Shadow – December 21……6-45
7-1 Archaeological Sensitive Area……7-5
7-2 Historic and Cultural Resources Map……7-12
7-3 Historic and Cultural Resources – Disposition Site 1 Map……7-13
7-4 Historic and Cultural Resources – Bay Street Corridor Project Area Map……7-14
7-5 Historic and Cultural Resources – Canal Street Corridor Project Area Map……7-15
7-6 Projected and Potential Development Sites Located in Proximity to Historic Resources…7-34
8-1 Urban Design and Visual Resources Study Areas……8-5
8-2A Primary Study Area Built FAR……8-8
8-2B Secondary Study Area Built FAR……8-9
8-3A Primary Study Area Existing Building Heights……8-10
8-3B Secondary Study Area Existing Building Heights……8-11
8-4A Bay Street Corridor Subarea Photographs……8-13
8-4B Bay Street Corridor Subarea Photographs……8-14
8-5A Stapleton Waterfront Subarea Photographs……8-17
8-5B Stapleton Waterfront Subarea Photographs……8-18
8-6A Van Duzer Street Subarea Photographs……8-20
8-6B Van Duzer Street Subarea Photographs……8-21
8-7A Canal Street Corridor Subarea Photographs……8-25
8-7B Canal Street Corridor Subarea Photographs……8-26
8-7C Canal Street Corridor Subarea Photographs……8-27
8-8 St, George Secondary Subarea Photographs……8-29
8-9 Tompkinsville Secondary Subarea Photographs……8-30
8-10 Stapleton Secondary Subarea Photographs……8-33
8-11 Clifton Secondary Subarea Photographs……8-34
8-12 Bay Street Corridor Subarea – Existing, No-Action, and With-Action Conditions……8-41
8-13 Bay Street Corridor Subarea – Existing, No-Action, and With-Action Conditions……8-42
8-14 Bay Street Corridor Subarea – Existing, No-Action, and With-Action Conditions……8-43
8-15 Bay Street Corridor Subarea – Existing, No-Action, and With-Action Conditions……8-44
8-16 Bay Street Corridor Subarea – Existing, No-Action, and With-Action Conditions……8-45
8-17 Bay Street Corridor Subarea – Existing, No-Action, and With-Action Conditions……8-46
8-18 Stapleton Waterfront Subarea- Existing, No-Action, and With-Action Conditions……8-48

8-19 Van Duzer Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-50
8-20 Van Duzer Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-51
8-21 Van Duzer Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-52
8-22 Canal Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-54
8-23 Canal Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-55
8-24 Canal Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-56
8-25 Canal Street Corridor Subarea- Existing, No-Action, and With-Action Conditions.....8-57
9-1 USGS Map.....9-6
9-2 Surface Waters Map.....9-8
9-3 NYSDEC Tidal Wetlands Map.....9-14
9-4 National Wetlands Inventory Map.....9-15
9-5 FEMA Map.....9-16
9-6 Geology Map.....9-18
9-7 NRCS Soils Map.....9-19
9-8 Ecological Communities Map.....9-21
9-9 Significant Natural Communities Map.....9-27
10-1 City-Owned and City-Leased Sites in the Project Area.....,10-2
10-2 Bay Street Corridor Projected and Potential Development Sites.....10-3
10-3 Canal Street Corridor Projected and Potential Development Sites.....10-4
11-1 Combined Sewer Outfall & Subcatchment Area Map.....11-7
14-1 Project Area Location Map.....14-2
14-2a Total Proposed Project Increment Weekday AM Peak Hour.....14-25
14-2b Total Proposed Project Increment Weekday AM Peak Hour.....14-26
14-3a Total Proposed Project Increment Weekday MD Peak Hour.....14-27
14-3b Total Proposed Project Increment Weekday MD Peak Hour.....14-28
14-4a Total Proposed Project Increment Weekday PM Peak Hour.....14-29
14-4b Total Proposed Project Increment Weekday PM Peak Hour.....14-30
14-5a Total Proposed Project Increment Saturday MD Peak Hour.....14-31
14-5b Total Proposed Project Increment Saturday MD Peak Hour.....14-32
14-6 Vehicular Study Locations.....14-35
14-7 Pedestrian Study Locations.....14-41
14-8a Existing Traffic Conditions Weekday AM Peak Hour.....14-54
14-8b Existing Traffic Conditions Weekday AM Peak Hour.....14-55
14-9a Existing Traffic Conditions Weekday MD Peak Hour.....14-56
14-9b Existing Traffic Conditions Weekday MD Peak Hour.....14-57
14-10a Existing Traffic Conditions Weekday PM Peak Hour.....14-58
14-10b Existing Traffic Conditions Weekday PM Peak Hour.....14-59
14-11a Existing Traffic Conditions Saturday MD Peak Hour.....14-60
14-11b Existing Traffic Conditions Saturday MD Peak Hour.....14-61
14-12a No-Action Traffic Conditions Weekday AM Peak Hour.....14-71
14-12b No-Action Traffic Conditions Weekday AM Peak Hour.....14-72
14-13a No-Action Traffic Conditions Weekday MD Peak Hour.....14-73
14-13b No-Action Traffic Conditions Weekday MD Peak Hour.....14-74
14-14a No-Action Traffic Conditions Weekday PM Peak Hour.....14-75
14-14b No-Action Traffic Conditions Weekday PM Peak Hour.....14-76
14-15a No-Action Traffic Conditions Saturday MD Peak Hour.....14-77
14-15b No-Action Traffic Conditions Saturday MD Peak Hour.....14-78
14-16a With-Action Traffic Conditions Weekday AM Peak Hour.....14-114
14-16b With-Action Traffic Conditions Weekday AM Peak Hour.....14-115
14-17a With-Action Traffic Conditions Weekday MD Peak Hour.....14-116

14-17b With-Action Traffic Conditions Weekday MD Peak Hour.....14-117
14-18a With-Action Traffic Conditions Weekday PM Peak Hour.....14-118
14-18b With-Action Traffic Conditions Weekday PM Peak Hour.....14-119
14-19a With-Action Traffic Conditions Saturday MD Peak Hour.....14-120
14-19b With-Action Traffic Conditions Saturday MD Peak Hour.....14-121
14-20 Transit Routes.....14-154
14-21 Parking Regulations.....14-183
15-1 Air Quality Mobile Source Analysis Sites.....15-14
15-2 Bay Street Grid Study Area Extent.....15-16
15-3A Bay Street HVAC Cluster Locations.....15-22
15-3B Canal Street HVAC Locations.....15-23
17-1 Bay Street Corridor and Stapleton Waterfront Phase III Noise Monitoring Locations .....17-4
17-2 Canal Street Corridor Noise Monitoring Locations .....17-5
17-3 City Disposition Sites Noise Monitoring Locations .....17-6
19-1 Neighborhood Character Subareas.....19-4
20-1 Assumed Construction Schedule for Assessment of Construction Impacts.....20-10
20-2 Short-Term (24-hour) $PM_{2.5}$ Construction Emissions Profile.....20-28
20-3 Construction Noise Receptor Locations.....20-37
20-4 Potential Construction Noise Impact Locations.....20-68
22-1 Reduced Rezoning Area Alternative- Location Map.....22-22
22-2 Reduced Rezoning Area Alternative- Open Space Study Areas Map.....22-30