Herkimer-Williams

Draft Environmental Impact Statement (DEIS)

CEQR No. 24DCP055K
ULURP Nos.: N250284ZRK, 250285ZMK, 250286ZSK, 250287ZSK, N250288PCK

Lead Agency:
City Planning Commission, City of New York
Daniel R. Garodnick, Chair

May 30, 2025

Herkimer-Williams

Draft Environmental Impact Statement (DEIS)

May 30, 2025

Project Location:	Community District 5 Borough of Brooklyn
CEQR No.:	24DCP055K
Type of Action:	Type I
ULURP Nos.:	N250284ZRK, 250285ZMK, 250286ZSK, 250287ZSK, N250288PCK
Lead Agency:	New York Department of City Planning, on behalf of the City Planning Commission, City of New York
Lead Agency Contact:	Stephanie Shellooe, AICP Director, Environmental Assessment and Review Division New York City Department of City Planning 120 Broadway, 31st Floor New York, New York, 10271
Prepared by:	Philip Habib & Associates, an AKRF Division
Prepared For:	Broadway Junction Partners LLC

A public hearing on the Draft Environmental Impact Statement (DEIS) will be held at a later date to be announced. Advance notice will be given of the time and place of the hearing. Writing comments on the DEIS are requested and will be received and considered by the Lead Agency until the 10th calendar day following the close of the public hearing. The DEIS is available on the website of the New York City Department of City Planning, via the Herkimer-Williams project page on ZAP: https://zap.planning.nyc.gov/projects/2021K0450

To view the Herkimer-Williams DEIS, navigate to the project page in ZAP, linked above, and select Public Documents, then "DEIS_24DCP055K."

TABLE OF CONTENTS

Executive Summary **ES-1**

Chapter 1: Project Description **1-1**
A. Introduction 1-1
B. Background and Existing Conditions 1-2
Project Area 1-2
Neighborhood Context 1-4
C. Description of the Proposed Actions 1-7
Zoning Map Amendment 1-8
Zoning Text Amendment – MIH 1-9
Zoning Text Amendment ZR 74-742 – Contiguity of Ownership of LSGD Parcels 1-9
Large-Scale General Development (LSGD) Special Permit 1-10
Retail Special Permit 1-10
Combination Acquisition and Site Selection of Real Property by the City 1-10
D. Purpose and Need for the Proposed Actions 1-11
E. Description of Proposed Development 1-15
F. Analysis Framework 1-18
Analysis Year 1-18
Reasonable Worst Case Development Scenario (RWCDS) 1-18
The Future without the Proposed Actions (No-Action Condition) 1-19
The Future with the Proposed Actions (With-Action Condition) 1-19
G. Public Review Process 1-21
Uniform Land Use Review Procedure (ULURP) 1-22
City Environmental Quality Review (CEQR) 1-22

Chapter 2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
B. Principal Conclusions 2-1
C. Methodology 2-2
Analysis Year 2-2
Study Area Definition 2-3
Data Sources 2-3
D. Detailed Assessment 2-3
Existing Conditions 2-3
The Future without the Proposed Actions (No-Action Condition) 2-16
The Future with the Proposed Actions (With-Action Condition) 2-17
Assessment 2-22

Chapter 3: Socioeconomic Conditions **3-1**
A. Introduction 3-1
B. Principal Conclusions 3-2
Direct Residential Displacement 3-2
Direct Business Displacement 3-2
Indirect Residential Displacement 3-3
Indirect Business Displacement 3-3
C. Methodology 3-4
Determining Whether a Socioeconomic Assessment is Appropriate 3-5
Analysis Format 3-7
Study Area Definition 3-8

D. Direct Business Displacement....3-9
E. Indirect Residential Displacement....3-18
F. Indirect Business Displacement....3-31

Chapter 4: Community Facilities and Services....4-1
A. Introduction....4-1
B. Principal Conclusions....4-2
Direct Effects....4-2
Indirect Effects....4-2
C. Preliminary Screening....4-3
Direct Effects....4-4
Indirect Effects....4-4
D. Indirect Effects on Public Schools....4-6
Methodology....4-6
Existing Conditions....4-8
The Future without the Proposed Actions (No-Action Condition)....4-9
The Future with the Proposed Actions (With-Action Condition)....4-10
E. Indirect Effects on Public Libraries....4-11
Methodology....4-11
Existing Conditions....4-12
The Future without the Proposed Actions (No-Action Condition)....4-13
The Future with the Proposed Actions (With-Action Condition)....4-13
F. Indirect Effects on Publicly Funded Early Child Care Centers....4-14
Definitions....4-14
Methodology....4-15
Existing Conditions....4-16
The Future without the Proposed Actions (No-Action Condition)....4-16
The Future with the Proposed Actions (With-Action Condition)....4-17

Chapter 5: Open Space....5-1
A. Introduction....5-1
B. Principal Conclusions....5-1
Direct Effects....5-1
Indirect Effects....5-1
C. Methodology....5-3
Study Area....5-3
Analysis Framework....5-3
Preliminary Assessment....5-5
Impact Assessment....5-5
D. Existing Conditions....5-6
Study Area Population....5-6
Inventory of Publicly Accessible Open Space....5-8
Assessment of Open Space Adequacy....5-14
E. The Future without the Proposed Actions (No-Action Condition)....5-16
Study Area Population....5-16
Open Space Resources....5-18
Assessment of Open Space Adequacy....5-18
F. The Future with the Proposed Actions (With-Action Condition)....5-19
Direct Effects....5-20
Indirect Effects....5-20

Chapter 6: Shadows....6-1
A. Introduction....6-1

B. Principal Conclusions 6-1
C. Methodology....6-1
D. Preliminary Screening Assessment....6-4
Tier 1 Screening Assessment 6-4
Tier 2 Screening Assessment 6-5
Tier 3 Screening Assessment 6-6
E. Detailed Analysis of Shadow Impacts....6-7
Resources of Concern 6-7
Detailed Shadows Analysis 6-8

Chapter 7: Historic and Cultural Resources 7-1
A. Introduction 7-1
B. Principal Conclusions 7-1
Direct (Physical) Impacts 7-1
Indirect (Contextual) Impacts 7-2
Construction-related Impacts....7-2
Shadows Impacts 7-2
C. Existing Conditions....7-3
Criteria & Regulations....7-3
Project Area 7-3
400-Foot Study Area 7-3
D. Future Without the Proposed Actions (No-Action Condition)....7-4
Anticipated Developments in the No-Action Condition 7-4
E. Future With the Proposed Actions (With-Action Condition) 7-5
Direct (Physical) Impacts 7-6
Indirect (Contextual) Impacts 7-6
Construction-related Impacts....7-7
Shadows Impacts 7-7

Chapter 8: Urban Design and Visual Resources....8-1
A. Introduction 8-1
B. Principal Conclusions 8-2
C. Methodology....8-3
Study Areas....8-4
D. Preliminary Assessment....8-5
E. Detailed Assessment 8-5
Existing Conditions....8-5
The Future without the Proposed Actions (No-Action Condition) 8-12
The Future with the Proposed Actions (With-Action Condition)....8-13
Assessment....8-19

Chapter 9: Hazardous Materials....9-1
A. Introduction 9-1
B. Principal Conclusions 9-1
C. Methodology....9-2
D. Existing Conditions....9-3
E. The Future without the Proposed Actions (No-Action Condition)....9-13
F. The Future with the Proposed Actions (With-Action Condition) 9-14

Chapter 10: Water and Sewer Infrastructure 10-1
A. Introduction 10-1
B. Principal Conclusions 10-1
Water Supply 10-1

Wastewater Treatment 10-1
Stormwater Conveyance 10-2
C. Methodology....10-2
Water Supply 10-2
Wastewater Treatment 10-2
Stormwater Conveyance 10-3
D. Existing Conditions....10-3
Wastewater Treatment 10-3
Stormwater Conveyance 10-4
E. The Future without the Proposed Actions (No-Action Condition)....10-5
Wastewater Treatment and Stormwater Conveyance....10-5
F. The Future with the Proposed Actions (With-Action Condition) 10-6
Wastewater Treatment 10-6
Stormwater Conveyance 10-7

Chapter 11: Solid Waste and Sanitation Services 11-1
A. Introduction....11-1
B. Principal Conclusions 11-1
C. Methodology....11-1
D. Existing Conditions....11-2
Solid Waste Sanitation Services....11-2
Solid Waste Generation at the Project Area....11-5
E. The Future without the Proposed Actions (No-Action Condition) 11-6
F. The Future with the Proposed Actions (With-Action Condition)....11-7

Chapter 12: Energy 12-1
A. Introduction....12-1
B. Principal Conclusions 12-2
C. Methodology....12-2
D. Background....12-3
Energy Supply and Transmission 12-3
Recent Energy Conservation Directives....12-4
E. Existing Energy Demand....12-4
F. The Future without the Proposed Actions (No-Action Condition)....12-5
G. The Future with the Proposed Actions (With-Action Condition)....12-5

Chapter 13: Transportation....13-1
A. Introduction....13-1
The Proposed Actions....13-1
The Reasonable Worst Case Development Scenario (RWCDS) 13-2
B. Principal Conclusions 13-4
Traffic....13-5
Transit....13-7
Pedestrians 13-7
Vehicular and Pedestrian Safety....13-8
Parking....13-9
C. Preliminary Screening 13-10
D. Level 1 Screening Assessment 13-10
Background....13-10
Transportation Planning Factors 13-11
Travel Demand Forecast....13-12
E. Level 2 Screening Assessment....13-19
Vehicular Traffic....13-19

Transit 13-20
Citywide Ferry Service (CWFS) 13-23
Pedestrians 13-23
Parking 13-24
F. Transportation Analyses Methodologies 13-24
Traffic 13-24
Transit 13-26
Pedestrians 13-28
Vehicular and Pedestrian Safety Evaluation 13-31
Parking 13-32
G. Traffic 13-32
Existing Conditions 13-32
The Future without the Proposed Actions (No-Action Condition) 13-36
The Future with the Proposed Actions (With-Action Condition) 13-42
H. Transit 13-46
Existing Conditions 13-46
The Future without the Proposed Actions (No-Action Condition) 13-48
The Future with the Proposed Actions (With-Action Condition) 13-52
I. Pedestrians 13-54
Existing Conditions 13-54
The Future without the Proposed Actions (No-Action Condition) 13-58
The Future with the Proposed Actions (With-Action Condition) 13-61
J. Vehicular and Pedestrian Safety Evaluation 13-65
Recent DOT Initiatives 13-65
K. Parking 13-68

Chapter 14: Air Quality 14-1
A. Introduction 14-1
B. Principal Conclusions 14-1
C. Pollutants for Analysis 14-3
Carbon Monoxide 14-3
Nitrogen Oxides, VOCs, and Ozone 14-3
Lead 14-4
Respirable Particulate Matter – PM_{10} and $PM_{2.5}$ 14-4
Sulfur Dioxide 14-5
Noncriteria Pollutants 14-5
D. Air Quality Regulations, Standards, and Benchmarks 14-6
National and State Air Quality Standards 14-6
NAAQS Attainment Status and State Implementation Plans 14-7
Determining the Significance of Air Quality Impacts 14-9
E. Methodology for Predicting Pollutant Concentrations 14-12
Mobile Sources 14-12
Stationary Sources 14-18
F. Existing Conditions 14-32
G. The Future without the Proposed Actions (No-Action Condition) 14-33
Mobile Sources 14-33
Stationary Sources 14-34
H. The Future with the Proposed Actions (With-Action Condition) 14-34
Mobile Sources 14-34
Stationary Sources 14-37

Chapter 15: Greenhouse Gas Emissions and Climate Change 15-1
A. Introduction 15-1

B. Principal Conclusions 15-2
C. Recognized Greenhouse Gases 15-2
D. Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 15-4
Federal Policies 15-4
New York State Climate Leadership and Community Protection Act 15-4
New York City Initiatives 15-5
Other Benchmarks 15-5
E. Methodology 15-6
Building Operational Emissions 15-6
Mobile Source Emissions 15-7
Construction Emissions 15-8
Emissions from Solid Waste Management 15-8
F. Protected GHG Emissions from the Proposed Actions 15-8
Building Operational Emissions 15-8
Mobile Source Emissions 15-9
Summary 15-9
Consistency with the GHG Reduction Goal 15-10

Chapter 16: Noise 16-1
A. Introduction 16-1
B. Principal Conclusions 16-1
C. Acoustical Fundamentals 16-2
"A"-Weighted Sound Level (dBA) 16-2
Sound Level Descriptors 16-2
D. Noise Standards and Criteria 16-3
New York CEQR Noise Criteria 16-3
E. Existing Noise Levels 16-5
Equipment Used During Noise Monitoring 16-5
Noise Measurements Results 16-6
F. Noise Prediction Methodology 16-7
General Methodology 16-7
Proportional Modeling 16-8
G. The Future without the Proposed Actions (No-Action Condition) 16-8
H. The Future with the Proposed Actions (With-Action Condition) 16-9
I. Noise Attenuation Measures 16-9
J. Mechanical Systems 16-12

Chapter 17: Public Health 17-1
A. Introduction 17-1
B. Principal Conclusions 17-1
C. Methodology 17-2
D. Preliminary Screening 17-2
Operational Air Quality 17-2
E. Assessment 17-3
Operational Air Quality 17-3

Chapter 18: Neighborhood Character 18-1
A. Introduction 18-1
B. Principal Conclusions 18-2
C. Methodology 18-3
Study Area 18-3
D. Preliminary Assessment 18-4
Defining Features 18-4

Assessment of the Potential to Affect the Defining Features of the Neighborhood.....18-7

Chapter 19: Construction.....19-1
A. Introduction.....19-1
B. Principal Conclusions.....19-2
Transportation.....19-2
Air Quality.....19-3
Noise.....19-4
Other Analysis Areas.....19-4
C. Government Coordination and Oversight.....19-6
D. Anticipated Construction Schedule.....19-7
E. Description of Construction Activities.....19-8
General Construction Practices.....19-8
Estimate of Construction Workers and Construction Period Trucks.....19-10
Determining Peak Year for Cumulative Construction and Operational Effects.....19-11
F. Detailed Analyses.....19-11
Transportation.....19-11
Air Quality.....19-15
Noise.....19-20
Vibration.....19-31
Other Technical Areas.....19-32

Chapter 20: Mitigation.....20-1
A. Introduction.....20-1
B. Principal Conclusions.....20-1
Transportation.....20-1
Air Quality.....20-3
Construction.....20-4
C. Transportation.....20-4
Traffic.....20-4
Transit.....20-15
Pedestrians.....20-16
D. Air Quality.....20-20
E. Construction.....20-20
Transportation.....20-20

Chapter 21: Alternatives.....21-1
A. Introduction.....21-1
B. Principal Conclusions.....21-2
No-Action Alternative.....21-2
No Significant Adverse Impacts Alternative.....21-2
C. No-Action Alternative.....21-2
Land Use, Zoning, and Public Policy.....21-3
Socioeconomic Conditions.....21-3
Community Facilities and Services.....21-3
Open Space.....21-4
Shadows.....21-4
Historic and Cultural Resources.....21-4
Urban Design and Visual Resources.....21-4
Hazardous Materials.....21-4
Water and Sewer Infrastructure.....21-5
Solid Waste and Sanitation Services.....21-5
Energy.....21-5

Transportation 21-5
Air Quality 21-7
Greenhouse Gas Emissions and Climate Change 21-7
Noise 21-7
Public Health 21-8
Neighborhood Character 21-8
Construction 21-8
D. No Significant Adverse Impacts Alternative 21-8
Transportation 21-9
Air Quality 21-9

Chapter 22: Unavoidable Adverse Impacts 22-1
A. Introduction 22-1
B. Transportation 22-1
Traffic 22-1
Transit 22-2
Pedestrians 22-2
C. Air Quality 22-2
D. Construction 22-3
Transportation 22-3

Chapter 23: Growth-Inducing Aspects of the Proposed Actions 23-1

Chapter 24: Irreversible and Irretrievable Commitments of Resources 24-1

Chapter 25: Effects on Disadvantaged Communities 25-1
A. Introduction 25-1
B. Principal Conclusions 25-2
C. Identification of Disadvantaged Communities 25-2
D. Disadvantaged Communities Assessment 25-3
Transportation (Traffic, Transit, and Pedestrians) 25-4
Air Quality (Mobile Sources) 25-4
Construction (Transportation) 25-5

APPENDICES

Appendix A: PAA Plan
Appendix B: Historic and Cultural Resources
Appendix C: Hazardous Materials
Appendix D: Water and Sewer Infrastructure
Appendix E: Transportation
Appendix F: Air Quality
Appendix G: Construction Noise

LIST OF TABLES

ES-1 Comparison of Existing and Proposed Zoning ES-9
ES-2 Proposed Development Program ES-15
ES-3 Comparison of 2036 No-Action and With-Action Conditions at the Project Area (Proposed Development) ES-20
ES-4 Comparison of 2036 No-Action and With-Action Conditions at the Project Area (Alternate Community Facility Scenario) ES-21
ES-5 Summary of Significantly Impacted Intersections ES-34
ES-6 Summary of Significant Pedestrian Impacts ES-36
ES-7 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts ES-46
ES-8 Summary of Significant Pedestrian Impacts ES-47
1-1 Comparison of Existing and Proposed Zoning 1-9
1-2 Proposed Development Program 1-15
1-3 Comparison of 2036 No-Action and With-Action Conditions at the Project Area (Proposed Development) 1-20
1-4 Comparison of 2036 No-Action and With-Action Conditions at the Project Area (Alternate Community Facility Scenario) 1-21
2-1 Existing Land Uses in the Secondary Study Area 2-8
2-2 Existing Zoning Districts in the Secondary Study Area 2-10
2-3 No-Action Condition Developments in Secondary Study Area 2-16
2-4 2036 RWCDS No-Action and With-Action Land Uses – Primary Study Area (Proposed Development) 2-18
2-5 2036 RWCDS No-Action and With-Action Land Uses – Primary Study Area (Alternate Community Facility Scenario) 2-19
2-6 Comparison of Existing and Proposed Zoning – Primary Study Area 2-23
3-1 Estimated 2021 Employment in the Socioeconomic Conditions Study Area, Brooklyn, and New York City 3-10
3-2 Businesses Subject to Potential Direct Business Displacement at the Project Area Due to Proposed Actions 3-12
3-3 Estimated Directly Displaced Employment 3-14
3-4 Household Income Characteristics within the Socioeconomic Conditions Study Area, Brooklyn, and New York City 3-19
3-5 Household Income Distribution: Socioeconomic Conditions Study Area, Brooklyn, and New York City (2018-2022) 3-20
3-6 Planned No-Action Residential Developments and Estimated Residential Population – Socioeconomic Conditions Study Area by 2036 3-21
3-7 2024 New York City AMI 3-23
3-8 Estimated Third Quartile Asking Rental Rates and Calculated Estimated Household Incomes for the Proposed Development's Market-Rate Units 3-24
3-9 Change in Residential Population, 2010 – 2020 3-25
3-10 Socioeconomic Conditions Study Area Residential Population Estimates 3-26
3-11 2036 No-Action and With-Action Residential Populations In The Socioeconomic Conditions Study Area 3-27
3-12 Trends in Median Asking Rent, 2018 to 2023 3-29
3-13 Comparison of Estimated Employment in the Socioeconomic Conditions Study Area (2016 – 2021) 3-33
3-14 Comparison of 2016 and 2024 Commercial Square Footages in the Socioeconomic Conditions Study Area 3-35
4-1 Preliminary Screening Analysis Criteria 4-4
4-2 Screening Analysis Criteria for the Proposed Actions 4-5

4-3 CSD 19, Sub-District 1 Elementary School Enrollment, Capacity, & Utilization for the 2023-2024 Academic Year 4-8
4-4 CSD 19, Sub-District 1 Intermediate School Enrollment, Capacity, & Utilization for the 2023-2024 Academic Year 4-9
4-5 Estimated 2036 Study Area No-Action Elementary & Intermediate School Enrollment....4-9
4-6 2036 Estimated No-Action Elementary and Intermediate School Enrollment, Capacity, & Utilization in CSD 19, Sub-District 1 4-10
4-7 2036 Estimated With-Action Elementary and Intermediate School Enrollment, Capacity, & Utilization....4-11
4-8 Existing Holdings-per-Resident Ratios at the Brownsville and Arlington Libraries 4-12
4-9 Anticipated No-Action Residential Development within the Library Catchment Areas....4-13
4-10 No-Action Holdings-per-Resident Ratios at the Brownsville and Arlington Libraries 4-13
4-11 2036 With-Action Library Catchment Area Population Increases....4-14
4-12 2036 With-Action Library Holdings-per-Resident Ratios at the Brownsville and Arlington Libraries 4-14
4-13 Comparison of Budget Capacity, Enrollment, Available Slots, & Utilization:2036 No-Action Condition....4-17
4-14 Comparison of Budget Capacity, Enrollment, Available Slots, & Utilization: 2036 With-Action Condition....4-18
4-15 Publicly Funded Child Care Centers Serving the Study Area 4-19
5-1 Guidance for Percentage Change in Open Space Ratio....5-6
5-2 Non-Residential Study Area Population 5-7
5-3 Residential Study Area Population 5-7
5-4 Residential Study Area Population Breakdown....5-8
5-5 Quantitative Open Space Resources 5-10
5-6 Qualitative Open Space Resources....5-12
5-7 Adequacy of Open Space Resources – Existing Conditions....5-15
5-8 No-Action Condition Developments in the Study Areas 5-17
5-9 No-Action Condition Study Area Populations 5-18
5-10 Adequacy of Open Space Resources in the Non-Residential Study Area – No-Action Condition 5-19
5-11 With-Action Condition Study Area Populations 5-20
5-12 Adequacy of Open Space Resources – With-Action Condition 5-21
5-13 Study Area Open Space Ratios Summary 5-23
6-1 Maximum Building and Bulkhead Heights Under the Proposed Actions 6-5
6-2 Resources Warranting Further Analysis Based on Tier 2 Screening Assessment....6-6
6-3 Sunlight-Sensitive Resources Warranting Further Analysis Based on Tier 3 Screening Assessment 6-7
6-4 Incremental Duration of Shadows on Sunlight-Sensitive Resources....6-8
10-1 Existing Water Consumption and Wastewater Generation on the Projected Development Sites 10-4
10-2 Existing 26th Ward WRRF Average Daily Sewer Flows 10-4
10-3 Projected Development Sites Runoff Coefficient – Existing Conditions....10-5
10-4 Projected Development Sites Stormwater and Sanitary Sewage Flow Volumes – Existing Conditions....10-5
10-5 Expected Water Consumption and Wastewater Generation on the Projected Development Sites – 2036 No-Action vs. 2036 With-Action Conditions....10-6
10-6 Projected Development Sites Runoff Coefficient – With-Action Condition 10-7
10-7 Projected Development Sites Stormwater and Sanitary Sewage Flow Volumes – With-Action vs. Existing Conditions 10-8
11-1 Existing Solid Waste Generation — Project Area 11-6
11-2 No-Action Solid Waste Generation — Project Area 11-7
11-3 With-Action Solid Waste Generation — Project Area (Alternate Community Facility Scenario)....11-8
11-4 Comparison of Weekly Solid Waste Generation in Project Area – Existing, No-Action, and With-Action Conditions (Alternate Community Facility Scenario) 11-9
12-1 Expected Energy Consumption – RWCDS No-Action vs. With-Action....12-1
12-2 Annual Existing Energy Consumption – Development Site 12-5
12-3 Annual No-Action to With-Action Energy Consumption – Project Area

(Alternate Community Facility Scenario) 12-6
13-1 2036 RWCDS No-Action and With-Action Land Uses – Proposed Development 13-3
13-2 2036 RWCDS No-Action and With-Action Land Uses – Alternate Community Facility Scenario 13-4
13-3 Number of Impacted Intersections and Lane Groups by Peak Hour 13-5
13-4 Summary of Significantly Impacted Intersections 13-6
13-5 Summary of Significant Pedestrian Impacts 13-8
13-6 High Crash Locations 13-9
13-7 Transportation Planning Factors 13-14
13-8 Travel Demand Forecast – Proposed Development 13-16
13-9 Travel Demand Forecast – Alternate Community Facility Scenario 13-17
13-10 Summary of Net Incremental Peak Hour Trips Generated
Under the Proposed Development RWCDS 13-19
13-11 Summary of Net Incremental Peak Hour Trips Generated
Under the Alternate Community Facility Scenario RWCDS 13-19
13-12 Net Incremental Peak Hour Subway Trips by Station – Alternate Community Facility Scenario 13-21
13-13 Net Incremental Peak Hour Subway Trips by Route and Direction –
Alternate Community Facility Scenario 13-22
13-14 Bus Routes Serving the Project Area 13-22
13-15 Net Incremental Bus Route Assignments – Alternate Community Facility Scenario 13-23
13-16 Intersection Level of Service Criteria 13-25
13-17 Level of Service Criteria for Subway Station Elements 13-26
13-18 Significant Impact Thresholds for Stairways and Passageways 13-27
13-19 Pedestrian Crosswalk/Corner Area and Sidewalk Levels of Service Descriptions 13-28
13-20 Significant Impact Criteria for Sidewalks in a CBD Location 13-30
13-21 Significant Impact Criteria for Corners and Crosswalks in a CBD Location 13-31
13-22 Existing Level of Service at Analyzed Intersections 13-35
13-23 No-Action Condition Development Projects Within Half-Mile Radius of Project Area 13-37
13-24 No-Action Condition Level of Service at Analyzed Intersections 13-40
13-25 With-Action Condition Level of Service at Analyzed Intersections 13-44
13-26 Existing Conditions Subway Station Stair Analysis 13-47
13-27 Existing Conditions Subway Station Fare Array Analysis 13-47
13-28 Existing Conditions Escalator Analysis 13-48
13-29 Existing Conditions Subway Line Haul Analysis 13-48
13-30 No-Action Condition Subway Station Stair Analysis 13-50
13-31 No-Action Condition Subway Station Fare Array Analysis 13-51
13-32 No-Action Condition Escalator Analysis 13-51
13-33 No-Action Condition Subway Line Haul Analysis 13-51
13-34 With-Action Condition Subway Station Stair Analysis 13-53
13-35 With-Action Condition Subway Station Fare Array Analysis 13-53
13-36 With-Action Condition Escalator Analysis 13-54
13-37 With-Action Condition Subway Line Haul Analysis 13-54
13-38 Existing Sidewalk Conditions 13-56
13-39 Existing Crosswalk Conditions 13-57
13-40 Existing Corner Conditions 13-57
13-41 No-Action Condition Sidewalk Conditions 13-59
13-42 No-Action Condition Crosswalk Conditions 13-60
13-43 No-Action Condition Corner Conditions 13-60
13-44 With-Action Sidewalk Conditions 13-63
13-45 With-Action Crosswalk Conditions 13-64
13-46 With-Action Corner Conditions 13-64
13-47 Crash Data Summary – 2018, 2019, 2023 13-68
13-48 Total Weekday Hourly Parking Accumulation for the Project Area – Proposed Development 13-71
13-49 Total Saturday Hourly Parking Accumulation for the Project Area – Proposed Development 13-72

13-50 Total Weekday Hourly Parking Accumulation for the Project Area – Alternate Community Facility Scenario 13-73
13-51 Total Saturday Hourly Parking Accumulation for the Project Area – Alternate Community Facility Scenario 13-74
14-1 National Ambient Air Quality Standards (NAAQS) 14-7
14-2 Industrial Source Analysis Relevant DEC Air Guideline Concentrations 14-10
14-3 Maximum Background Pollutant Concentrations for Mobile Source Analysis 14-16
14-4 Mobile Source Analysis Sites 14-16
14-5 Exhaust Stack Parameters and Emission Rates – Heating and Hot Water Systems 14-20
14-6 Maximum Background Pollutant Concentrations 14-21
14-7 Industrial Sources within 400-Feet of the Project Area 14-23
14-8 Typical Composition of VOC Emissions from Auto Spray Paint Booths 14-24
14-9 Facility Pollutants and Emission Rates 14-25
14-10 Industrial Uses Categories Analyzed 14-28
14-11 Industrial Source Analysis Emissions Profile 14-29
14-12 Stack Parameters and Emission Rates from the NYCT East New York Bus Depot 14-32
14-13 Representative Monitored Ambient Air Quality Data 14-33
14-14 Maximum Predicted 8-Hour Average CO No Action Concentrations 14-34
14-15 Maximum Predicted 8-Hour CO With-Action Concentrations (ppm) 14-35
14-16 Maximum Predicted 24-Hour Average $PM_{2.5}$ With-Action and Incremental Concentrations ($\mu g/m^3$) 14-35
14-17 Maximum Predicted Annual Average $PM_{2.5}$ With-Action and Incremental Concentrations ($\mu g/m^3$) 14-35
14-18 Maximum Predicted 8-Hour Average CO Concentrations from the Atypical Roadways on the Proposed Development 14-36
14-19 Maximum Predicted 24-Hour Average $PM_{2.5}$ Concentrations from Atypical Roadways on the Proposed Development 14-37
14-20 Maximum Predicted Annual Average $PM_{2.5}$ from Atypical Roadways on the Proposed Development 14-37
14-21 Maximum Modeled Pollutant Concentrations on the Projected Development Sites from Heating and Hot Water Systems ($\mu g/m^3$) 14-37
14-22 Maximum Modeled Pollutant Concentrations on Off-Site Locations from Heating and Hot Water Systems ($\mu g/m^3$) 14-38
14-23 Maximum Modeled Impacts on the Projected Development Sites from Existing Industrial Sources 14-40
14-24 Estimated Maximum Hazard Index – Existing Industrial Uses 14-41
14-25 Estimated Maximum Cancer Risk – Existing Industrial Uses 14-42
14-26 Maximum Modeled Pollutant Concentrations ($\mu g/m^3$) From Potential Light Industrial Sources in the Project Area 14-43
14-27 Maximum Modeled Pollutant Concentrations ($\mu g/m^3$) From Potential Light Industrial Uses on Off-site Locations 14-44
14-28 Air Pollutant Emissions Limits – Future Uses 14-45
14-29 Estimated Maximum Hazard Index – Potential Light Industrial Uses 14-46
14-30 Estimated Maximum Cancer Risk – Potential Light Industrial Uses 14-47
14-31 Maximum Modeled Pollutant Concentrations — Cumulative Effects from Existing Industrial Sources and Potential Light Industrial Sources 14-47
14-32 Maximum Modeled Pollutant Concentrations on the Proposed Development ($\mu g/m^3$)—Additional Sources 14-48
15-1 Global Warming Potential (GWP) for Primary Greenhouse Gases 15-3
15-2 Proposed Actions' (Alternate Community Facility Scenario) Annual Vehicle Miles Traveled (miles per year) 15-7
15-3 Annual Building Operational Emissions – Alternate Community Facility Scenario 15-8
15-4 Annual Mobile Source Emissions for 2036 – Alternate Community Facility Scenario 15-9
15-5 Summary of Total Annual GHG Emissions Under the Proposed Actions – Alternate Community Facility Scenario 15-10

16-1 Noise Levels of Common Sources....16-2
16-2 Noise Exposure Guidelines for Use in City Environmental Impact Review....16-4
16-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels....16-5
16-4 Noise Measurement Locations....16-5
16-5 Existing Noise Levels at Receptor Sites 3-9 (in dBA)....16-6
16-6 Existing Noise Levels at Receptor Sites 1 and 2 (in dBA)....16-7
16-7 Measured and Calculated L_{dn} at Train Dominant Receptor Sites (in dBA)....16-7
16-8 No-Action Condition Noise Levels (in dBA)....16-9
16-9 With-Action Condition Noise Levels (in dBA)....16-9
16-10 Minimum Building Attenuation to Comply With CEQR Requirements (in dBA)....16-10
16-11 Minimum Required Attenuation at Projected Development Sites (in dBA)....16-11
19-1 Construction Oversight in New York City....19-7
19-2 Average Incremental Number of Daily Construction Workers and Trucks by Year and Quarter....19-11
19-3 2035 (Second Quarter) Peak Incremental Construction Vehicle Trip Projections (in PCEs)....19-13
19-4 2035 (Second Quarter) Construction Worker Parking Accumulation....19-15
19-5 Maximum Pollutant Concentrations....19-19
19-6 Noise Receptors by Location and Land Use....19-22
19-7 Summary of Construction Noise Analysis Periods....19-25
19-8 Construction Equipment Noise Emissions in dBA....19-28
19-9 Measured Existing Noise Levels (in dBA)....19-28
19-10 Construction Noise Analysis Results in dBA....19-29
19-11 Vibration Source Levels for Construction Equipment (dBA)....19-32
20-1 Summary of Lane Groups/Intersections with Significant Adverse Traffic Impacts....20-2
20-2 Lane Groups With Unmitigated Significant Adverse Traffic Impacts....20-2
20-3 Summary of Significant Pedestrian Impacts....20-3
20-4 Proposed Traffic Mitigation Measures....20-6
20-5 Action-With-Mitigation Conditions at Impacted Lane Groups – AM....20-7
20-6 Action-With-Mitigation Conditions at Impacted Lane Groups – Midday....20-9
20-7 Action-With-Mitigation Conditions at Impacted Lane Groups – PM....20-11
20-8 Action-With-Mitigation Conditions at Impacted Lane Groups – Saturday....20-13
20-9 Minimum Required Subway Stairway Widening to Mitigate Impacts at the Broadway Junction (A/C/J/L/Z) Subway Station Complex....20-15
20-10 Summary of Significant Pedestrian Impacts....20-16
20-11 Action-With-Mitigation Sidewalk Conditions....20-17
20-12 Action-With-Mitigation Crosswalk Conditions....20-18
20-13 Action-With-Mitigation Corner Conditions....20-19
25-1 NYS Disadvantaged Communities in the Half-Mile Study Area....25-4

LIST OF FIGURES

		Following Page
ES-1	Project Location Map – Aerial View	ES-1
ES-2	Existing Zoning Map	ES-4
ES-3	Existing Land Uses	ES-5
ES-4	Transit Service Map	ES-6
ES-5	Proposed Zoning	ES-8
ES-6	Projected Development Site 1A Site Plan	ES-15
ES-7	Projected Development Site 1B Site Plan	ES-16
ES-8	Projected Development Site 1B Zoning Sections	ES-16
ES-9	Projected Development Site 1C Site Plan	ES-16
ES-10	Projected Development Site 1C Zoning Sections	ES-16
ES-11	Projected Development Sites 1D and 1E Site Plan	ES-16
ES-12	Projected Development Sites 1D and 1E Zoning Sections	ES-16
ES-13	Projected Development Sites 1A-1E Axonometric Zoning Sections	ES-17
ES-14	Proposed Actions' RWCDS Construction Phasing	ES-18
1-1	Project Location Map – Aerial View	1-1
1-2	Existing Zoning Map	1-4
1-3	Existing Land Uses	1-5
1-4	Transit Service Map	1-6
1-5	Proposed Zoning	1-8
1-6	Projected Development Site 1A Site Plan	1-15
1-7	Projected Development Site 1B Site Plan	1-16
1-8	Projected Development Site 1B Zoning Sections	1-16
1-9	Projected Development Site 1C Site Plan	1-16
1-10	Projected Development Site 1C Zoning Sections	1-16
1-11	Projected Development Sites 1D and 1E Site Plan	1-16
1-12	Projected Development Sites 1D and 1E Zoning Sections	1-16
1-13	Projected Development Sites 1A-1E Axonometric Zoning Sections	1-17
1-14	Proposed Actions' RWCDS Construction Phasing	1-18
2-1	Primary and Secondary Study Areas – Land Use	2-3
2-2	Primary and Secondary Study Areas – Zoning	2-9
2-3	East New York Industrial Business Zone	2-12
2-4	East Brooklyn Business Improvement District	2-13
2-5	FRESH Program	2-17
2-6	No-Action Development Projects	2-17
3-1	Socioeconomic Conditions Study Area	3-8
4-1	CSD 19 Sub-district 1 Elementary and Middle Schools	4-7
4-2	Study Area Libraries	4-11
4-3	Brownsville Library Catchment Area	4-11
4-4	Arlington Library Catchment Area	4-11
4-5	Publicly-Funded Early Childhood Centers	4-27
5-1	Open Space Study Areas	5-3
5-2	Walk to a Park Service Area	5-4
5-3	Open Space Resources	5-9
5-4	No-Action Development Projects	5-17
6-1	Tier I and Tier II Screening Assessments	6-5
6-2a	Tier III Screening	6-7

6-2b Tier III Screening 6-7
6-3a Callahan-Kelly Playground Incremental Shadows on March 21/September 21 Analysis Day 6-10
6-3b Callahan-Kelly Playground Incremental Shadows on March 21/September 21 Analysis Day 6-10
6-4a Callahan-Kelly Playground Incremental Shadows on December 21 Analysis Day 6-10
6-4b Callahan-Kelly Playground Incremental Shadows on December 21 Analysis Day 6-10
6-5a Jewel Square Incremental Shadows on March 21/September 21 Analysis Day 6-11
6-5b Jewel Square Incremental Shadows on March 21/September 21 Analysis Day 6-11
6-5c Jewel Square Incremental Shadows on March 21/September 21 Analysis Day 6-11
6-6a Jewel Square Incremental Shadows on May 6/August 6 Analysis Day 6-12
6-6b Jewel Square Incremental Shadows on May 6/August 6 Analysis Day 6-12
6-6c Jewel Square Incremental Shadows on May 6/August 6 Analysis Day 6-12
6-7a Jewel Square Incremental Shadows on June 21 Analysis Day 6-12
6-7b Jewel Square Incremental Shadows on June 21 Analysis Day 6-12
6-7c Jewel Square Incremental Shadows on June 21 Analysis Day 6-13
6-8a Jewel Square Incremental Shadows on December 21 Analysis Day 6-13
6-8b Jewel Square Incremental Shadows on December 21 Analysis Day 6-13
6-9 Aerial View of Jewel Square 6-13
6-10 Jamaica Avenue Greenstreet Incremental Shadows on March 21/September 21 Analysis Day 6-16
6-11 Cemetery of the Evergreens Incremental Shadows on December 21 Analysis Day 6-17
7-1 Historic and Cultural Resources Map 7-1
7-2 Historic and Cultural Resources Photos 7-3
8-1 Primary and Secondary Study Areas - Urban Design and Visual Resources 8-4
8-2a Photo Indicator Map 8-5
8-2b Primary Study Area Photos 8-5
8-2c Primary Study Area Photos 8-5
8-3a Secondary Study Area Photos 8-5
8-3b Secondary Study Area Photos 8-5
8-3c Secondary Study Area Photos 8-5
8-3d Secondary Study Area Photos 8-5
8-3e Secondary Study Area Photos 8-5
8-4 Building Density Map 8-5
8-5 Building Heights Map 8-5
8-6 Projected Development Site 1A Site Plan 8-14
8-7 Projected Development Site 1B Site Plan 8-14
8-8 Projected Development Site 1B Zoning Sections 8-14
8-9 Projected Development Site 1C Site Plan 8-15
8-10 Projected Development Site 1C Zoning Sections 8-15
8-11 Projected Development Sites 1D and 1E Site Plan 8-15
8-12 Projected Development Sites 1D and 1E Zoning Sections 8-15
8-13 Projected Development Sites 1A-1E Axonometric Zoning Sections 8-17
8-14 No-Action Condition and With-Action Condition Massing Comparison - Photo Indicator Map 8-21
8-15 No-Action Condition and With-Action Condition Massing Comparison - View 1 8-21
8-16 No-Action Condition and With-Action Condition Massing Comparison - View 2 8-21
8-17 No-Action Condition and With-Action Condition Massing Comparison - View 3 8-21
8-18 No-Action Condition and With-Action Condition Massing Comparison - View 4 8-21
8-19 No-Action Condition and With-Action Condition Massing Comparison - View 5 8-21
8-20 No-Action Condition and With-Action Condition Massing Comparison - View 6 8-21
8-21 No-Action Condition and With-Action Condition Massing Comparison - View 7 8-21
8-22 No-Action Condition and With-Action Condition Massing Comparison - View 8 8-21
8-23 No-Action Condition and With-Action Condition Massing Comparison - View 9 8-21
8-24 No-Action Condition and With-Action Condition Massing Comparison - View 10 8-21
8-25 No-Action Condition and With-Action Condition Massing Comparison - View 11 8-21
8-26 No-Action Condition and With-Action Condition Massing Comparison - View 12 8-21

8-27 No-Action Condition and With-Action Condition Massing Comparison - View 13 8-21
8-28 No-Action Condition and With-Action Condition Massing Comparison - View 14 8-21
13-1 Project Location Map - Aerial View 13-1
13-2 Traffic Analysis Locations 13-20
13-3 Transit Service Map 13-21
13-4 Analyzed Pedestrian Elements 13-24
13-5 Bike Routes Map 13-34
13-6a Existing Weekday AM Peak Hour Traffic Volumes 13-34
13-6b Existing Weekday Midday Peak Hour Traffic Volumes 13-34
13-6c Existing Weekday PM Peak Hour Traffic Volumes 13-34
13-6d Existing Saturday Peak Hour Traffic Volumes 13-34
13-7 No-Action Development Projects 13-39
13-8a No-Action Weekday AM Peak Hour Traffic Volumes 13-39
13-8b No-Action Weekday Midday Peak Hour Traffic Volumes 13-39
13-8c No-Action Weekday PM Peak Hour Traffic Volumes 13-39
13-8d No-Action Saturday Peak Hour Traffic Volumes 13-39
13-9a Weekday AM Incremental Project Vehicle Trip Assignments 13-43
13-9b Weekday MD Incremental Project Vehicle Trip Assignments 13-43
13-9c Weekday PM Incremental Project Vehicle Trip Assignments 13-43
13-9d Saturday Incremental Project Vehicle Trip Assignments 13-43
13-10a With-Action Weekday AM Peak Hour Traffic Volumes 13-43
13-10b With-Action Weekday Midday Peak Hour Traffic Volumes 13-43
13-10c With-Action Weekday PM Peak Hour Traffic Volumes 13-43
13-10d With-Action Saturday Peak Hour Traffic Volumes 13-43
13-11a Broadway Junction (A/C/J/L/Z) Subway Station - IND Line 13-46
13-11b Broadway Junction (A/C/J/L/Z) Subway Station - BMT Lines 13-46
13-12a Broadway Junction (A/C/J/L/Z) Subway Station Planned Improvements - IND Line 13-49
13-12b Broadway Junction (A/C/J/L/Z) Subway Station Planned Improvements - BMT Lines 13-49
13-13 Vision Zero Map 13-65
15-1 New York State Disadvantaged Communities 15-4
16-1 Noise Measurement Locations 16-10
16-2 Required Building Noise Attenuation 16-5
18-1 Neighborhood Character Study Area and Land Uses 18-1
19-1 Construction Noise Receptor Locations 19-24
25-1 DEC Disadvantaged Communities in the Study Area 25-3